

2021 Annual Groundwater Monitoring and Corrective Action Report

Columbia Energy Center
Dry Ash Disposal Facility, Modules 1 through 3
Pardeeville, Wisconsin

Prepared for:

Alliant Energy



SCS ENGINEERS

25221067.00 | January 31, 2022

2830 Dairy Drive
Madison, WI 53718-6751
608-224-2830

OVERVIEW OF CURRENT STATUS

Columbia Energy Center, Dry Ash Disposal Facility, Modules 1 through 3 2021 Annual Report

In accordance with §257.90(e)(6), this section at the beginning of the annual report provides an overview of the current status of groundwater monitoring and corrective action programs for the coal combustion residual (CCR) unit. The groundwater monitoring system for the Columbia Energy Center (COL) Dry Ash Disposal Facility Modules 1 through 3 monitors a single CCR unit. Supporting information is provided in the text of the annual report.

Category	Rule Requirement	Site Status
Monitoring Status – Start of Year	(i) At the start of the current annual reporting period, whether the CCR unit was operating under the detection monitoring program in §257.94 or the assessment monitoring program in §257.95;	Detection
Monitoring Status – End of Year	(ii) At the end of the current annual reporting period, whether the CCR unit was operating under the detection monitoring program in §257.94 or the assessment monitoring program in §257.95;	Detection
Statistically Significant Increases (SSIs)	(iii) If it was determined that there was an SSI over background for one or more constituents listed in appendix III to this part pursuant to §257.94(e):	
	(A) Identify those constituents listed in appendix III to this part and the names of the monitoring wells associated with such an increase; and	<u>April 2021</u> Boron: MW-33AR, MW-34A, MW-302 Chloride: MW-33AR Sulfate: MW-33AR, MW-34A, MW-302 <u>October 2021</u> Same as April 2021
	(B) Provide the date when the assessment monitoring program was initiated for the CCR unit.	Alternative Source Demonstrations prepared for October 2020 and April 2021 events during 2021. Assessment monitoring not required. Alternative source for October 2021 SSIs will be evaluated in 2022.

Category	Rule Requirement	Site Status
Statistically Significant Levels (SSL) Above Groundwater Protection Standard (GPS)	(iv) If it was determined that there was an SSL above the GPS for one or more constituents listed in appendix IV to this part pursuant to §257.95(g) include all of the following:	Not applicable – Appendix IV sampling not required
	(A) Identify those constituents listed in appendix IV to this part and the names of the monitoring wells associated with such an increase;	
	(B) Provide the date when the assessment of corrective measures was initiated for the CCR unit;	
	(C) Provide the date when the public meeting was held for the assessment of corrective measures for the CCR unit; and	
	(D) Provide the date when the assessment of corrective measures was completed for the CCR unit.	
Selection of Remedy	(v) Whether a remedy was selected pursuant to §257.97 during the current annual reporting period, and if so, the date of remedy selection; and	Not applicable – Site is in detection monitoring
Corrective Action	(vi) Whether remedial activities were initiated or are ongoing pursuant to §257.98 during the current annual reporting period.	Not applicable – Site is in detection monitoring

Table of Contents

Section	Page
Overview of Current Status	i
1.0 Introduction.....	1
2.0 Background.....	1
2.1 Geologic and Hydrogeologic Setting.....	1
2.1.1 Regional Information.....	1
2.1.2 Site Information	2
2.2 CCR Rule Monitoring System	2
3.0 §257.90(e) Annual Report Requirements.....	2
3.1 §257.90(e)(1) Site Map.....	3
3.2 §257.90(e)(2) Monitoring System Changes.....	3
3.3 §257.90(e)(3) Summary of Sampling Events.....	3
3.4 §257.90(e)(4) Monitoring Transition Narrative.....	4
3.5 §257.90(e)(5) Other Requirements.....	4
3.5.1 § 257.90(e) General Requirements.....	4
3.5.2 §257.94(d) Alternative Detection Monitoring Frequency.....	5
3.5.3 §257.94(e)(2) Alternative Source Demonstration for Detection Monitoring	5
3.5.4 §257.95(c) Alternative Assessment Monitoring Frequency	6
3.5.5 §257.95(d)(3) Assessment Monitoring Results and Standards	6
3.5.6 §257.95(g)(3)(ii) Alternative Source Demonstration for Assessment Monitoring ..	6
3.5.7 §257.96(a) Extension of Time for Corrective Measures Assessment	6
3.6 §257.90(e)(6) Overview.....	6
4.0 References.....	7

Tables

Table 1.	Groundwater Monitoring Well Network
Table 2.	CCR Rule Groundwater Samples Summary
Table 3.	Groundwater Elevation – State Monitoring Program and CCR Well Network
Table 4.	Horizontal Gradients and Flow Velocity
Table 5.	2021 Groundwater Analytical Results Summary
Table 6.	2021 Groundwater Field Data Summary

Figures

Figure 1.	Site Location Map
Figure 2.	Site Plan and Monitoring Well Locations
Figure 3.	Water Table Map – April 2021
Figure 4.	Water Table Map – October 2021

Appendices

Appendix A	Regional Hydrogeologic Information
Appendix B	Boring Logs and Well Construction Documentation
Appendix C	Laboratory Reports
	C1 April 2021 Detection Monitoring
	C2 October 2021 Detection Monitoring
Appendix D	Historical Monitoring Results
Appendix E	Statistical Evaluation
Appendix F	Alternative Source Demonstrations
	F1 October 2020 Detection Monitoring
	F2 April 2021 Detection Monitoring

I:\25221067.00\Deliverables\2021 Fed Annual Report - COL Mod 1-3\220131_2021 Annual CCR GW Report COL MOD 1-3 LF_Final.docx

1.0 INTRODUCTION

This 2021 Annual Groundwater Monitoring and Corrective Action Report was prepared to support compliance with the groundwater monitoring requirements of the Coal Combustion Residuals (CCR) Rule [40 Code of Federal Regulations (CFR) 257.50-107]. Specifically, this report was prepared to fulfill the requirements of 40 CFR 257.90(e). The applicable sections of the Rule are provided below in italics, followed by applicable information relative to the 2021 Annual Groundwater Monitoring and Corrective Action Report for the CCR Units. The site location is shown on **Figure 1**.

This report covers the period of groundwater monitoring from January 1, 2021, through December 31, 2021.

The groundwater monitoring system for the Columbia Energy Center (COL) Dry Ash Disposal Facility Modules 1 through 3 monitors a single CCR unit:

- COL Dry Ash Disposal Facility – Modules 1-3 (existing CCR Landfill)

The system is designed to detect monitored constituents at the waste boundary of Modules 1 through 3 of the COL Dry Ash Disposal Facility as required by 40 CFR 257.91(d). The groundwater monitoring system consists of two upgradient and three downgradient monitoring wells (**Table 1** and **Figure 2**). A separate groundwater monitoring system evaluates groundwater conditions for Modules 4 through 6 of the COL Dry Ash Disposal Facility.

2.0 BACKGROUND

To provide context for the required annual report information, the following background information is provided in this section of the report, prior to the required information:

- Geologic and hydrogeologic setting
- CCR Rule monitoring system

2.1 GEOLOGIC AND HYDROGEOLOGIC SETTING

2.1.1 Regional Information

For the purposes of groundwater monitoring, the surficial sand and gravel aquifer is considered to be the uppermost aquifer unit, as defined under 40 CFR 257.53, at the COL Ash Disposal Facility Modules 1 through 3. Immediately underlying the surficial sand and gravel aquifer is the Cambrian-Ordovician sandstone aquifer. A summary of the regional hydrogeologic stratigraphy is presented in **Appendix A**.

The sand and gravel aquifer is capable of producing sufficient water for industrial or municipal use in some parts of Columbia County and is capable of producing sufficient water for domestic use in many areas, including along the Wisconsin River near the Columbia Energy Center (Harr et al., 1978). A map showing expected well yields within the sand and gravel aquifer in Columbia County is included in **Appendix A**.

Regional groundwater flow in the site vicinity is generally west toward the Wisconsin River. A map showing the regional water table elevations is included with the regional hydrogeologic information in **Appendix A**.

2.1.2 Site Information

Soils at the site are primarily sand to a depth of approximately 50 to 100 feet and overlie sandstone bedrock. Soils encountered during the site feasibility study for the COL Ash Disposal Facility were described as generally sandy with interbedded silty clay lenses up to 20 feet thick (Warzyn, 1978). During drilling of CCR wells MW-301 and MW-302, the unconsolidated materials were identified as consisting primarily of silty sand and sand. Boring logs for previously installed monitoring wells MW-33AR, MW-34A, MW-84A, and M-4R show silty sand and sand as the primary unconsolidated materials at these locations. The boring logs for Ash Disposal Facility Modules 1 through 3 CCR monitoring wells are provided in **Appendix B**. All CCR monitoring wells are screened within the unconsolidated sand unit.

Shallow groundwater at the site generally flows to the north and west across the existing landfill area. The water table elevations and groundwater flow directions for the April 2021 monitoring event are shown on **Figure 3**, and the water table elevations and groundwater flow directions for the October 2021 monitoring event are shown on **Figure 4**. The groundwater elevation data for the CCR monitoring wells are provided in **Table 3**. Calculated horizontal gradients and flow velocities for representative flow paths are provided in **Table 4**.

2.2 CCR RULE MONITORING SYSTEM

The groundwater monitoring system established in accordance with the CCR Rule consists of two upgradient (background) monitoring wells and four downgradient monitoring wells (**Table 1** and **Figure 2**). The background wells include MW-301 and MW-84A. The downgradient wells include MW-302, MW-33AR, and MW-34A. MW-1AR was added to the monitoring program in 2021 as a supplemental well because monitoring data has indicated that the groundwater flow direction in this part of the site is sometimes to the northeast. The monitoring network certification was updated with the addition of MW-1AR in January 2022. The CCR Rule wells are installed within the sand and gravel aquifer. Well depths range from approximately 29 to 43 feet, measured from the top of the well casing.

3.0 §257.90(e) ANNUAL REPORT REQUIREMENTS

Annual groundwater monitoring and corrective action report. For existing CCR landfills and existing CCR surface impoundments, no later than January 31, 2018, and annually thereafter, the owner or operator must prepare an annual groundwater monitoring and corrective action report. For new CCR landfills, new CCR surface impoundments, and all lateral expansions of CCR units, the owner or operator must prepare the initial annual groundwater monitoring and corrective action report no later than January 31 of the year following the calendar year a groundwater monitoring system has been established for such CCR unit as required by this subpart, and annually thereafter. For the preceding calendar year, the annual report must document the status of the groundwater monitoring and corrective action program for the CCR unit, summarize key actions completed, describe any problems encountered, discuss actions to resolve the problems, and project key activities for the upcoming year. For purposes of this section, the owner or operator has prepared the annual report when the report is placed in the facility's operating record as required by § 257.105(h)(1). At a minimum, the annual groundwater monitoring and corrective action report must contain the following information, to the extent available:

3.1 §257.90(e)(1) SITE MAP

A map, aerial image, or diagram showing the CCR unit and all background (or upgradient) and downgradient monitoring wells, to include the well identification numbers, that are part of the groundwater monitoring program for the CCR unit;

A map of the site location is provided on **Figure 1**. A map showing the Dry Ash Disposal Facility Modules 1 through 3 and all background (or upgradient) and downgradient monitoring wells with identification numbers for the groundwater monitoring program is provided as **Figure 2**. Other CCR units are also shown on **Figure 2**.

3.2 §257.90(e)(2) MONITORING SYSTEM CHANGES

Identification of any monitoring wells that were installed or decommissioned during the preceding year, along with a narrative description of why those actions were taken;

MW-1AR was added to the monitoring program in 2021 as a downgradient well. MW-1AR was installed in November 1994 and is also included in the state monitoring program at the site. MW-1AR was added to the CCR Rule monitoring program because it is located to the northeast of Modules 1 through 3 and monitoring data have indicated that the groundwater flow direction in the northeast portion of the CCR Unit is sometimes to the northeast.

No wells were decommissioned as part of the groundwater monitoring program for Modules 1 through 3 of the Dry Ash Disposal Facility in 2021.

3.3 §257.90(e)(3) SUMMARY OF SAMPLING EVENTS

In addition to all the monitoring data obtained under §§ 257.90 through 257.98, a summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the detection monitoring or assessment monitoring programs;

Two semiannual groundwater sampling events were completed in 2021 at the COL Dry Ash Disposal Modules 1 through 3 as part of ongoing detection monitoring. An additional resampling event for field pH only at select wells was completed in June 2021.

Groundwater samples collected during the semiannual events, in April and October 2021, were analyzed for the Appendix III constituents. A summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the detection or assessment monitoring program is included in **Table 2**.

The sampling results for Appendix III parameters in 2021 are summarized in **Table 5**. Field parameter results for the 2021 sampling events are provided in **Table 6**. The analytical laboratory reports for 2021 are provided in **Appendix C**. Historical results for each monitoring well are summarized in **Appendix D**.

3.4 §257.90(e)(4) MONITORING TRANSITION NARRATIVE

A narrative discussion of any transition between monitoring programs (e.g., the date and circumstances for transitioning from detection monitoring to assessment monitoring in addition to identifying the constituent(s) detected at a statistically significant increase over background levels);

There were no transitions between monitoring programs during 2021. The COL Dry Ash Disposal Facility, Modules 1 through 3, remained in the detection monitoring program.

In 2021, the monitoring results for the October 2020 and April 2021 monitoring events were evaluated for statistically significant increases (SSIs) in detection monitoring parameters relative to background. The comparison to background was based on a prediction limit approach, comparing the results to interwell upper prediction limits (UPLs) based on background monitoring results from the upgradient wells (MW-84A and MW-301). The interwell UPLs were most recently updated in January 2020 using background data collected through October 2019. The Unified Guidance for Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities (U.S. EPA, 2009; Section 5.3.1) recommends periodic updating of background for both intrawell and interwell analyses. For semiannual monitoring, an update interval of 2 to 3 years is recommended; therefore, the next UPL update is planned for 2022 or 2023. The UPL calculations are included in **Appendix E**. The UPLs calculated in January 2020 were applied to the evaluation of the October 2020 and April 2021 monitoring results.

For the October 2020 and April 2021 events, SSIs for boron, chloride, and sulfate were identified. Individual upper prediction limit (UPL) exceedances for field pH were identified at select wells in April 2021, however the field pH results during the June 2021 resampling event did not exceed the UPL; therefore, the April pH results do not represent SSIs.

Alternative source demonstrations (ASDs) were completed for the October 2020 and April 2021 events, demonstrating that sources other than the CCR units were the likely cause of the observed concentrations of boron, chloride, and sulfate. The ASD reports are provided in **Appendix F**. A similar evaluation of alternative sources is anticipated to be performed in 2022 for SSIs identified in the October 2021 monitoring results.

3.5 §257.90(e)(5) OTHER REQUIREMENTS

Other information required to be included in the annual report as specified in §§ 257.90 through 257.98.

Additional potentially applicable requirements for the annual report, and the location of the requirement within the Rule, are provided in the following sections. For each cited section of the Rule, the portion referencing the annual report requirement is provided below in italics, followed by applicable information relative to the 2021 Annual Groundwater Monitoring and Corrective Action Report for the CCR Units.

3.5.1 § 257.90(e) General Requirements

For the preceding calendar year, the annual report must document the status of the groundwater monitoring and corrective action program for the CCR unit, summarize key actions completed, describe any problems encountered, discuss actions to resolve the problems, and project key activities for the upcoming year.

Status of Groundwater Monitoring and Corrective Action Program: The groundwater monitoring and corrective action program was in detection monitoring throughout 2021.

Summary of Key Actions Completed:

- Statistical evaluation and determination of SSIs for the October 2020 and April 2021 monitoring events.
- ASD reports for the SSIs identified from the October 2020 and April 2021 monitoring events.
- Two semiannual groundwater sampling and analysis events (April and October 2021) and a resample event (June 2021).
- Added MW-1AR to the monitoring program.

Description of Any Problems Encountered: No problems were encountered in 2021.

Discussion of Actions to Resolve the Problems: Not applicable.

Projection of Key Activities for the Upcoming Year (2022):

- Statistical evaluation and determination of any SSIs for the October 2021 and April 2022 monitoring events.
- If an SSI is determined, then within 90 days either:
 - Complete ASD (if applicable), or
 - Establish an assessment monitoring program.
- Two semiannual groundwater sampling and analysis events (April and October 2022).

3.5.2 §257.94(d) Alternative Detection Monitoring Frequency

The owner or operator must include the demonstration providing the basis for the alternative monitoring frequency and the certification by a qualified professional engineer in the annual groundwater monitoring and corrective action report required by § 257.90(e).

Not applicable. No alternative detection monitoring frequency has been proposed.

3.5.3 §257.94(e)(2) Alternative Source Demonstration for Detection Monitoring

The owner or operator must also include the demonstration in the annual groundwater monitoring and corrective action report required by § 257.90(e), in addition to the certification by a qualified professional engineer.

The ASD reports prepared to address the SSIs observed for the October 2020 and May 2021 sampling events are provided in **Appendix F**. The ASD reports are certified by a qualified professional engineer.

3.5.4 §257.95(c) Alternative Assessment Monitoring Frequency

The owner or operator must include the demonstration providing the basis for the alternative monitoring frequency and the certification by a qualified professional engineer in the annual groundwater monitoring and corrective action report required by § 257.90(e).

Not applicable. Assessment monitoring has not been initiated.

3.5.5 §257.95(d)(3) Assessment Monitoring Results and Standards

Include the recorded concentrations required by paragraph (d)(1) of this section, identify the background concentrations established under § 257.94(b), and identify the groundwater protection standards established under paragraph (d)(2) of this section in the annual groundwater monitoring and corrective action report required by § 257.90(e).

Not applicable. Assessment monitoring has not been initiated.

3.5.6 §257.95(g)(3)(ii) Alternative Source Demonstration for Assessment Monitoring

The owner or operator must also include the demonstration in the annual groundwater monitoring and corrective action report required by § 257.90(e), in addition to the certification by a qualified professional engineer.

Not applicable. Assessment monitoring has not been initiated.

3.5.7 §257.96(a) Extension of Time for Corrective Measures Assessment

The assessment of corrective measures must be completed within 90 days, unless the owner or operator demonstrates the need for additional time to complete the assessment of corrective measure due to site-specific conditions or circumstances. The owner or operator must obtain a certification from a qualified professional engineer attesting that the demonstration is accurate. The 90-day deadline to complete the assessment of corrective measures may be extended for longer than 60 days. The owner or operator must also include the demonstration in the annual groundwater monitoring and corrective action report required by § 257.90(e), in addition to the certification by a qualified professional engineer.

Not applicable. Corrective measures assessment has not been initiated.

3.6 §257.90(E)(6) OVERVIEW

A section at the beginning of the annual report that provides an overview of the current status of groundwater monitoring and corrective action programs for the CCR unit.

The specific requirements for the overview under §257.90(e)(6) are listed and the information is provided at the beginning of this report, before the Table of Contents.

4.0 REFERENCES

Harr, C.A., L.C. Trotta, and R.G. Borman, 1978, "Ground-Water Resources and Geology of Columbia County, Wisconsin," University of Wisconsin-Extension Geological and Natural History Survey Information Circular Number 37, 1978.

U.S. Environmental Protection Agency (U.S. EPA), 2009, Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities, Unified Guidance, EPA 530-R-09-007, March 2009.

Warzyn Engineering, Inc., 1978, Feasibility Study, Proposed Fly Ash and/or Scrubber Sludge Disposal Facility – Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Tables

- 1 Groundwater Monitoring Well Network
- 2 CCR Rule Groundwater Samples Summary
- 3 Groundwater Elevation – State Monitoring Program
and CCR Well Network
- 4 Horizontal Gradients and Flow Velocity
- 5 2021 Groundwater Analytical Results Summary
- 6 2021 Groundwater Field Data Summary

**Table 1. Groundwater Monitoring Well Network
Columbia Energy Center Dry Ash Disposal Facility, Modules 1-3
SCS Engineers Project #25221067.00**

Monitoring Well	Location in Monitoring Network	Role in Monitoring Network
MW-84A	Upgradient	Background
MW-301	Upgradient	Background
MW-302	Downgradient	Compliance
MW-34A	Downgradient	Compliance
MW-33AR	Downgradient	Compliance
MW-1AR	Downgradient	Compliance

Created by: MDB
 Last revision by: MDB
 Checked by: JAO

Date: 12/15/2021
 Date: 12/15/2021
 Date: 12/22/2021

**Table 2. CCR Rule Groundwater Samples Summary
Columbia Energy Center Dry Ash Disposal Facility, Modules 1-3
SCS Engineers Project #25221067.00**

Sample Dates	Compliance Wells				Background Wells	
	MW-302	MW-34A	MW-33AR	MW-1AR	MW-84A	MW-301
4/13-14/2021	D	D	D	D	D	D
6/11/2021	--	D-R	D-R	--	--	--
10/12-14/2021	D	D	D	D	D	D
Total Samples	2	3	3	2	2	2

Abbreviations:

D = Required by Detection Monitoring Program

D-R = Detection Monitoring Retest Sample

-- = Not sampled

Created by:	<u>MDB</u>	Date:	<u>12/15/2021</u>
Last revision by:	<u>MDB</u>	Date:	<u>12/15/2021</u>
Checked by:	<u>JAO</u>	Date:	<u>12/22/2021</u>

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25221067.00**

Dry Ash Facility (Facility ID #03025)	Well Number	MW-1AR	MW-4	MW-5R	MW-33AR	MW-33BR	MW-34A	MW-34B	MW-37A	MW-83	MW-84A	MW-84B	MW-86	MW-91AR	MW-91B	MW-92A	MW-92B
	Top of Casing Elevation (feet amsl)	822.55	819.74	805.44	808.29	808.39	805.95	806.05	813.04	807.96	814.28	814.26	824.79	809.03	808.45	808.47	808.41
	Total Depth (ft from top of casing)	44.40	39.58	25.97	31.08	57.50	35.43	56.95	31.80	25.42	40.21	52.02	45.43	32.90	52.38	28.94	51.75
Measurement Date																	
October 2, 2012	783.41	783.70	784.96	782.38	782.23	783.03	782.99	782.66	dry	783.84	783.94	783.81	784.09	783.90	784.49	784.06	
April 15, 2013	785.44	784.02	786.09	784.16	784.14	784.74	784.79	783.87	784.49	785.83	785.76	785.22	785.14	785.01	785.75	785.34	
October 8, 2013													785.66	785.42	785.97	785.52	
October 15, 2013	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.66	785.42	785.97	785.52
April 14, 2014	784.95	784.09	785.63	783.74	783.91	784.63	784.70	783.45	783.73	785.58	785.52	784.96	785.04	784.96	785.99	785.54	
October 2-3, 2014	785.03	785.39	786.08	784.37	784.28	784.57	784.54	784.56	dry	785.24	785.18	785.19	785.47	785.28	785.75	785.33	
April 13-14, 2015	783.96	783.63	785.25	783.01	782.74	783.65	783.95	782.87	dry	784.43	784.51	784.17	784.48	784.37	785.07	784.66	
October 6-7, 2015	784.28	784.44	785.72	783.68	783.33	784.05	784.02	783.66	dry	784.80	784.76	784.66	784.89	784.70	785.20	784.76	
April 4-6, 2016	785.82	aband	787.02	785.29	785.07	785.63	785.67	784.76	785.43	786.37	786.26	785.89	786.05	785.95	786.61	786.21	
October 11-13, 2016	786.64	aband	788.00	787.36	786.46	786.45	786.32	786.40	786.81	787.22	787.11	786.96	787.17	786.81	787.68	787.25	
April 10-13, 2017	786.96	aband	788.13	786.39	785.99	786.30	786.28	786.34	786.23	787.16	787.06	786.96	787.24	787.03	787.90	787.60	
October 3-5, 2017	785.48	aband	786.66	784.51	784.22	784.67	784.63	784.86	784.29	NM	786.49	785.58	786.08	785.83	786.47	786.02	
October 9-10, 2017	NM	aband	NM	NM	NM	NM	NM	NM	NM	785.56 ⁽⁶⁾	NM	NM	NM	NM	NM	NM	
February 21, 2018	783.97	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	784.68	784.46	NM	NM
April 23-25, 2018	783.99	aband	785.36	783.09	786.36	781.77	780.79	783.28	783.32	785.88	784.91	782.54	784.71	784.53	785.23	784.81	
October 23-25, 2018	788.25	aband	789.71	788.77	787.96	787.88	787.73	787.62	788.26	788.32	788.19	788.21	788.59	788.31	789.32	788.87	
April 1-4, 2019	787.05	aband	788.64	786.63	786.54	786.82	786.92	786.47	786.78	787.35	787.34	787.16	787.45	787.18	788.04	787.63	
October 7-9, 2019	787.26	aband	789.23	788.26	787.64	787.92	787.74	786.77	788.90	787.79	787.73	787.44	787.78	787.62	788.63	788.17	
May 27-28, 2020	786.92	aband	788.34	786.01	785.75	785.98	785.99	786.22	786.03	787.02	786.99	786.94	787.26	787.05	787.86	787.47	
October 7-8, 2020	785.95	aband	787.76	785.91	785.45	785.70	785.68	785.52	785.72	786.10	786.06	786.10	786.55	786.33	786.85	786.38	
February 25, 2021	NM	aband	NM	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	
April 14, 2021	785.11	aband	787.29	784.27	784.05	784.77	784.77	784.46	c	785.84	785.81	785.60	785.86	785.69	786.47	786.06	
June 11, 2021	NM	aband	NM	784.19	NM	784.66	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	
October 11-12, 14, 2021	784.47	adand	786.78	783.73	783.60	784.42	784.41	783.88	783.87	784.96	784.88	784.79	785.14	784.94	785.55	785.11	
October 17, 2021	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	
Bottom of Well Elevation (ft)	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	

Ash Pond Facility (Facility ID #02325)	Well Number	M-3	M-4R	MW-39A	MW-39B	MW-48A	MW-48B	MW-57	MW-59	MW-216R	MW-217	MW-220RR	SG-1	SG-2	SG-3	SG-4	
	Top of Casing Elevation (feet amsl)	788.23	806.10	809.62	809.50	828.86	828.84	786.29	815.48	814.21	791.55	792.90	792.90	792.06	795.25	808.60	805.36
	Total Depth (ft from top of casing)	16.90	25.55	34.80	76.07	51.88	75.80	14.40	38.50	37.85	37.37	18.96	--	--	--	--	
Measurement Date																	
October 2, 2012	780.13	786.76	781.49	781.34	782.03	781.93	780.58	779.88	781.91	780.95	780.55	789.14	793.85	dry	dry		
April 15, 2013	785.16	788.39	783.97	784.00	783.77	783.78	784.69	783.66	784.09	784.75	785.02	789.5 ⁽¹¹⁾	NM	dry	dry		
October 8, 2013	781.22	786.67	NM	NM	783.69	783.58	NM	NM	783.39	782.27	782.36	789.5 ⁽¹¹⁾	791.33	dry	dry		
October 15, 2013	NM	NM	782.94	782.81	NM	NM	782.47	783.49	NM	NM	NM	NM	NM	NM	NM		
April 14, 2014	786.04	788.96	783.57	783.68	783.56	783.57	785.51	783.41	783.73	785.25	785.87	788.90	dry	dry	dry		
October 1-3, 2014	781.16	787.55	783.42	783.32	784.05	783.94	782.32	783.55	783.79	782.63	783.03	NM	dry	dry	dry		
April 13-14, 2015	783.08	786.83	782.77	782.68	782.80	782.82	782.81	782.83	782.93	783.34	783.42	789.3	791.70	dry	dry		
October 6-7, 2015	780.66	786.12	782.97	782.81	783.10	783.01	781.82	783.25	783.18	781.95	782.26	788.48	791.58	dry	dry		
April 4-6, 2016	784.21	789.09	785.27	785.27	784.79	784.76	783.21	784.97	785.68	785.02	784.36	NM	793.40	dry	dry		
October 11-13, 2016	781.88	787.88	785.75	785.52	785.73	785.61	783.12	786.51	786.16	783.75	784.09	788.32	792.52	dry	dry		
April 10-13, 2017	782.94	787.95	785.44	785.20	785.82	785.69	782.77	786.09	785.95	784.29	784.09	788.31	793.85	dry	dry		
October 3-5, 2017	780.93	787.04	783.35	783.18	784.30	784.19	782.37	784.23	783.89	782.48	782.61	788.3	793.45	dry	dry		
April 23-25, 2018	782.89	790.43	782.86	782.87	783.14	783.09	783.04	783.02	783.23	783.26	783.45	788.38	>795.25	dry	dry		
October 23-25, 2018	782.95	788.47	787.12	786.88	787.12	786.99	783.48	787.73	787.49	784.90	784.52	787.76	793.25	dry	dry		
April 1-4, 2019	785.68	789.44	786.28	786.31	786.56	786.45	785.27	787.39	786.53	786.33	785.46	788.40	794.60	dry	dry		
October 7-9, 2019	785.33	790.65	787.10	787.02	786.68	786.65	785.29	786.68	787.07	786.01	785.42	748.48	795.20	dry	dry		
May 27-29, 2020	781.80	787.73	785.12	784.92	785.74	785.59	783.11	785.89	785.60	783.41	783.89	748.48	>795.25	dry	dry		
October 7-8 & 17, 2020	781.42	787.74	784.74	784.64	785.03	784.96	782.83	785.43	785.10	783.06	783.49	788.34	793.32	dry	NM		
April 12, 2021	782.30	786.34	783.66	783.65	784.13	784.08	782.79	784.08	783.97	783.15	783.49	788.03	793.45	below gauge	dry		
October 11-12, 14, 2021	781.03	786.33	782.94	782.85	783.09	783.03	781.94	783.11	783.04	782.15	782.66	788.59	795.13	dry	dry		
Bottom of Well Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--		

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25221067.00**

CCR Rule Wells	Well Number	MW-301	MW-302	MW-303	MW-304	MW-305	M-4R	MW-33AR	MW-34A	MW-84A	MW-306	MW-307	MW-308	MW-309	MW-310	MW-311
	Top of Casing Elevation (feet amsl)	806.89	813.00	811.52	805.42	806.32	806.10	808.29	805.95	814.28	807.63	806.89	806.9	813.27	813.62	809.74
	Screen Length (ft)	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10
	Total Depth (ft from top of casing)	29.40	33.6	35.80	25.7	25.6	39.58	31.08	35.43	40.21	27	26.5	28	37.67	38.41	36.19
	Top of Well Screen Elevation (ft)	787.49	789.40	785.72	789.72	790.72	776.52	787.21	780.52	784.07	790.63	790.39	788.90	785.60	785.21	783.55
	Measurement Date															
	December 21-22, 2015	NM	784.78	784.11	786.13	788.96	787.58	783.77	783.50	785.31	NM	NM	NM	NM	NM	NM
	May 27-29, 2020	787.77	787.29	785.56	789.30	787.78	787.73	786.01	785.98	787.02	785.77	785.35	786.28	785.98	785.81	785.85
	June 30, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.18	NM	NM
	August 6, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.93	NM	NM
	October 7-8, 2020	786.53	786.74	785.16	788.52	787.96	787.74	785.91	785.70	786.10	785.39	784.71	785.68	785.47	785.56	785.83
	December 11, 2020	NM	NM	NM	NM	788.19	NM	NM	NM	NM	NM	NM	NM	785.26	785.26	NM
	February 25, 2021	NM	NM	784.27	NM	788.36	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM
	April 12, 2021	786.50	785.77	784.07	787.99	788.11	786.34	784.27	784.77	785.84	784.32	784.21	785.55	784.29	784.24	784.15
	June 11, 2021	NM	NM	NM	NM	NM	NM	784.19	784.66	NM	NM	NM	NM	784.20	784.05	NM
	July 20, 2021	NM	NM	783.64	NM	788.39	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM
October 11-12, 14, 2021	785.28	785.09	783.09	787.78	787.75	786.33	783.73	784.42	784.96	782.93	782.44	783.76	783.65	783.48	783.48	
December 21, 2021	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	782.93	NM	NM	
Bottom of Well Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	780.63	780.39	778.90	775.60	775.21	773.55	

Notes: Created by: MDB Date: 5/6/2013
 NM = not measured Last revision by: JAO Date: 12/22/2021
 Checked by: RM Date: 12/22/2021

- (1) The elevation for SG-1 is read off of the staff gauge (rather than measured from the top of the gauge).
- (2) SG-2 could not be located during the April 2013 event.
- (3) SG-3 could not be located during the October 2013 event. SG-1 could not be safely accessed during the October 2013 event.
- (4) LH-2 measurements are given as leachate depth, measured by a transducer.
- (5) LH-2 and LH-3 measurements were collected by WPL staff on October 9, 2017.
- (6) The depth to water at MW-84A was not measured prior to purging for sampling during the October 3-5, 2017 sampling event. The level was allowed to return to static and was measured on 10/10/2017.

\\Mad-fs01\data\Projects\25221067.00\Data and Calculations\Tables\wlstat_Columbia.xls]levels

**Table 4. Horizontal Gradients and Flow Velocity
Columbia Energy Center - MOD 1-3 /
SCS Engineers Project #25221067.00
January - December 2021**

Northwest					
Sampling Dates	h1 (ft)	h2 (ft)	Δl (ft)	Δh/Δl (ft/ft)	V (ft/d)
4/12-14/2021	785.86	778.12	731.13	0.0106	0.269
10/11-14/2021	785.14	784.47	725.13	0.0009	0.024

Northeast					
Sampling Dates	h1 (ft)	h2 (ft)	Δl (ft)	Δh/Δl (ft/ft)	V (ft/d)
4/12/14/2021	785.00	784.27	144.6	0.0050	0.128
10/11-14/2021	785.00	783.73	539.43	0.0024	0.060

Wells	K Values (cm/sec)	K Values (ft/d)
MW-34A	N/A	N/A
MW-302	3.22E-02	91.2
MW-33AR	4.01E-04	1.1
Geometric	3.59E-03	10.2

Assumed Porosity, n
0.40

Groundwater flow velocity equation: $V = [K*(\Delta h/\Delta l)] / n$

ft = feet

ft/d = feet per day

K = hydraulic conductivity

n = effective porosity

V = groundwater flow velocity

h1, h2 = point interpreted groundwater elevation at locations 1 and 2

Δl = distance between location 1 and 2

Δh/Δl = hydraulic gradient

Created by: RM
Last revision by: RM
Checked by: MDB

Date: 12/29/2020
Date: 1/3/2022
Date: 1/4/2022

**Table 5. 2021 Groundwater Analytical Results Summary
Columbia Energy Center Dry Ash Disposal Facility, Modules 1-3 / SCS Engineers Project #25221067.00**

Parameter Name	UPL Method	UPL	Background Wells				Compliance Wells									
			MW-301		MW-84A		MW-33AR			MW-34A			MW-302		MW-1AR	
			4/14/2021	10/14/2021	4/14/2021	10/14/2021	4/13/2021	6/11/2021	10/12/2021	4/13/2021	6/11/2021	10/12/2021	4/13/2021	10/14/2021	4/14/2021	10/14/2021
Appendix III																
Boron, µg/L	P	35.6	22.2	31.4	14.3	11.1	473	--	564	203	--	212	521	495	16.1	12.4
Calcium, µg/L	NP	129,000	117,000 P6	67,800 P6	69,100	75,300	51,600	--	53700	61,600	--	58,100	82,400	84,100	85,500	87,600
Chloride, mg/L	P	6.2	1.5 J	2.7	4.4	3.5	26.9	--	22.6	2.3	--	1.9 J, M0	1.4 J	1.3 J	1.5 J	1.2 J
Fluoride, mg/L	DQ	DQ	<0.095	<0.095	<0.095	<0.095	<0.095	--	<0.095	<0.095	--	<0.095 M0	<0.095	<0.095	<0.095	<0.095
Field pH, Std. Units	P	7.78	6.66	7.01	7.34	7.42	8.78	7.71	7.59	7.93	7.61	7.68	7.51	7.07	7.52	7.44
Sulfate, mg/L	P	30.3	8.5	17.4	1.4 J	1.3 J	94.3	--	96.4	59.3	--	56.1	36.9	37.8	4.4 M0	3.1
Total Dissolved Solids, mg/L	NP	514	472	334	328	326	362	--	374	290	--	278	370	394	318	350

 Blue shaded cell indicates the compliance well result exceeds the UPL and the LOQ.

Abbreviations:

mg/L = milligrams per liter
µg/L = micrograms per liter

LOD = Limit of Detection
LOQ = Limit of Quantitation

UPL = Upper Prediction Limit
P = Parametric UPL with 1-of-2 retesting

DQ = Double Quantification Rule (not detected in background)
NP = Nonparametric UPL (highest background value) with 1-of-2 retesting

Laboratory Notes and Qualifiers:

J = Estimated concentration at or above the LOD and below the LOQ.

P6 = Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

M0 = Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits

Notes:

1. An individual result above the UPL or GPS does not constitute an SSI above background or statistically significant level above the GPS. See the accompanying letter text for identification of statistically significant results.
2. Interwell UPLs calculated based on results from background wells MW-84 and MW-301.

Created by: MDB
Last revision by: MDB
Checked by: JAO
Proj Mgr QA/QC: TK

Date: 5/13/2021
Date: 12/15/2021
Date: 12/22/2021
Date: 1/7/2022

Table 6. 2021 Groundwater Field Data Summary
Columbia Energy Center - Dry Ash Disposal Facility - MOD 1-3 / SCS Engineers Project #25221067.00

Well	Sample Date	Groundwater Elevation (feet)	Field Temperature (deg C)	Field pH (Std. Units)	Oxygen, Dissolved (mg/L)	Field Specific Conductance (umhos/cm)	Field Oxidation Potential (mV)	Turbidity (NTU)
MW-84A	4/14/2021	785.84	10.2	7.34	9.80	610.9	95.6	2.45
	10/14/2021	784.96	12.50	7.42	9.25	598.9	89.7	3.41
MW-301	4/14/2021	786.50	7.4	6.66	3.90	857.0	102.9	2.41
	10/14/2021	785.28	11.10	7.01	0.25	597.2	57.8	3.21
MW-302	4/13/2021	785.77	9.6	7.51	9.92	661.3	127.0	2.60
	10/12/2021	785.09	11.50	7.07	8.07	663.7	149.1	2.54
MW-33AR	4/13/2021	784.27	9.8	8.78	10.11	622.0	125.3	0.63
	6/11/2021	784.19	12.7	7.71	11.42	609.0	85.3	0.00
	10/12/2021	783.73	13.5	7.59	NR	623.2	90.0	0.00
MW-34A	4/13/2021	784.77	10.3	7.93	10.47	472.6	118.8	36.34
	6/11/2021	784.66	12.2	7.61	11.77	472.7	73.4	9.72
	10/14/2021	784.42	13.0	7.68	10.10	478.1	72.6	21.13
MW-1AR	4/14/2021	778.12	7.2	7.26	7.52	611.7	100.4	136.1
	10/14/2021	784.47	14.90	7.44	7.83	653.0	143.6	29.69

Notes/Abbreviations:

NR = Not Reported


1) October 2021 Dissolved Oxygen result for MW-33AR not reported due to instrument calibration issues that resulted in rejection of the field-recorded result.

Created by: NDK
 Last revision by: MDB
 Checked by: JAO

Date: 4/21/2021
 Date: 12/15/2021
 Date: 12/22/2021

Figures


- 1 Site Location Map
- 2 Site Plan and Monitoring Well Locations
- 3 Water Table Map – April 2021
- 4 Water Table Map – October 2021




POYNETTE QUADRANGLE
 WISCONSIN-COLUMBIA CO.
 7.5 MINUTE SERIES (TOPOGRAPHIC)
 2018
 SCALE: 1" = 2,000'



CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954		SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER PARDEEVILLE, WI		ENGINEER	SITE LOCATION MAP	
	PROJECT NO.	25220067.00		DRAWN BY:	BSS		SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	FIGURE
	DRAWN:	12/02/2019		CHECKED BY:	MDB			1
REVISED:	01/10/2020	APPROVED BY:	TK 04/10/2020					




LEGEND	
	EXISTING MAJOR CONTOUR (10' INTERVAL)
	EXISTING MINOR CONTOUR (2' CONTOUR)
	EXISTING FENCE LINE
	EXISTING TRACKS
	EXISTING PAVED ROAD
	EXISTING UNPAVED ROAD
	EDGE OF WATER
	APPROVED LIMITS OF WASTE (DRY ASH LANDFILL)
	CONSTRUCTED LIMITS OF WASTE (DRY ASH LANDFILL)
	WATER SUPPLY WELL
	STAFF GAUGE
	WATER TABLE WELL
	PIEZOMETER
	SURFACE WATER SAMPLE LOCATION
	LYSIMETER
	ABANDONED WATER TABLE WELL
	ABANDONED PIEZOMETER
	LEACHATE HEADWELL
	CCR UNIT
	CCR MONITORING WELL
	CCR BACKGROUND MONITORING WELL



- NOTES:
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, AND MAY 2019.
 2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
 3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
 4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
 5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
 6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
 7. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.


PROJECT NO. 25221067.00	DRAWN BY: KP	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULE 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	FIGURE 2
DRAWN: 06/29/2021	CHECKED BY: NDK				
REVISED: 12/21/2021	APPROVED BY: TK 12/22/2021				



- LEGEND**
- (solid line) EXISTING MAJOR CONTOUR (10' INTERVAL)
 - (dashed line) EXISTING MINOR CONTOUR (2' CONTOUR)
 - x - x - (dashed line) EXISTING FENCE LINE
 - ||||| (dashed line) EXISTING TRACKS
 - ==== (dashed line) EXISTING PAVED ROAD
 - (dashed line) EXISTING UNPAVED ROAD
 - - - - (dashed line) EDGE OF WATER
 - (dashed line) APPROVED LIMITS OF WASTE (DRY ASH LANDFILL)
 - · — (dashed line) CONSTRUCTED LIMITS OF WASTE (DRY ASH LANDFILL)
 - ⊕ (circle with dot) WATER SUPPLY WELL
 - ⊖ (circle with horizontal line) STAFF GAUGE
 - ⊙ (circle with dot) WATER TABLE WELL
 - ⊗ (circle with dot) PIEZOMETER
 - ⊗ (circle with cross) SURFACE WATER SAMPLE LOCATION
 - ⊠ (square with cross) LYSIMETER
 - ⊖ (circle with horizontal line) ABANDONED WATER TABLE WELL
 - ⊗ (circle with dot) ABANDONED PIEZOMETER
 - ⚡ (lightning bolt) LEACHATE HEADWELL
 - (solid line) CCR UNIT
 - ⊕ (circle with dot) CCR MONITORING WELL
 - ⊙ (circle with dot) CCR BACKGROUND MONITORING WELL
 - 787.62 (text) WATER TABLE ELEVATION
 - [788.87] (text) POTENTIOMETRIC SURFACE ELEVATION (NOT CONTOURED)
 - (795.20) (text) SURFACE WATER ELEVATION (NOT CONTOURED)
 - (solid line) WATER TABLE CONTOUR
 - (arrow) APPROXIMATE GROUNDWATER FLOW DIRECTION

- NOTES:**
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, AND MAY 2019.
 2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
 3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
 4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
 5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
 6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
 7. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON APRIL 12-14, 2021.
 8. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.


PROJECT NO. 25221067.00	DRAWN BY: KP	<p>SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830</p>	<p>CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954</p>	<p>SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULE 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI</p>	<p>FIGURE 3</p>
DRAWN: 06/29/2021	CHECKED BY: NDK				
REVISED: 12/27/2021	APPROVED BY: TK 12/27/2021				



LEGEND	
	EXISTING MAJOR CONTOUR (10' INTERVAL)
	EXISTING MINOR CONTOUR (2' CONTOUR)
	EXISTING FENCE LINE
	EXISTING TRACKS
	EXISTING PAVED ROAD
	EXISTING UNPAVED ROAD
	EDGE OF WATER
	APPROVED LIMITS OF WASTE (DRY ASH LANDFILL)
	CONSTRUCTED LIMITS OF WASTE (DRY ASH LANDFILL)
	WATER SUPPLY WELL
	STAFF GAUGE
	WATER TABLE WELL
	PIEZOMETER
	SURFACE WATER SAMPLE LOCATION
	LYSIMETER
	ABANDONED WATER TABLE WELL
	ABANDONED PIEZOMETER
	LEACHATE HEADWELL
	CCR UNIT
	CCR MONITORING WELL
	CCR BACKGROUND MONITORING WELL
787.62	WATER TABLE ELEVATION
[788.87]	POTENTIOMETRIC SURFACE ELEVATION (NOT CONTOURED)
(795.20)	SURFACE WATER ELEVATION (NOT CONTOURED)
	WATER TABLE CONTOUR
	APPROXIMATE GROUNDWATER FLOW DIRECTION

- NOTES:
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, AND MAY 2019.
 2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
 3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
 4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
 5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
 6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
 7. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON OCTOBER 11-14, 2021.
 8. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.

PROJECT NO. 25221067.00	DRAWN BY: KP	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULE 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	WATER TABLE MAP OCTOBER 2021	FIGURE
DRAWN: 10/26/2021	CHECKED BY: NDK					4
REVISED: 12/27/2021	APPROVED BY: TK 12/27/2021					



Appendix A
Regional Hydrogeologic Information

**Table COL-3. Regional Hydrogeologic Stratigraphy
Columbia Energy Center / SCS Engineers Project #25215053**



Approximate Age	Hydrogeologic Unit	General Thickness (feet)	Name of Rock Unit*	Predominant Lithology
Quaternary (0-1 million years old)	Surficial Aquifer	0 to 300+	Holocene & Pleistocene Deposits	<ul style="list-style-type: none"> • Unconsolidated clay, silt, sand, gravel, cobbles, boulders, and organic matter
Ordovician (460 to 490 million years old)	Sandstone Aquifer	0 to 800+	Galena Decorah Platteville St. Peter Prairie du Chien	<ul style="list-style-type: none"> • Dolomite and shaley dolomite • Sandstone
Cambrian (490 to 500 million years old)			Trempeleau Franconia Galesville Eau Claire Mt. Simon	<ul style="list-style-type: none"> • Sandstone
Precambrian (more than 1 billion years old)	Used for domestic supply in some areas	--	Precambrian	<ul style="list-style-type: none"> • Igneous and metamorphic rocks

*This nomenclature and classification of rock units in this report are those of the Wisconsin Geological and Natural History Survey and do not necessarily coincide with those accepted by the U.S. Geological Survey.

Sources:

Harr, C.A., L.C. Trotta, and R.G. Borman, "Ground-Water Resources and Geology of Columbia County, Wisconsin," University of Wisconsin-Extension Geological and Natural History Survey Information Circular Number 37, 1978.
Wisconsin Geological and Natural History Survey, Bedrock Stratigraphic Units in Wisconsin, UW Extension Educational Series 51, ISSN: 1052-2115, 2011.

I:\25215053\Reports\Report 3 - Columbia\Tables\Table_2_Regional_Hydrogeologic_Stratigraphy.doc



EXPLANATION


Probable well yields



Boundary of saturated sand-and-gravel aquifer

Figure 9. Probably well yields from the sand-and-gravel aquifer.

Generalized water-table elevation in Columbia County, Wisconsin



Appendix B


Boring Logs and Well Construction Documentation

Route To: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name WPL-Columbia		License/Permit/Monitoring Number SCS#: 25215135.00		Boring Number MW-301	
Boring Drilled By: Name of crew chief (first, last) and Firm Kevin Durst Badger State Drilling			Date Drilling Started 11/11/2015	Date Drilling Completed 11/11/2015	Drilling Method hollow stem auger
WI Unique Well No. VY701	DNR Well ID No.	Common Well Name	Final Static Water Level Feet	Surface Elevation 803.69 Feet	Borehole Diameter 8.5 in.
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/>			Local Grid Location		
State Plane 541562.2 N, 2025001.0 E		S/C/N		<input type="checkbox"/> N <input type="checkbox"/> E	
1/4 of		1/4 of Section 27, T 12 N, R 9 E		Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W	
Facility ID		County Columbia	County Code 11	Civil Town/City/ or Village Portage	

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments				
									Pocket Penetration (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200					
S1	21	7 6 9 10	1 2	SILTY SAND, yellowish brown (10YR 5/6), fine to medium grained.														
S2	20	6 7 9 10	3 4	Same as above except, 10YR 5/4 (top section), 10YR 3/6 (bottom section), trace gravel.														
S3	22	7 6 9 6	5 6	Same as above except, 10YR 3/4 (bottom), 10YR 5/4 (top), trace little roots and sticks, trace gravel.	SM													
S4	21	4 5 6 5	7 8	Same as above except, 10YR (top), 10YR 4/6 (bottom), trace clay at bottom.														
S5	18	2 2 4 5	9 10	Same as above except, fine to coarse grained sand, little gravel, trace clay in top half, 10YR 3/6.														
S6	20	2 3 3 3	11 12	Same as above except, 10YR 6/8.														

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature 	Firm SCS Engineers 2830 Dairy Drive Madison, WI 53711	Tel: (608) 224-2830 Fax:
--------------------------------------------------------------------------------------------------	-----------------------------------------------------------------	-----------------------------

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name WPL-Columbia		SCS#: 25215135.00		License/Permit/Monitoring Number	Boring Number MW-302
Boring Drilled By: Name of crew chief (first, last) and Firm Kevin Durst Badger State Drilling			Date Drilling Started 11/11/2015	Date Drilling Completed 11/12/2015	Drilling Method hollow stem auger
WI Unique Well No. VY702	DNR Well ID No.	Common Well Name	Final Static Water Level Feet	Surface Elevation 809.93 Feet	Borehole Diameter 8.5 in.
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/> State Pla 541964.7 N, 2123849 E S/C/N			Lat _____ "	Local Grid Location <input type="checkbox"/> N <input type="checkbox"/> E <input type="checkbox"/> S <input type="checkbox"/> W	
1/4 of _____		1/4 of Section 27 , T 12 N, R 9 E	Long _____ "		Feet <input type="checkbox"/> Feet <input type="checkbox"/> W
Facility ID	County Columbia	County Code 11	Civil Town/City/ or Village Portage		

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments		
									Pocket Penetration (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200			
S1	12	10 13 17 16	1 2	SILTY SAND, fine to medium grained, trace gravel, 10YR 5/6.												
S2	12	10 12 8 6	4 5	Same as above except, large gravel at bottom, trace to little gravel.												
S3	20	2 4 4 5	7	Same as above except, 10YR 4/6.	SM											
S4	23	3 3 4 5	9	Same as above except, 10YR 5/8.												
S5	20	3 3 3 4	12	Same as above except, 10YR 6/6.												
S6	20	3 4 4 7	14	POORLY GRADED SAND, 10YR 6/6.	SP											

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature <i>[Signature]</i> for Zach Watson	Firm SCS Engineers 2830 Dairy Drive Madison, WI 53711	Tel: (608) 224-2830 Fax:
-------------------------------------------------	--------------------------------------------------------------------	-----------------------------


This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Route To: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name Alliant Energy - Columbia		License/Permit/Monitoring Number 03025		Boring Number MW-33AR	
Boring Drilled By: Name of crew chief (first, last) and Firm Ryan Fisher Boart Longyear		Date Drilling Started 4/9/2003		Date Drilling Completed 4/9/2003	
Drilling Method 4 1/4" HSA		WI Unique Well No. PE223		DNR Well ID No. 138	
Common Well Name MW-33AR		Final Static Water Level Feet MSL		Surface Elevation 805.4 Feet MSL	
Borehole Diameter 8.0 inches		Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/>		Local Grid Location	
State Plane 542,663 N, 2,123,584 E S/C/N		Lat _____ "		<input type="checkbox"/> N <input type="checkbox"/> E	
NE 1/4 of SW 1/4 of Section 27, T 12 N, R 9 E		Long _____ "		<input type="checkbox"/> S <input type="checkbox"/> W	
Facility ID 111049180		County Columbia		County Code 11	
				Civil Town/City/ or Village Pacific	

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties						RQD/ Comments
									Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200		
			2.5 5.0 7.5 10.0 12.5 15.0 17.5 20.0 22.5 25.0 27.5	Blind drilled to 29 feet. See log of MW-33BR for lithology.	SM										
				End of boring at 29 feet.											

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature  Firm **RMT, Inc.**


Tel:
Fax:

Route To: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name Alliant Energy - Columbia		License/Permit/Monitoring Number 03025		Boring Number MW-33BR	
Boring Drilled By: Name of crew chief (first, last) and Firm Ryan Fisher Boart Longyear		Date Drilling Started 4/8/2003		Date Drilling Completed 4/9/2003	
WI Unique Well No. PE224		DNR Well ID No. 140		Common Well Name MW-33BR	
Final Static Water Level 785.3 Feet MSL		Surface Elevation 805.3 Feet MSL		Borehole Diameter 8.0 inches	
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Boring Location <input checked="" type="checkbox"/>		State Plane 542,660 N, 2,123,585 E S/C/N		Local Grid Location	
NE 1/4 of SW 1/4 of Section 27, T 12 N, R 9 E		Lat _____ "		<input type="checkbox"/> N <input type="checkbox"/> E	
		Long _____ "		Feet <input type="checkbox"/> S <input type="checkbox"/> W	
Facility ID 111049180		County Columbia		County Code 11	
				Civil Town/City/ or Village Pacific	

Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments		
									Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200			
AUGE	60		1													
			2													
			3													
			4													
1 SS	24	4	5	SILTY SAND (SM), 85% fine to medium sand, 15% fines, nonplastic, 10YR 5/4 yellowish brown, no odor, moist.	SM											
		4	6													
		4	7													
		4	8													
		4	9													
2 SS	24	3	10													
		5	11													
		5	12													
			13													
			14													
			15													











I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature  Firm **RMT, Inc.** Tel: _____ Fax: _____

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Boring Number **MW-33BR** Use only as an attachment to Form 4400-122.

Page 2 of 3

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Alt. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	
3 SS	24	4	15											
		5	16											
		4	17											
		5	18											
4 SS	24	4	20	Same as above, but wet.	SM									
		3	21											
		4	22											
		4	23											
5 SS	24	50/0	25	Hit a rock, auger through.										
			26											
			27											
			28											
6 SS	24	8	30	SILTY SAND WITH GRAVEL (SM), 70% fine to medium sand, 15% gravel, 15% fines, nonplastic, 10YR 4/3 brown, wet, dense.										
		20	31											
		19	32											
		27	33											
7 SS	24	10	35		SM									
		17	36											
		19	37											
		24	38											
			39											
			40											

Boring Number **MW-33BR** Use only as an attachment to Form 4400-122.

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Att. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	
8 SS	24	18 20 28 39	18 20 28 39 41 42 43 44	Same as above.										
9 SS	24	27 50/2	45 46 47 48 49 50 51		SM									
10 SS	24	7 50/1	52 53 54 55 56	WEATHERED SANDSTONE, 95% poorly graded medium sand, 5% fines, white to brown, well sorted and rounded, poorly cemented.										
			56	End of boring at 56 feet.										

Route To: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

MONITORING WELL CONSTRUCTION
Form 4400-113A Rev. 7-98

Facility/Project Name Alliant Energy - Columbia	Local Grid Location of Well ft. <input type="checkbox"/> N. <input type="checkbox"/> S. <input type="checkbox"/> E. <input type="checkbox"/> W.	Well Name MW-33AR
Facility License, Permit or Monitoring No. 03025	Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/>) or Well Location <input checked="" type="checkbox"/> Lat. _____ Long. _____ or	Wis. Unique Well No. PE223 DNR Well Number 138
Facility ID 111049180	St. Plane 542,663 ft. N, 2,123,584 ft. E. S/C/N	Date Well Installed 04/09/2003
Type of Well Well Code 71/dw	Section Location of Waste/Source NE 1/4 of SW 1/4 of Sec. 27, T. 12 N, R. 9 E W	Well Installed By: (Person's Name and Firm) R. Fischer
Distance from Waste/Source 500 ft. Enf. Stds. Apply <input type="checkbox"/>	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input checked="" type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	Gov. Lot Number Boart Longyear

A. Protective pipe, top elevation 808.09 ft. MSL
 B. Well casing, top elevation 808.29 ft. MSL
 C. Land surface elevation 805.4 ft. MSL
 D. Surface seal, bottom 804.4 ft. MSL or 1.0 ft.

12. USCS classification of soil near screen:
 GP GM GC GW SW SP
 SM SC ML MH CL CH
 Bedrock


13. Sieve analysis attached? Yes No

14. Drilling method used: Rotary 5 0
 Hollow Stem Auger 4 1
 Other

15. Drilling fluid used: Water 0 2 Air 0 1
 Drilling Mud 0 3 None 9 9

16. Drilling additives used? Yes No
 Describe _____

17. Source of water (attach analysis, if required):



1. Cap and lock? Yes No

2. Protective cover pipe:
 a. Inside diameter: 4.0 in.
 b. Length: 7.0 ft.
 c. Material: Steel 0 4
 Other

d. Additional protection? Yes No
 If yes, describe: _____

3. Surface seal: Bentonite 3 0
 Concrete 0 1
 Other

4. Material between well casing and protective pipe: Bentonite 3 0
 Other

5. Annular space seal: a. Granular/Chipped Bentonite 3 3
 b. _____ Lbs/gal mud weight . . . Bentonite-sand slurry 3 5
 c. 10.5 Lbs/gal mud weight . . . Bentonite slurry 3 1
 d. _____ % Bentonite . . . Bentonite-cement grout 5 0
 e. 3.5 Ft³ volume added for any of the above
 f. How installed: Tremie 0 1
 Tremie pumped 0 2
 Gravity 0 8

6. Bentonite seal: a. Bentonite granules 3 3
 b. 1/4 in. 3/8 in. 1/2 in. Bentonite chips 3 2
 c. _____ Other

7. Fine sand material: Manufacturer, product name & mesh size
 a. #7 Badger
 b. Volume added 0.5 ft³

8. Filter pack material: Manufacturer, product name & mesh size
 a. #40 Badger
 b. Volume added 4.5 ft³

9. Well casing: Flush threaded PVC schedule 40 2 3
 Flush threaded PVC schedule 80 2 4
 Other

10. Screen material: PVC
 a. Screen Type: Factory cut 1 1
 Continuous slot 0 1
 Other
 b. Manufacturer Boart Longyear
 c. Slot size: 0.010 in.
 d. Slotted length: 10.0 ft.

11. Backfill material (below filter pack): None 1 4
 Other

E. Bentonite seal, top 794.4 ft. MSL or 11.0 ft.
 F. Fine sand, top 789.4 ft. MSL or 16.0 ft.
 G. Filter pack, top 788.4 ft. MSL or 17.0 ft.
 H. Screen joint, top 787.4 ft. MSL or 18.0 ft.
 I. Well bottom 777.4 ft. MSL or 28.0 ft.
 J. Filter pack, bottom 776.4 ft. MSL or 29.0 ft.
 K. Borehole, bottom 776.4 ft. MSL or 29.0 ft.
 L. Borehole, diameter 8.0 in.
 M. O.D. well casing 2.37 in.
 N. I.D. well casing 2.06 in.

I hereby certify that the information on this form is true and correct to the best of my knowledge.
 Signature R. M. Ch Firm RMT, Inc. Tel: _____ Fax: _____

Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.

WARZYN



ENGINEERING INC

LOG OF TEST BORING

Project Wisconsin Power & Light

Location Columbia Generating Station

Boring No. MW-84A

Surface Elevation 813.4

Job No. C 7134

Sheet 1 of 1

1409 EMIL STREET • P.O. BOX 9538, MADISON, WIS. 53715 • TEL. (608) 257-4848

SAMPLE						VISUAL CLASSIFICATION and Remarks	SOIL PROPERTIES				
No.	Type	Recovery		Moisture			q _c	W	LL	PL	D
		↓	↓	N	Depth						
						Dark Brown Silty SAND (SM)					
					5	Brown Fine to Medium SAND, Little Silt, Trace to Little Gravel and Boulders (SM)					
					10						
					15						
					20						
					25						
					30						
					35						
					40						
							End Boring at 37'				
							Well Installed at 37'				

WATER LEVEL OBSERVATIONS

While Drilling _____

Upon Completion of Drilling _____

Time After Drilling _____

Depth to Water _____

Depth to Cave In _____

GENERAL NOTES

Start 10/5/83 Complete 10/5/83

Crew Chief JVS Rig B-40

Drilling Method ED 0-37'

Route To: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name Alliant Energy - Columbia	County Columbia	Well Name MW-33AR	
Facility License, Permit or Monitoring Number 03025	County Code 11	Wis. Unique Well Number PE223	DNR Well Number 138

1. Can this well be purged dry? Yes No

2. Well development method:
- surged with bailer and bailed 4 1
 - surged with bailer and pumped 6 1
 - surged with block and bailed 4 2
 - surged with block and pumped 6 2
 - surged with block, bailed, and pumped 7 0
 - compressed air 2 0
 - bailed only 1 0
 - pumped only 5 1
 - pumped slowly 5 0
 - other _____ _____

3. Time spent developing well **60 min.**

4. Depth of well (from top of well casing) **31.3 ft.**

5. Inside diameter of well **2.06 in.**

6. Volume of water in filter pack and well casing **6.0 gal.**

7. Volume of water removed from well **35.0 gal.**

8. Volume of water added (if any) **0.0 gal.**

9. Source of water added _____

10. Analysis performed on water added? Yes No
(If yes, attach results)

17. Additional comments on development:
Pumped dry 3 times.

	Before Development	After Development
11. Depth to Water (from top of well casing)	a. 23.47 ft.	23.62 ft.
Date	b. 4/10/2003	4/10/2003
Time	c. 08:50 <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.	11:50 <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.
12. Sediment in well bottom	0.0 inches	0.0 inches
13. Water clarity (Describe)	Clear <input type="checkbox"/> 1 0 Opaque, brown	Clear <input type="checkbox"/> 2 0 Slight, tan

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids **72 mg/l**

15. COD **mg/l**

16. Well developed by: Person's Name and Firm

Peter M. Chase
RMT, Inc.

Facility Address or Owner/Responsible Party Address

Name: **Peter M. Chase**

Firm: **RMT, Inc.**

Street: **744 Heartland Tr.**

City/State/Zip: **Madison, WI 53717**

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: 

Print Name: **Peter M. Chase**

Firm: **RMT, Inc.**

NOTE: See instructions for more information including a list of county codes and well type codes.

SUBSTATION

ASH POND
DISCHARGE
DRAINAGE DITCH
ERR
B# 34A&B

medium to
coarse sand
and gravel

fill-
fine to
medium
sand

fine to
medium
sand

dstone

Scale:

Horizontal 1" = 100'


Vertical 1" = 10'

No legend available

Warzyn Engineering Inc.
Geologic Cross Sections

Drawing No. C7134-11

Date 1-20-78



TYPICAL MONITORING WELL DETAIL

NOT TO SCALE

Date - 1-20-78 Drawing No. 7134-9
 Warzyn Engineering Inc.

WELL DETAIL INFORMATION SHEET

JOB NO. C 7134


BORING NO. MW-84A

DATE 10/5/83

Elev. 814.57 Steel
Elev. 814.32 PVC CHIEF JS

LOCATION WP&L-Columbia Generating Station

Elev. 813.4
All depth measurements of well detail assumed to be from ground surface unless otherwise indicated.



- ① DEPTH TO BOTTOM OF BOREHOLE
37 FEET
- ② LENGTH OF WELL POINT, WELL SCREEN,
OR SLOTTED PIPE 10 FEET
- ③ TOTAL LENGTH OF SOLID PIPE 29
FEET @ 2 IN. DIAMETER
- ④ HEIGHT OF WELL CASING ABOVE GROUND
2 FEET
- ⑤ TYPE OF FILTER MATERIAL AROUND WELL
POINT OR SLOTTED PIPE Flint Sand
- ⑥ DEPTH OF LOWER OR BOTTOM SEAL
3 FEET
- ⑦ DEPTH OF UPPER OR TOP SEAL
0 FEET
- ⑧ TYPE OF BACKFILL Spoils (Sand)
- ⑨ PROTECTIVE CASING YES NO
HEIGHT ABOVE GROUND 2'
LOCKING CAP YES NO
- ⑩ CONCRETE CAP YES NO

WATER LEVEL CHECKS

* From top of casing, if protective casing higher take measurement from top of protective casing.

BORING #	DATE	TIME	DEPTH TO WATER	REMARKS
84A	10/7/83	3 days	21'	
84B	10/7/83	3 days	19'6"	



Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name Alliant-Columbia	County Name Columbia	Well Name MW-301	
Facility License, Permit or Monitoring Number	County Code 11	Wis. Unique Well Number VY701	DNR Well ID Number

1. Can this well be purged dry? Yes No

2. Well development method
- surged with bailer and bailed 4 1
 - surged with bailer and pumped 6 1
 - surged with block and bailed 4 2
 - surged with block and pumped 6 2
 - surged with block, bailed and pumped 7 0
 - compressed air 2 0
 - bailed only 1 0
 - pumped only 5 1
 - pumped slowly 5 0
 - Other

3. Time spent developing well _____ 120 min.

4. Depth of well (from top of well casing) _____ 29 . 4 ft.

5. Inside diameter of well _____ 2 . 00 in.

6. Volume of water in filter pack and well casing _____ 7 . 6 gal.

7. Volume of water removed from well _____ 84 . 0 gal.

8. Volume of water added (if any) _____ gal.

9. Source of water added _____

10. Analysis performed on water added? Yes No
(If yes, attach results)

17. Additional comments on development:

	Before Development	After Development
11. Depth to Water (from top of well casing)	a. _____ 21 . 72 ft.	_____ 21 . 77 ft.
Date	b. <u>12</u> / <u>02</u> / <u>2015</u>	<u>12</u> / <u>02</u> / <u>2015</u>
	m m d d y y y y	m m d d y y y y
Time	c. _____ 08 : 30 <input checked="" type="checkbox"/> a.m. _____ 10 : 30 <input checked="" type="checkbox"/> a.m.	_____ p.m. _____ p.m.
12. Sediment in well bottom	_____ 0 . inches	_____ 0 . inches
13. Water clarity	Clear <input type="checkbox"/> 1 0 Turbid <input checked="" type="checkbox"/> 1 5 (Describe)	Clear <input checked="" type="checkbox"/> 2 0 Turbid <input type="checkbox"/> 2 5 (Describe)

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids _____ mg/l _____ mg/l

15. COD _____ mg/l _____ mg/l

16. Well developed by: Name (first, last) and Firm
First Name: Gary Last Name: Sterkel
Firm: SCS ENGINEERS

Name and Address of Facility Contact /Owner/Responsible Party

First Name: Nate Last Name: Sievers

Facility/Firm: Wisconsin Power and Light

Street: W8375 Murray Rd.

City/State/Zip: Pardeville, WI 53954

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: *[Handwritten Signature]* for Gary Sterkel

Print Name: Gary Sterkel

Firm: SCS ENGINEERS

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

Facility/Project Name Alliant - Columbia	County Name Columbia	Well Name MW-302	
Facility License, Permit or Monitoring Number	County Code 11	Wis. Unique Well Number VY702	DNR Well ID Number

1. Can this well be purged dry? Yes No

2. Well development method
- surged with bailer and bailed 4 1
 - surged with bailer and pumped 6 1
 - surged with block and bailed 4 2
 - surged with block and pumped 6 2
 - surged with block, bailed and pumped 7 0
 - compressed air 2 0
 - bailed only 1 0
 - pumped only 5 1
 - pumped slowly 5 0
 - Other

3. Time spent developing well _____ 120 min.

4. Depth of well (from top of well casing) _____ 33.6 ft.

5. Inside diameter of well _____ 2.00 in.

6. Volume of water in filter pack and well casing _____ 5.4 gal.

7. Volume of water removed from well _____ 60.0 gal.

8. Volume of water added (if any) _____ gal.

9. Source of water added _____

10. Analysis performed on water added? Yes No
(If yes, attach results)

17. Additional comments on development:

	Before Development	After Development
11. Depth to Water (from top of well casing)	a. _____ 28 _____ 37 ft.	_____ 28 _____ 41 ft.
Date	b. <u>12</u> / <u>02</u> / <u>2015</u>	<u>12</u> / <u>02</u> / <u>2015</u>
Time	c. <u>02</u> : <u>00</u> <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.	<u>04</u> : <u>00</u> <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.
12. Sediment in well bottom	_____ 0 _____ inches	_____ 0 _____ inches
13. Water clarity	Clear <input type="checkbox"/> 1 0 Turbid <input checked="" type="checkbox"/> 1 5 (Describe)	Clear <input checked="" type="checkbox"/> 2 0 Turbid <input type="checkbox"/> 2 5 (Describe)

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids _____ mg/l _____ mg/l

15. COD _____ mg/l _____ mg/l

16. Well developed by: Name (first, last) and Firm
First Name: Gary Last Name: Sterkel
Firm: SCS ENGINEERS

Name and Address of Facility Contact/Owner/Responsible Party

First Name: Nate Last Name: Sievers

Facility/Firm: Wisconsin Power and Light

Street: W8375 Murray Rd.

City/State/Zip: Pardeeville, WI 53954

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: *[Handwritten Signature]* for G.S.

Print Name: Gary Sterkel

Firm: SCS ENGINEERS

State of Wisconsin
Department of Natural Resources

Route to: Watershed/Wastewater Waste Management
Remediation/Redevelopment Other

MONITORING WELL CONSTRUCTION
Form 4400-113A Rev. 7-98

Facility/Project Name WPL-Columbia	Local Grid Location of Well ft. <input type="checkbox"/> N. <input type="checkbox"/> S. <input type="checkbox"/> E. <input type="checkbox"/> W.	Well Name MW-301
Facility License, Permit or Monitoring No.	Local Grid Origin (estimated: <input type="checkbox"/>) or Well Location ft. <input type="checkbox"/> N. <input type="checkbox"/> S. <input type="checkbox"/> E. <input type="checkbox"/> W.	Wis. Unique Well No. <input type="checkbox"/> DNR Well ID No. <input type="checkbox"/>
Facility ID	St. Plane 541562.2 ft. N., 2125001 ft. E. S/C/N	Date Well Installed 11 / 11 / 2015 m m d d y y y y
Type of Well Well Code 11 / MW	Section Location of Waste/Source SW 1/4 of SE 1/4 of Sec. 27, T. 12 N, R. 9 <input checked="" type="checkbox"/> E <input type="checkbox"/> W	Well Installed By: Name (first, last) and Firm Kevin Duerst Badger State Drilling
Distance from Waste/Source ft. <input type="checkbox"/> Enf. Stds. Apply <input type="checkbox"/>	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	

- A. Protective pipe, top elevation -- 807.16 ft. MSL
- B. Well casing, top elevation -- 806.89 ft. MSL
- C. Land surface elevation -- 803.69 ft. MSL
- D. Surface seal, bottom -- 791.69 ft. MSL or -- 12 ft.

12. USCS classification of soil near screen:
 GP GM GC GW SP
 SM SC ML MH CL CH
 Bedrock

13. Sieve analysis performed? Yes No


14. Drilling method used: Rotary 50
 Hollow Stem Auger 41
 Other

15. Drilling fluid used: Water 02 Air 01
 Drilling Mud 03 None 99

16. Drilling additives used? Yes No

Describe _____

17. Source of water (attach analysis, if required): _____



- 1. Cap and lock? Yes No
- 2. Protective cover pipe:
 - a. Inside diameter: 6 in.
 - b. Length: 5 ft.
 - c. Material: Steel 04
Other
 - d. Additional protection? Yes No
If yes, describe: bumper posts
- 3. Surface seal: Bentonite 30
Concrete 01
Other
- 4. Material between well casing and protective pipe: Bentonite 30
Bentonite to grade, sand above Other
- 5. Annular space seal:
 - a. Granular/Chipped Bentonite 33
 - b. ___ Lbs/gal mud weight . . . Bentonite-sand slurry 35
 - c. ___ Lbs/gal mud weight Bentonite slurry 31
 - d. ___ % Bentonite Bentonite-cement grout 50
 - e. ___ Ft³ volume added for any of the above
 - f. How installed: Tremie 01
Tremie pumped 02
Gravity 08
- 6. Bentonite seal:
 - a. Bentonite granules 33
 - b. 1/4 in. 3/8 in. 1/2 in. Bentonite chips 32
 - c. 4 ft³ Other
- 7. Fine sand material: Manufacturer, product name & mesh size
a. RW Sidley Inc. #7
- b. Volume added 0.5 ft³
- 8. Filter pack material: Manufacturer, product name & mesh size
a. RW Sidley #5
- b. Volume added 2 ft³
- 9. Well casing: Flush threaded PVC schedule 40 23
Flush threaded PVC schedule 80 24
Other
- 10. Screen material: PVC
a. Screen type: Factory cut 11
Continuous slot 01
Other
- b. Manufacturer Johnson
- c. Slot size: 0.01 in.
- d. Slotted length: 10 ft.
- 11. Backfill material (below filter pack): None 14
Native

- E. Bentonite seal, top -- 803.69 ft. MSL or -- 0 ft.
- F. Fine sand, top -- 791.69 ft. MSL or -- 12 ft.
- G. Filter pack, top -- 789.69 ft. MSL or -- 14 ft.
- H. Screen joint, top -- 787.69 ft. MSL or -- 16 ft.
- I. Well bottom -- 777.69 ft. MSL or -- 26 ft.
- J. Filter pack, bottom -- 776.69 ft. MSL or -- 27 ft.
- K. Borehole, bottom -- 775.69 ft. MSL or -- 28 ft.
- L. Borehole, diameter -- 8.5 in.
- M. O.D. well casing -- 2.4 in.
- N. I.D. well casing -- 2.0 in.

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature *[Signature]* Firm SCS ENGINEERS, 2830 Dairy Drive, Madison, WI 53718-6751


Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.

State of Wisconsin
Department of Natural Resources

Route to: Watershed/Wastewater Waste Management
 Remediation/Redevelopment Other

MONITORING WELL CONSTRUCTION
Form 4400-113A Rev. 7-98

Facility/Project Name WPL-Columbia	Local Grid Location of Well ft. <input type="checkbox"/> N. <input type="checkbox"/> S. <input type="checkbox"/> E. <input type="checkbox"/> W.	Well Name MW-302
Facility License, Permit or Monitoring No.	Local Grid Origin (estimated: <input type="checkbox"/>) or Well Location Lat. _____ " Long. _____ or _____	Wis. Unique Well No. <input type="checkbox"/> DNR Well ID No. <input type="checkbox"/>
Facility ID	St. Plane: 541964.7 ft. N, 2123849 ft. E. S/C/N	Date Well Installed 11 / 12 / 2015 m m d d y y y y
Type of Well Well Code 11 / MW	Section Location of Waste/Source SE 1/4 of SW 1/4 of Sec. 27, T. 12 N, R. 9 <input checked="" type="checkbox"/> E <input type="checkbox"/> W	Well Installed By: Name (first, last) and Firm Kevin Duerst
Distance from Waste/Source _____ ft.	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	Gov. Lot Number _____
Enf. Stds. Apply <input type="checkbox"/>		Badger State Drilling

<p>A. Protective pipe, top elevation -- 813.19 ft. MSL</p> <p>B. Well casing, top elevation -- 813.00 ft. MSL</p> <p>C. Land surface elevation -- 809.93 ft. MSL</p> <p>D. Surface seal, bottom -- 793.53 ft. MSL or -- 16.4 ft.</p> <div style="border: 1px solid black; padding: 5px;"> <p>12. USCS classification of soil near screen: GP <input type="checkbox"/> GM <input type="checkbox"/> GC <input type="checkbox"/> GW <input type="checkbox"/> SW <input type="checkbox"/> SP <input checked="" type="checkbox"/> SM <input type="checkbox"/> SC <input type="checkbox"/> ML <input type="checkbox"/> MH <input type="checkbox"/> CL <input type="checkbox"/> CH <input type="checkbox"/> Bedrock <input type="checkbox"/></p> <p>13. Sieve analysis performed? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>14. Drilling method used: Rotary <input type="checkbox"/> 50 Hollow Stem Auger <input checked="" type="checkbox"/> 41 Other <input type="checkbox"/></p> <p>15. Drilling fluid used: Water <input type="checkbox"/> 02 Air <input type="checkbox"/> 01 Drilling Mud <input type="checkbox"/> 03 None <input checked="" type="checkbox"/> 99</p> <p>16. Drilling additives used? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>Describe _____</p> <p>17. Source of water (attach analysis, if required): _____</p> </div> <p>E. Bentonite seal, top -- 809.93 ft. MSL or -- 0 ft.</p> <p>F. Fine sand, top -- 793.53 ft. MSL or -- 16.4 ft.</p> <p>G. Filter pack, top -- 791.53 ft. MSL or -- 18.4 ft.</p> <p>H. Screen joint, top -- 789.53 ft. MSL or -- 20.4 ft.</p> <p>I. Well bottom -- 779.53 ft. MSL or -- 30.4 ft.</p> <p>J. Filter pack, bottom -- 776.93 ft. MSL or -- 33 ft.</p> <p>K. Borehole, bottom -- 776.93 ft. MSL or -- 33 ft.</p> <p>L. Borehole, diameter -- 8.5 in.</p> <p>M. O.D. well casing -- 2 3/8 in.</p> <p>N. I.D. well casing -- 2 in.</p>	 <p>1. Cap and lock? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>2. Protective cover pipe: a. Inside diameter: -- 6 in. b. Length: -- 5 ft. c. Material: Steel <input type="checkbox"/> 04 Other <input type="checkbox"/> d. Additional protection? <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, describe: yes bumper posts</p> <p>3. Surface seal: Bentonite <input checked="" type="checkbox"/> 30 Concrete <input type="checkbox"/> 01 Other <input type="checkbox"/></p> <p>4. Material between well casing and protective pipe: Bentonite <input checked="" type="checkbox"/> 30 Bentonite to grade, sand above Other <input type="checkbox"/></p> <p>5. Annular space seal: a. Granular/Chipped Bentonite <input type="checkbox"/> 33 b. _____ Lbs/gal mud weight . . . Bentonite-sand slurry <input type="checkbox"/> 35 c. _____ Lbs/gal mud weight Bentonite slurry <input type="checkbox"/> 31 d. _____ % Bentonite Bentonite-cement grout <input type="checkbox"/> 50 e. _____ Ft³ volume added for any of the above f. How installed: Tremie <input type="checkbox"/> 01 Tremie pumped <input type="checkbox"/> 02 Gravity <input type="checkbox"/> 08</p> <p>6. Bentonite seal: a. Bentonite granules <input type="checkbox"/> 33 b. <input type="checkbox"/> 1/4 in. <input checked="" type="checkbox"/> 3/8 in. <input type="checkbox"/> 1/2 in. Bentonite chips <input type="checkbox"/> 32 c. 4.7 ft³ Other <input type="checkbox"/></p> <p>7. Fine sand material: Manufacturer, product name & mesh size a. RW Sidley Inc. #7 <input type="checkbox"/> b. Volume added 1 ft³</p> <p>8. Filter pack material: Manufacturer, product name & mesh size a. RW Sidley #5 <input type="checkbox"/> b. Volume added 2.5 ft³</p> <p>9. Well casing: Flush threaded PVC schedule 40 <input checked="" type="checkbox"/> 23 Flush threaded PVC schedule 80 <input type="checkbox"/> 24 Other <input type="checkbox"/></p> <p>10. Screen material: PVC a. Screen type: Factory cut <input checked="" type="checkbox"/> 11 Continuous slot <input type="checkbox"/> 01 Other <input type="checkbox"/> b. Manufacturer Johnson c. Slot size: 0.01 in. d. Slotted length: -- 10 ft.</p> <p>11. Backfill material (below filter pack): None <input type="checkbox"/> 14 Native Other <input checked="" type="checkbox"/></p>
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature Kevin Duerst for Zach Watson Firm SCS ENGINEERS, 2830 Dairy Drive, Madison, WI 53718-6751

Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.

830

Warzyn Engineering Inc.

Log of soil borings

Drawing No. C71342

Date 8-26-77

BROWN

B #1
NW #1A

825

820

815

810

805

800

795

790

785

780

1' DARK BROWN SILTY SAND TOPSOIL

Red. brown fine-medium sand, some silt

Brown fine med. sand trace to little silt occasional gravel, occasional uniform medium sand

Light brown fine sand, trace to little silt.

Brown silty-fine medium sand occasional gravel

16

16

40

50

60

70

32

39

60

70

6

58

37

OCCASIONAL SILT

20

17

7

37

28

6.11.78


11.11.78

2.11.78

27.11.78

24.11.78

24.11.78



Facility/Project Name WP&L Columbia - Dry Ash	Local Grid Location of Well _____ ft. <input type="checkbox"/> N. _____ ft. <input type="checkbox"/> E. _____ ft. <input type="checkbox"/> S. _____ ft. <input type="checkbox"/> W.	Well Name MW-1AR
Facility License, Permit or Monitoring Number 03025	Grid Origin Location Lat. _____ Long. _____ or St. Plane <u>542,635</u> ft. N, <u>2,156,555</u> ft. E.	Wis. Unique Well Number _____ DNR Well Number _____
Type of Well: Water Table Observation Well <input checked="" type="checkbox"/> 11 Piezometer <input type="checkbox"/> 12	Section Location of Waste/Source <input checked="" type="checkbox"/> E. SW <input type="checkbox"/> of SE <input type="checkbox"/> of Sec. 27, T12N, R9 <input type="checkbox"/> W.	Date Well Installed <u>11</u> / <u>15</u> / <u>94</u> MM DD YY
Distance Well is From Waste/Source Boundary ft.	Location of Well Relative to Waste/Source U <input type="checkbox"/> Upgradient S <input type="checkbox"/> Sidegradient D <input type="checkbox"/> Downgradient N <input checked="" type="checkbox"/> Not Known	Well Installed By: (Persons' Name and Firm) Frank Badula Environmental & Foundation Drilling, Inc.
Is Well A Point of Enforcement Std. Application? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		

- A. Protective pipe, top elevation 822.47 ft. MSL
 B. Well casing, top elevation 822.55 ft. MSL
 C. Land surface elevation 820.1 ft. MSL
 D. Surface seal, bottom 819.6 ft. MSL or 0.5 ft.

12. USCS classification of soil near screen:
 GP GM GC GW SW SP
 SM SC ML MH CL CH
 Bedrock


13. Sieve analysis attached? Yes No

14. Drilling method used: Rotary 50
 Hollow Stem Auger 41
 Other

15. Drilling fluid used: Water 02 Air 01
 Drilling Mud 03 None 99

16. Drilling additives used? Yes No
 Describe _____

17. Source of water (attach analysis):




1. Cap and lock? Yes No
2. Protective cover pipe:
 a. Inside diameter: 5.0 in.
 b. Length: 7.0 ft.
 c. Material: Flush Mount Steel 04
 Other
 d. Additional protection? Yes No
 If yes, describe: _____
3. Surface seal: Bentonite 30
 Concrete 01
 Other
4. Material between well casing and protective pipe:
 Bentonite 30
 Annular space seal
 Other
5. Annular space seal:
 a. Granular Bentonite 33
 b. Lbs/gal mud weight... Bentonite-sand slurry 35
 c. Lbs/gal mud weight... Bentonite slurry 31
 d. % Bentonite... Bentonite-cement grout 50
 e. 400 lb volume added for any of the above
 f. How installed: Tremie 01
 Tremie pumped 02
 Gravity 08
6. Bentonite seal:
 a. Bentonite granules 33
 b. 1/4 in. 3/8 in. 1/2 in. Bentonite pellets 32
 c. Other
7. Fine sand material: Manufacturer, product name, mesh size
 a. Silica sand
 b. Volume added 50 lb
8. Filter pack material: Manufacturer, product, mesh size
 a. Badger Mining #30
 b. Volume added 250 lb
9. Well casing: Flush threaded PVC schedule 40 23
 Flush threaded PVC schedule 80 24
 Other
10. Screen Material: PVC
 a. Screen type: Factory cut 11
 Continuous slot 01
 Other
 b. Manufacturer Northern Air
 c. Slot size: 0.010 in.
 d. Slotted length: 9.6 ft.
11. Backfill material (below filter pack): None 14
 Other


- E. Bentonite seal, top 800.1 ft. MSL or 20.0 ft.
 F. Fine sand, top 792.1 ft. MSL or 28.0 ft.
 G. Filter pack, top 790.1 ft. MSL or 30.0 ft.
 H. Screen joint, top 788.1 ft. MSL or 32.0 ft.
 I. Well bottom 778.1 ft. MSL or 42.0 ft.
 J. Filter pack, bottom 777.1 ft. MSL or 43.0 ft.
 K. Borehole, bottom 777.1 ft. MSL or 43.0 ft.
 L. Borehole, diameter 8.3 in.
 M. O.D. well casing 2.2 in.
 N. I.D. well casing 2.03 in.

I hereby certify that the information on this form is true and correct to the best of my knowledge.
 Signature [Signature] Firm RMT, Inc.

Please complete both sides of this form and return to the appropriate DNR office listed at the top of this form as required by chs. 144, 147 and 160, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with ch. 144, Wis. Stats., failure to file this form may result in a forfeiture of not less than \$10, nor more than \$5,000 for each day of violation. In accordance with ch. 147, Wis. Stats., failure to file this form may result in a forfeiture of not more than \$10,000 for each day of violation. NOTE: Shaded areas are for DNR use only. See instructions for more information including where the completed form should be sent.



Appendix C
Laboratory Reports



Appendix C1
April 2021 Detection Monitoring

April 30, 2021

Meghan Blodgett
SCS ENGINEERS
2830 Dairy Drive
Madison, WI 53718

RE: Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on April 16, 2021. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky
dan.milewsky@pacelabs.com
(920)469-2436
Project Manager

Enclosures

cc: Tom Karwoski, SCS ENGINEERS
Nicole Kron, SCS ENGINEERS
Jeff Maxted, ALLIANT ENERGY
Marc Morandi, ALLIANT ENERGY



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40225269

Pace Analytical Services Green Bay

1241 Bellevue Street, Green Bay, WI 54302

Florida/NELAP Certification #: E87948

Illinois Certification #: 200050

Kentucky UST Certification #: 82

Louisiana Certification #: 04168

Minnesota Certification #: 055-999-334

New York Certification #: 12064

North Dakota Certification #: R-150

Virginia VELAP ID: 460263

South Carolina Certification #: 83006001

Texas Certification #: T104704529-14-1

Wisconsin Certification #: 405132750

Wisconsin DATCP Certification #: 105-444

USDA Soil Permit #: P330-16-00157

Federal Fish & Wildlife Permit #: LE51774A-0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE SUMMARY

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40225269

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40225269001	MW-1AR	Water	04/14/21 11:00	04/16/21 07:45
40225269002	MW-302	Water	04/13/21 15:10	04/16/21 07:45
40225269003	MW-33AR	Water	04/13/21 12:50	04/16/21 07:45
40225269004	MW-34A	Water	04/13/21 11:05	04/16/21 07:45
40225269005	FIELD BLANK-MOD1-3LF	Water	04/13/21 12:50	04/16/21 07:45

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40225269

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40225269001	MW-1AR	EPA 6020	DS1	2
			VGC	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40225269002	MW-302	EPA 6020	DS1	2
			VGC	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40225269003	MW-33AR	EPA 6020	DS1	2
			VGC	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40225269004	MW-34A	EPA 6020	DS1	2
			VGC	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40225269005	FIELD BLANK-MOD1-3LF	EPA 6020	DS1, KXS	2
			SM 2540C	HNT
		EPA 9040	ALY	1
		EPA 300.0	HMB	3

PASI-G = Pace Analytical Services - Green Bay

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Sample: MW-1AR **Lab ID: 40225269001** Collected: 04/14/21 11:00 Received: 04/16/21 07:45 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay							
Boron	16.1	ug/L	10.0	3.0	1	04/20/21 06:41	04/22/21 21:07	7440-42-8	
Calcium	85500	ug/L	254	76.2	1	04/20/21 06:41	04/22/21 21:07	7440-70-2	
Field Data		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	7.26	Std. Units			1		04/14/21 11:00		
Field Specific Conductance	611.7	umhos/cm			1		04/14/21 11:00		
Oxygen, Dissolved	7.52	mg/L			1		04/14/21 11:00	7782-44-7	
REDOX	100.4	mV			1		04/14/21 11:00		
Turbidity	136.1	NTU			1		04/14/21 11:00		
Static Water Level	778.12	feet			1		04/14/21 11:00		
Temperature, Water (C)	7.2	deg C			1		04/14/21 11:00		
2540C Total Dissolved Solids		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	318	mg/L	20.0	8.7	1		04/20/21 12:34		
9040 pH		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	7.4	Std. Units	0.10	0.010	1		04/19/21 09:56		H6
300.0 IC Anions		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	1.5J	mg/L	2.0	0.43	1		04/28/21 23:41	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/28/21 23:41	16984-48-8	
Sulfate	4.4	mg/L	2.0	0.44	1		04/28/21 23:41	14808-79-8	M0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Sample: MW-302 **Lab ID: 40225269002** Collected: 04/13/21 15:10 Received: 04/16/21 07:45 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay							
Boron	521	ug/L	10.0	3.0	1	04/20/21 06:41	04/22/21 21:14	7440-42-8	
Calcium	82400	ug/L	254	76.2	1	04/20/21 06:41	04/22/21 21:14	7440-70-2	
Field Data		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	7.51	Std. Units			1		04/13/21 15:10		
Field Specific Conductance	661.3	umhos/cm			1		04/13/21 15:10		
Oxygen, Dissolved	9.92	mg/L			1		04/13/21 15:10	7782-44-7	
REDOX	127.0	mV			1		04/13/21 15:10		
Turbidity	2.60	NTU			1		04/13/21 15:10		
Static Water Level	785.77	feet			1		04/13/21 15:10		
Temperature, Water (C)	9.6	deg C			1		04/13/21 15:10		
2540C Total Dissolved Solids		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	370	mg/L	20.0	8.7	1		04/20/21 12:35		
9040 pH		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	7.4	Std. Units	0.10	0.010	1		04/19/21 09:57		H6
300.0 IC Anions		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	1.4J	mg/L	2.0	0.43	1		04/29/21 00:24	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/29/21 00:24	16984-48-8	
Sulfate	36.9	mg/L	2.0	0.44	1		04/29/21 00:24	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Sample: MW-33AR **Lab ID: 40225269003** Collected: 04/13/21 12:50 Received: 04/16/21 07:45 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay							
Boron	473	ug/L	10.0	3.0	1	04/20/21 06:41	04/22/21 21:21	7440-42-8	
Calcium	51600	ug/L	254	76.2	1	04/20/21 06:41	04/22/21 21:21	7440-70-2	
Field Data		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	8.78	Std. Units			1		04/13/21 12:50		
Field Specific Conductance	622.0	umhos/cm			1		04/13/21 12:50		
Oxygen, Dissolved	10.11	mg/L			1		04/13/21 12:50	7782-44-7	
REDOX	125.3	mV			1		04/13/21 12:50		
Turbidity	0.63	NTU			1		04/13/21 12:50		
Static Water Level	784.27	feet			1		04/13/21 12:50		
Temperature, Water (C)	9.8	deg C			1		04/13/21 12:50		
2540C Total Dissolved Solids		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	362	mg/L	20.0	8.7	1		04/20/21 12:35		
9040 pH		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	7.8	Std. Units	0.10	0.010	1		04/19/21 09:58		H6
300.0 IC Anions		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	26.9	mg/L	2.0	0.43	1		04/29/21 00:38	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/29/21 00:38	16984-48-8	
Sulfate	94.3	mg/L	20.0	4.4	10		04/29/21 02:33	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Sample: MW-34A **Lab ID: 40225269004** Collected: 04/13/21 11:05 Received: 04/16/21 07:45 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay									
Boron	203	ug/L	10.0	3.0	1	04/20/21 06:41	04/22/21 21:28	7440-42-8	
Calcium	61600	ug/L	254	76.2	1	04/20/21 06:41	04/22/21 21:28	7440-70-2	
Field Data									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	7.93	Std. Units			1		04/13/21 11:05		
Field Specific Conductance	472.6	umhos/cm			1		04/13/21 11:05		
Oxygen, Dissolved	10.47	mg/L			1		04/13/21 11:05	7782-44-7	
REDOX	118.8	mV			1		04/13/21 11:05		
Turbidity	36.34	NTU			1		04/13/21 11:05		
Static Water Level	784.77	feet			1		04/13/21 11:05		
Temperature, Water (C)	10.3	deg C			1		04/13/21 11:05		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	290	mg/L	20.0	8.7	1		04/20/21 12:35		
9040 pH									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.8	Std. Units	0.10	0.010	1		04/19/21 09:59		H6
300.0 IC Anions									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	2.3	mg/L	2.0	0.43	1		04/29/21 00:53	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/29/21 00:53	16984-48-8	
Sulfate	59.3	mg/L	2.0	0.44	1		04/29/21 00:53	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Sample: FIELD BLANK-MOD1-3LF **Lab ID: 40225269005** Collected: 04/13/21 12:50 Received: 04/16/21 07:45 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay									
Boron	<3.0	ug/L	10.0	3.0	1	04/20/21 06:41	04/22/21 18:31	7440-42-8	
Calcium	<76.2	ug/L	254	76.2	1	04/20/21 06:41	04/24/21 02:16	7440-70-2	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	<8.7	mg/L	20.0	8.7	1		04/20/21 12:35		
9040 pH									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	6.5	Std. Units	0.10	0.010	1		04/19/21 10:01		H6
300.0 IC Anions									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	<0.43	mg/L	2.0	0.43	1		04/29/21 01:07	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/29/21 01:07	16984-48-8	
Sulfate	<0.44	mg/L	2.0	0.44	1		04/29/21 01:07	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40225269

QC Batch: 382941	Analysis Method: SM 2540C
QC Batch Method: SM 2540C	Analysis Description: 2540C Total Dissolved Solids
	Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40225269001, 40225269002, 40225269003, 40225269004, 40225269005

METHOD BLANK: 2208850 Matrix: Water

Associated Lab Samples: 40225269001, 40225269002, 40225269003, 40225269004, 40225269005

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	04/20/21 12:31	

LABORATORY CONTROL SAMPLE: 2208851

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	564	542	96	80-120	

SAMPLE DUPLICATE: 2208852

Parameter	Units	40225218004 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	140	140	0	10	

SAMPLE DUPLICATE: 2208853

Parameter	Units	40225218010 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	530	556	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40225269

QC Batch:	382734	Analysis Method:	EPA 9040
QC Batch Method:	EPA 9040	Analysis Description:	9040 pH
		Laboratory:	Pace Analytical Services - Green Bay

Associated Lab Samples: 40225269001, 40225269002, 40225269003, 40225269004, 40225269005

SAMPLE DUPLICATE: 2207891

Parameter	Units	40225153001 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.1	7.2	0	20	H6

SAMPLE DUPLICATE: 2207905

Parameter	Units	40225178001 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.6	7.6	0	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

QC Batch: 383574 Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40225269001, 40225269002, 40225269003, 40225269004, 40225269005

METHOD BLANK: 2212748 Matrix: Water
Associated Lab Samples: 40225269001, 40225269002, 40225269003, 40225269004, 40225269005

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	04/28/21 14:06	
Fluoride	mg/L	<0.095	0.32	04/28/21 14:06	
Sulfate	mg/L	<0.44	2.0	04/28/21 14:06	

LABORATORY CONTROL SAMPLE: 2212749

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	21.5	107	90-110	
Fluoride	mg/L	2	2.1	103	90-110	
Sulfate	mg/L	20	21.4	107	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2212750 2212751

Parameter	Units	40225233001		MSD		MS		MSD		% Rec Limits	RPD	Max RPD	Qual
		Result	MS Spike Conc.	MSD Spike Conc.	Result	MSD Result	% Rec	% Rec					
Chloride	mg/L	2.5	20	20	24.3	24.4	109	110	90-110	1	15		
Fluoride	mg/L	<0.95	20	20	22.2	19.8	111	99	90-110	11	15	M0	
Sulfate	mg/L	345	200	200	545	491	100	73	90-110	11	15	M0	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2212752 2212753

Parameter	Units	40225269001		MSD		MS		MSD		% Rec Limits	RPD	Max RPD	Qual
		Result	MS Spike Conc.	MSD Spike Conc.	Result	MSD Result	% Rec	% Rec					
Chloride	mg/L	1.5J	20	20	23.5	23.6	110	110	90-110	0	15		
Fluoride	mg/L	<0.095	2	2	2.2	2.2	107	108	90-110	1	15		
Sulfate	mg/L	4.4	20	20	26.5	26.6	111	111	90-110	0	15	M0	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40225269

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

H6 Analysis initiated outside of the 15 minute EPA required holding time.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40225269

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40225269001	MW-1AR	EPA 3010	382878	EPA 6020	382964
40225269002	MW-302	EPA 3010	382878	EPA 6020	382964
40225269003	MW-33AR	EPA 3010	382878	EPA 6020	382964
40225269004	MW-34A	EPA 3010	382878	EPA 6020	382964
40225269005	FIELD BLANK-MOD1-3LF	EPA 3010	382878	EPA 6020	382964
40225269001	MW-1AR				
40225269002	MW-302				
40225269003	MW-33AR				
40225269004	MW-34A				
40225269001	MW-1AR	SM 2540C	382941		
40225269002	MW-302	SM 2540C	382941		
40225269003	MW-33AR	SM 2540C	382941		
40225269004	MW-34A	SM 2540C	382941		
40225269005	FIELD BLANK-MOD1-3LF	SM 2540C	382941		
40225269001	MW-1AR	EPA 9040	382734		
40225269002	MW-302	EPA 9040	382734		
40225269003	MW-33AR	EPA 9040	382734		
40225269004	MW-34A	EPA 9040	382734		
40225269005	FIELD BLANK-MOD1-3LF	EPA 9040	382734		
40225269001	MW-1AR	EPA 300.0	383574		
40225269002	MW-302	EPA 300.0	383574		
40225269003	MW-33AR	EPA 300.0	383574		
40225269004	MW-34A	EPA 300.0	383574		
40225269005	FIELD BLANK-MOD1-3LF	EPA 300.0	383574		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

40225269

Addresses		Order By :	Ship To :	Return To:	
Company	SCS ENGINEERS	Company	SCS ENGINEERS (Pace Analytical Green)	Company	Pace Analytical Green Bay
Contact	Blodgett, Meghan	Contact	Paul Grover	Contact	Milewsky, Dan
Email	mblodgett@scsengineers.com	Email	pgrover@scsengineers.com	Email	dan.milewsky@pacelabs.com
Address	2830 Dairy Drive	Address	2830 Dairy Drive	Address	1241 Bellevue Street
Address 2		Address 2		Address 2	Suite 9
City	Madison	City	Madison	City	Green Bay
State	WI Zip 53718	State	WI Zip 53718	State	WI Zip 54302
Phone	608-216-7362	Phone	608-216-7362	Phone	(920)469-2436

Info			
Project Name	25219067 Columbia CCR Mod 1-3	Due Date	04/09/2021
Profile	3946	Quote	
Project Manager	Milewsky, Dan	Return Date	
Carrier	Most Economical	Location	

Trip Blanks

Include Trip Blanks

Bottle Labels

Blank

Pre-Printed No Sample IDs

Pre-Printed With Sample IDs

Bottles

Boxed Cases

Individually Wrapped

Grouped By Sample ID/Matrix

Return Shipping Labels

No Shipper

With Shipper

Misc

Sampling Instructions

Custody Seal

Temp. Blanks

Coolers

Syringes

Extra Bubble Wrap

Short Hold/Rush Stickers

DI Water

USDA Regulated Soils

COC Options

Number of Blanks

Pre-Printed

# of Samples	Matrix	Test	Container	Total	# of	Lot #	Notes
5	WT	Boron/Calcium	250mL plastic w/HNO3	5	0	M-0-290-03BB	
5	WT	pH	250mL plastic unpres	5	0	M-0-290-04BB	
5	WT	TDS, Cl, F, SO4	250mL plastic unpres	5	0	M-0-290-04BB	

Hazard Shipping Placard In Place : NA

*Sample receiving hours are typically 8am-5pm, but may differ by location. Please check with your Pace Project Manager.

*Pace Analytical reserves the right to return hazardous, toxic, or radioactive samples to you.

*Pace Analytical reserves the right to charge for unused bottles, as well as cost associated with sample storage/disposal.

*Payment term are net 30 days.

*Please include the proposal number on the chain of custody to insure proper billing.

LAB USE:

Ship Date :

Prepared By:

Verified By:

Sample

ALL SAMPLES UNFILTERED

CLIENT USE (Optional):

Date Rec'd:

Received By:

Verified By:

Client Name: SCS Engineers

Sample Preservation Receipt Form
Project # 100225269

Page Analytical Services, LLC
1241 Bellevue Street, Suite 9
Green Bay, WI 54302

All containers needing preservation have been checked and noted below: Yes No N/A
Lab Lot# of pH paper: 10D3661

Lab Std #ID of preservation (if pH adjusted):


Initial when completed: 1/2

Date/Time:

Page Lab #	Glass						Plastic					Vials					Jars			General			VOA Vials (>6mm) *			Volume (mL)						
	AG1U	BG1U	AG1H	AG4S	AG4U	AG5U	BG3U	BP1U	BP3U	BP3B	BP3N	BP3S	VG9A	DG9T	VG9U	VG9H	VG9M	VG9D	JGFU	JG9U	WGFU	WPFU	SP5T	ZPLC	GN		H2SO4 pH ≤2	NaOH+Zn Act pH ≥9	NaOH pH ≥12	HNO3 pH ≤2	pH after adjusted	
001																																2.5/5/10
002									2																							2.5/5/10
003									2																							2.5/5/10
004									2																							2.5/5/10
005									2																							2.5/5/10
006																																2.5/5/10
007																																2.5/5/10
008																																2.5/5/10
009																																2.5/5/10
010																																2.5/5/10
011																																2.5/5/10
012																																2.5/5/10
013																																2.5/5/10
014																																2.5/5/10
015																																2.5/5/10
016																																2.5/5/10
017																																2.5/5/10
018																																2.5/5/10
019																																2.5/5/10
020																																2.5/5/10

Exceptions to preservation check: VOA, Coliform, TOC, TOX, TOH, O&G, WI DRO, Phenolics, Other: _____ Headspace in VOA Vials (>6mm): Yes No N/A *If yes look in headspace column

AG1U	1 liter amber glass	BP1U	1 liter plastic unpres	VG9A	40 mL clear ascorbic	JGFU	4 oz amber jar unpres
BG1U	1 liter clear glass	BP3U	250 mL plastic unpres	DG9T	40 mL amber Na Thio	JG9U	9 oz amber jar unpres
AG1H	1 liter amber glass HCL	BP3B	250 mL plastic NaOH	VG9U	40 mL clear vial unpres	WGFU	4 oz clear jar unpres
AG4S	125 mL amber glass H2SO4	BP3N	250 mL plastic HNO3	VG9H	40 mL clear vial HCL	WPFU	4 oz plastic jar unpres
AG4U	120 mL amber glass unpres	BP3S	250 mL plastic H2SO4	VG9M	40 mL clear vial MeOH	SP5T	120 mL plastic Na Trisulfate
AG5U	100 mL amber glass unpres			VG9D	40 mL clear vial DI	ZPLC	ziploc bag
AG2S	500 mL amber glass H2SO4					GN	
BG3U	250 mL clear glass unpres						

 1241 Bellevue Street, Green Bay, WI 54302	Document Name: Sample Condition Upon Receipt (SCUR)	Document Revised: 26Mar2020
	Document No.: ENV-FRM-GBAY-0014-Rev.00	Author: Pace Green Bay Quality Office

Sample Condition Upon Receipt Form (SCUR)

Project #: _____

Client Name: SCS Engineers

WO# : 40225269

Courier: CS Logistics Fed Ex Speedee UPS Waltco
 Client Pace Other: _____



Tracking #: _____

Custody Seal on Cooler/Box Present: yes no Seals intact: yes no

Custody Seal on Samples Present: yes no Seals intact: yes no

Packing Material: Bubble Wrap Bubble Bags None Other

Thermometer Used SR - 90 Type of Ice: Wet Blue Dry None Samples on ice, cooling process has begun

Cooler Temperature Uncorr: 1 JCorr: S

Temp Blank Present: yes no

Biological Tissue is Frozen: yes no

Person examining contents:	
Date: <u>4/16/24</u>	Initials: <u>[Signature]</u>
Labeled By Initials: <u>[Signature]</u>	

Temp should be above freezing to 6°C.
 Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time: _____
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:	For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	8.
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
-Pace Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
-Pace IR Containers Used:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix: <u>W</u>		
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution: _____ If checked, see attached form for additional comments

Person Contacted: _____ Date/Time: _____

Comments/ Resolution: _____

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir

May 11, 2021

Meghan Blodgett
SCS ENGINEERS
2830 Dairy Drive
Madison, WI 53718

RE: Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on April 16, 2021. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay
- Pace Analytical Services - Greensburg

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky
dan.milewsky@pacelabs.com
(920)469-2436
Project Manager

Enclosures

cc: Tom Karwoski, SCS ENGINEERS
Nicole Kron, SCS ENGINEERS
Jeff Maxted, ALLIANT ENERGY
Marc Morandi, ALLIANT ENERGY



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601

ANAB DOD-ELAP Rad Accreditation #: L2417

Alabama Certification #: 41590

Arizona Certification #: AZ0734

Arkansas Certification

California Certification #: 04222CA

Colorado Certification #: PA01547

Connecticut Certification #: PH-0694

Delaware Certification

EPA Region 4 DW Rad

Florida/TNI Certification #: E87683

Georgia Certification #: C040

Florida: Cert E871149 SEKS WET

Guam Certification

Hawaii Certification

Idaho Certification

Illinois Certification

Indiana Certification

Iowa Certification #: 391

Kansas/TNI Certification #: E-10358

Kentucky Certification #: KY90133

KY WW Permit #: KY0098221

KY WW Permit #: KY0000221

Louisiana DHH/TNI Certification #: LA180012

Louisiana DEQ/TNI Certification #: 4086

Maine Certification #: 2017020

Maryland Certification #: 308

Massachusetts Certification #: M-PA1457

Michigan/PADEP Certification #: 9991

Missouri Certification #: 235

Montana Certification #: Cert0082

Nebraska Certification #: NE-OS-29-14

Nevada Certification #: PA014572018-1

New Hampshire/TNI Certification #: 297617

New Jersey/TNI Certification #: PA051

New Mexico Certification #: PA01457

New York/TNI Certification #: 10888

North Carolina Certification #: 42706

North Dakota Certification #: R-190

Ohio EPA Rad Approval: #41249

Oregon/TNI Certification #: PA200002-010

Pennsylvania/TNI Certification #: 65-00282

Puerto Rico Certification #: PA01457

Rhode Island Certification #: 65-00282

South Dakota Certification

Tennessee Certification #: 02867

Texas/TNI Certification #: T104704188-17-3

Utah/TNI Certification #: PA014572017-9

USDA Soil Permit #: P330-17-00091

Vermont Dept. of Health: ID# VT-0282

Virgin Island/PADEP Certification

Virginia/VELAP Certification #: 9526

Washington Certification #: C868

West Virginia DEP Certification #: 143

West Virginia DHHR Certification #: 9964C

Wisconsin Approve List for Rad

Wyoming Certification #: 8TMS-L

Pace Analytical Services Green Bay

1241 Bellevue Street, Green Bay, WI 54302

Florida/NELAP Certification #: E87948

Illinois Certification #: 200050

Kentucky UST Certification #: 82

Louisiana Certification #: 04168

Minnesota Certification #: 055-999-334

New York Certification #: 12064

North Dakota Certification #: R-150

Virginia VELAP ID: 460263

South Carolina Certification #: 83006001

Texas Certification #: T104704529-14-1

Wisconsin Certification #: 405132750

Wisconsin DATCP Certification #: 105-444

USDA Soil Permit #: P330-16-00157

Federal Fish & Wildlife Permit #: LE51774A-0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE SUMMARY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40225276001	MW-301	Water	04/14/21 14:55	04/16/21 07:40
40225276002	MW-84A	Water	04/14/21 13:40	04/16/21 07:40

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
40225276001	MW-301	EPA 6020	KXS	14	PASI-G
		EPA 7470	AJT	1	PASI-G
			VGC	7	PASI-G
		EPA 903.1	MK1	1	PASI-PA
		EPA 904.0	VAL	1	PASI-PA
		Total Radium Calculation	RMK	1	PASI-PA
		SM 2540C	JXM	1	PASI-G
		EPA 9040	ALY	1	PASI-G
		EPA 300.0	HMB	3	PASI-G
		40225276002	MW-84A	EPA 6020	KXS
EPA 7470	AJT			1	PASI-G
	VGC			7	PASI-G
EPA 903.1	MK1			1	PASI-PA
EPA 904.0	VAL			1	PASI-PA
Total Radium Calculation	RMK			1	PASI-PA
SM 2540C	JXM			1	PASI-G
EPA 9040	ALY			1	PASI-G
EPA 300.0	HMB			3	PASI-G

PASI-G = Pace Analytical Services - Green Bay
PASI-PA = Pace Analytical Services - Greensburg

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

Sample: MW-301 **Lab ID: 40225276001** Collected: 04/14/21 14:55 Received: 04/16/21 07:40 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS									
Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay									
Antimony	<0.15	ug/L	1.0	0.15	1	04/21/21 06:55	04/21/21 21:48	7440-36-0	
Arsenic	<0.28	ug/L	1.0	0.28	1	04/21/21 06:55	04/21/21 21:48	7440-38-2	
Barium	8.9	ug/L	2.3	0.70	1	04/21/21 06:55	04/21/21 21:48	7440-39-3	
Beryllium	<0.25	ug/L	1.0	0.25	1	04/21/21 06:55	04/21/21 21:48	7440-41-7	
Boron	22.2	ug/L	10.0	3.0	1	04/21/21 06:55	04/21/21 21:48	7440-42-8	
Cadmium	<0.15	ug/L	1.0	0.15	1	04/21/21 06:55	04/21/21 21:48	7440-43-9	
Calcium	117000	ug/L	2540	762	10	04/21/21 06:55	04/21/21 19:30	7440-70-2	P6
Chromium	<1.0	ug/L	3.4	1.0	1	04/21/21 06:55	04/21/21 21:48	7440-47-3	
Cobalt	<0.12	ug/L	1.0	0.12	1	04/21/21 06:55	04/21/21 21:48	7440-48-4	
Lead	<0.24	ug/L	1.0	0.24	1	04/21/21 06:55	04/21/21 21:48	7439-92-1	
Lithium	0.58J	ug/L	1.0	0.22	1	04/21/21 06:55	04/21/21 21:48	7439-93-2	
Molybdenum	<0.44	ug/L	1.5	0.44	1	04/21/21 06:55	04/21/21 21:48	7439-98-7	
Selenium	<0.32	ug/L	1.1	0.32	1	04/21/21 06:55	04/22/21 10:16	7782-49-2	
Thallium	<0.14	ug/L	1.0	0.14	1	04/21/21 06:55	04/21/21 21:48	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470 Preparation Method: EPA 7470 Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	04/22/21 11:00	04/23/21 09:30	7439-97-6	
Field Data									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	6.66	Std. Units			1		04/14/21 14:55		
Field Specific Conductance	857.0	umhos/cm			1		04/14/21 14:55		
Oxygen, Dissolved	3.90	mg/L			1		04/14/21 14:55	7782-44-7	
REDOX	102.9	mV			1		04/14/21 14:55		
Turbidity	2.41	NTU			1		04/14/21 14:55		
Static Water Level	786.50	feet			1		04/14/21 14:55		
Temperature, Water (C)	7.4	deg C			1		04/14/21 14:55		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	472	mg/L	20.0	8.7	1		04/20/21 15:00		
9040 pH									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	6.9	Std. Units	0.10	0.010	1		04/19/21 10:15		H6
300.0 IC Anions									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	1.5J	mg/L	2.0	0.43	1		04/30/21 16:37	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/30/21 16:37	16984-48-8	
Sulfate	8.5	mg/L	2.0	0.44	1		04/30/21 16:37	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

Sample: MW-84A **Lab ID: 40225276002** Collected: 04/14/21 13:40 Received: 04/16/21 07:40 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020 MET ICPMS		Analytical Method: EPA 6020 Preparation Method: EPA 3010 Pace Analytical Services - Green Bay							
Antimony	0.55J	ug/L	1.0	0.15	1	04/21/21 06:55	04/21/21 22:15	7440-36-0	
Arsenic	0.91J	ug/L	1.0	0.28	1	04/21/21 06:55	04/21/21 22:15	7440-38-2	
Barium	13.4	ug/L	2.3	0.70	1	04/21/21 06:55	04/21/21 22:15	7440-39-3	
Beryllium	0.47J	ug/L	1.0	0.25	1	04/21/21 06:55	04/21/21 22:15	7440-41-7	
Boron	14.3	ug/L	10.0	3.0	1	04/21/21 06:55	04/21/21 22:15	7440-42-8	
Cadmium	0.53J	ug/L	1.0	0.15	1	04/21/21 06:55	04/21/21 22:15	7440-43-9	
Calcium	69100	ug/L	254	76.2	1	04/21/21 06:55	04/21/21 22:15	7440-70-2	
Chromium	2.6J	ug/L	3.4	1.0	1	04/21/21 06:55	04/21/21 22:15	7440-47-3	
Cobalt	0.52J	ug/L	1.0	0.12	1	04/21/21 06:55	04/21/21 22:15	7440-48-4	
Lead	0.55J	ug/L	1.0	0.24	1	04/21/21 06:55	04/21/21 22:15	7439-92-1	
Lithium	1.0	ug/L	1.0	0.22	1	04/21/21 06:55	04/21/21 22:15	7439-93-2	
Molybdenum	0.62J	ug/L	1.5	0.44	1	04/21/21 06:55	04/21/21 22:15	7439-98-7	
Selenium	0.48J	ug/L	1.1	0.32	1	04/21/21 06:55	04/22/21 10:44	7782-49-2	
Thallium	0.66J	ug/L	1.0	0.14	1	04/21/21 06:55	04/21/21 22:15	7440-28-0	
7470 Mercury		Analytical Method: EPA 7470 Preparation Method: EPA 7470 Pace Analytical Services - Green Bay							
Mercury	<0.066	ug/L	0.20	0.066	1	04/22/21 11:00	04/23/21 09:32	7439-97-6	
Field Data		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	7.34	Std. Units			1		04/14/21 13:40		
Field Specific Conductance	610.9	umhos/cm			1		04/14/21 13:40		
Oxygen, Dissolved	9.80	mg/L			1		04/14/21 13:40	7782-44-7	
REDOX	95.6	mV			1		04/14/21 13:40		
Turbidity	2.45	NTU			1		04/14/21 13:40		
Static Water Level	785.84	feet			1		04/14/21 13:40		
Temperature, Water (C)	10.2	deg C			1		04/14/21 13:40		
2540C Total Dissolved Solids		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	328	mg/L	20.0	8.7	1		04/20/21 15:01		
9040 pH		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	7.6	Std. Units	0.10	0.010	1		04/19/21 10:17		H6
300.0 IC Anions		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	4.4	mg/L	2.0	0.43	1		04/30/21 16:52	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		04/30/21 16:52	16984-48-8	
Sulfate	1.4J	mg/L	2.0	0.44	1		04/30/21 16:52	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

QC Batch: 383173	Analysis Method: EPA 7470
QC Batch Method: EPA 7470	Analysis Description: 7470 Mercury
	Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40225276001, 40225276002

METHOD BLANK: 2210149 Matrix: Water

Associated Lab Samples: 40225276001, 40225276002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Mercury	ug/L	<0.066	0.20	04/23/21 08:32	

LABORATORY CONTROL SAMPLE: 2210150

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	ug/L	5	4.7	93	85-115	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2210151 2210152

Parameter	Units	2210151		2210152		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual	
		40225233001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result							MSD Result
Mercury	ug/L	<0.066	5	5	4.8	4.7	97	94	85-115	3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

QC Batch: 383007 Analysis Method: EPA 6020
QC Batch Method: EPA 3010 Analysis Description: 6020 MET
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40225276001, 40225276002

METHOD BLANK: 2209295 Matrix: Water

Associated Lab Samples: 40225276001, 40225276002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Antimony	ug/L	<0.15	1.0	04/21/21 18:28	
Arsenic	ug/L	<0.28	1.0	04/21/21 18:28	
Barium	ug/L	<0.70	2.3	04/21/21 18:28	
Beryllium	ug/L	<0.25	1.0	04/21/21 18:28	
Boron	ug/L	<3.0	10.0	04/21/21 18:28	
Cadmium	ug/L	<0.15	1.0	04/21/21 18:28	
Calcium	ug/L	<76.2	254	04/21/21 18:28	
Chromium	ug/L	<1.0	3.4	04/21/21 18:28	
Cobalt	ug/L	<0.12	1.0	04/21/21 18:28	
Lead	ug/L	<0.24	1.0	04/21/21 18:28	
Lithium	ug/L	<0.22	1.0	04/21/21 18:28	
Molybdenum	ug/L	<0.44	1.5	04/21/21 18:28	
Selenium	ug/L	<0.32	1.1	04/21/21 18:28	
Thallium	ug/L	<0.14	1.0	04/21/21 18:28	

LABORATORY CONTROL SAMPLE: 2209296

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	ug/L	500	517	103	80-120	
Arsenic	ug/L	500	492	98	80-120	
Barium	ug/L	500	490	98	80-120	
Beryllium	ug/L	500	477	95	80-120	
Boron	ug/L	500	486	97	80-120	
Cadmium	ug/L	500	509	102	80-120	
Calcium	ug/L	5000	4980	100	80-120	
Chromium	ug/L	500	502	100	80-120	
Cobalt	ug/L	500	486	97	80-120	
Lead	ug/L	500	487	97	80-120	
Lithium	ug/L	500	484	97	80-120	
Molybdenum	ug/L	500	494	99	80-120	
Selenium	ug/L	500	515	103	80-120	
Thallium	ug/L	500	491	98	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

Parameter	Units	MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2209297		2209298		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40225276001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result								
Antimony	ug/L	<0.15	500	500	531	529	106	106	75-125	0	20		
Arsenic	ug/L	<0.28	500	500	495	490	99	98	75-125	1	20		
Barium	ug/L	8.9	500	500	504	503	99	99	75-125	0	20		
Beryllium	ug/L	<0.25	500	500	475	472	95	94	75-125	1	20		
Boron	ug/L	22.2	500	500	519	512	99	98	75-125	1	20		
Cadmium	ug/L	<0.15	500	500	510	509	102	102	75-125	0	20		
Calcium	ug/L	117000	5000	5000	122000	120000	104	64	75-125	2	20	P6	
Chromium	ug/L	<1.0	500	500	511	511	102	102	75-125	0	20		
Cobalt	ug/L	<0.12	500	500	493	494	99	99	75-125	0	20		
Lead	ug/L	<0.24	500	500	512	504	102	101	75-125	2	20		
Lithium	ug/L	0.58J	500	500	487	482	97	96	75-125	1	20		
Molybdenum	ug/L	<0.44	500	500	514	518	103	103	75-125	1	20		
Selenium	ug/L	<0.32	500	500	483	484	97	97	75-125	0	20		
Thallium	ug/L	<0.14	500	500	526	523	105	105	75-125	0	20		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

QC Batch: 382972 Analysis Method: SM 2540C
QC Batch Method: SM 2540C Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40225276001, 40225276002

METHOD BLANK: 2209087 Matrix: Water
Associated Lab Samples: 40225276001, 40225276002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	04/20/21 14:59	

LABORATORY CONTROL SAMPLE: 2209088

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	564	554	98	80-120	

SAMPLE DUPLICATE: 2209089

Parameter	Units	40225276001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	472	486	3	10	

SAMPLE DUPLICATE: 2209090

Parameter	Units	40225343004 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	850	808	5	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

QC Batch: 382737

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40225276001, 40225276002

SAMPLE DUPLICATE: 2207896

Parameter	Units	40225270004 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	6.3	6.4	1	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

QC Batch: 383702 Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40225276001, 40225276002

METHOD BLANK: 2213287 Matrix: Water

Associated Lab Samples: 40225276001, 40225276002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	04/30/21 01:17	
Fluoride	mg/L	<0.095	0.32	04/30/21 01:17	
Sulfate	mg/L	<0.44	2.0	04/30/21 01:17	

LABORATORY CONTROL SAMPLE: 2213288

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	21.5	108	90-110	
Fluoride	mg/L	2	2.1	107	90-110	
Sulfate	mg/L	20	21.6	108	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2213289 2213290

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40225270001 Result	Spike Conc.	Spike Conc.	Result								
Chloride	mg/L	390	400	400	816	808	107	105	90-110	1	15		
Fluoride	mg/L	<0.095	2	2	1.8	1.9	91	93	90-110	1	15		
Sulfate	mg/L	30.3	20	20	50.5	50.7	101	102	90-110	0	15		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

Sample: MW-301 **Lab ID: 40225276001** Collected: 04/14/21 14:55 Received: 04/16/21 07:40 Matrix: Water
PWS: Site ID: Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
Pace Analytical Services - Greensburg						
Radium-226	EPA 903.1	0.418 ± 0.563 (0.946) C:NA T:91%	pCi/L	05/10/21 16:44	13982-63-3	
Pace Analytical Services - Greensburg						
Radium-228	EPA 904.0	0.739 ± 0.509 (0.983) C:66% T:83%	pCi/L	05/07/21 15:44	15262-20-1	
Pace Analytical Services - Greensburg						
Total Radium	Total Radium Calculation	1.16 ± 1.07 (1.93)	pCi/L	05/11/21 15:49	7440-14-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

Sample: MW-84A **Lab ID: 40225276002** Collected: 04/14/21 13:40 Received: 04/16/21 07:40 Matrix: Water
PWS: Site ID: Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
	Pace Analytical Services - Greensburg					
Radium-226	EPA 903.1	-0.289 ± 0.530 (1.20) C:NA T:92%	pCi/L	05/10/21 17:00	13982-63-3	
	Pace Analytical Services - Greensburg					
Radium-228	EPA 904.0	0.285 ± 0.346 (0.732) C:73% T:95%	pCi/L	05/11/21 11:28	15262-20-1	
	Pace Analytical Services - Greensburg					
Total Radium	Total Radium Calculation	0.285 ± 0.876 (1.93)	pCi/L	05/11/21 15:49	7440-14-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

QC Batch: 445315

Analysis Method: EPA 904.0

QC Batch Method: EPA 904.0

Analysis Description: 904.0 Radium 228

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40225276002

METHOD BLANK: 2149683

Matrix: Water

Associated Lab Samples: 40225276002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-228	0.373 ± 0.381 (0.787) C:76% T:77%	pCi/L	05/11/21 11:27	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

QC Batch: 445314

Analysis Method: EPA 904.0

QC Batch Method: EPA 904.0

Analysis Description: 904.0 Radium 228

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40225276001

METHOD BLANK: 2149682

Matrix: Water

Associated Lab Samples: 40225276001

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-228	0.621 ± 0.331 (0.589) C:74% T:104%	pCi/L	05/07/21 12:16	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40225276

QC Batch: 445313

Analysis Method: EPA 903.1

QC Batch Method: EPA 903.1

Analysis Description: 903.1 Radium-226

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40225276001, 40225276002

METHOD BLANK: 2149681

Matrix: Water

Associated Lab Samples: 40225276001, 40225276002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-226	0.301 ± 0.462 (0.795) C:NA T:96%	pCi/L	05/10/21 16:18	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

DEFINITIONS

Act - Activity

Unc - Uncertainty: SDWA = 1.96 sigma count uncertainty, all other matrices = Expanded Uncertainty (95% confidence interval).

Gamma Spec = Expanded Uncertainty (95.4% Confidence Interval)

(MDC) - Minimum Detectable Concentration

Trac - Tracer Recovery (%)

Carr - Carrier Recovery (%)

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

H6 Analysis initiated outside of the 15 minute EPA required holding time.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40225276

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40225276001	MW-301	EPA 3010	383007	EPA 6020	383093
40225276002	MW-84A	EPA 3010	383007	EPA 6020	383093
40225276001	MW-301	EPA 7470	383173	EPA 7470	383221
40225276002	MW-84A	EPA 7470	383173	EPA 7470	383221
40225276001	MW-301				
40225276002	MW-84A				
40225276001	MW-301	EPA 903.1	445313		
40225276002	MW-84A	EPA 903.1	445313		
40225276001	MW-301	EPA 904.0	445314		
40225276002	MW-84A	EPA 904.0	445315		
40225276001	MW-301	Total Radium Calculation	447511		
40225276002	MW-84A	Total Radium Calculation	447511		
40225276001	MW-301	SM 2540C	382972		
40225276002	MW-84A	SM 2540C	382972		
40225276001	MW-301	EPA 9040	382737		
40225276002	MW-84A	EPA 9040	382737		
40225276001	MW-301	EPA 300.0	383702		
40225276002	MW-84A	EPA 300.0	383702		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Container Order #800030 40225276

Addresses		Ship To :	Return To:
Order By :			
Company <u>SCS ENGINEERS</u>	Company <u>SCS ENGINEERS (Pace Analytical Green)</u>	Company <u>Pace Analytical Green Bay</u>	
Contact <u>Blodgett, Meghan</u>	Contact <u>Paul Grover</u>	Contact <u>Milewsky, Dan</u>	
Email <u>mblodgett@scsengineers.com</u>	Email <u>pgrover@scsengineers.com</u>	Email <u>dan.milewsky@pacelabs.com</u>	
Address <u>2830 Dairy Drive</u>	Address <u>2830 Dairy Drive</u>	Address <u>1241 Bellevue Street</u>	
Address 2 _____	Address 2 _____	Address 2 <u>Suite 9</u>	
City <u>Madison</u>	City <u>Madison</u>	City <u>Green Bay</u>	
State <u>WI</u> Zip <u>53718</u>	State <u>WI</u> Zip <u>53718</u>	State <u>WI</u> Zip <u>54302</u>	
Phone <u>608-216-7362</u>	Phone <u>608-216-7362</u>	Phone <u>(920)469-2436</u>	

Info			
Project Name <u>25219067 Columbia CCR Background</u>	Due Date <u>04/09/2021</u>	Profile <u>3946</u>	Quote _____
Project Manager <u>Milewsky, Dan</u>	Return Date _____	Carrier <u>Most Economical</u>	Location _____

Trip Blanks

Include Trip Blanks

Bottle Labels

Blank

Pre-Printed No Sample IDs

Pre-Printed With Sample IDs

Bottles

Boxed Cases

Individually Wrapped

Grouped By Sample ID/Matrix

Return Shipping Labels

No Shipper

With Shipper

Misc

Sampling Instructions

Custody Seal

Temp. Blanks

Coolers

Syringes

Extra Bubble Wrap

Short Hold/Rush Stickers

DI Water Liter(s)

USDA Regulated Soils

COC Options

Number of Blanks

Pre-Printed

# of Samples	Matrix	Test	Container	Total	# of	Lot #	Notes
2	WT	Radium 226	1L Plastic HNO3 pres	2	0		
2	WT	Radium 228	1L Plastic HNO3 pres	2	0		
2	WT	Metals	250mL plastic w/HNO3	2	0	M-0-290-03BB	
2	WT	pH	250mL plastic unpres	2	0	M-0-290-04BB	
2	WT	TDS, Cl, F, SO4	250mL plastic unpres	2	0	M-0-290-04BB	

Hazard Shipping Placard In Place : NA

*Sample receiving hours are typically 8am-5pm, but may differ by location. Please check with your Pace Project Manager.

*Pace Analytical reserves the right to return hazardous, toxic, or radioactive samples to you.

*Pace Analytical reserves the right to charge for unused bottles, as well as cost associated with sample storage/disposal.

*Payment term are net 30 days.

*Please include the proposal number on the chain of custody to insure proper billing.

LAB USE:

Ship Date :	<u>04/07/2021</u>
Prepared By:	<u>Mai Yer Her</u>
Verified By:	<input style="width: 100%;" type="text"/>


Sample

Full List Metals = B, Ca, Sb, As, Ba, Be, Cd, Cr, Co, Pb, Li Hg, Mo, Se, Tl

ALL SAMPLES UNFILTERED

CLIENT USE (Optional):

Date Rec'd:	<input style="width: 100%;" type="text"/>
Received By:	<input style="width: 100%;" type="text"/>
Verified By:	<input style="width: 100%;" type="text"/>

 1241 Bellevue Street, Green Bay, WI 54302	Document Name: Sample Condition Upon Receipt (SCUR)	Document Revised: 26Mar2020
	Document No.: ENV-FRM-GBAY-0014-Rev.00	Author: Pace Green Bay Quality Office

Sample Condition Upon Receipt Form (SCUR)

Client Name: SCS Engineers
Courier: CS Logistics Fed Ex Speedee UPS Waltco
 Client Pace Other: _____

Project #: _____

WO#: 40225276



Tracking #: _____
Custody Seal on Cooler/Box Present: yes no **Seals intact:** yes no
Custody Seal on Samples Present: yes no **Seals intact:** yes no
Packing Material: Bubble Wrap Bubble Bags None Other
Thermometer Used SR-99 **Type of Ice:** Wet Blue Dry None Samples on ice, cooling process has begun
Cooler Temperature Uncorr: 1.0 I/Corr: 1.0
Temp Blank Present: yes no **Biological Tissue is Frozen:** yes no


Person examining contents:
 Date: 4-16-21 / Initials: MLR
 Labeled By Initials: MLR

Temp should be above freezing to 6°C.
Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.	<u>sample MLR 4-16-21</u>
Chain of Custody Filled Out:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	2.	<u>copy to info, proj. state, sample type MLR</u>
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.	<u>4-16-21</u>
Sampler Name & Signature on COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.	
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.	
- VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time:	
Short Hold Time Analysis (<72hr):	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	6.	
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.	
Sufficient Volume:		8.	
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A			
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.	
-Pace Containers Used:	<input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
-Pace IR Containers Used:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A		
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.	
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.	
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.	
-Includes date/time/ID/Analysis Matrix: <u>W</u>			
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.	
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A		
Pace Trip Blank Lot # (if purchased):			

Client Notification/ Resolution: _____ If checked, see attached form for additional comments
 Person Contacted: _____ Date/Time: _____
 Comments/ Resolution: _____

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir



Appendix C2
October 2021 Detection Monitoring

November 02, 2021

Meghan Blodgett
SCS ENGINEERS
2830 Dairy Drive
Madison, WI 53718

RE: Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40235316

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on October 16, 2021. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky
dan.milewsky@pacelabs.com
(920)469-2436
Project Manager

Enclosures

cc: Sherren Clark, SCS Engineers
Tom Karwoski, SCS ENGINEERS
Nicole Kron, SCS ENGINEERS
Jeff Maxted, ALLIANT ENERGY
Marc Morandi, ALLIANT ENERGY



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Pace Analytical Services Green Bay

1241 Bellevue Street, Green Bay, WI 54302

Florida/NELAP Certification #: E87948

Illinois Certification #: 200050

Kentucky UST Certification #: 82

Louisiana Certification #: 04168

Minnesota Certification #: 055-999-334

New York Certification #: 12064

North Dakota Certification #: R-150

Virginia VELAP ID: 460263

South Carolina Certification #: 83006001

Texas Certification #: T104704529-14-1

Wisconsin Certification #: 405132750

Wisconsin DATCP Certification #: 105-444

USDA Soil Permit #: P330-16-00157

Federal Fish & Wildlife Permit #: LE51774A-0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE SUMMARY

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40235316001	MW-1AR	Water	10/14/21 15:00	10/16/21 08:35
40235316002	MW-302	Water	10/14/21 10:20	10/16/21 08:35
40235316003	MW-33AR	Water	10/12/21 17:00	10/16/21 08:35
40235316004	MW-34A	Water	10/12/21 16:55	10/16/21 08:35
40235316005	FIELD BLANK-MOD1-3LF	Water	10/12/21 10:20	10/16/21 08:35

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40235316001	MW-1AR	EPA 6020B	KXS	2
			MEA	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40235316002	MW-302	EPA 6020B	KXS	2
			MEA	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40235316003	MW-33AR	EPA 6020B	KXS	2
			MEA	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40235316004	MW-34A	EPA 6020B	KXS	2
			MEA	7
		SM 2540C	HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3
40235316005	FIELD BLANK-MOD1-3LF	EPA 6020B	KXS	2
			HNT	1
		EPA 9040	ALY	1
		EPA 300.0	HMB	3

PASI-G = Pace Analytical Services - Green Bay

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Sample: MW-1AR **Lab ID: 40235316001** Collected: 10/14/21 15:00 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3010A Pace Analytical Services - Green Bay							
Boron	12.4	ug/L	10.0	3.0	1	10/20/21 06:24	10/26/21 15:50	7440-42-8	
Calcium	87600	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 15:50	7440-70-2	
Field Data		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	7.44	Std. Units			1		10/14/21 15:00		
Field Specific Conductance	653.0	umhos/cm			1		10/14/21 15:00		
Oxygen, Dissolved	7.83	mg/L			1		10/14/21 15:00	7782-44-7	
REDOX	143.6	mV			1		10/14/21 15:00		
Turbidity	29.69	NTU			1		10/14/21 15:00		
Static Water Level	784.47	feet			1		10/14/21 15:00		
Temperature, Water (C)	14.9	deg C			1		10/14/21 15:00		
2540C Total Dissolved Solids		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	350	mg/L	20.0	8.7	1		10/19/21 13:31		
9040 pH		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	7.7	Std. Units	0.10	0.010	1		10/19/21 12:18		H6
300.0 IC Anions		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	1.2J	mg/L	2.0	0.43	1		10/29/21 16:58	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		10/29/21 16:58	16984-48-8	
Sulfate	3.1	mg/L	2.0	0.44	1		10/29/21 16:58	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Sample: MW-302 **Lab ID: 40235316002** Collected: 10/14/21 10:20 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Boron	495	ug/L	10.0	3.0	1	10/20/21 06:24	10/26/21 15:57	7440-42-8	
Calcium	84100	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 15:57	7440-70-2	
Field Data									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	7.07	Std. Units			1		10/14/21 10:20		
Field Specific Conductance	663.7	umhos/cm			1		10/14/21 10:20		
Oxygen, Dissolved	8.07	mg/L			1		10/14/21 10:20	7782-44-7	
REDOX	149.1	mV			1		10/14/21 10:20		
Turbidity	2.54	NTU			1		10/14/21 10:20		
Static Water Level	785.09	feet			1		10/14/21 10:20		
Temperature, Water (C)	11.5	deg C			1		10/14/21 10:20		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	394	mg/L	20.0	8.7	1		10/19/21 13:31		
9040 pH									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.7	Std. Units	0.10	0.010	1		10/19/21 12:20		H6
300.0 IC Anions									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	1.3J	mg/L	2.0	0.43	1		10/29/21 17:13	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		10/29/21 17:13	16984-48-8	
Sulfate	37.8	mg/L	2.0	0.44	1		10/29/21 17:13	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Sample: MW-33AR **Lab ID: 40235316003** Collected: 10/12/21 17:00 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Boron	564	ug/L	20.0	6.1	2	10/20/21 06:24	10/27/21 19:57	7440-42-8	
Calcium	53700	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 16:04	7440-70-2	
Field Data									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	7.59	Std. Units			1		10/12/21 17:00		
Field Specific Conductance	623.2	umhos/cm			1		10/12/21 17:00		
Oxygen, Dissolved	0.26	mg/L			1		10/12/21 17:00	7782-44-7	
REDOX	90.0	mV			1		10/12/21 17:00		
Turbidity	0.00	NTU			1		10/12/21 17:00		
Static Water Level	783.73	feet			1		10/12/21 17:00		
Temperature, Water (C)	13.5	deg C			1		10/12/21 17:00		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	374	mg/L	20.0	8.7	1		10/19/21 13:31		
9040 pH									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	8.0	Std. Units	0.10	0.010	1		10/19/21 12:23		H6
300.0 IC Anions									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	22.6	mg/L	2.0	0.43	1		10/29/21 17:28	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		10/29/21 17:28	16984-48-8	
Sulfate	96.4	mg/L	10.0	2.2	5		10/29/21 18:12	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

Sample: MW-34A **Lab ID: 40235316004** Collected: 10/12/21 16:55 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS		Analytical Method: EPA 6020B Preparation Method: EPA 3010A Pace Analytical Services - Green Bay							
Boron	212	ug/L	10.0	3.0	1	10/20/21 06:24	10/26/21 16:12	7440-42-8	
Calcium	58100	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 16:12	7440-70-2	
Field Data		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	7.68	Std. Units			1		10/12/21 16:55		
Field Specific Conductance	478.1	umhos/cm			1		10/12/21 16:55		
Oxygen, Dissolved	10.10	mg/L			1		10/12/21 16:55	7782-44-7	
REDOX	72.6	mV			1		10/12/21 16:55		
Turbidity	21.13	NTU			1		10/12/21 16:55		
Static Water Level	784.42	feet			1		10/12/21 16:55		
Temperature, Water (C)	13.0	deg C			1		10/12/21 16:55		
2540C Total Dissolved Solids		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	278	mg/L	20.0	8.7	1		10/19/21 13:32		
9040 pH		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	7.8	Std. Units	0.10	0.010	1		10/21/21 11:06		H6
300.0 IC Anions		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	1.9J	mg/L	2.0	0.43	1		10/30/21 11:12	16887-00-6	M0
Fluoride	<0.095	mg/L	0.32	0.095	1		11/01/21 12:51	16984-48-8	M0
Sulfate	56.1	mg/L	10.0	2.2	5		10/30/21 14:58	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40235316

Sample: FIELD BLANK-MOD1-3LF **Lab ID: 40235316005** Collected: 10/12/21 10:20 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Boron	<3.0	ug/L	10.0	3.0	1	10/20/21 06:24	10/26/21 13:45	7440-42-8	
Calcium	<76.2	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 13:45	7440-70-2	
2540C Total Dissolved Solids									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	<8.7	mg/L	20.0	8.7	1		10/19/21 13:32		
9040 pH									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	8.5	Std. Units	0.10	0.010	1		10/21/21 11:10		H6
300.0 IC Anions									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	<0.43	mg/L	2.0	0.43	1		11/01/21 13:36	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		11/01/21 13:36	16984-48-8	
Sulfate	<0.44	mg/L	2.0	0.44	1		11/01/21 13:36	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

QC Batch: 399050 Analysis Method: EPA 6020B
 QC Batch Method: EPA 3010A Analysis Description: 6020B MET
 Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235316001, 40235316002, 40235316003, 40235316004, 40235316005

METHOD BLANK: 2304130 Matrix: Water

Associated Lab Samples: 40235316001, 40235316002, 40235316003, 40235316004, 40235316005

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Boron	ug/L	<3.0	10.0	10/26/21 13:37	
Calcium	ug/L	<76.2	254	10/26/21 13:37	

LABORATORY CONTROL SAMPLE: 2304131

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Boron	ug/L	250	243	97	80-120	
Calcium	ug/L	10000	10000	100	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2304132 2304133

Parameter	Units	40235317001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Boron	ug/L	31.4	250	250	273	277	97	98	75-125	1	20	
Calcium	ug/L	67800	10000	10000	77700	80700	100	129	75-125	4	20 P6	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40235316

QC Batch: 398939 Analysis Method: SM 2540C
QC Batch Method: SM 2540C Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235316001, 40235316002, 40235316003, 40235316004, 40235316005

METHOD BLANK: 2303507 Matrix: Water
Associated Lab Samples: 40235316001, 40235316002, 40235316003, 40235316004, 40235316005

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	10/19/21 13:29	

LABORATORY CONTROL SAMPLE: 2303508

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	575	566	98	80-120	

SAMPLE DUPLICATE: 2303509

Parameter	Units	40235220001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	248	272	9	10	

SAMPLE DUPLICATE: 2303510

Parameter	Units	40235316003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	374	390	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

QC Batch: 398932

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235316001, 40235316002, 40235316003

SAMPLE DUPLICATE: 2303461

Parameter	Units	40234686001 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	8.2	8.3	0	20	H6

SAMPLE DUPLICATE: 2303462

Parameter	Units	40234894004 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.9	7.9	0	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

QC Batch: 399227

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235316004, 40235316005

SAMPLE DUPLICATE: 2304971

Parameter	Units	40235095010 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.8	7.8	0	20	H6

SAMPLE DUPLICATE: 2304972

Parameter	Units	40235316004 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.8	7.8	1	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40235316

QC Batch: 399898 Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235316001, 40235316002, 40235316003

METHOD BLANK: 2309116 Matrix: Water
Associated Lab Samples: 40235316001, 40235316002, 40235316003

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	10/28/21 21:51	
Fluoride	mg/L	<0.095	0.32	10/28/21 21:51	
Sulfate	mg/L	<0.44	2.0	10/28/21 21:51	

LABORATORY CONTROL SAMPLE: 2309117

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	21.2	106	90-110	
Fluoride	mg/L	2	2.1	105	90-110	
Sulfate	mg/L	20	21.0	105	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2309118 2309119

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40235178006	Result	Spike Conc.	Spike Conc.								
Chloride	mg/L	10.7	100	100	118	118	108	108	90-110	0	15		
Fluoride	mg/L	1.1J	10	10	11.7	11.7	106	106	90-110	0	15		
Sulfate	mg/L	139	100	100	233	232	94	93	90-110	0	15		

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2309120 2309121

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40235316003	Result	Spike Conc.	Spike Conc.								
Chloride	mg/L	22.6	20	20	43.2	43.2	103	103	90-110	0	15		
Fluoride	mg/L	<0.095	2	2	2.2	2.2	109	110	90-110	0	15		
Sulfate	mg/L	96.4	100	100	197	199	100	103	90-110	1	15		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40235316

QC Batch: 399901 Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235316004, 40235316005

METHOD BLANK: 2309132 Matrix: Water

Associated Lab Samples: 40235316004, 40235316005

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	10/30/21 10:42	
Fluoride	mg/L	<0.095	0.32	11/01/21 12:21	
Sulfate	mg/L	<0.44	2.0	10/30/21 10:42	

LABORATORY CONTROL SAMPLE: 2309133

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	21.3	107	90-110	
Fluoride	mg/L	2	2.0	102	90-110	
Sulfate	mg/L	20	21.2	106	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2309134 2309135

Parameter	Units	40235316004		2309135		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		Result	MS Spike Conc.	MSD Spike Conc.	MS Result								
Chloride	mg/L	1.9J	20	20	24.0	24.0	111	110	90-110	0	15	M0	
Fluoride	mg/L	<0.095	2	2	2.2	2.2	111	111	90-110	0	15	M0	
Sulfate	mg/L	56.1	100	100	164	163	108	107	90-110	1	15		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: 25219067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40235316

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

H6 Analysis initiated outside of the 15 minute EPA required holding time.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25219067 COLUMBIA CCR MOD 1-3
Pace Project No.: 40235316

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40235316001	MW-1AR	EPA 3010A	399050	EPA 6020B	399167
40235316002	MW-302	EPA 3010A	399050	EPA 6020B	399167
40235316003	MW-33AR	EPA 3010A	399050	EPA 6020B	399167
40235316004	MW-34A	EPA 3010A	399050	EPA 6020B	399167
40235316005	FIELD BLANK-MOD1-3LF	EPA 3010A	399050	EPA 6020B	399167
40235316001	MW-1AR				
40235316002	MW-302				
40235316003	MW-33AR				
40235316004	MW-34A				
40235316001	MW-1AR	SM 2540C	398939		
40235316002	MW-302	SM 2540C	398939		
40235316003	MW-33AR	SM 2540C	398939		
40235316004	MW-34A	SM 2540C	398939		
40235316005	FIELD BLANK-MOD1-3LF	SM 2540C	398939		
40235316001	MW-1AR	EPA 9040	398932		
40235316002	MW-302	EPA 9040	398932		
40235316003	MW-33AR	EPA 9040	398932		
40235316004	MW-34A	EPA 9040	399227		
40235316005	FIELD BLANK-MOD1-3LF	EPA 9040	399227		
40235316001	MW-1AR	EPA 300.0	399898		
40235316002	MW-302	EPA 300.0	399898		
40235316003	MW-33AR	EPA 300.0	399898		
40235316004	MW-34A	EPA 300.0	399901		
40235316005	FIELD BLANK-MOD1-3LF	EPA 300.0	399901		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

40235316

Addresses

Order By :

Ship To :

Return To:

Company SCS ENGINEERS
 Contact Blodgett, Meghan
 Email mblodgett@scsengineers.com
 Address 2830 Dairy Drive
 Address 2 _____
 City Madison
 State WI Zip 53718
 Phone 608-216-7362

Company SCS ENGINEERS (Pace Analytical Green
 Contact Adam Watson
 Email awatson@scsengineers.com
 Address 2830 Dairy Drive
 Address 2 _____
 City Madison
 State WI Zip 53718
 Phone 608-216-7362

Company Pace Analytical Green Bay
 Contact Milewsky, Dan
 Email dan.milewsky@pacelabs.com
 Address 1241 Bellevue Street
 Address 2 Suite 9
 City Green Bay
 State WI Zip 54302
 Phone (920)469-2436

Info

Project Name 25219067 Columbia CCR Primary Pond Due Date 10/08/2021 Profile 3946-12 Quote _____
 Project Manager Milewsky, Dan Return Date _____ Carrier Most Economical Location _____

Trip Blanks

Include Trip Blanks

Bottle Labels

Blank
 Pre-Printed No Sample IDs
 Pre-Printed With Sample IDs

Bottles

Boxed Cases
 Individually Wrapped
 Grouped By Sample ID/Matrix

Return Shipping Labels

No Shipper
 With Shipper

Misc

Sampling Instructions
 Custody Seal
 Temp. Blanks
 Coolers _____
 Syringes _____
 Extra Bubble Wrap
 Short Hold/Rush Stickers
 DI Water 3 Liter(s)
 USDA Regulated Soils

COC Options

Number of Blanks _____
 Pre-Printed _____

# of Samples	Matrix	Test	Container	Total	# of	Lot #	Notes
6	WT	Radium 226	1L Plastic HNO3 pres	6	0		
6	WT	Radium 228	1L Plastic HNO3 pres	6	0		
6	WT	Metals	250mL plastic w/HNO3	6	0	M-1-106-03BB	
6	WT	pH	250mL plastic unpres	6	0	M-1-203-03BB	
6	WT	TDS, Cl, F, SO4	250mL plastic unpres	6	0	M-1-203-03BB	

Hazard Shipping Placard In Place : NA

*Sample receiving hours are typically 8am-5pm, but may differ by location. Please check with your Pace Project Manager.
 *Pace Analytical reserves the right to return hazardous, toxic, or radioactive samples to you.
 *Pace Analytical reserves the right to charge for unused bottles, as well as cost associated with sample storage/disposal.
 *Payment term are net 30 days.
 *Please include the proposal number on the chain of custody to insure proper billing.

LAB USE:

Ship Date : 10/07/2021
 Prepared By: Mai Yer Her
 Verified By: _____

Sample

Full List Metals = B, Ca, Sb, As, Ba, Be, Cd, Cr, Co, Pb, Li, Mo, Se, Tl
 ALL SAMPLES UNFILTERED

CLIENT USE (Optional):

Date Rec'd: _____
 Received By: _____
 Verified By: _____



1241 Bellevue Street, Green Bay, WI 54302

Document Name:
Sample Condition Upon Receipt (SCUR)

Document No.:
ENV-FRM-GBAY-0014-Rev.00

Document Revised: 26Mar2020

Author:
Pace Green Bay Quality Office

Sample Condition Upon Receipt Form (SCUR)

Project #:

Client Name: SCS Engineers

Courier: CS Logistics Fed Ex Speedee UPS Waltco
 Client Pace Other: _____

Tracking #: _____

Custody Seal on Cooler/Box Present: yes no Seals intact: yes no

Custody Seal on Samples Present: yes no Seals intact: yes no

Packing Material: Bubble Wrap Bubble Bags None Other

Thermometer Used SR-107 Type of Ice: Wet Blue Dry None

Cooler Temperature Uncorr: 5 /Corr: 5

Temp Blank Present: yes no

Biological Tissue is Frozen: yes no

Temp should be above freezing to 6°C.

Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

WO#: **40235316**



40235316

Person examining contents:

Date: 10/16/21 Initials: ARJ

Labeled By Initials: MP

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	2. <u>File, Proj. #</u> <u>10/16/21 ARJ</u>
Chain of Custody Relinquished:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time:
Short Hold Time Analysis (<72hr):	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
-Pace Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
-Pace IR Containers Used:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix: <u>W</u>		
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution:

If checked, see attached form for additional comments

Person Contacted: _____ Date/Time: _____

Comments/ Resolution: _____

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir

December 08, 2021

Meghan Blodgett
SCS ENGINEERS
2830 Dairy Drive
Madison, WI 53718

RE: Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on October 16, 2021. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay
- Pace Analytical Services - Greensburg

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky
dan.milewsky@pacelabs.com
(920)469-2436
Project Manager

Enclosures

cc: Sherren Clark, SCS Engineers
Tom Karwoski, SCS ENGINEERS
Nicole Kron, SCS ENGINEERS
Ryan Matzuk, SCS Engineers
Jeff Maxted, ALLIANT ENERGY
Marc Morandi, ALLIANT ENERGY



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

CERTIFICATIONS

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601
ANAB DOD-ELAP Rad Accreditation #: L2417
Alabama Certification #: 41590
Arizona Certification #: AZ0734
Arkansas Certification
California Certification #: 04222CA
Colorado Certification #: PA01547
Connecticut Certification #: PH-0694
Delaware Certification
EPA Region 4 DW Rad
Florida/TNI Certification #: E87683
Georgia Certification #: C040
Florida: Cert E871149 SEKS WET
Guam Certification
Hawaii Certification
Idaho Certification
Illinois Certification
Indiana Certification
Iowa Certification #: 391
Kansas/TNI Certification #: E-10358
Kentucky Certification #: KY90133
KY WW Permit #: KY0098221
KY WW Permit #: KY0000221
Louisiana DHH/TNI Certification #: LA180012
Louisiana DEQ/TNI Certification #: 4086
Maine Certification #: 2017020
Maryland Certification #: 308
Massachusetts Certification #: M-PA1457
Michigan/PADEP Certification #: 9991

Missouri Certification #: 235
Montana Certification #: Cert0082
Nebraska Certification #: NE-OS-29-14
Nevada Certification #: PA014572018-1
New Hampshire/TNI Certification #: 297617
New Jersey/TNI Certification #: PA051
New Mexico Certification #: PA01457
New York/TNI Certification #: 10888
North Carolina Certification #: 42706
North Dakota Certification #: R-190
Ohio EPA Rad Approval: #41249
Oregon/TNI Certification #: PA200002-010
Pennsylvania/TNI Certification #: 65-00282
Puerto Rico Certification #: PA01457
Rhode Island Certification #: 65-00282
South Dakota Certification
Tennessee Certification #: 02867
Texas/TNI Certification #: T104704188-17-3
Utah/TNI Certification #: PA014572017-9
USDA Soil Permit #: P330-17-00091
Vermont Dept. of Health: ID# VT-0282
Virgin Island/PADEP Certification
Virginia/VELAP Certification #: 9526
Washington Certification #: C868
West Virginia DEP Certification #: 143
West Virginia DHHR Certification #: 9964C
Wisconsin Approve List for Rad
Wyoming Certification #: 8TMS-L

Pace Analytical Services Green Bay

1241 Bellevue Street, Green Bay, WI 54302
Florida/NELAP Certification #: E87948
Illinois Certification #: 200050
Kentucky UST Certification #: 82
Louisiana Certification #: 04168
Minnesota Certification #: 055-999-334
New York Certification #: 12064
North Dakota Certification #: R-150

Virginia VELAP ID: 460263
South Carolina Certification #: 83006001
Texas Certification #: T104704529-14-1
Wisconsin Certification #: 405132750
Wisconsin DATCP Certification #: 105-444
USDA Soil Permit #: P330-16-00157
Federal Fish & Wildlife Permit #: LE51774A-0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE SUMMARY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40235317001	MW-301	Water	10/14/21 17:05	10/16/21 08:35
40235317002	MW-84A	Water	10/14/21 15:20	10/16/21 08:35

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

SAMPLE ANALYTE COUNT

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
40235317001	MW-301	EPA 6020B	KXS	15	PASI-G
		EPA 7470	AJT	1	PASI-G
			MEA	7	PASI-G
		EPA 903.1	SLC	1	PASI-PA
		EPA 904.0	VAL	1	PASI-PA
		Total Radium Calculation	JAL	1	PASI-PA
		SM 2540C	HNT	1	PASI-G
		EPA 9040	ALY	1	PASI-G
		EPA 300.0	HMB	3	PASI-G
		40235317002	MW-84A	EPA 6020B	KXS
EPA 7470	AJT			1	PASI-G
	MEA			7	PASI-G
EPA 903.1	SLC			1	PASI-PA
EPA 904.0	VAL			1	PASI-PA
Total Radium Calculation	JAL			1	PASI-PA
SM 2540C	HNT			1	PASI-G
EPA 9040	ALY			1	PASI-G
EPA 300.0	HMB			3	PASI-G

PASI-G = Pace Analytical Services - Green Bay
PASI-PA = Pace Analytical Services - Greensburg

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

Sample: MW-301 **Lab ID: 40235317001** Collected: 10/14/21 17:05 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Lithium	0.46J	ug/L	1.0	0.22	1	10/20/21 06:24	10/26/21 14:44	7439-93-2	
Beryllium	<0.25	ug/L	1.0	0.25	1	10/20/21 06:24	10/26/21 14:44	7440-41-7	
Boron	31.4	ug/L	10.0	3.0	1	10/20/21 06:24	10/26/21 14:44	7440-42-8	
Calcium	67800	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 14:44	7440-70-2	P6
Chromium	<1.0	ug/L	3.4	1.0	1	10/20/21 06:24	10/26/21 14:44	7440-47-3	
Cobalt	0.34J	ug/L	1.0	0.12	1	10/20/21 06:24	10/26/21 14:44	7440-48-4	
Arsenic	0.35J	ug/L	1.0	0.28	1	10/20/21 06:24	10/26/21 14:44	7440-38-2	
Selenium	<0.32	ug/L	1.1	0.32	1	10/20/21 06:24	10/26/21 14:44	7782-49-2	
Molybdenum	<0.44	ug/L	1.5	0.44	1	10/20/21 06:24	10/26/21 14:44	7439-98-7	
Cadmium	<0.15	ug/L	1.0	0.15	1	10/20/21 06:24	10/26/21 14:44	7440-43-9	
Antimony	<0.15	ug/L	1.0	0.15	1	10/20/21 06:24	10/26/21 14:44	7440-36-0	
Barium	7.7	ug/L	2.3	0.70	1	10/20/21 06:24	10/26/21 14:44	7440-39-3	
Mercury	<0.093	ug/L	0.31	0.093	1	10/20/21 06:24	10/26/21 14:44	7439-97-6	
Thallium	0.17J	ug/L	1.0	0.14	1	10/20/21 06:24	10/26/21 14:44	7440-28-0	
Lead	<0.24	ug/L	1.0	0.24	1	10/20/21 06:24	10/26/21 14:44	7439-92-1	
7470 Mercury									
Analytical Method: EPA 7470 Preparation Method: EPA 7470									
Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	11/11/21 10:35	11/12/21 13:03	7439-97-6	H1,M0
Field Data									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	7.01	Std. Units			1		10/14/21 17:05		
Field Specific Conductance	597.2	umhos/cm			1		10/14/21 17:05		
Oxygen, Dissolved	0.25	mg/L			1		10/14/21 17:05	7782-44-7	
REDOX	57.8	mV			1		10/14/21 17:05		
Turbidity	3.21	NTU			1		10/14/21 17:05		
Static Water Level	785.28	feet			1		10/14/21 17:05		
Temperature, Water (C)	11.1	deg C			1		10/14/21 17:05		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	334	mg/L	20.0	8.7	1		10/19/21 13:33		
9040 pH									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.3	Std. Units	0.10	0.010	1		10/21/21 11:12		H6
300.0 IC Anions									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	2.7	mg/L	2.0	0.43	1		11/09/21 02:59	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		11/09/21 02:59	16984-48-8	
Sulfate	17.4	mg/L	2.0	0.44	1		11/09/21 02:59	14808-79-8	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

Sample: MW-84A **Lab ID: 40235317002** Collected: 10/14/21 15:20 Received: 10/16/21 08:35 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6020B MET ICPMS									
Analytical Method: EPA 6020B Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Antimony	<0.15	ug/L	1.0	0.15	1	10/20/21 06:24	10/26/21 15:28	7440-36-0	
Arsenic	0.41J	ug/L	1.0	0.28	1	10/20/21 06:24	10/26/21 15:28	7440-38-2	
Barium	12.9	ug/L	2.3	0.70	1	10/20/21 06:24	10/26/21 15:28	7440-39-3	
Beryllium	<0.25	ug/L	1.0	0.25	1	10/20/21 06:24	10/26/21 15:28	7440-41-7	
Boron	11.1	ug/L	10.0	3.0	1	10/20/21 06:24	10/26/21 15:28	7440-42-8	
Cadmium	<0.15	ug/L	1.0	0.15	1	10/20/21 06:24	10/26/21 15:28	7440-43-9	
Calcium	75300	ug/L	254	76.2	1	10/20/21 06:24	10/26/21 15:28	7440-70-2	
Chromium	1.9J	ug/L	3.4	1.0	1	10/20/21 06:24	10/26/21 15:28	7440-47-3	
Cobalt	0.12J	ug/L	1.0	0.12	1	10/20/21 06:24	10/26/21 15:28	7440-48-4	
Lead	<0.24	ug/L	1.0	0.24	1	10/20/21 06:24	10/26/21 15:28	7439-92-1	
Lithium	0.28J	ug/L	1.0	0.22	1	10/20/21 06:24	10/26/21 15:28	7439-93-2	
Mercury	<0.093	ug/L	0.31	0.093	1	10/20/21 06:24	10/26/21 15:28	7439-97-6	
Molybdenum	<0.44	ug/L	1.5	0.44	1	10/20/21 06:24	10/26/21 15:28	7439-98-7	
Selenium	<0.32	ug/L	1.1	0.32	1	10/20/21 06:24	10/26/21 15:28	7782-49-2	
Thallium	0.19J	ug/L	1.0	0.14	1	10/20/21 06:24	10/26/21 15:28	7440-28-0	
7470 Mercury									
Analytical Method: EPA 7470 Preparation Method: EPA 7470									
Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	11/11/21 10:35	11/12/21 13:10	7439-97-6	H1
Field Data									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	7.42	Std. Units			1		10/14/21 15:20		
Field Specific Conductance	598.9	umhos/cm			1		10/14/21 15:20		
Oxygen, Dissolved	9.25	mg/L			1		10/14/21 15:20	7782-44-7	
REDOX	89.7	mV			1		10/14/21 15:20		
Turbidity	3.41	NTU			1		10/14/21 15:20		
Static Water Level	784.96	feet			1		10/14/21 15:20		
Temperature, Water (C)	12.5	deg C			1		10/14/21 15:20		
2540C Total Dissolved Solids									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	326	mg/L	20.0	8.7	1		10/19/21 13:33		
9040 pH									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.8	Std. Units	0.10	0.010	1		10/21/21 11:15		H6
300.0 IC Anions									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	3.5	mg/L	2.0	0.43	1		11/09/21 03:56	16887-00-6	M0
Fluoride	<0.095	mg/L	0.32	0.095	1		11/09/21 03:56	16984-48-8	M0
Sulfate	1.3J	mg/L	2.0	0.44	1		11/09/21 03:56	14808-79-8	M0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

QC Batch: 401437	Analysis Method: EPA 7470
QC Batch Method: EPA 7470	Analysis Description: 7470 Mercury
	Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235317001, 40235317002

METHOD BLANK: 2317754 Matrix: Water

Associated Lab Samples: 40235317001, 40235317002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Mercury	ug/L	<0.066	0.20	11/12/21 12:58	

LABORATORY CONTROL SAMPLE: 2317755

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	ug/L	5	5.6	111	85-115	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2317756 2317757

Parameter	Units	2317756		2317757		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40235317001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result						
Mercury	ug/L	<0.066	5	5	6.2	6.2	123	123	85-115	0	20 M0

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

QC Batch: 399050 Analysis Method: EPA 6020B
QC Batch Method: EPA 3010A Analysis Description: 6020B MET
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235317001, 40235317002

METHOD BLANK: 2304130 Matrix: Water
Associated Lab Samples: 40235317001, 40235317002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Antimony	ug/L	<0.15	1.0	10/26/21 13:37	
Arsenic	ug/L	<0.28	1.0	10/26/21 13:37	
Barium	ug/L	<0.70	2.3	10/26/21 13:37	
Beryllium	ug/L	<0.25	1.0	10/26/21 13:37	
Boron	ug/L	<3.0	10.0	10/26/21 13:37	
Cadmium	ug/L	<0.15	1.0	10/26/21 13:37	
Calcium	ug/L	<76.2	254	10/26/21 13:37	
Chromium	ug/L	<1.0	3.4	10/26/21 13:37	
Cobalt	ug/L	<0.12	1.0	10/26/21 13:37	
Lead	ug/L	<0.24	1.0	10/26/21 13:37	
Lithium	ug/L	<0.22	1.0	10/26/21 13:37	
Mercury	ug/L	<0.093	0.31	10/26/21 13:37	
Molybdenum	ug/L	<0.44	1.5	10/26/21 13:37	
Selenium	ug/L	<0.32	1.1	10/26/21 13:37	
Thallium	ug/L	<0.14	1.0	10/26/21 13:37	

LABORATORY CONTROL SAMPLE: 2304131

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	ug/L	250	241	96	80-120	
Arsenic	ug/L	250	239	96	80-120	
Barium	ug/L	250	243	97	80-120	
Beryllium	ug/L	250	240	96	80-120	
Boron	ug/L	250	243	97	80-120	
Cadmium	ug/L	250	244	98	80-120	
Calcium	ug/L	10000	10000	100	80-120	
Chromium	ug/L	250	232	93	80-120	
Cobalt	ug/L	250	242	97	80-120	
Lead	ug/L	250	231	93	80-120	
Lithium	ug/L	250	242	97	80-120	
Mercury	ug/L	5	5.1	102	80-120	
Molybdenum	ug/L	250	240	96	80-120	
Selenium	ug/L	250	246	98	80-120	
Thallium	ug/L	250	237	95	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

Parameter	Units	2304132		2304133		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40235317001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result								
Antimony	ug/L	<0.15	250	250	240	243	96	97	75-125	1	20		
Arsenic	ug/L	0.35J	250	250	240	241	96	96	75-125	1	20		
Barium	ug/L	7.7	250	250	251	254	97	98	75-125	1	20		
Beryllium	ug/L	<0.25	250	250	238	238	95	95	75-125	0	20		
Boron	ug/L	31.4	250	250	273	277	97	98	75-125	1	20		
Cadmium	ug/L	<0.15	250	250	243	244	97	98	75-125	1	20		
Calcium	ug/L	67800	10000	10000	77700	80700	100	129	75-125	4	20	P6	
Chromium	ug/L	<1.0	250	250	232	236	93	94	75-125	2	20		
Cobalt	ug/L	0.34J	250	250	241	245	96	98	75-125	2	20		
Lead	ug/L	<0.24	250	250	234	236	93	94	75-125	1	20		
Lithium	ug/L	0.46J	250	250	242	244	97	98	75-125	1	20		
Mercury	ug/L	<0.093	5	5	5.2	5.4	104	107	75-125	3	20		
Molybdenum	ug/L	<0.44	250	250	244	245	97	98	75-125	1	20		
Selenium	ug/L	<0.32	250	250	244	245	98	98	75-125	0	20		
Thallium	ug/L	0.17J	250	250	243	244	97	97	75-125	0	20		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

QC Batch: 398939 Analysis Method: SM 2540C
QC Batch Method: SM 2540C Analysis Description: 2540C Total Dissolved Solids
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235317001, 40235317002

METHOD BLANK: 2303507 Matrix: Water
Associated Lab Samples: 40235317001, 40235317002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	10/19/21 13:29	

LABORATORY CONTROL SAMPLE: 2303508

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	575	566	98	80-120	

SAMPLE DUPLICATE: 2303509

Parameter	Units	40235220001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	248	272	9	10	

SAMPLE DUPLICATE: 2303510

Parameter	Units	40235316003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	374	390	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

QC Batch: 399227

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40235317001, 40235317002

SAMPLE DUPLICATE: 2304971

Parameter	Units	40235095010 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.8	7.8	0	20	H6

SAMPLE DUPLICATE: 2304972

Parameter	Units	40235316004 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.8	7.8	1	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

QC Batch: 400930 Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235317001, 40235317002

METHOD BLANK: 2315482 Matrix: Water
Associated Lab Samples: 40235317001, 40235317002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	11/08/21 19:10	
Fluoride	mg/L	<0.095	0.32	11/08/21 19:10	
Sulfate	mg/L	<0.44	2.0	11/08/21 19:10	

LABORATORY CONTROL SAMPLE: 2315483

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	18.7	94	90-110	
Fluoride	mg/L	2	1.9	93	90-110	
Sulfate	mg/L	20	18.2	91	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2315484 2315485

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40235824001 Result	Spike Conc.	Spike Conc.	Conc.								
Chloride	mg/L	7.3	20	20	29.8	30.1	113	114	90-110	1	15	M0	
Fluoride	mg/L	<0.095	2	2	2.2	2.2	110	111	90-110	1	15	M0	
Sulfate	mg/L	18.5	20	20	41.0	41.1	112	113	90-110	0	15	M0	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2315486 2315487

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40235317002 Result	Spike Conc.	Spike Conc.	Conc.								
Chloride	mg/L	3.5	20	20	25.8	27.1	111	118	90-110	5	15	M0	
Fluoride	mg/L	<0.095	2	2	2.2	2.3	109	114	90-110	5	15	M0	
Sulfate	mg/L	1.3J	20	20	23.2	24.5	109	116	90-110	6	15	M0	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

Sample: MW-301 **Lab ID: 40235317001** Collected: 10/14/21 17:05 Received: 10/16/21 08:35 Matrix: Water
PWS: Site ID: Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
	Pace Analytical Services - Greensburg					
Radium-226	EPA 903.1	0.172 ± 0.337 (0.617) C:NA T:96%	pCi/L	11/17/21 12:14	13982-63-3	
	Pace Analytical Services - Greensburg					
Radium-228	EPA 904.0	-0.0327 ± 0.419 (0.973) C:61% T:89%	pCi/L	11/15/21 11:02	15262-20-1	
	Pace Analytical Services - Greensburg					
Total Radium	Total Radium Calculation	0.172 ± 0.756 (1.59)	pCi/L	11/24/21 15:38	7440-14-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
Sample: MW-84A Lab ID: 40235317002 Collected: 10/14/21 15:20 Received: 10/16/21 08:35 Matrix: Water PWS: Site ID: Sample Type:						
Pace Analytical Services - Greensburg						
Radium-226	EPA 903.1	0.000 ± 0.242 (0.493) C:NA T:100%	pCi/L	11/17/21 12:14	13982-63-3	
Pace Analytical Services - Greensburg						
Radium-228	EPA 904.0	0.243 ± 0.576 (1.27) C:60% T:88%	pCi/L	11/15/21 11:01	15262-20-1	
Pace Analytical Services - Greensburg						
Total Radium	Total Radium Calculation	0.243 ± 0.818 (1.76)	pCi/L	11/24/21 15:38	7440-14-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

QC Batch: 471019

Analysis Method: EPA 903.1

QC Batch Method: EPA 903.1

Analysis Description: 903.1 Radium-226

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40235317001, 40235317002

METHOD BLANK: 2273682

Matrix: Water

Associated Lab Samples: 40235317001, 40235317002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-226	-0.0899 ± 0.216 (0.540) C:NA T:95%	pCi/L	11/17/21 12:14	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL - RADIOCHEMISTRY

Project: 25219067 COLUMBIA CCR BACKGRND

Pace Project No.: 40235317

QC Batch: 471020

Analysis Method: EPA 904.0

QC Batch Method: EPA 904.0

Analysis Description: 904.0 Radium 228

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40235317001, 40235317002

METHOD BLANK: 2273691

Matrix: Water

Associated Lab Samples: 40235317001, 40235317002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-228	0.552 ± 0.431 (0.853) C:67% T:79%	pCi/L	11/19/21 11:42	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALIFIERS

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

DEFINITIONS

Act - Activity

Unc - Uncertainty: SDWA = 1.96 sigma count uncertainty, all other matrices = Expanded Uncertainty (95% confidence interval).

Gamma Spec = Expanded Uncertainty (95.4% Confidence Interval)

(MDC) - Minimum Detectable Concentration

Trac - Tracer Recovery (%)

Carr - Carrier Recovery (%)

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

WORKORDER QUALIFIERS

WO: 40235317

[1] Mercury by Method 7470 was analyzed past hold due to laboratory oversight. Mercury by Method 6020 has been provided as supplemental data.

ANALYTE QUALIFIERS

H1 Analysis conducted outside the recognized method holding time.

H6 Analysis initiated outside of the 15 minute EPA required holding time.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25219067 COLUMBIA CCR BACKGRND
Pace Project No.: 40235317

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40235317001	MW-301	EPA 3010A	399050	EPA 6020B	399167
40235317002	MW-84A	EPA 3010A	399050	EPA 6020B	399167
40235317001	MW-301	EPA 7470	401437	EPA 7470	401479
40235317002	MW-84A	EPA 7470	401437	EPA 7470	401479
40235317001	MW-301				
40235317002	MW-84A				
40235317001	MW-301	EPA 903.1	471019		
40235317002	MW-84A	EPA 903.1	471019		
40235317001	MW-301	EPA 904.0	471020		
40235317002	MW-84A	EPA 904.0	471020		
40235317001	MW-301	Total Radium Calculation	474011		
40235317002	MW-84A	Total Radium Calculation	474011		
40235317001	MW-301	SM 2540C	398939		
40235317002	MW-84A	SM 2540C	398939		
40235317001	MW-301	EPA 9040	399227		
40235317002	MW-84A	EPA 9040	399227		
40235317001	MW-301	EPA 300.0	400930		
40235317002	MW-84A	EPA 300.0	400930		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Order By :	Ship To :	Return To:
Company <u>SCS ENGINEERS</u>	Company <u>SCS ENGINEERS (Pace Analytical Green</u>	Company <u>Pace Analytical Green Bay</u>
Contact <u>Blodgett, Meghan</u>	Contact <u>Adam Watson</u>	Contact <u>Milewsky, Dan</u>
Email <u>mblodgett@scsengineers.com</u>	Email <u>awatson@scsengineers.com</u>	Email <u>dan.milewsky@pacelabs.com</u>
Address <u>2830 Dairy Drive</u>	Address <u>2830 Dairy Drive</u>	Address <u>1241 Bellevue Street</u>
Address 2 _____	Address 2 _____	Address 2 <u>Suite 9</u>
City <u>Madison</u>	City <u>Madison</u>	City <u>Green Bay</u>
State <u>WI</u> Zip <u>53718</u>	State <u>WI</u> Zip <u>53718</u>	State <u>WI</u> Zip <u>54302</u>
Phone <u>608-216-7362</u>	Phone <u>608-216-7362</u>	Phone <u>(920)469-2436</u>

Project Name <u>25219067 Columbia CCR Secondary Pond</u>	Due Date <u>10/08/2021</u>	Profile <u>3946-12</u>	Quote _____
Project Manager <u>Milewsky, Dan</u>	Return Date _____	Carrier <u>Most Economical</u>	Location _____

Trip Blanks

Include Trip Blanks

Bottle Labels

Blank

Pre-Printed No Sample IDs

Pre-Printed With Sample IDs

Bottles

Boxed Cases

Individually Wrapped

Grouped By Sample ID/Matrix

Return Shipping Labels

No Shipper

With Shipper

Misc

Sampling Instructions

Custody Seal

Temp. Blanks

Coolers _____

Syringes _____

Extra Bubble Wrap

Short Hold/Rush Stickers

DI Water 1 Liter(s)

USDA Regulated Soils

COC Options

Number of Blanks _____

Pre-Printed _____

# of Samples	Matrix	Test	Container	Total	# of	Lot #	Notes
4	WT	Metals	250mL plastic w/HNO3	4	0	M-1-106-03BB	
4	WT	pH	250mL plastic unpres	4	0	M-1-203-03BB	
4	WT	TDS, Cl, F, SO4	250mL plastic unpres	4	0	M-1-203-03BB	
4	WT	Radium 226	1L plastic HNO3 preserved	4	0		
4	WT	Radium 228	1L Plastic HNO3 Presered	4	0		

Hazard Shipping Placard In Place : NA

*Sample receiving hours are typically 8am-5pm, but may differ by location. Please check with your Pace Project Manager.

*Pace Analytical reserves the right to return hazardous, toxic, or radioactive samples to you.

*Pace Analytical reserves the right to charge for unused bottles, as well as cost associated with sample storage/disposal.

*Payment term are net 30 days.

*Please include the proposal number on the chain of custody to insure proper billing.

LAB USE:

Ship Date : 10/07/2021

Prepared By: Mai Yer Her

Verified By: _____

Sample

Metals=As,Ba,Cr,Co,Li,Mo,Se,Ca,B
ALL SAMPLES UNFILTERED

CLIENT USE (Optional):


Date Rec'd: _____

Received By: _____

Verified By: _____

Sample Condition Upon Receipt Form (SCUR)

Client Name: SCS Engineers

Project #:
 WO#: 40235317

 40235317

Courier: CS Logistics Fed Ex Speedee UPS Walco
 Client Pace Other: _____

Tracking #: _____
 Custody Seal on Cooler/Box Present: yes no Seals intact: yes no
 Custody Seal on Samples Present: yes no Seals intact: yes no
 Packing Material: Bubble Wrap Bubble Bags None Other
 Thermometer Used SR-107 Type of Ice: Wet Blue Dry None
 Cooler Temperature Uncorr: 5 /Corr: 5

Samples on ice, cooling process has begun
 Person examining contents:
 Date: 10/16/21 / Initials: ARJ
 Labeled By Initials: MP


Temp Blank Present: yes no Biological Tissue is Frozen: yes no

Temp should be above freezing to 6°C.
 Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	2. <u>P.I.H.</u> <u>10/16/21 ARJ</u>
Chain of Custody Relinquished:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	3. <u>does have date/time 10/16/21 ARJ</u>
Sampler Name & Signature on COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time: _____
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
-Pace Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
-Pace IR Containers Used:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix: <u>W</u>		
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased): _____		

Client Notification/ Resolution: _____ If checked, see attached form for additional comments
 Person Contacted: _____ Date/Time: _____
 Comments/ Resolution: _____

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir



Appendix D
Historical Monitoring Results

Single Location

Name: WPL - Columbia

Location ID: MW-1AR			
Number of Sampling Dates: 2			
Parameter Name	Units	4/14/2021	10/14/2021
Boron	ug/L	16.1	12.4
Calcium	ug/L	85500	87600
Chloride	mg/L	1.5	1.2
Fluoride	mg/L	<0.095	<0.095
Field pH	Std. Units	7.26	7.44
Sulfate	mg/L	4.4	3.1
Total Dissolved Solids	mg/L	318	350
Field Specific Conductance	umhos/cm	611.7	653
Oxygen, Dissolved	mg/L	7.52	7.83
Field Oxidation Potential	mV	100.4	143.6
Groundwater Elevation	feet	778.12	784.47
Temperature	deg C	7.2	14.9
Turbidity	NTU	136.1	29.69
pH at 25 Degrees C	Std. Units	7.4	7.7

Single Location

Name: WPL - Columbia

Location ID: MW-33AR															
Number of Sampling Dates: 20															
Parameter Name	Units	12/21/2015	4/5/2016	7/7/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/7/2017	10/24/2017	4/24/2018	9/21/2018	10/22/2018	4/2/2019
Boron	ug/L	954	813	794	827	812	763	760	692	697	678	601	683	682	568
Calcium	ug/L	50000	48900	50500	79000	63100	57500	66800	80700	84800	98200	99800	--	66900	131000
Chloride	mg/L	10.6	12.5	12.5	52.5	39.6	41.4	47.1	68.1	105	119	188	32.6	14.4	229
Fluoride	mg/L	<0.2	<0.2	<0.2	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.1	<0.1
Field pH	Std. Units	7.87	8.08	7.68	8.23	7.63	8.62	8.19	7.78	7.47	7.81	7.74	8.16	7.69	7.72
Sulfate	mg/L	96.2	91.5	99.2	124	132	133	139	151	164	175	163	124	112	201
Total Dissolved Solids	mg/L	356	354	364	456	440	426	446	492	598	606	692	466	388	784
Antimony	ug/L	0.14	0.11	0.18	0.79	0.11	0.12	<0.073	<0.15	0.35	--	--	--	--	--
Arsenic	ug/L	0.46	0.38	0.52	1.2	0.32	0.45	0.31	0.36	0.59	--	--	--	--	--
Barium	ug/L	25.8	24.8	26.8	47.7	37.8	33.8	35.1	37.7	42.4	--	--	--	--	--
Beryllium	ug/L	<0.13	<0.13	<0.13	0.28	<0.13	<0.13	<0.13	<0.18	0.19	--	--	--	--	--
Cadmium	ug/L	<0.089	<0.089	0.11	0.66	<0.089	<0.089	<0.089	<0.081	0.22	--	--	--	--	--
Chromium	ug/L	2.3	2.1	1.9	2.2	1.9	2	2.4	1.5	1.7	--	--	--	--	--
Cobalt	ug/L	<0.036	<0.036	0.13	0.68	0.039	0.065	<0.036	<0.085	0.23	--	--	--	--	--
Lead	ug/L	<0.04	<0.04	0.14	0.73	<0.04	0.046	<0.04	<0.2	0.35	--	--	--	--	--
Lithium	ug/L	1.3	1.3	1.1	2.8	1.4	1.3	1.2	1.4	1.4	--	--	--	--	--
Mercury	ug/L	<0.1	<0.1	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	--	--	--	--
Molybdenum	ug/L	4.7	4.1	4.4	2.4	3.8	3.6	3	1.3	2.1	--	--	--	--	--
Selenium	ug/L	2.2	2	2.1	2.9	2	2.3	2.3	1.9	2.4	--	--	--	--	--
Thallium	ug/L	<0.14	<0.14	0.17	0.76	<0.14	<0.14	<0.14	<0.14	0.31	--	--	--	--	--
Total Radium	pCi/L	0.76	0.852	1.79	1.01	1.53	0.556	0.313	0.829	1.12	--	--	--	--	--
Radium-226	pCi/L	0.202	0.709	0.835	-0.209	0.834	0.314	0.166	0.3	0.426	--	--	--	--	--
Radium-228	pCi/L	0.558	0.143	0.951	1.01	0.698	0.242	0.147	0.529	0.698	--	--	--	--	--
Field Specific Conductance	umhos/cm	607	417.6	583.4	1255	702	797	1165	689	823	804	1079	632	618.4	1312
Oxygen, Dissolved	mg/L	10.6	9.67	3.82	9.98	9.41	6.46	9.98	10.7	8.1	9.5	3	10.33	9.88	10.22
Field Oxidation Potential	mV	269	176	39.9	67.7	73.5	193.9	833	101.5	152.1	191	33.8	2.9	136.9	129
Groundwater Elevation	feet	783.77	763.29	785.19	787.36	785.66	785.88	786.39	787.27	786.11	784.13	783.09	787.9	788.77	786.63
Temperature	deg C	11.6	10.1	11.9	13.2	12.2	11.3	10.3	10.9	12.3	12.5	10.9	13.8	13.6	10.3
Turbidity	NTU	--	1.37	0.57	0.45	0.44	0.23	0.45	0.68	0.32	3.24	0.61	3.79	4.69	2.71
pH at 25 Degrees C	Std. Units	7.8	7.8	7.7	7.6	7.6	7.6	8	7.8	7.4	7.7	7.7	7.8	7.8	7.6

Location ID: MW-33AR

Number of Sampling Dates: 20

Parameter Name	Units	10/8/2019	5/28/2020	10/8/2020	4/13/2021	6/11/2021	10/12/2021							
Boron	ug/L	548	566	569	473	--	564							
Calcium	ug/L	121000	58400	57100	51600	--	53700							
Chloride	mg/L	153	15.9	27.3	26.9	--	22.6							
Fluoride	mg/L	<0.1	<0.095	<0.095	<0.095	--	<0.095							
Field pH	Std. Units	7.74	7.59	7.7	8.78	7.71	7.59							
Sulfate	mg/L	182	104	97.4	94.3	--	96.4							
Total Dissolved Solids	mg/L	634	376	270	362	--	374							
Antimony	ug/L	--	--	--	--	--	--							
Arsenic	ug/L	--	--	--	--	--	--							
Barium	ug/L	--	--	--	--	--	--							
Beryllium	ug/L	--	--	--	--	--	--							
Cadmium	ug/L	--	--	--	--	--	--							
Chromium	ug/L	--	--	--	--	--	--							
Cobalt	ug/L	--	--	--	--	--	--							
Lead	ug/L	--	--	--	--	--	--							
Lithium	ug/L	--	--	--	--	--	--							
Mercury	ug/L	--	--	--	--	--	--							
Molybdenum	ug/L	--	--	--	--	--	--							
Selenium	ug/L	--	--	--	--	--	--							
Thallium	ug/L	--	--	--	--	--	--							
Total Radium	pCi/L	--	--	--	--	--	--							
Radium-226	pCi/L	--	--	--	--	--	--							
Radium-228	pCi/L	--	--	--	--	--	--							
Field Specific Conductance	umhos/cm	1102	633.4	623.5	622	609	623.2							
Oxygen, Dissolved	mg/L	12.19	10.35	9.31	10.11	11.42	0.26							
Field Oxidation Potential	mV	165.1	199.4	160.4	125.3	85.3	90							
Groundwater Elevation	feet	788.26	786.01	785.91	784.27	784.19	783.73							
Temperature	deg C	12.8	10.7	13.8	9.8	12.7	13.5							
Turbidity	NTU	2.13	0	0	0.63	0	0							
pH at 25 Degrees C	Std. Units	7.6	7.6	7.8	7.8	--	8							

Single Location

Name: WPL - Columbia

Location ID: MW-34A		Number of Sampling Dates: 22													
Parameter Name	Units	12/21/2015	4/5/2016	7/7/2016	7/28/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/7/2017	10/24/2017	4/24/2018	9/21/2018	10/22/2018
Boron	ug/L	230/205	220	216	--	212	224	214	214	201	205	208	209	241	233
Calcium	ug/L	65300/65200	63500	60000	--	55600	62800	58900	66300	66900	67300	69600	69600	--	70100
Chloride	mg/L	4.9/4.8	5.1	5.6	--	6.8	7.1	7.2	6.2	7.8	7.4	7.6	8.2	17.1	19.9
Fluoride	mg/L	<0.2/<0.2	<0.2	<0.2	--	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.1
Field pH	Std. Units	7.91	7.92	7.52	7.4	8.19	7.43	7.71	8.03	7.57	7.39	7.67	7.8	8.12	7.64
Sulfate	mg/L	69.9/71.3	71.6	63.4	--	54.8	63.9	71.2	87.6	106	105	98	144	141	123
Total Dissolved Solids	mg/L	300/324	298	304	--	288	242	310	330	366	358	340	412	460	392
Antimony	ug/L	<0.073/<0.073	<0.073	<0.073	--	0.59	<0.073	<0.073	<0.073	<0.15	<0.15	--	--	--	--
Arsenic	ug/L	0.2/0.2	0.35	0.26	--	0.87	0.23	0.36	0.29	<0.28	0.36	--	--	--	--
Barium	ug/L	15.8/11.1	9.1	9.4	--	9.9	9.5	8.9	11.6	9.9	10.2	--	--	--	--
Beryllium	ug/L	<0.13/<0.13	<0.13	<0.13	--	0.28	<0.13	<0.13	<0.13	<0.18	<0.18	--	--	--	--
Cadmium	ug/L	<0.089/<0.089	<0.089	<0.089	--	0.51	<0.089	<0.089	<0.089	<0.081	0.089	--	--	--	--
Chromium	ug/L	2.5/2.2	2	2.2	--	2.2	1.8	1.8	2.4	1.7	1.5	--	--	--	--
Cobalt	ug/L	0.29/0.13	0.048	0.16	--	0.53	<0.036	<0.036	0.18	<0.085	0.13	--	--	--	--
Lead	ug/L	0.38/0.18	0.046	0.18	--	0.61	0.049	<0.04	0.18	<0.2	<0.2	--	--	--	--
Lithium	ug/L	0.7/0.64	0.4	0.56	--	0.8	0.51	0.46	0.57	0.45	0.62	--	--	--	--
Mercury	ug/L	<0.1/<0.1	<0.1	<0.13	--	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	--	--	--
Molybdenum	ug/L	1.1/1.1	1.1	1.1	--	1.7	1.1	1	1.1	0.93	1.1	--	--	--	--
Selenium	ug/L	0.77/1	0.78	0.71	--	1.2	0.45	0.82	1.2	0.77	1.2	--	--	--	--
Thallium	ug/L	<0.14/<0.14	<0.14	<0.14	--	0.68	<0.14	<0.14	<0.14	<0.14	0.24	--	--	--	--
Total Radium	pCi/L	0.689 /0.696	0.869	--	0.788	0.602	0.509	0.477	0.215	0.373	0.348	--	--	--	--
Radium-226	pCi/L	0.585 /0.198	0.869	--	-0.132	0.256	-0.235	0.477	0	-0.29	0.0539	--	--	--	--
Radium-228	pCi/L	0.104 /0.498	-0.021	--	0.788	0.346	0.509	-0.459	0.215	0.373	0.294	--	--	--	--
Field Specific Conductance	umhos/cm	517	386.9	494.3	503.6	819	490	470.9	843	499.1	510.6	454	581.4	578	607.7
Oxygen, Dissolved	mg/L	10	9.38	3.96	5.11	10.33	9.9	9.83	9.96	10.27	8.02	9.9	2.45	10.54	10.62
Field Oxidation Potential	mV	255	163.5	28.8	130.8	77.5	72.9	17.9	82.5	109.3	144.8	207	38.3	-2.6	118.8
Groundwater Elevation	feet	783.5	795.16	785.05	784.86	786.45	785.72	785.98	786.3	786.66	785.81	784.5	781.77	787.01	787.88
Temperature	deg C	11.7	10.9	10.8	10.9	12.2	12.3	12.3	11	11	11.5	11.7	11	12.45	12.7
Turbidity	NTU	--	4.08	6.3	4.96	2.27	0.95	2.09	15.96	3.7	2.68	14.34	2.72	24.9	9.32
pH at 25 Degrees C	Std. Units	7.7/7.7	7.7	7.4	--	7.6	7.4	7.3	7.9	7.7	7.8	7.7	7.7	7.7	7.8

Location ID: MW-34A

Number of Sampling Dates: 22

Parameter Name	Units	4/2/2019	10/8/2019	5/28/2020	10/8/2020	2/25/2021	4/13/2021	6/11/2021	10/12/2021
Boron	ug/L	204	207	210	213	--	203	--	212
Calcium	ug/L	67500	78800	58700	61300	--	61600	--	58100
Chloride	mg/L	18.7	57.9	3.9	2.1	--	2.3	--	1.9
Fluoride	mg/L	<0.1	<0.1	<0.095	<0.095	--	<0.095	--	<0.095
Field pH	Std. Units	7.73	7.79	7.4	7.81	7.57	7.93	7.61	7.68
Sulfate	mg/L	70.4	39.8	44.4	58.7	--	59.3	--	56.1
Total Dissolved Solids	mg/L	310	314	284	306	--	290	--	278
Antimony	ug/L	--	--	--	--	--	--	--	--
Arsenic	ug/L	--	--	--	--	--	--	--	--
Barium	ug/L	--	--	--	--	--	--	--	--
Beryllium	ug/L	--	--	--	--	--	--	--	--
Cadmium	ug/L	--	--	--	--	--	--	--	--
Chromium	ug/L	--	--	--	--	--	--	--	--
Cobalt	ug/L	--	--	--	--	--	--	--	--
Lead	ug/L	--	--	--	--	--	--	--	--
Lithium	ug/L	--	--	--	--	--	--	--	--
Mercury	ug/L	--	--	--	--	--	--	--	--
Molybdenum	ug/L	--	--	--	--	--	--	--	--
Selenium	ug/L	--	--	--	--	--	--	--	--
Thallium	ug/L	--	--	--	--	--	--	--	--
Total Radium	pCi/L	--	--	--	--	--	--	--	--
Radium-226	pCi/L	--	--	--	--	--	--	--	--
Radium-228	pCi/L	--	--	--	--	--	--	--	--
Field Specific Conductance	umhos/cm	531.7	572.9	459	464.2	--	472.6	472.7	478.1
Oxygen, Dissolved	mg/L	10.22	11.71	10.12	9.88	--	10.47	11.77	10.1
Field Oxidation Potential	mV	104.4	150.9	198.5	143.2	--	118.8	73.4	72.6
Groundwater Elevation	feet	786.82	787.92	785.98	785.7	--	784.77	784.66	784.42
Temperature	deg C	10.6	13.4	11.1	12.9	--	10.3	12.2	13
Turbidity	NTU	64.77	52.88	84.51	55	--	36.34	9.72	21.13
pH at 25 Degrees C	Std. Units	7.7	7.7	7.6	7.7	--	7.8	--	7.8

Single Location

Name: WPL - Columbia

Location ID: MW-84A															
Number of Sampling Dates: 20															
Parameter Name	Units	12/22/2015	4/5/2016	7/8/2016	7/28/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/8/2017	10/24/2017	4/25/2018	8/8/2018	10/24/2018
Boron	ug/L	11.9	14	14.7	--	11.1	14.7	16.1	12.9	14.8	22.9	13.8	25	12.8	10.1
Calcium	ug/L	74000	72200	67600	--	74000	76000	70800	73200	76100	74900	77500	76600	76000	74000
Chloride	mg/L	4.9	4.7	5.1	--	4.3	4.7	4.6	4.9	5.5	5.5	5.1	4.8	4.9	4.2
Fluoride	mg/L	<0.2	<0.2	<0.2	--	<0.1	<0.1	0.12	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Field pH	Std. Units	7.6	7.61	7.45	7.34	7.91	7.25	6.99	7.8	7.28	7.23	7.68	7.45	7.38	7.24
Sulfate	mg/L	4.9	4.3	3.7	--	2.6	2.7	3	2.8	2.7	2	2.2	2.8	1.9	1.6
Total Dissolved Solids	mg/L	316	322	316	--	324	316	328	342	344	342	314	328	372	330
Antimony	ug/L	<0.073	0.084	0.1	--	<0.073	<0.073	<0.073	<0.073	<0.15	<0.15	--	<0.15	<0.15	<0.15
Arsenic	ug/L	0.15	0.29	0.14	--	0.35	0.19	0.35	<0.099	<0.28	0.28	--	<0.28	<0.28	0.33
Barium	ug/L	15.3	12.7	12.2	--	14.2	18.4	13.8	14.1	13.4	14	--	14.6	13.7	14.5
Beryllium	ug/L	<0.13	<0.13	<0.13	--	<0.13	<0.13	<0.13	<0.13	<0.18	<0.18	--	<0.18	<0.18	<0.18
Cadmium	ug/L	<0.089	<0.089	<0.089	--	<0.089	<0.089	<0.089	<0.089	<0.081	<0.081	--	<0.081	--	<0.15
Chromium	ug/L	2.5	1.9	1.8	--	2	2	1.9	2.4	2	1.6	--	2.4	1.5	1.6
Cobalt	ug/L	0.095	<0.036	0.053	--	<0.036	<0.036	<0.036	<0.036	<0.085	<0.085	--	<0.085	<0.085	<0.12
Lead	ug/L	0.16	<0.04	0.39	--	0.049	0.11	<0.04	0.041	<0.2	<0.2	--	<0.2	--	<0.24
Lithium	ug/L	0.72	0.44	0.5	--	0.56	0.56	0.56	0.55	0.46	0.58	--	0.5	0.4	0.49
Mercury	ug/L	<0.1	<0.1	<0.13	--	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	<0.13	--	<0.084
Molybdenum	ug/L	<0.07	<0.07	0.073	--	0.12	<0.07	<0.07	<0.07	<0.44	<0.44	--	<0.44	<0.44	<0.44
Selenium	ug/L	<0.21	<0.21	<0.21	--	<0.21	<0.21	<0.21	<0.21	<0.32	<0.32	--	<0.32	<0.32	<0.32
Thallium	ug/L	<0.14	<0.14	<0.14	--	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	--	<0.14	<0.14	<0.14
Total Radium	pCi/L	0.593	0.0809	--	1.37	0.825	0.404	1.39	0.0929	0.676	0.509	--	0.526	0.529	0.62
Radium-226	pCi/L	0.156	-0.088	--	-0.058	0.132	0.168	0.624	0.0768	0.27	0.242	--	0.155	-0.203	0.313
Radium-228	pCi/L	0.437	0.0809	--	1.37	0.693	0.236	0.766	0.0161	0.406	0.267	--	0.371	0.529	0.307
Field Specific Conductance	umhos/cm	599	427	574.8	579.3	1002	578.2	489	948	535.3	557.2	491	581.7	617.1	609
Oxygen, Dissolved	mg/L	9.7	9.37	3.78	5.11	9.61	8.94	6.48	9.28	9.46	7.5	9.3	3.94	8.84	10.01
Field Oxidation Potential	mV	154	165.1	139.9	138.3	82.7	87	192.9	102	123.6	204.7	210	53.3	142.7	71.5
Groundwater Elevation	feet	785.31	786.3	785.89	785.61	787.22	786.63	786.7	787.16	787.63	786.68	785.32	785.88	786.55	788.32
Temperature	deg C	10.4	10.2	11.3	11	11.5	10.8	10.9	10.6	11.3	11.2	11.1	10.2	12	11.6
Turbidity	NTU	--	0.86	2.75	0.17	0.3	0.25	0.33	0.04	0.56	0.08	2.93	0.81	0.71	3.79
pH at 25 Degrees C	Std. Units	7.5	7.4	7.4	--	7.3	7.4	7.3	7.7	7.6	7.4	7.6	7.6	7.4	7.5

Location ID: MW-84A

Number of Sampling Dates: 20

Parameter Name	Units	4/3/2019	10/9/2019	2/3/2020	5/29/2020	10/8/2020	4/14/2021						
Boron	ug/L	13.6	12	15.7	10	9.7	14.3						
Calcium	ug/L	80100	73500	72700	77600	69200	69100						
Chloride	mg/L	3.6	3.9	3.7	3.7	4.3	4.4						
Fluoride	mg/L	<0.1	<0.1	--	<0.095	<0.095	<0.095						
Field pH	Std. Units	7.03	7.23	7.51	7.34	7.49	7.34						
Sulfate	mg/L	1.4	1.3	<2.2	1.5	1.3	1.4						
Total Dissolved Solids	mg/L	318	310	316	340	320	328						
Antimony	ug/L	<0.15	<0.15	--	<0.15	<0.15	0.55						
Arsenic	ug/L	<0.28	0.46	0.38	0.34	0.49	0.91						
Barium	ug/L	14.7	13.2	14	13.9	12.6	13.4						
Beryllium	ug/L	<0.18	<0.25	--	<0.25	<0.25	0.47						
Cadmium	ug/L	<0.15	<0.15	--	<0.15	<0.15	0.53						
Chromium	ug/L	1.8	1.6	1.6	1.7	1.6	2.6						
Cobalt	ug/L	<0.12	<0.12	<0.12	<0.12	<0.12	0.52						
Lead	ug/L	<0.24	<0.24	--	<0.24	<0.24	0.55						
Lithium	ug/L	0.56	0.52	0.58	0.4	0.39	1						
Mercury	ug/L	<0.084	<0.084	--	<0.084	<0.066	<0.066						
Molybdenum	ug/L	<0.44	<0.44	<0.44	<0.44	<0.44	0.62						
Selenium	ug/L	<0.32	<0.32	<0.32	<0.32	<0.32	0.48						
Thallium	ug/L	<0.14	<0.14	<0.14	<0.14	<0.14	0.66						
Total Radium	pCi/L	0.681	0.247	0.1	0.395	0.39	0.285						
Radium-226	pCi/L	0.199	0.247	0.1	0.368	0	-0.289						
Radium-228	pCi/L	0.482	-0.024	-0.153	0.0273	0.39	0.285						
Field Specific Conductance	umhos/cm	637.2	614.1	618.4	613.7	610.1	610.9						
Oxygen, Dissolved	mg/L	9.49	11.36	8.43	9.81	9.39	9.8						
Field Oxidation Potential	mV	103.4	181.7	121.5	135	153.2	95.6						
Groundwater Elevation	feet	787.35	787.79	786.5	787.02	786.1	785.84						
Temperature	deg C	10.2	11.8	10.3	10.6	11.9	10.2						
Turbidity	NTU	1.9	2.41	1.23	2.15	0	2.45						
pH at 25 Degrees C	Std. Units	7.4	7.5	7.4	7.6	7.6	7.6						

Single Location

Name: WPL - Columbia

Location ID: MW-301															
Number of Sampling Dates: 19															
Parameter Name	Units	12/22/2015	4/5/2016	7/8/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/8/2017	10/23/2017	4/25/2018	8/8/2018	10/24/2018	4/2/2019
Boron	ug/L	26.5	25.2	23.6	30.6	32.8	32.6	28.8	21.3	30.6	34.3	24.3	22.8	27.8	26.9
Calcium	ug/L	126000	115000	108000	118000	129000	124000	120000	111000	108000	87200	112000	105000	101000	126000
Chloride	mg/L	3.7	4	3.5	2.2	2	1.5	2	3.5	5.5	4	2.3	5.2	3.2	0.79
Fluoride	mg/L	<0.2	<0.2	<0.2	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Field pH	Std. Units	6.85	7.01	6.87	7.28	6.63	7.1	7.11	6.7	6.75	7.37	6.76	6.91	6.79	6.62
Sulfate	mg/L	9.3	15.3	15	13.9	12.3	6.5	10.3	17.1	31.6	27.5	8.6	21.6	19.2	4.4
Total Dissolved Solids	mg/L	478	486	464	490	444	514	502	458	462	362	464	502	424	462
Antimony	ug/L	0.15	0.094	0.13	<0.073	0.4	<0.073	<0.073	<0.15	<0.15	--	<0.15	0.36	<0.15	0.32
Arsenic	ug/L	0.26	0.26	0.19	0.24	0.4	0.13	0.18	<0.28	<0.28	--	<0.28	0.45	<0.28	0.4
Barium	ug/L	20.2	11.1	11.6	15.6	15	13.5	13.2	11.3	11.8	--	9.3	10.2	11.5	11.8
Beryllium	ug/L	<0.13	<0.13	<0.13	<0.13	0.19	<0.13	<0.13	<0.18	<0.18	--	<0.18	0.37	<0.18	0.28
Cadmium	ug/L	<0.089	<0.089	<0.089	<0.089	0.32	<0.089	<0.089	<0.081	<0.081	--	<0.081	--	<0.15	0.21
Chromium	ug/L	2.1	0.58	0.59	<0.39	0.7	0.53	0.7	2.3	<1	--	<1	<1	<1	<1
Cobalt	ug/L	1.4	0.25	0.22	0.041	0.38	0.071	0.064	0.13	0.12	--	<0.085	0.28	<0.12	0.35
Lead	ug/L	0.9	0.077	0.48	<0.04	0.34	<0.04	<0.04	<0.2	<0.2	--	<0.2	--	<0.24	0.3
Lithium	ug/L	1.3	0.58	0.69	0.6	0.87	0.67	0.68	0.62	0.6	--	0.55	0.85	0.52	0.9
Mercury	ug/L	<0.1	<0.1	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	<0.13	--	<0.084	<0.084
Molybdenum	ug/L	0.35	0.15	0.14	0.12	0.38	<0.07	<0.07	<0.44	<0.44	--	<0.44	<0.44	<0.44	<0.44
Selenium	ug/L	0.3	0.21	0.39	<0.21	0.26	<0.21	<0.21	<0.32	<0.32	--	<0.32	0.71	<0.32	0.49
Thallium	ug/L	<0.14	<0.14	<0.14	<0.14	0.48	<0.14	<0.14	<0.14	<0.14	--	<0.14	0.3	<0.14	0.48
Total Radium	pCi/L	1.31	1.11	0.89	0.631	1.01	2.42	1.35	1.3	1.74	--	0.882	0.0351	0.652	0.552
Radium-226	pCi/L	0.655	0.294	0.404	-0.067	0.108	1.46	0.513	0.287	1.09	--	0.122	-0.06	0.247	0
Radium-228	pCi/L	0.651	0.82	0.486	0.631	0.905	0.964	0.833	1.01	0.647	--	0.76	0.0351	0.405	0.552
Field Specific Conductance	umhos/cm	897	573	796	1464	859	1018	1354	698.4	691.7	561	774	799	767	883
Oxygen, Dissolved	mg/L	1.7	2.71	1.47	1.99	1.34	1.24	1.44	1.81	1.43	1.1	2.35	2.14	2.49	2.2
Field Oxidation Potential	mV	135	123.7	133.9	100.8	95.8	226.1	100.9	115.1	187.4	204	74.3	126.5	77.9	152.1
Groundwater Elevation	feet	785.56	768.12	786.31	787.64	787.37	787.27	787.89	788.25	787.34	785.89	785.29	787.06	788.98	787.04
Temperature	deg C	9.7	7.7	10	11.2	10.1	8.8	7.7	8.9	10.2	11.1	7.4	10.6	11.1	7.5
Turbidity	NTU	--	1.52	3.89	0.59	0.74	0.42	0.1	0.22	0.18	1.52	1.12	0.46	3.3	2.02
pH at 25 Degrees C	Std. Units	7	7	6.8	6.8	6.9	6.9	7.1	7	7	7.3	7	7	7.1	6.8

Location ID: MW-301

Number of Sampling Dates: 19

Parameter Name	Units	10/9/2019	2/3/2020	5/29/2020	10/8/2020	4/14/2021							
Boron	ug/L	35.9	27.9	21.3	28.8	22.2							
Calcium	ug/L	114000	113000	112000	93000	117000							
Chloride	mg/L	1.7	1.3	2	3.4	1.5							
Fluoride	mg/L	<0.1	--	<0.095	<0.095	<0.095							
Field pH	Std. Units	6.67	6.89	6.73	6.95	6.66							
Sulfate	mg/L	8.4	7.2	11.5	25.1	8.5							
Total Dissolved Solids	mg/L	418	462	452	412	472							
Antimony	ug/L	<0.15	--	<0.15	0.33	<0.15							
Arsenic	ug/L	0.42	<0.28	0.33	0.62	<0.28							
Barium	ug/L	10	10.9	9.8	9.4	8.9							
Beryllium	ug/L	<0.25	--	<0.25	<0.25	<0.25							
Cadmium	ug/L	<0.15	--	<0.15	0.19	<0.15							
Chromium	ug/L	<1	<1	<1	<1	<1							
Cobalt	ug/L	<0.12	0.17	<0.12	0.29	<0.12							
Lead	ug/L	<0.24	--	<0.24	0.25	<0.24							
Lithium	ug/L	0.61	0.67	0.47	0.46	0.58							
Mercury	ug/L	<0.084	--	<0.084	<0.066	<0.066							
Molybdenum	ug/L	<0.44	<0.44	<0.44	<0.44	<0.44							
Selenium	ug/L	<0.32	<0.32	<0.32	<0.32	<0.32							
Thallium	ug/L	<0.14	<0.14	<0.14	0.3	<0.14							
Total Radium	pCi/L	0.701	0.502	0.193	0.38	1.16							
Radium-226	pCi/L	0.252	0.136	0	0.0511	0.418							
Radium-228	pCi/L	0.449	0.366	0.193	0.329	0.739							
Field Specific Conductance	umhos/cm	801	868	797	760	857							
Oxygen, Dissolved	mg/L	1.67	1.07	2	1.22	3.9							
Field Oxidation Potential	mV	173	132.3	118.7	183.9	102.9							
Groundwater Elevation	feet	788.47	787.24	787.77	786.53	786.5							
Temperature	deg C	11.3	8.5	8.1	11	7.4							
Turbidity	NTU	2.12	1.41	0	0	2.41							
pH at 25 Degrees C	Std. Units	7	6.8	7	7.2	6.9							

Single Location


Name: WPL - Columbia

Location ID: MW-302															
Number of Sampling Dates: 19															
Parameter Name	Units	12/22/2015	4/5/2016	7/7/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/8/2017	10/24/2017	4/24/2018	9/21/2018	10/22/2018	4/2/2019
Boron	ug/L	80	78.8	134	132	106	149	322	671	833	691	1950	203	296	254
Calcium	ug/L	68800	65900	66900	71700	76100	75400	79600	88900	87100	94400	110000	--	56900	62400
Chloride	mg/L	4.2	4.1	3.1	1.1	1.2	1.6	1.6	3.5	4.5	6.9	15	1.7	1.8	1.5
Fluoride	mg/L	<0.2	<0.2	<0.2	<0.1	<0.1	0.13	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.1	<0.1
Field pH	Std. Units	7.63	7.7	7.29	7.72	7.12	8.21	7.63	7.16	7.04	8.23	7.21	7.74	7.22	7.32
Sulfate	mg/L	37.4	55.6	35.4	64.7	56.4	61.6	81.3	84.6	79	78.4	109	30	26.9	25.2
Total Dissolved Solids	mg/L	312	312	344	360	330	384	436	466	470	446	598	280	288	290
Antimony	ug/L	0.17	0.092	0.2	0.14	0.14	0.17	<0.073	<0.15	<0.15	--	--	--	--	--
Arsenic	ug/L	<0.099	0.17	0.23	0.2	<0.099	0.24	<0.099	<0.28	<0.28	--	--	--	--	--
Barium	ug/L	14.3	9.7	14.6	16.4	16.9	17.8	20.3	22	22.2	--	--	--	--	--
Beryllium	ug/L	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.18	<0.18	--	--	--	--	--
Cadmium	ug/L	<0.089	<0.089	0.14	<0.089	<0.089	<0.089	<0.089	<0.081	<0.081	--	--	--	--	--
Chromium	ug/L	2.3	3.3	2.7	1.7	2.4	2.6	2.7	2.3	2	--	--	--	--	--
Cobalt	ug/L	0.11	0.11	0.2	<0.036	0.079	0.083	0.08	<0.085	<0.085	--	--	--	--	--
Lead	ug/L	0.1	0.084	0.24	<0.04	0.073	0.075	0.047	<0.2	<0.2	--	--	--	--	--
Lithium	ug/L	17.1	13.7	4.5	3	3.3	3.2	2.7	2.2	2.4	--	--	--	--	--
Mercury	ug/L	<0.1	<0.1	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	--	--	--	--
Molybdenum	ug/L	8.9	8	2.4	1.6	1.6	1.6	1.5	1.3	1.6	--	--	--	--	--
Selenium	ug/L	2.8	2.7	1.8	1.2	2	1.6	2.5	2	2.4	--	--	--	--	--
Thallium	ug/L	<0.14	<0.14	0.24	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	--	--	--	--	--
Total Radium	pCi/L	0.184	0.505	1.21	0.4	0.252	2.6	0.555	1.45	0.731	--	--	--	--	--
Radium-226	pCi/L	0.184	0.1	-0.358	0.208	-0.103	1.37	0.077	0.649	0.193	--	--	--	--	--
Radium-228	pCi/L	-0.028	0.405	1.21	0.192	0.252	1.23	0.478	0.802	0.538	--	--	--	--	--
Field Specific Conductance	umhos/cm	566	383.6	578	1006	588.9	726	1114	641.8	679	596	894	461	507.6	538.6
Oxygen, Dissolved	mg/L	6.8	9.7	3.7	9.37	8.5	6.22	9.53	9.91	7.4	8.7	2.8	9.82	9.34	9.65
Field Oxidation Potential	mV	132	198.6	80	96.3	88.9	223.4	107.4	130.4	191.1	220	49.1	56	135.1	126.7
Groundwater Elevation	feet	784.78	778.91	786.28	787.76	787.05	786.89	787.55	788.37	787.55	785.94	784.37	788.37	789.16	787.56
Temperature	deg C	10.6	9.8	11.2	12.2	11.1	10.4	9.5	10.1	11.4	11.4	10.7	12.45	13.1	9.8
Turbidity	NTU	--	9.69	2.08	0.81	1.78	1.26	1.68	1.9	0.83	2.61	3.42	5.26	5.23	9.72
pH at 25 Degrees C	Std. Units	7.5	7.6	7.3	7.2	7.1	7.8	7.6	7.5	7.4	7.2	7.4	7.4	7.3	7.4

Location ID: MW-302

Number of Sampling Dates: 19

Parameter Name	Units	10/9/2019	5/29/2020	10/8/2020	4/13/2021	10/14/2021								
Boron	ug/L	246	611	648	521	495								
Calcium	ug/L	61400	90500	80600	82400	84100								
Chloride	mg/L	1.1	1.2	1.1	1.4	1.3								
Fluoride	mg/L	<0.1	<0.095	<0.095	<0.095	<0.095								
Field pH	Std. Units	7.08	7.2	7.21	7.51	7.07								
Sulfate	mg/L	16.7	34.6	36.5	36.9	37.8								
Total Dissolved Solids	mg/L	274	404	378	370	394								
Antimony	ug/L	--	--	--	--	--								
Arsenic	ug/L	--	--	--	--	--								
Barium	ug/L	--	--	--	--	--								
Beryllium	ug/L	--	--	--	--	--								
Cadmium	ug/L	--	--	--	--	--								
Chromium	ug/L	--	--	--	--	--								
Cobalt	ug/L	--	--	--	--	--								
Lead	ug/L	--	--	--	--	--								
Lithium	ug/L	--	--	--	--	--								
Mercury	ug/L	--	--	--	--	--								
Molybdenum	ug/L	--	--	--	--	--								
Selenium	ug/L	--	--	--	--	--								
Thallium	ug/L	--	--	--	--	--								
Total Radium	pCi/L	--	--	--	--	--								
Radium-226	pCi/L	--	--	--	--	--								
Radium-228	pCi/L	--	--	--	--	--								
Field Specific Conductance	umhos/cm	515.4	694.7	643.1	661.3	663.7								
Oxygen, Dissolved	mg/L	11.38	10	9.21	9.92	8.07								
Field Oxidation Potential	mV	134.5	169.2	152.7	127	149.1								
Groundwater Elevation	feet	788.31	787.29	786.74	785.77	785.09								
Temperature	deg C	12.6	9.8	11.8	9.6	11.5								
Turbidity	NTU	2.01	2.88	0	2.6	2.54								
pH at 25 Degrees C	Std. Units	7.4	7.4	7.6	7.4	7.7								



Appendix E
Statistical Evaluation


Prediction Limit

Columbia Energy Center Client: SCS Engineers Data: Input -191203 Printed 1/8/2020, 6:56 PM

Constituent	Well	Upper Lim.	Lower Lim.	Date	Observ.	Sig.	Bg N	Bg Wells	Bg Mean	Std. Dev.	%NDs	ND Adj.	Transform	Alpha	Method
Boron (ug/L)	MW-302	35.6	n/a	10/9/2019	246	Yes	30	MW-301,MW-84A	21.48	8.076	0	None	No	0.002922	Param Inter 1 of 2
Boron (ug/L)	MW-33AR	35.6	n/a	10/8/2019	548	Yes	30	MW-301,MW-84A	21.48	8.076	0	None	No	0.002922	Param Inter 1 of 2
Boron (ug/L)	MW-34A	35.6	n/a	10/8/2019	207	Yes	30	MW-301,MW-84A	21.48	8.076	0	None	No	0.002922	Param Inter 1 of 2
Calcium (ug/L)	MW-302	129000	n/a	10/9/2019	61400	No	30	MW-84A,MW-301	n/a	n/a	0	n/a	n/a	0.00197	NP Inter (normality) ...
Calcium (ug/L)	MW-33AR	129000	n/a	10/8/2019	121000	No	30	MW-84A,MW-301	n/a	n/a	0	n/a	n/a	0.00197	NP Inter (normality) ...
Calcium (ug/L)	MW-34A	129000	n/a	10/8/2019	78800	No	30	MW-84A,MW-301	n/a	n/a	0	n/a	n/a	0.00197	NP Inter (normality) ...
Chloride (mg/L)	MW-302	6.2	n/a	10/9/2019	1.1	No	30	MW-301,MW-84A	3.86	1.338	0	None	No	0.002922	Param Inter 1 of 2
Chloride (mg/L)	MW-33AR	6.2	n/a	10/8/2019	153	Yes	30	MW-301,MW-84A	3.86	1.338	0	None	No	0.002922	Param Inter 1 of 2
Chloride (mg/L)	MW-34A	6.2	n/a	10/8/2019	57.9	Yes	30	MW-301,MW-84A	3.86	1.338	0	None	No	0.002922	Param Inter 1 of 2
Field pH (Std. Units)	MW-302	7.78	n/a	10/9/2019	7.08	No	31	MW-301,MW-84A	7.158	0.3555	0	None	No	0.002922	Param Inter 1 of 2
Field pH (Std. Units)	MW-33AR	7.78	n/a	10/8/2019	7.74	No	31	MW-301,MW-84A	7.158	0.3555	0	None	No	0.002922	Param Inter 1 of 2
Field pH (Std. Units)	MW-34A	7.78	n/a	10/8/2019	7.79	Yes	31	MW-301,MW-84A	7.158	0.3555	0	None	No	0.002922	Param Inter 1 of 2
Fluoride (mg/L)	MW-302	0.200	n/a	10/9/2019	0.1ND	No	30	MW-301,MW-84A	n/a	n/a	96.67	n/a	n/a	0.00197	NP Inter (NDs) 1 of 2
Fluoride (mg/L)	MW-33AR	0.200	n/a	10/8/2019	0.1ND	No	30	MW-301,MW-84A	n/a	n/a	96.67	n/a	n/a	0.00197	NP Inter (NDs) 1 of 2
Fluoride (mg/L)	MW-34A	0.200	n/a	10/8/2019	0.1ND	No	30	MW-301,MW-84A	n/a	n/a	96.67	n/a	n/a	0.00197	NP Inter (NDs) 1 of 2
Sulfate (mg/L)	MW-302	30.3	n/a	10/9/2019	16.7	No	30	MW-301,MW-84A	1.735	0.9574	0	None	ln(x)	0.002922	Param Inter 1 of 2
Sulfate (mg/L)	MW-33AR	30.3	n/a	10/8/2019	182	Yes	30	MW-301,MW-84A	1.735	0.9574	0	None	ln(x)	0.002922	Param Inter 1 of 2
Sulfate (mg/L)	MW-34A	30.3	n/a	10/8/2019	39.8	Yes	30	MW-301,MW-84A	1.735	0.9574	0	None	ln(x)	0.002922	Param Inter 1 of 2
Total Dissolved Solids (mg/L)	MW-302	514	n/a	10/9/2019	274	No	30	MW-84A,MW-301	n/a	n/a	0	n/a	n/a	0.00197	NP Inter (normality) ...
Total Dissolved Solids (mg/L)	MW-33AR	514	n/a	10/8/2019	634	Yes	30	MW-84A,MW-301	n/a	n/a	0	n/a	n/a	0.00197	NP Inter (normality) ...
Total Dissolved Solids (mg/L)	MW-34A	514	n/a	10/8/2019	314	No	30	MW-84A,MW-301	n/a	n/a	0	n/a	n/a	0.00197	NP Inter (normality) ...

Exceeds Limit: MW-302, MW-33AR, MW-34A

Boron
Interwell Parametric




Background Data Summary: Mean=21.48, Std. Dev.=8.076, n=30. Seasonality was not detected with 95% confidence. Normality test: Shapiro Wilk @alpha = 0.01, calculated = 0.9105, critical = 0.9. Kappa = 1.752 (c=6, w=3, 1 of 2, event alpha = 0.05132). Report alpha = 0.008742. Individual comparison alpha = 0.002922. Comparing 3 points to limit.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Within Limit

Calcium
Interwell Non-parametric




Non-parametric test used in lieu of parametric prediction limit because the Shapiro Wilk normality test showed the data to be non-normal at the 0.01 alpha level. Limit is highest of 30 background values. Annual per-constituent alpha = 0.01176. Individual comparison alpha = 0.00197 (1 of 2). Comparing 3 points to limit. Seasonality was not detected with 95% confidence.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Exceeds Limit: MW-33AR, MW-34A

Chloride
Interwell Parametric




Background Data Summary: Mean=3.86, Std. Dev.=1.338, n=30. Seasonality was not detected with 95% confidence. Normality test: Shapiro Wilk @alpha = 0.01, calculated = 0.9071, critical = 0.9. Kappa = 1.752 (c=6, w=3, 1 of 2, event alpha = 0.05132). Report alpha = 0.008742. Individual comparison alpha = 0.002922. Comparing 3 points to limit.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Exceeds Limit: MW-34A

Field pH
Interwell Parametric



Background Data Summary: Mean=7.158, Std. Dev.=0.3555, n=31. Seasonality was not detected with 95% confidence. Normality test: Shapiro Wilk @alpha = 0.01, calculated = 0.9611, critical = 0.902. Kappa = 1.748 (c=6, w=3, 1 of 2, event alpha = 0.05132). Report alpha = 0.008742. Individual comparison alpha = 0.002922. Comparing 3 points to limit.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Prediction Limit

Constituent: Boron (ug/L) Analysis Run 1/8/2020 6:56 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)
12/21/2015			463 (D)		
12/22/2015	26.5	80			11.9
4/5/2016	25.2	78.8	516.5 (D)		14
7/7/2016		134	505 (D)		
7/8/2016	23.6				14.7
10/13/2016	30.6	132	519.5 (D)		11.1
12/29/2016	32.8	106	518 (D)		14.7
1/25/2017	32.6	149	488.5 (D)		16.1
4/11/2017	28.8	322	487 (D)		12.9
6/6/2017	21.3	671	446.5 (D)		14.8
8/7/2017			451 (D)		
8/8/2017	30.6	833			22.9
10/23/2017	34.3				
10/24/2017		691	443 (D)		13.8
4/24/2018		1950	405 (D)		
4/25/2018	24.3				25
8/8/2018	22.8				12.8
9/21/2018		203	462 (D)		
10/22/2018		296	457.5 (D)		
10/24/2018	27.8				10.1 (J)
4/2/2019	26.9	254	386 (D)		
4/3/2019					13.6
10/8/2019			548	207	
10/9/2019	35.9	246			12

Prediction Limit

Constituent: Calcium (ug/L) Analysis Run 1/8/2020 6:56 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-33AR	MW-84A (bg)	MW-302	MW-301 (bg)	MW-34A
12/21/2015	60167 (D)				
12/22/2015		74000	68800	126000	
4/5/2016	56200 (D)	72200	65900	115000	
7/7/2016	55250 (D)		66900		
7/8/2016		67600		108000	
10/13/2016	67300 (D)	74000	71700	118000	
12/29/2016	62950 (D)	76000	76100	129000	
1/25/2017	58200 (D)	70800	75400	124000	
4/11/2017	66550 (D)	73200	79600	120000	
6/6/2017	73800 (D)	76100	88900	111000	
8/7/2017	76050 (D)				
8/8/2017		74900	87100	108000	
10/23/2017				87200	
10/24/2017	83900 (D)	77500	94400		
4/24/2018	84700 (D)		110000		
4/25/2018		76600		112000	
8/8/2018		76000		105000	
10/22/2018	68500 (D)		56900		
10/24/2018		74000		101000	
4/2/2019	99250 (D)		62400	126000	
4/3/2019		80100			
10/8/2019	121000				78800
10/9/2019		73500	61400	114000	

Prediction Limit

Constituent: Chloride (mg/L) Analysis Run 1/8/2020 6:56 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)
12/21/2015			10.6	4.85 (D)	
12/22/2015	3.7 (J)	4.2			4.9
4/5/2016	4	4.1	12.5	5.1	4.7
7/7/2016		3.1 (J)	12.5	5.6	
7/8/2016	3.5 (J)				5.1
10/13/2016	2.2	1.1 (J)	52.5	6.8	4.3
12/29/2016	2 (J)	1.2 (J)	39.6	7.1	4.7
1/25/2017	1.5 (J)	1.6 (J)	41.4	7.2	4.6
4/11/2017	2	1.6 (J)	47.1	6.2	4.9
6/6/2017	3.5	3.5	68.1	7.8	5.5
8/7/2017			105	7.4	
8/8/2017	5.5	4.5			5.5
10/23/2017	4				
10/24/2017		6.9	119	7.6	5.1
4/24/2018		15	188	8.2	
4/25/2018	2.3				4.8
8/8/2018	5.2				4.9
9/21/2018		1.7 (J)	32.6	17.1	
10/22/2018		1.8 (J)	14.4	19.9	
10/24/2018	3.2				4.2
4/2/2019	0.79 (J)	1.5 (J)	229	18.7	
4/3/2019					3.6
10/8/2019			153	57.9	
10/9/2019	1.7 (J)	1.1 (J)			3.9


Prediction Limit

Constituent: Field pH (Std. Units) Analysis Run 1/8/2020 6:56 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)
12/21/2015			7.87	7.91	
12/22/2015	6.85	7.63			7.6
4/5/2016	7.01	7.7	8.08	7.92	7.61
7/7/2016		7.29	7.68	7.52	
7/8/2016	6.87				7.45
7/28/2016				7.4	7.34
10/13/2016	7.28	7.72	8.23	8.19	7.91
12/29/2016	6.63	7.12	7.63	7.43	7.25
1/25/2017	7.1	8.21	8.62	7.71	6.99
4/11/2017	7.11	7.63	8.19	8.03	7.8
6/6/2017	6.7	7.16	7.78	7.57	7.28
8/7/2017			7.47	7.39	
8/8/2017	6.75	7.04			7.23
10/23/2017	7.37				
10/24/2017		8.23	7.81	7.67	7.68
4/24/2018		7.21	7.74	7.8	
4/25/2018	6.76				7.45
8/8/2018	6.91				7.38
9/21/2018		7.74	8.16	8.12	
10/22/2018		7.22	7.69	7.64	
10/24/2018	6.79				7.24
4/2/2019	6.62	7.32	7.72	7.73	
4/3/2019					7.03
10/8/2019			7.74	7.79	
10/9/2019	6.67	7.08			7.23

Within Limit

Fluoride Interwell Non-parametric




Non-parametric test used in lieu of parametric prediction limit because censored data exceeded 50%. Limit is highest of 30 background values. 96.67% NDs. Annual per-constituent alpha = 0.01176. Individual comparison alpha = 0.00197 (1 of 2). Comparing 3 points to limit. Seasonality was not detected with 95% confidence.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Exceeds Limit: MW-33AR, MW-34A

Sulfate Interwell Parametric




Background Data Summary (based on natural log transformation): Mean=1.735, Std. Dev.=0.9574, n=30. Seasonality was not detected with 95% confidence. Normality test: Shapiro Wilk @alpha = 0.01, calculated = 0.9384, critical = 0.9. Kappa = 1.752 (c=6, w=3, 1 of 2, event alpha = 0.05132). Report alpha = 0.008742. Individual comparison alpha = 0.002922. Comparing 3 points to limit.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Exceeds Limit: MW-33AR

Total Dissolved Solids Interwell Non-parametric



Non-parametric test used in lieu of parametric prediction limit because the Shapiro Wilk normality test showed the data to be non-normal at the 0.01 alpha level. Limit is highest of 30 background values. Annual per-constituent alpha = 0.01176. Individual comparison alpha = 0.00197 (1 of 2). Comparing 3 points to limit. Seasonality was not detected with 95% confidence.

Prediction Limit Analysis Run 1/8/2020 6:54 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

Prediction Limit

Constituent: Fluoride (mg/L) Analysis Run 1/8/2020 6:56 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-33AR	MW-34A	MW-301 (bg)	MW-84A (bg)	MW-302
12/21/2015	<0.2	<0.2 (D)			
12/22/2015			<0.2	<0.2	<0.2
4/5/2016	<0.2	<0.2	<0.2	<0.2	<0.2
7/7/2016	<0.2	<0.2			<0.2
7/8/2016			<0.2	<0.2	
10/13/2016	<0.5	<0.1	<0.1	<0.1	<0.1
12/29/2016	<0.1	<0.1	<0.1	<0.1	<0.1
1/25/2017	<0.1	<0.1	<0.1	0.12 (J)	0.13 (J)
4/11/2017	<0.1	<0.1	<0.1	<0.1	<0.1
6/6/2017	<0.1	<0.1	<0.1	<0.1	<0.1
8/7/2017	<0.1	<0.1			
8/8/2017			<0.1	<0.1	<0.1
10/23/2017			<0.1		
10/24/2017	<0.1	<0.1		<0.1	<0.1
4/24/2018	<0.1	<0.1			<0.1
4/25/2018			<0.1	<0.1	
8/8/2018			<0.1	<0.1	
10/22/2018	<0.1	<0.1			<0.1
10/24/2018			<0.1	<0.1	
4/2/2019	<0.1	<0.1	<0.1		<0.1
4/3/2019				<0.1	
10/8/2019	<0.1	<0.1			
10/9/2019			<0.1	<0.1	<0.1

Prediction Limit

Constituent: Sulfate (mg/L) Analysis Run 1/8/2020 6:56 PM
Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)
12/21/2015			96.2	70.6 (D)	
12/22/2015	9.3	37.4			4.9
4/5/2016	15.3	55.6	91.5	71.6	4.3
7/7/2016		35.4	99.2	63.4	
7/8/2016	15				3.7 (J)
10/13/2016	13.9	64.7	124	54.8	2.6 (J)
12/29/2016	12.3 (J)	56.4	132	63.9	2.7 (J)
1/25/2017	6.5	61.6	133	71.2	3
4/11/2017	10.3	81.3	139	87.6	2.8 (J)
6/6/2017	17.1	84.6	151	106	2.7 (J)
8/7/2017			164	105	
8/8/2017	31.6	79			2 (J)
10/23/2017	27.5				
10/24/2017		78.4	175	98	2.2 (J)
4/24/2018		109	163	144	
4/25/2018	8.6				2.8 (J)
8/8/2018	21.6				1.9 (J)
9/21/2018		30	124	141	
10/22/2018		26.9	112	123	
10/24/2018	19.2				1.6 (J)
4/2/2019	4.4	25.2	201	70.4	
4/3/2019					1.4 (J)
10/8/2019			182	39.8	
10/9/2019	8.4	16.7			1.3 (J)

Prediction Limit

Constituent: Total Dissolved Solids (mg/L) Analysis Run 1/8/2020 6:56 PM

Columbia Energy Center Client: SCS Engineers Data: Input -191203

	MW-34A	MW-33AR	MW-301 (bg)	MW-84A (bg)	MW-302
12/21/2015	312 (D)	356			
12/22/2015			478	316	312
4/5/2016	298	354	486	322	312
7/7/2016	304	364			344
7/8/2016			464	316	
10/13/2016	288	456	490	324	360
12/29/2016	242	440	444	316	330
1/25/2017	310	426	514	328	384
4/11/2017	330	446	502	342	436
6/6/2017	366	492	458	344	466
8/7/2017	358	598			
8/8/2017			462	342	470
10/23/2017			362		
10/24/2017	340	606		314	446
4/24/2018	412	692			598
4/25/2018			464	328	
8/8/2018			502	372	
9/21/2018	460	466			280
10/22/2018	392	388			288
10/24/2018			424	330	
4/2/2019	310	784	462		290
4/3/2019				318	
10/8/2019	314	634			
10/9/2019			418	310	274

Attachment E

Sanitas Settings

Test for Normality using Shapiro-Wilk/Francia at Alpha = 0.01

Use Non-Parametric Test when Non-Detects Percent > 50

Use Aitchison's Adjustment when Non-Detects Percent > 15

Optional Further Refinement: Use when NDs % > 50

Use Poisson Prediction Limit when Non-Detects Percent > 0

Transformation

Use Ladder of Powers

Natural Log or No Transformation

Never Transform

Use Specific Transformation: Natural Log

Use Best W Statistic

Plot Transformed Values

Deseasonalize (Intra- and InterWell)

If Seasonality Is Detected

If Seasonality Is Detected Or Insufficient to Test

Always (When Sufficient Data) Never

Always Use Non-Parametric

Facility α

Statistical Evaluations per Year: 2

Constituents Analyzed: 6

Downgradient (Compliance) Wells: 3

Sampling Plan

Comparing Individual Observations

1 of 1 1 of 2 1 of 3 1 of 4

2 of 4 ("Modified California")

IntraWell Other

Stop if Background Trend Detected at Alpha = 0.05

Plot Background Data

Override Standard Deviation:

Override DF: Override Kappa:

Automatically Remove Background Outliers

2-Tailed Test Mode...

Show Deselected Data Lighter

Non-Parametric Limit = Highest Background Value

Non-Parametric Limit when 100% Non-Detects:

Highest/Second Highest Background Value

Most Recent PQL if available, or MDL

Most Recent Background Value (subst. method)

Rank Von Neumann, Wilcoxon Rank Sum / Mann-Whitney


- Use Modified Alpha...
- 2-Tailed Test Mode...
- Combine Background Wells on Mann-Whitney...

Outlier Tests


- EPA 1989 Outlier Screening (fixed alpha of 0.05)
- Dixon's at $\alpha=$ or if n > Rosner's at $\alpha=$ Use EPA Screening to establish Suspected Outliers
- Tukey's Outlier Screening, with IQR Multiplier = Use Ladder of Powers to achieve Best W Stat
- Test For Normality using Shapiro-Wilk/Francia at Alpha = 0.05
 - Stop if Non-Normal
 - Continue with Parametric Test if Non-Normal
 - Tukey's if Non-Normal, with IQR Multiplier = Use Ladder of Powers to achieve Best W Stat
- No Outlier If Less Than Times Median
- Apply Rules found in Ohio Guidance Document 0715
- Combine Background Wells on the Outlier Report...

Piper, Stiff Diagram

- Combine Wells Label Constituents
- Combine Dates Label Axes
- Use Default Constituent Names Note Cation-Anion Balance (Piper only)
- Use Constituent Definition File



Appendix F
Alternative Source Demonstrations



Appendix F1
October 2020 Detection Monitoring

Alternative Source Demonstration October 2020 Detection Monitoring

Dry Ash Disposal Facility, Modules 1-3
Columbia Energy Center
Pardeeville, Wisconsin

Prepared for:



SCS ENGINEERS

25221067.00 | April 15, 2021

2830 Dairy Drive
Madison, WI 53718-6751
608-224-2830

Table of Contents

Section	Page
PE Certification	iii
1.0 Introduction	1
1.1 §257.94(e)(2) Alternative Source Demonstration Requirements	1
1.2 Site Information and Map	1
1.3 Statistically Significant Increases Identified	2
1.4 Overview of Alternative Source Demonstration.....	2
2.0 Background	3
2.1 Regional Geology and Hydrogeology	3
2.1.1 Regional Information.....	3
2.1.2 Site Information.....	3
2.2 CCR Rule Monitoring System	3
2.3 Other Monitoring Wells.....	4
3.0 Methodology and Analysis Review	4
3.1 Sampling and Field Analysis	4
3.2 Laboratory Analysis Review	4
3.3 Statistical Evaluation Review.....	5
3.4 Summary of Methodology and Analysis Review Findings.....	5
4.0 Alternative Sources	5
4.1 Potential Causes of SSI.....	5
4.1.1 Natural Variation	5
4.1.2 Man-Made Alternative Sources	5
4.2 Lines of Evidence	6
4.2.1 Pre-Landfill Water Quality	6
4.2.2 Long-Term Concentration Trends.....	6
4.2.3 Groundwater Flow Direction Changes.....	7
4.2.4 Chloride and Boron Leachate Concentrations	7
5.0 Alternative Source Demonstration Conclusions	8
6.0 Site Groundwater Monitoring Recommendations	8
7.0 References	8

Tables

Table 1.	Groundwater Analytical Results Summary – October 2020 Event
Table 2.	Historical Analytical Results for Parameters with SSIs
Table 3.	Groundwater Elevation – State Monitoring Program and CCR Well Network
Table 4.	Analytical Results – Lysimeters and Leachate Pond

Figures




- Figure 1. Site Location Map
- Figure 2. Site Plan and Monitoring Well Locations
- Figure 3. Water Table Map – October 2020

Appendices

- Appendix A Trend Plots for CCR Wells
- Appendix B Feasibility Study Water Quality Information
- Appendix C Long-Term Concentration Trend Plots
- Appendix D Historical Groundwater Flow Maps

I:\25221067.00\Deliverables\2020 Oct ASD MOD 1-3 LF\210415_COL_1-3 LF_Oct20 ASD_Final.docx

PE CERTIFICATION

	<p>I, Sherren Clark, hereby certify that that the information in this alternative source demonstration is accurate and meets the requirements of 40 CFR 257.94(e)(2). This certification is based on my review of the groundwater data and related site information available for the Columbia Energy Center Dry Ash Disposal Facility. I am a duly licensed Professional Engineer under the laws of the State of Wisconsin.</p>
	<p style="text-align: center;">  4-15-2021 </p>
	<p>(signature) (date)</p>
	<p style="text-align: center;">  (printed or typed name) </p> <p>License number E-29863</p> <p>My license renewal date is July 31, 2022.</p> <p>Pages or sheets covered by this seal: Alternative Source Demonstration, October 2020 Detection Monitoring, Dry Ash Disposal Facility, Modules 1-3, Columbia Energy Center, Pardeeville, Wisconsin</p>

[This page left blank intentionally]

1.0 INTRODUCTION

This Alternative Source Demonstration (ASD) was prepared to support compliance with the groundwater monitoring requirements of the “Coal Combustion Residuals (CCR) Final Rule” published by the U.S. Environmental Protection Agency (USEPA) in the *Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule*, dated April 17, 2015 (USEPA, 2015), and subsequent amendments. Specifically, this report was prepared to fulfill the requirements of 40 CFR 257.94(e)(2). The applicable sections of the Rule are provided below in *italics*.

1.1 §257.94(E)(2) ALTERNATIVE SOURCE DEMONSTRATION REQUIREMENTS

The owner and operator may demonstrate that a source other than the CCR Unit caused the statistically significant increase over background levels for a constituent or that the statistically significant increase resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality. The owner or operator must complete the written demonstration within 90 days of detecting a statistically significant increase over background levels.

An ASD is completed when there are exceedances of one or more benchmarks established within the groundwater monitoring program. The ASD is completed to determine if any other sources are likely causes of the identified exceedance(s) of established benchmark(s) at the site. This ASD was performed in response to results indicating a statistically significant increase (SSI) over background levels during detection monitoring under the CCR Rule.

This ASD report is evaluating the SSIs observed in the statistical evaluation of the October 2020 detection monitoring event at the Columbia Energy Center (COL) Dry Ash Disposal Facility, Modules 1-3 CCR Units. The first ASD was prepared for this facility evaluating the SSIs observed in the statistical evaluation of the October 2017 detection monitoring event (SCS Engineers [SCS], 2018). The October 2017 ASD and subsequent semiannual updates have concluded that several lines of evidence demonstrated that SSIs reported for boron, chloride, and sulfate concentrations in the downgradient monitoring wells were likely due to man-made sources other than the CCR Units and/or naturally occurring constituents in the alluvial aquifer.

As discussed in more detail in **Section 4.2** of this ASD, the findings for the October 2020 monitoring event were consistent with those for the previous events.

1.2 SITE INFORMATION AND MAP

The COL site is located at W8375 Murray Road, Pardeeville, Columbia County, Wisconsin (**Figure 1**). The COL site is an active coal-burning generating station, which has been burning coal and disposing of CCR on site since the mid-1970s. The layout of the site is shown on **Figure 2**. The COL property includes two areas of CCR storage and disposal. These are the Dry Ash Disposal Facility (ADF) and the Ash Ponds Facility. This ASD will evaluate the conditions at the site for Modules 1-3 of the ADF only. The ADF is operated under the Wisconsin Department of Natural Resources (WDNR) License No. 3025.

The groundwater monitoring system for the COL ADF Modules 1-3 (MOD 1-3) is a multi-unit system, monitoring three existing CCR Units:

- COL Dry ADF – Modules 1-3 (existing CCR Landfill)

Modules 1-3 were previously described as separate existing CCR landfills, although they are contiguous and are managed as a single landfill by the facility and by the WDNR. WPL recently clarified that Modules 1-3 are one existing CCR landfill under the federal CCR Rule, and this report reflects WPL's clarification.

A map showing the CCR Units and all background (or upgradient) and downgradient monitoring wells with identification numbers for the CCR groundwater monitoring program and the state monitoring program is provided as **Figure 2**. Separate monitoring systems have been established for the other CCR units at COL, which include Module 4 of the COL ADF, the primary ash pond, and the secondary ash pond.

1.3 STATISTICALLY SIGNIFICANT INCREASES IDENTIFIED

SSIs were identified by comparing the monitoring results to Upper Prediction Limits (UPLs) established in accordance with 40 CFR 257.93(f)(3) and the statistical method previously selected for the CCR Unit. The UPLs are based on an interwell approach using two background monitoring wells: MW-84A and MW-301. The interwell UPLs were calculated based on a 1-of-2 resampling approach. Resampling was completed in February 2021 for pH at MW-34A. The UPLs and results for the October 2020 monitoring event, including the February resample, are summarized in the attached **Table 1**.

The October 2020 SSIs include the following parameters and wells:

- Boron: MW-33AR, MW-34A, MW-302
- Chloride: MW-33AR
- Sulfate: MW-33AR, MW-34A, MW-302

Field pH exceeded the UPL in the October 2020 sample, but not in the February 2021 resample; therefore, it is not an SSI under the 1-of-2 resampling approach. Concentration trends for the parameters with SSIs are shown in **Appendix A**.

1.4 OVERVIEW OF ALTERNATIVE SOURCE DEMONSTRATION

This ASD report includes:

- Background information (**Section 2.0**)
- Evaluation of potential that SSIs are due to methodology or analysis (**Section 3.0**)
- Evaluation of potential that SSIs are due to natural sources or man-made sources other than the CCR Units (**Section 4.0**)
- ASD conclusions (**Section 5.0**)
- Monitoring recommendations (**Section 6.0**)

The CCR Rule constituent results from background and compliance sampling for parameters with SSIs are provided in **Table 2**. The laboratory reports for the October 2020 detection monitoring event were included in the 2020 Annual Groundwater Monitoring and Corrective Action Report completed in January 2021. Complete laboratory reports for the background monitoring events and the

previous detection monitoring events were included in previous annual groundwater monitoring and corrective action reports.

2.0 BACKGROUND

To provide context for the ASD evaluation, the following background information is provided in this section of the report, prior to the ASD evaluation sections:

- Geologic and hydrogeologic setting
- CCR Rule monitoring system
- Other monitoring wells

A more detailed discussion of the background information for the site is provided in the ASD for the October 2017 event (SCS, 2018).

2.1 REGIONAL GEOLOGY AND HYDROGEOLOGY

2.1.1 Regional Information

For the purposes of groundwater monitoring, the surficial sand and gravel aquifer is considered the uppermost aquifer, as defined under 40 CFR 257.53. Immediately underlying the surficial sand and gravel aquifer is the Cambrian-Ordovician sandstone aquifer.

Additional details on the regional geology and hydrogeology were provided in the October 2017 ASD (SCS, 2018).

2.1.2 Site Information

Soils at the site are primarily sand to a depth of approximately 50 to 100 feet, and overlie sandstone bedrock. Soils encountered during the site feasibility study for the COL ADF were described as generally sandy with interbedded silty clay lenses up to 20 feet thick (Warzyn, 1978). During drilling of CCR wells MW-301 and MW-302, the unconsolidated materials were identified as consisting primarily of silty sand. Boring logs for previously installed monitoring wells MW-33AR, MW-34A, MW-84A, and M-4R show silty sand and sand as the primary unconsolidated materials at these locations. All CCR monitoring wells are screened within the unconsolidated sand unit.

Shallow groundwater at the site generally flows to the north and west across the existing landfill Mod 1-3 area, then generally flows west toward the Wisconsin River. A groundwater flow map for October 2020 is shown on **Figure 3**. The groundwater elevation data for the CCR monitoring wells and state monitoring program wells are provided in **Table 3**.

2.2 CCR RULE MONITORING SYSTEM

The groundwater monitoring system established in accordance with the CCR Rule consists of two upgradient (background) monitoring wells and three downgradient monitoring wells. The background wells include MW-301 and MW-84A. The downgradient wells include MW-302, MW-33AR, and MW-34A. The CCR Rule wells are installed within the sand and gravel aquifer. Well depths range from approximately 29 to 40 feet, measured from the top of the well casing.

2.3 OTHER MONITORING WELLS

Additional groundwater monitoring wells currently exist at COL as part of the monitoring systems developed for the state monitoring program and for the other CCR Units.

Monitoring wells for the state monitoring program are installed in the unconsolidated sand and gravel unit, which is the uppermost aquifer as defined under 40 CFR 257.53. This shallow monitoring system includes water table wells and mid-depth piezometers. Well depths range from approximately 14 to 76 feet, measured from the top of the well casing.

3.0 METHODOLOGY AND ANALYSIS REVIEW

To evaluate the potential that an SSI is due to a source other than the regulated CCR Unit, SCS used a two-step evaluation process. First, the sample collection, field and laboratory analysis, and statistical evaluation were reviewed to identify any potential error or analysis that led to exceedance of the benchmark. Second, potential alternative sources, including natural variation and man-made sources other than the CCR Unit, were evaluated. This section of the report provides the findings of the methodology and analysis review. **Section 4.0** of the report addresses the potential alternative sources.

3.1 SAMPLING AND FIELD ANALYSIS

Field notes and sampling results were reviewed to determine if any sampling error may have caused or contributed to the observed SSIs. Potential field sampling errors or issues could include mislabeling of samples, improper sample handling, missed holding times, cross contamination during sampling, or other field error. Field blank sample results were also reviewed for any indication of potential contamination from sampling equipment or containers. Based on the review of the field notes and results, SCS did not identify any indication that the SSI concentrations were due to a sampling error.

SCS did not identify any issues with the sampling procedures or field analysis based on review of the data and field notes. Because boron, chloride, and sulfate are laboratory parameters, there is little potential for a field analysis error to contribute to an SSI.

3.2 LABORATORY ANALYSIS REVIEW

The laboratory reports for the October 2020 detection monitoring event were reviewed to determine if any laboratory analysis error or issue may have caused or contributed to an observed SSI for boron, chloride, or sulfate. The laboratory report review included reviewing the laboratory quality control flags and narrative, verifying that correct methods were used and desired detection limits were achieved, and checking the field and laboratory blank sample results.

Based on the review of the laboratory reports, SCS did not identify any indication that the SSIs were due to a laboratory analysis error. There were no laboratory quality control flags or issues identified in the laboratory report that affect the usability of the data for detection monitoring.

Time series plots of the SSI constituent analytical data were also reviewed for any anomalous results that might indicate a possible sampling or laboratory error (e.g., dilution error or incorrect sample labeling). The time series plots are provided in **Appendix A**. The concentrations observed are similar to historical concentrations.

3.3 STATISTICAL EVALUATION REVIEW

The review of the statistical results and methods included a quality control check of the following:

- Input analytical data vs. laboratory analytical reports
- Statistical method and process for each SSI

Based on the review of the statistical evaluation, SCS did not identify any errors or issues in the statistical evaluation that caused or contributed to the determination of interwell SSIs for the October 2020 detection monitoring event. For the October 2020 event, SCS recalculated the Appendix III parameter UPLs using additional rounds of groundwater data collected since the first calculations of the Appendix III parameter UPLs in early 2018. The updated UPLs are shown in **Table 1**.

3.4 SUMMARY OF METHODOLOGY AND ANALYSIS REVIEW FINDINGS

In summary, there were no changes to the SSI determinations for the October 2020 monitoring event based on the methodology and analysis review. No errors or issues caused or contributed to the reported SSIs identified.

4.0 ALTERNATIVE SOURCES

This section of the report discusses the potential alternative sources for the boron, chloride, and sulfate SSIs at the downgradient monitoring wells; identifies the most likely alternative source(s); and presents the lines of evidence indicating that an alternative source is the most likely cause of the observed SSIs.

4.1 POTENTIAL CAUSES OF SSI

4.1.1 Natural Variation

The statistical analysis was completed using an interwell approach, comparing the October 2020 detection monitoring results to the UPLs calculated based on sampling of the background wells (MW-84A and MW-301). If concentrations of a constituent that is naturally present in the aquifer vary spatially, then the potential exists that the downgradient concentrations may be higher than upgradient concentrations due to natural variation. Previous compliance results for boron, chloride, and sulfate at COL MOD 1-3 LF are shown in **Table 2**.

Although natural variation is present in the shallow aquifer, it does not appear likely that natural variation is the primary source causing the boron, chloride, and sulfate SSIs.

4.1.2 Man-Made Alternative Sources

Man-made alternative sources that could potentially contribute to the boron, chloride, and sulfate SSIs could include the closed ash pond landfill, the active ash ponds, the former ash pond effluent ditch, the coal storage area, road salt use, railroad operations, or other plant operations.

Based on the groundwater flow directions and on previous investigations at the site, the former ash pond effluent ditch appears to be the most likely cause of the boron and/or sulfate SSIs for wells

MW-33AR, MW-34A, and MW-302. The ash pond effluent ditch also likely contributed to the chloride SSIs at MW-33AR.

4.2 LINES OF EVIDENCE

The lines of evidence indicating that the SSIs for boron, chloride, and sulfate in compliance wells MW-33AR, MW-34A, and MW-302, relative to the background wells, are due to an alternative source include:

1. Elevated concentrations of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located, before the landfill was constructed.
2. Monitoring performed under the state program documents that the concentrations of boron, chloride, and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation.
3. Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west and/or north.
4. The increased and variable chloride results for well B-33AR in the last 2 years have not correlated with an increase in boron, as would be expected for a CCR leachate source; therefore, an alternative source is more likely.

4.2.1 Pre-Landfill Water Quality

Elevated concentrations of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located, before the landfill was constructed. Groundwater monitoring performed in 1977 and 1978 as part of the feasibility study for the landfill permitting showed that wells located along the west side of the future landfill footprint, where the current compliance wells are located, had elevated results for sulfate, chloride, and specific conductance.

The 1978 Feasibility Study (Warzyn, 1978) for the dry ADF discusses the influence of the ash pond effluent ditch on groundwater west of the proposed site. The former ash pond effluent ditch, shown on **Figure 2**, carried effluent from the ash ponds located north of the plant, and flowed south between the west side of the current landfill and the substation. Groundwater monitoring in December 1977 indicated that sulfate was present at 1,200 milligrams per liter (mg/L) in MW-33A, which was located near the point where the ash pond effluent discharged from a culvert into the effluent ditch. The sulfate concentration at this well decreased to 830 mg/L in the December 1978 sampling (Warzyn, 1979). Current concentrations of sulfate in this area, while above background, are much lower. The October 2020 sulfate result for MW-33AR (installed to replace MW-33A) was 97.4 mg/L, for MW-34A was 58.7 mg/L, and for MW-302 was 36.5 mg/L.

Selected text and tables from the 1978 Feasibility Study and the 1979 Supplementary Feasibility Study Report are included in **Appendix B**.

4.2.2 Long-Term Concentration Trends

Monitoring performed under the state program documents that the concentrations of boron and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation. Routine groundwater monitoring for the COL ADF began after the Plan

of Operation was approved and prior to initial CCR disposal. The earliest data available from the WDNR Groundwater Environmental Monitoring System (GEMS) database is from September 1984. Initial placement of CCR in test plots in Module 1 of the ADF was approved in October 1984 and CCR disposal began sometime after that. Therefore, the initial groundwater monitoring results in the GEMS database represent pre-disposal conditions for the landfill.

The historic monitoring data show that concentrations of boron and sulfate were significantly higher in the area west of the landfill where the compliance wells are located. Graphs of historical concentrations are provided in **Appendix C**. Results for compliance well MW-33AR are plotted with results from well MW-33A. MW-33AR was a replacement well for MW-33A at a slightly different location and depth. The well screen was installed approximately 10 feet higher in MW-33AR than in MW-33A, intersecting the water table, which may explain the increase in concentration that occurred with the well replacement. Results for compliance well MW-302 are plotted with results from monitoring well MW-85, which was located near the current MW-302 location (see **Figure 2**) and was monitored from September 1984 through September 1995.

The recent boron concentrations are consistent with generally decreasing or stable historical concentrations at MW-33AR and MW-34A (**Appendix A** and **Appendix C**).

4.2.3 Groundwater Flow Direction Changes

Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west. The 1978 Feasibility Study report states that the southern 2/3 of the proposed fill area (including the area of the active CCR landfill phases) exhibits a southeast and southerly groundwater flow direction, toward an agricultural drainage ditch southeast and south of the landfill area. The 1981 Plan of Operation indicates that flow in the landfill area is to the east-southeast. A water table map prepared by RMT, based on October 2002 water level measurements, shows flow under the landfill generally to the east and northeast from a groundwater high near the effluent ditch and Wisconsin Pollutant Discharge Elimination System (WPDES) pond between the landfill and the substation. The 1981 and 2002 water table maps are provided in **Appendix D**.

Under current conditions, groundwater flow below the active landfill area is generally to the west and northwest. The flow changes with time reflect the termination of discharge to the ash pond effluent ditch in the mid-2000s. When discharge via this ditch was active, the ditch was a source of recharge to the groundwater and created a high groundwater area with flow moving away from the ditch to the east. After discharge to the ditch was terminated, water levels in this area decreased significantly and the groundwater flow direction changed.

With the changes in groundwater flow, historically impacted groundwater moved in alternating directions. While the effluent ditch was active, impacted groundwater likely moved eastward past the current compliance wells, as indicated by the long-term concentration data. Although the compliance wells are downgradient from the landfill under current flow conditions, the observed groundwater impacts may be residual from the past when the wells were downgradient from the effluent ditch.

4.2.4 Chloride and Boron Leachate Concentrations

The chloride results for well MW-33AR increased beginning in 2016, peaked in April 2018 and April 2019, and decreased significantly in 2020, without a corresponding increase or variability in boron (**Table 2** and **Appendix A**). The lack of correlation with boron indicates the source of the increase and

subsequent decrease in chloride is not likely the CCR landfill. Sampling of the landfill leachate pond and the lysimeters indicates that boron and chloride concentrations are generally both elevated in leachate (**Table 4**); therefore, a leachate source would tend to influence concentrations of both parameters. Furthermore, the peak chloride concentrations in the groundwater samples from MW-33AR in 2018 and 2019 exceeded the chloride concentrations measured in the leachate, with the exception of the October 2020 chloride result at LP-1 (**Table 4**), indicating the leachate is not the source of chloride at this location (**Tables 2 and 4**). An alternative man-made source, such as road salt, is a more likely source of chloride than the CCR Units.

5.0 ALTERNATIVE SOURCE DEMONSTRATION CONCLUSIONS

The lines of evidence discussed above regarding the SSIs reported for boron, chloride, and sulfate concentrations in downgradient monitoring wells MW-33AR, MW-34A, and/or MW-302 demonstrate that the SSIs are likely primarily due to sources other than the CCR Units. Boron, sulfate, and chloride concentrations were elevated prior to disposal of CCR in the landfill and are associated with historical discharges from the ash ponds via the effluent ditch located west of the landfill. Elevated chloride concentrations detected at well MW-33AR appear likely to be related to an alternative non-CCR source, such as salt.

6.0 SITE GROUNDWATER MONITORING RECOMMENDATIONS

In accordance with section 257.94(e)(2) of the CCR Rule, the COL MOD 1-3 CCR Units may continue with detection monitoring based on this ASD. The ASD report will be included in the 2021 Annual Report due January 31, 2022.

7.0 REFERENCES

SCS Engineers, 2018, Alternative Source Demonstration, October 2017 Detection Monitoring, Columbia Energy Center Dry Ash Disposal Facility, April 2018.

USEPA, 2015, Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule, April 2015.

Warzyn Engineering, Inc., 1978, Feasibility Study, Proposed Fly Ash and/or Scrubber Sludge Disposal Facility – Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Warzyn Engineering, Inc., 1979, and Preliminary Engineering Concepts, Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Tables

- 1 Groundwater Analytical Results Summary – October 2020 Event
- 2 Historical Analytical Results for Parameters with SSIs
- 3 Groundwater Elevation – State Monitoring Program and CCR Well Network
- 4 Analytical Results – Lysimeters and Leachate Pond

**Table 1. Groundwater Analytical Results Summary - October 2020 Event
Columbia Landfill MOD 1-3 / SCS Engineers Project #25221067.00**

Parameter Name	UPL	Background Wells		Compliance Wells			
		MW-84A	MW-301	MW-33AR	MW-34A		MW-302
		10/8/2020	10/8/2020	10/8/2020	10/8/2020	2/25/2021	10/8/2020
Appendix III							
Boron, ug/L	35.6	9.7 J	28.8	569	213	--	648
Calcium, ug/L	129,000	69,200	93,000	57,100	61,300	--	80,600
Chloride, mg/L	6.2	4.3	3.4	27.3	2.1	--	1.1 J
Fluoride, mg/L	DQ	<0.095	<0.095	<0.095	<0.095	--	<0.095
Field pH, Std. Units	7.78	7.49	6.95	7.70	7.81	7.57	7.21
Sulfate, mg/L	30.3	1.3 J	25.1	97.4	58.7	--	36.5
Total Dissolved Solids, mg/L	514	320	412	270	306	--	378

4.4 Blue shaded cell indicates the compliance well result exceeds the UPL (background) and the Limit of Quantitation (LOQ).

Abbreviations:

UPL = Upper Prediction Limit

DQ = Double Qualification

SSI = Statistically Significant Increase

LOQ = Limit of Quantitation

LOD = Limit of Detection

-- = Not applicable/not measured

µg/L = micrograms per liter

mg/L = milligrams per liter

Lab Notes:

J = Estimated concentration at or above the LOD and below the LOQ.

1. An individual result above the UPL does not constitute an SSI above background. See the accompanying report text for identification of statistically significant results.
2. Interwell UPLs calculated based on results from background wells MW-84A and MW-301. Interwell UPLs based on 1-of-2 retesting approach. UPLs updated in January 2020 based on background well results through October 2019.

Created by:	<u>NDK</u>	Date:	<u>6/15/2020</u>
Last revision by:	<u>NDK</u>	Date:	<u>3/4/2021</u>
Checked by:	<u>RM</u>	Date:	<u>3/5/2021</u>

**Table 2. Historical Analytical Results for Parameters with SSIs
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-302	12/22/2015	80.0	4.20	37.4
		4/5/2016	78.8	4.10	55.6
		7/7/2016	134	3.10 J	35.4
		10/13/2016	132	1.10 J	64.7
		12/29/2016	106	1.20 J	56.4
		1/25/2017	149	1.60 J	61.6
		4/11/2017	322	1.60 J	81.3
		6/6/2017	671	3.50	84.6
		8/8/2017	833	4.50	79.0
		10/24/2017	691	6.90	78.4
		4/24/2018	1,950	15.0	109
		9/21/2018	203	1.70 J	30.0
		10/22/2018	296	1.80 J	26.9
		4/2/2019	254	1.50 J	25.2
		10/9/2019	246	1.10 J	16.7
		5/29/2020	611	1.20 J	34.6
10/8/2020	648	1.1 J	36.5		
Compliance	MW-33AR	12/21/2015	954	10.6	96.2
		4/5/2016	813	12.5	91.5
		7/7/2016	794	12.5	99.2
		10/13/2016	827	52.5	124
		12/29/2016	812	39.6	132
		1/25/2017	763	41.4	133
		4/11/2017	760	47.1	139
		6/6/2017	692	68.1	151
		8/7/2017	697	105	164
		10/24/2017	678	119	175
		4/24/2018	601	188	163
		9/21/2018	683	32.6	124
		10/22/2018	682	14.4	112
		4/2/2019	568	229	201
		10/8/2019	548	153	182
		5/28/2020	566	15.9	104
10/8/2020	569	27.3	97.4		

**Table 2. Historical Analytical Results for Parameters with SSIs
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-34A	12/21/2015	230	4.90	69.9
		4/5/2016	220	5.10	71.6
		7/7/2016	216	5.60	63.4
		7/28/2016	-	-	-
		10/13/2016	212	6.80	54.8
		12/29/2016	224	7.10	63.9
		1/25/2017	214	7.20	71.2
		4/11/2017	214	6.20	87.6
		6/6/2017	201	7.80	106
		8/7/2017	205	7.40	105
		10/24/2017	208	7.60	98.0
		4/24/2018	209	8.20	144
		9/21/2018	241	17.1	141
		10/22/2018	233	19.9	123
		4/4/2019	204	18.7	70.4
		10/8/2019	207	57.9	39.8
		5/28/2020	210	3.90	44.4
10/8/2020	213	2.10	58.7		

Abbreviations:

µg/L = micrograms per liter or parts per billion (ppb)

mg/l = milligrams per liter or parts per million (ppm)

J = Estimated value below the laboratory's limit of quantitation

B = Analyte was detected in the associated Method Blank.

Notes:

(1) Analytical laboratory reports provided in the Annual Groundwater Monitoring and Corrective Action Reports.

Created by:	<u>NDK</u>	Date:	<u>3/19/2020</u>
Last revision by:	<u>RM</u>	Date:	<u>2/10/2021</u>
Scientist Check:	<u>NDK</u>	Date:	<u>3/4/2021</u>

I:\25221067.00\Deliverables\2020 Oct ASD MOD 1-3 LF\Tables\[Table 2 - Historical Results for Parameters with SSIs.xlsx]Table 2. Analy. Rslts- CCR

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25221067.00**

Dry Ash Facility (Facility ID #03025)	Well Number	MW-1AR	MW-4	MW-5R	MW-33AR	MW-33BR	MW-34A	MW-34B	MW-37A	MW-83	MW-84A	MW-84B	MW-86	MW-91AR	MW-91B	MW-92A	MW-92B	
	Top of Casing Elevation (feet amsl)	822.55	819.74	805.44	808.29	808.39	805.95	806.05	813.04	807.96	814.28	814.26	824.79	809.03	808.45	808.47	808.41	
	Screen Length (ft)																	
	Total Depth (ft from top of casing)	44.40	39.58	25.97	31.08	57.50	35.43	56.95	31.80	25.42	40.21	52.02	45.43	32.90	52.38	28.94	51.75	
	Top of Well Screen Elevation (ft)	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	
	Measurement Date																	
	October 2, 2012	783.41	783.70	784.96	782.38	782.23	783.03	782.99	782.66	dry	783.84	783.94	783.81	784.09	783.90	784.49	784.06	
	April 15, 2013	785.44	784.02	786.09	784.16	784.14	784.74	784.79	783.87	784.49	785.83	785.76	785.22	785.14	785.01	785.75	785.34	
	October 8, 2013													785.66	785.42	785.97	785.52	
	October 15, 2013	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.66	785.42	785.97	785.52
	April 14, 2014	784.95	784.09	785.63	783.74	783.91	784.63	784.70	783.45	783.73	785.58	785.52	784.96	785.04	784.96	785.99	785.54	
	October 2-3, 2014	785.03	785.39	786.08	784.37	784.28	784.57	784.54	784.56	dry	785.24	785.18	785.19	785.47	785.28	785.75	785.33	
	April 13-14, 2015	783.96	783.63	785.25	783.01	782.74	783.65	783.95	782.87	dry	784.43	784.51	784.17	784.48	784.37	785.07	784.66	
	October 6-7, 2015	784.28	784.44	785.72	783.68	783.33	784.05	784.02	783.66	dry	784.80	784.76	784.66	784.89	784.70	785.20	784.76	
	April 4-6, 2016	785.82	aband	787.02	785.29	785.07	785.63	785.67	784.76	785.43	786.37	786.26	785.89	786.05	785.95	786.61	786.21	
	October 11-13, 2016	786.64	aband	788.00	787.36	786.46	786.45	786.32	786.40	786.81	787.22	787.11	786.96	787.17	786.81	787.68	787.25	
	April 10-13, 2017	786.96	aband	788.13	786.39	785.99	786.30	786.28	786.34	786.23	787.16	787.06	786.96	787.24	787.03	787.90	787.60	
	October 3-5, 2017	785.48	aband	786.66	784.51	784.22	784.67	784.63	784.86	784.29	NM	786.49	785.58	786.08	785.83	786.47	786.02	
	October 9-10, 2017	NM	aband	NM	NM	NM	NM	NM	NM	NM	785.56 ⁽⁶⁾	NM	NM	NM	NM	NM	NM	
	February 21, 2018	783.97	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	784.68	784.46	NM	NM	
	April 23-25, 2018	783.99	aband	785.36	783.09	786.36	781.77	780.79	783.28	783.32	785.88	784.91	782.54	784.71	784.53	785.23	784.81	
	October 23-25, 2018	788.25	aband	789.71	788.77	787.96	787.88	787.73	787.62	788.26	788.32	788.19	788.21	788.59	788.31	789.32	788.87	
	April 1-4, 2019	787.05	aband	788.64	786.63	786.54	786.82	786.92	786.47	786.78	787.35	787.34	787.16	787.45	787.18	788.04	787.63	
October 7-9, 2019	787.26	aband	789.23	788.26	787.64	787.92	787.74	786.77	788.90	787.79	787.73	787.44	787.78	787.62	788.63	788.17		
May 27-28, 2020	786.92	aband	788.34	786.01	785.75	785.98	785.99	786.22	786.03	787.02	786.99	786.94	787.26	787.05	787.86	787.47		
October 7-8, 2020	785.95	aband	787.76	785.91	785.45	785.70	785.68	785.52	785.72	786.10	786.06	786.10	786.55	786.33	786.85	786.38		
February 25, 2021	NM	aband	NM	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM		
Bottom of Well Elevation (ft)	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66		
Ash Pond Facility (Facility ID #02325)	Well Number	M-3	M-4R	MW-39A	MW-39B	MW-48A	MW-48B	MW-57	MW-59	MW-216R	MW-217	MW-220RR	SG-1	SG-2	SG-3	SG-4		
	Top of Casing Elevation (feet amsl)	788.23	806.10	809.62	809.50	828.86	828.84	786.29	815.48	814.21	791.55	792.90	792.06	795.25	808.60	805.36		
	Screen Length (ft)																	
	Total Depth (ft from top of casing)	16.90	25.55	34.80	76.07	51.88	75.80	14.40	38.50	37.85	37.37	18.96	--	--	--	--		
	Top of Well Screen Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--		
	Measurement Date																	
	October 2, 2012	780.13	786.76	781.49	781.34	782.03	781.93	780.58	779.88	781.91	780.95	780.55	789.14	793.85	dry	dry		
	April 15, 2013	785.16	788.39	783.97	784.00	783.77	783.78	784.69	783.66	784.09	784.75	785.02	789.5 ⁽¹⁾	NM	dry	dry		
	October 8, 2013	781.22	786.67	NM	NM	783.69	783.58	NM	NM	783.39	782.27	782.36	789.5 ⁽¹⁾	791.33	dry	dry		
	October 15, 2013	NM	NM	782.94	782.81	NM	NM	782.47	783.49	NM	NM	NM	NM	NM	NM	NM		
	April 14, 2014	786.04	788.96	783.57	783.68	783.56	783.57	785.51	783.41	783.73	785.25	785.87	788.90	dry	dry	dry		
	October 1-3, 2014	781.16	787.55	783.42	783.32	784.05	783.94	782.32	783.55	783.79	782.63	783.03	NM	dry	dry	dry		
	April 13-14, 2015	783.08	786.83	782.77	782.68	782.80	782.82	782.81	782.83	782.93	783.34	783.42	789.3	791.70	dry	dry		
	October 6-7, 2015	780.66	786.12	782.97	782.81	783.10	783.01	781.82	783.25	783.18	781.95	782.26	788.48	791.58	dry	dry		
	April 4-6, 2016	784.21	789.09	785.27	785.27	784.79	784.76	783.21	784.97	785.68	785.02	784.36	NM	793.40	dry	dry		
	October 11-13, 2016	781.88	787.88	785.75	785.52	785.73	785.61	783.12	786.51	786.16	783.75	784.09	788.32	792.52	dry	dry		
	April 10-13, 2017	782.94	787.95	785.44	785.20	785.82	785.69	782.77	786.09	785.95	784.29	784.09	788.31	793.85	dry	dry		
	October 3-5, 2017	780.93	787.04	783.35	783.18	784.30	784.19	782.37	784.23	783.89	782.48	782.61	788.3	793.45	dry	dry		
	April 23-25, 2018	782.89	790.43	782.86	782.87	783.14	783.09	783.04	783.02	783.23	783.26	783.45	788.38	>795.25	dry	dry		
	October 23-25, 2018	782.95	788.47	787.12	786.88	787.12	786.99	783.48	787.73	787.49	784.90	784.52	787.76	793.25	dry	dry		
	April 1-4, 2019	785.68	789.44	786.28	786.31	786.56	786.45	785.27	787.39	786.53	786.33	785.46	--	794.60	dry	dry		
	October 7-9, 2019	785.33	790.65	787.10	787.02	786.68	786.65	785.29	786.68	787.07	786.01	785.42	748.48	795.20	dry	dry		
	May 27-29, 2020	781.80	787.73	785.12	784.92	785.74	785.59	783.11	785.89	785.60	783.41	783.89	748.48	>795.25	dry	dry		
October 7-8 & 17, 2020	781.42	787.74	784.74	784.64	785.03	784.96	782.83	785.43	785.10	783.06	783.49	788.34	793.32	dry	NM			
Bottom of Well Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--			

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25221067.00**

Well Number	MW-301	MW-302	MW-303	MW-304	MW-305	M-4R	MW-33AR	MW-34A	MW-84A	MW-306	MW-307	MW-308	MW-309	MW-310	MW-311
Top of Casing Elevation (feet amsl)	806.89	813.00	811.52	805.42	806.32	806.10	808.29	805.95	814.28	807.63	806.89	806.9	813.27	813.62	809.74
Screen Length (ft)	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10
Total Depth (ft from top of casing)	29.40	33.6	35.80	25.7	25.6	39.58	31.08	35.43	40.21	27	26.5	28	37.67	38.41	36.19
Top of Well Screen Elevation (ft)	787.49	789.40	785.72	789.72	790.72	776.52	787.21	780.52	784.07	790.63	790.39	788.90	785.60	785.21	783.55
Measurement Date													--	--	--
December 21-22, 2015	NM	784.78	784.11	786.13	788.96	787.58	783.77	783.50	785.31	--	--	--	--	--	--
April 4-5, 2016	786.78	785.81	785.48	788.08	789.61	789.09	785.29	785.63	786.37	--	--	--	--	--	--
July 7-8, 2016	786.31	786.28	784.60	787.36	789.26	787.43	785.19	785.05	785.89	--	--	--	--	--	--
July 28, 2016	NM	NM	784.35	NM	NM	NM	NM	784.86	785.61	--	--	--	--	--	--
October 11-13, 2016	787.64	787.76	786.18	788.18	789.78	787.88	787.36	786.45	787.22	--	--	--	--	--	--
December 29, 2016	787.37	787.05	NM	NM	NM	NM	785.66	785.72	786.63	--	--	--	--	--	--
January 25-26, 2017	787.27	786.89	785.28	789.34	789.36	789.64	785.88	785.98	786.70	785.50	785.36	785.73	--	--	--
April 10 & 11, 2017	787.89	787.55	786.00	788.22	789.57	787.95	786.39	786.30	787.16	786.22	785.64	786.51	--	--	--
June 6, 2017	788.25	788.37	786.49	788.58	789.79	787.83	787.27	786.66	787.63	786.85	786.07	786.46	--	--	--
August 7-9, 2017	787.34	787.55	785.42	789.52	789.30	788.54	786.11	785.81	786.68	785.69	785.19	785.37	--	--	--
October 23-24, 2017	785.89	785.94	783.92	788.97	788.14	788.00	784.13	784.50	785.32	783.97	784.79	784.17	--	--	--
February 21, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.19	783.05	783.02
March 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.10	783.10	783.00
April 23-25, 2018	785.29	784.37	783.27	789.69	787.67	790.43	783.09	781.77	785.88	783.24	783.65	782.65	783.07	782.97	781.83
May 24, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.79	785.09	NM	785.45	785.97	786.11
June 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.03	786.64	786.47
July 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.27	786.35	786.55
August 7, 2018	787.06	NM	785.20	788.25	788.56	787.63	NM	NM	786.55	NM	NM	NM	NM	NM	NM
August 22, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.54	785.40	785.46
September 21, 2018	NM	788.37	786.50	NM	NM	NM	787.90	787.01	NM	NM	NM	NM	787.08	787.24	787.66
October 22-24, 2018	788.98	789.16	787.51	789.05	790.04	788.47	788.77	787.88	788.32	787.66	786.57	787.81	787.99	788.18	788.64
April 1-4, 2019	787.04	787.56	786.52	789.72	790.07	789.44	786.63	786.82	787.35	786.72	786.71	787.53	786.30	786.38	786.38
June 12, 2019	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	787.25	NM
June 19, 2019	NM	NM	786.81	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM
October 7-9, 2019	788.47	788.31	787.02	790.41	790.36	790.65	NM	NM	NM	787.47	786.99	787.18	787.26	787.94	787.64
December 13, 2019	--	--	--	--	--	--	--	--	--	787.03	785.68	786.43	--	--	--
December 23, 2019	--	--	--	--	--	--	--	--	--	--	--	--	--	775.22	--
January 17, 2020	--	--	785.58	--	--	--	--	--	--	--	--	--	--	--	--
February 3, 2020	787.24	NM	NM	NM	NM	NM	NM	NM	786.50	785.77	785.57	786.48	NM	NM	NM
May 27-29, 2020	787.77	787.29	785.56	789.30	787.78	787.73	786.01	785.98	787.02	785.77	785.35	786.28	785.98	785.81	785.85
June 30, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.18	NM	NM
August 6, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.93	NM	NM
October 7-8, 2020	786.53	786.74	785.16	788.52	787.96	787.74	785.91	785.70	786.10	785.39	784.71	785.68	785.47	785.56	785.83
December 11, 2020	--	--	--	--	788.19	--	--	--	--	--	--	--	785.26	785.26	--
February 25, 2021	NM	NM	784.27	NM	788.36	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM
Bottom of Well Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	780.63	780.39	778.90	775.60	775.21	773.55

Notes:
NM = not measured

Created by: MDB Date: 5/6/2013
Last revision by: ZTW Date: 2/25/2021
Checked by: RM Date: 4/5/2021
Proj Mgr QA/QC: TK Date: 4/5/2021

- (1) The elevation for SG-1 is read off of the staff gauge (rather than measured from the top of the gauge).
- (2) SG-2 could not be located during the April 2013 event.
- (3) SG-3 could not be located during the October 2013 event. SG-1 could not be safely accessed during the October 2013 event.
- (4) LH-2 measurements are given as leachate depth, measured by a transducer.
- (5) LH-2 and LH-3 measurements were collected by WPL staff on October 9, 2017.
- (6) The depth to water at MW-84A was not measured prior to purging for sampling during the October 3-5 sampling event. The level was allowed to return to static and was measured on 10/10/2017.

**Table 4. Analytical Results - Lysimeters and Leachate Pond
Columbia Dry Ash Disposal Facility
SCS Engineers Project #25221067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LS-1	2015-Apr	DRY	--	--	--
	2015-Oct	BROKEN	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	--	6530	12.3	789
	2017-Apr	--	6510	20.7 J	814
	2017-Oct	--	6200	14.2 J	764
	2018-Apr	--	5920	16 J	856
	2018-Oct	DRY	--	--	--
	2019-Apr	--	5,640	22 J	911
	2019-Oct	--	6,180	19.2 J	861
	2020-May	--	6,180	25.4 J	1,040
	2020-Oct	--	5,640	27.2 J	950
LS-3R	2015-Apr	--	6480	20.6 B	807
	2015-Oct	DRY	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	DRY	--	--	--
	2017-Apr	DRY	--	--	--
	2017-Oct	DRY	--	--	--
	2018-Apr	DRY	--	--	--
	2018-Oct	--	6180	26.2 J	841
	2019-Apr	DRY	--	--	--
	2019-Oct	DRY	--	--	--
	2020-May	DRY	--	--	--
	2020-Oct	DRY	--	--	--

**Table 4. Analytical Results - Lysimeters and Leachate Pond
Columbia Dry Ash Disposal Facility
SCS Engineers Project #25221067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LP-1	2015-Apr	--	4060	27.8	734
	2015-Oct	--	4,300	37.1	820
	2016-Apr	--	1,830	26.8	416
	2016-Oct	--	4,610	71.5	835
	2017-Apr	--	2,690	66.3	587
	2017-Oct	--	4,970	91.7	739
	2018-Apr	--	2,060	63.2	634
	2018-Oct	--	2,630	151	907
	2019-Apr	--	570	35.1	249
	2019-Oct	--	1,270	63.9	602
	2020-May	--	2,460	179	952
	2020-Oct	--	2,710	243	1,160

Abbreviations:

µg/L = micrograms per liter
mg/L = milligrams per liter

-- = not analyzed
µmhos/cm = micromhos/centimeter

Notes:


B = Analyte was detected in the associated method blank.
J = Estimated concentration at or above the LOD and below the LOQ.

Created by: TLC Date: 12/1/2014
Last revision by: RM Date: 2/26/2021
Checked by: NDK Date: 2/26/2021

I:\25221067.00\Deliverables\2020 Oct ASD MOD 1-3 LF\Tables\[Table 4 - Leachate_2015-Oct 2020 ASD.xlsx]Lys LP1
App III

Figures


- 1 Site Location Map
- 2 Site Plan and Monitoring Well Locations
- 3 Water Table Map – October 2020



POYNETTE QUADRANGLE
 WISCONSIN-COLUMBIA CO.
 7.5 MINUTE SERIES (TOPOGRAPHIC)
 2018
 SCALE: 1" = 2,000'



CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954		SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER PARDEEVILLE, WI		ENGINEER	SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830		SITE LOCATION MAP	
	PROJECT NO.	25220067.00		DRAWN BY:	BSS		FIGURE	1		
	DRAWN:	12/02/2019		CHECKED BY:	MDB					
REVISED:	01/10/2020	APPROVED BY:	TK 04/10/2020							




PROJECT NO.	25220067.00	DRAWN BY:	BSS/ZTW		ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULE 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	SITE PLAN AND MONITORING WELL LOCATIONS	FIGURE
DRAWN:	12/02/2019	CHECKED BY:	TK					2
REVISED:	01/05/2021	APPROVED BY:	TK 01/28/2021					

I:\25220067.00\Drawings\ASD Mod 1-3 LF\Site Plan and Monitoring Well Locations\MOD1-3.dwg, 1/28/2021 11:32:08 AM


Appendix A
Trend Plots for CCR Wells

Boron




Time Series Analysis Run 2/10/2021 3:14 PM View: COL Primary Pond
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

Chloride




Time Series Analysis Run 2/10/2021 3:14 PM View: COL Primary Pond
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

Sulfate



Time Series Analysis Run 2/10/2021 3:14 PM View: COL Primary Pond
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020



Appendix B
Feasibility Study Water Quality Information

1370



FEASIBILITY STUDY
PROPOSED FLY ASH AND/OR SCRUBBER SLUDGE
DISPOSAL FACILITY-COLUMBIA SITE
WISCONSIN POWER AND LIGHT COMPANY
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

Jan 78

C 7134

conceivable that groundwater flow in the area north of Murray Road may be altered such that contaminants derived from the present ash settling basin might be diverted southerly towards the homes along Murray Road. These questions would have to be addressed in greater detail, consistent with the goals of Wisconsin Power and Light Company.

WATER QUALITY

During the first two weeks of December, 1977, 64 water samples were obtained from surface waters and groundwater monitoring wells at the Columbia Energy Center. The purpose of the sampling was to assess background water quality in the vicinity of the proposed disposal site. The sampling stations included 59 monitoring wells, the cooling lake, ash settling pond, the drainage ditch carrying the ash pond discharge waters and the agricultural drainage ditch along the southern boundary of the site. Due to the large number of sampling stations, the analyses were limited to pH, specific conductance, iron, calcium, magnesium, sulfate and chloride. The analytical data is contained in Appendix F and is discussed below.

pH

Most groundwaters found in the United States have pH values ranging from around 6.0 to 8.5. The pH of a water represents the result of a number of interrelated chemical equilibria. This equilibria can be altered shortly after sampling by gains or losses of carbon dioxide, the oxidation of ferrous iron and numerous other chemical reactions. Thus, pH measurements must be taken shortly after obtaining the sample. For this study, the pH of samples was determined immediately upon return to the laboratory.

Within the proposed site boundaries at the Columbia Energy Center, pH values ranged between 6.3 and 8.1 and averaged 7.5. Typically, the lower pH values were observed in the lowland areas and wetlands, probably as a result of acidic organic soils. The pH of water in the ash disposal settling pond and the cooling lake was 11.4 and 8.3, respectively.

SPECIFIC CONDUCTANCE

Specific conductance, or conductivity, is the ability of a substance to conduct an electric current. The conductance determination is correlative with the dissolved-solids concentration. Conductivity, however, is temperature dependent and thus requires the reference of specific conductance measurements to a standard temperature. The values discussed here are referred to 25°C.

The specific conductance of groundwater in the study area ranged from 220 umhos/cm to a maximum of 2600 umhos/cm. The highest conductivity readings were observed in monitoring wells located along the coal storage area and the drainage ditch carrying the ash pond discharge where values up to 2600 umhos/cm were measured. The conductivity of the ash pond effluent was 1380 umhos/cm. This data appears to confirm earlier speculation of infiltration of effluent from the ash pond discharge channel and from the coal storage area into the groundwater. Conductance within the proposed site boundaries averaged approximately 465 umhos/cm.

Conductivity in the ash disposal settling pond was measured at 1510 umhos/cm. Shallow monitoring wells M-6 and 39A, located adjacent to the pond also exhibited elevated values of 1160 umhos/cm and 1800 umhos/cm, respectively.


High conductivities were also observed along U. S. Highway 51 at monitoring wells 51A and 51B. The chloride data, discussed below, indicates infiltration of road salt has probably occurred at this location.

Specific conductance measurements obtained in the vicinity of the proposed disposal site are shown on Drawing C 7134-15.

IRON

The element iron is an abundant element found in most rocks and soil. It generally occurs as sulfides and oxides in igneous and metamorphic rocks and as iron oxide and hydroxide cementing materials in coarse-grained sedimentary rocks.

Ferrous iron is unstable in the presence of oxygen where it is bound to hydroxide anions as $2\text{Fe}(\text{OH})_3$.



If subjected to a strong reducing environment, such as a marsh, the reaction is reversed and iron goes back into solution. The amount which dissolves is related to a number of variables including the velocity with which water moves through this environment.

The U. S. Public Health Service recommends an iron concentration of less than 0.3 mg/l in water used for drinking and culinary purposes. Laundry and porcelain tend to be stained when concentrations reach 0.5 to 1.0 mg/l. At this level it can also be tasted.

The presence of iron under the proposed disposal area in the majority of cases was below the detection limit of 0.1 mg/l. In monitoring wells 5 and 18, located in or near the central marsh area, iron increased to 10 mg/l and 5.7 mg/l, respectively. In the southern marsh, monitoring wells exhibited concentrations between 0.5 mg/l and 6.1 mg/l. Although the iron concentration in the cooling lake was below the detection limit, down-gradient wells 44 and 30A located on the cooling lake dike yielded values of 11 mg/l and 26 mg/l iron respectively. Boring logs indicated trace amounts of organic material at the base of the dike which is probably the reason for the high concentrations observed. At the same location, iron in well 30B installed to a depth of 100 feet below the surface was below 0.1 mg/l. Thus, the occurrence of high iron concentrations in this area appears restricted to groundwater in the upper portion of the aquifer where organic material is present and conditions are favorable for the dissolution of iron.

The ash pond discharge in the drainage ditch paralleling the west site boundary showed an iron concentration of 3.7 mg/l. Shallow monitoring wells 33A and 34A adjacent to the ditch indicated less than 0.1 mg/l iron.

North of Murray Road the iron concentration in monitoring wells in the marsh and uplands were typically less than 0.1 mg/l. Although the ash basin had less than 0.1 mg/l iron, several wells along cross-section F-F' showed anomalously high values (#M6-2.3 mg/l; #47-16 mg/l; #51B-21 mg/l).

CALCIUM

Calcium, because of its relative abundance and mobility, is the principle cation in most natural fresh water. Calcium is a constituent of many rock types but is found in greatest quantities in waters leaching deposits of limestone and dolomite. In sandstone and other detrital rock, calcium carbonate is a common cement between grains.

Monitoring wells located within the site boundaries exhibited calcium concentrations between 30 mg/l and 66 mg/l and averaged about 42 mg/l. Similar to iron, the concentrations of calcium in monitoring wells along cross-section F-F' were anomalously high, up to 150 mg/l calcium. Water table wells along the drainage ditch carrying the ash pond discharge averaged 83 mg/l while the ash pond effluent contained 28 mg/l. Generally the amount of calcium in groundwater decreased with depth. Nested monitoring wells typically showed somewhat lower concentrations of calcium in the deeper wells.

MAGNESIUM

As a relatively abundant element on the earth's crust, the principle sources of magnesium in natural waters are considered to be ferromagnesian minerals in igneous rocks and magnesium carbonate in carbonate rocks (limestone and dolomite). Waters in which magnesium is the predominant cation are somewhat unusual. Like calcium, magnesium imparts the property of hardness to water and is, therefore, of concern to industrial users.

Generally, concentrations of magnesium were 1/3 to 1/2 of the calcium levels. Magnesium concentrations within the site boundaries ranged between 10 mg/l and 36 mg/l and averaged 27 mg/l. Similar to calcium and iron, higher magnesium values were observed, in general, north of Murray Road and especially in monitoring wells along cross-section F-F'.



SULFATE

Sulphur is widely distributed in reduced form in both igneous and sedimentary rocks as metallic sulfides and when present in sufficient concentrations, constitutes ore of economic importance. During weathering processes with aerated water, the sulfides are oxidized to sulfate ions and are dissolved into water. Pyrite (FeS_2) crystals often occur in sedimentary rocks and are particularly associated with biogenic deposits such as coal which were deposited under strongly reducing conditions.

The concentrations of sulfate in groundwater in the vicinity of the proposed disposal site ranged from less than 1 mg./l to 1,200 mg./l of sulfate. (Refer to Drawing C 7134-15.) Typically, within the site boundaries concentrations averaged approximately 12 mg./l. Near the coal storage area, however, significant increases were observed. Observation wells 26A, 26B, and 42 exhibited concentrations between 900 and 1100 mg./l. The depth of sulfate enrichment in groundwater, near the coal pile, appears to extend to considerable depths, indicated by relatively high sulfate concentrations in Well 26B sealed 100 feet below ground surface. The oxidation of pyrite minerals in the coal leaching into the groundwater is probably the major source of the high concentrations observed.

Sulfate concentrations in the ash disposal settling pond were 520 mg./l. In the ditch carrying the ash pond discharge, the effluent is treated with sulfuric acid which results in precipitation of barium sulfate and aluminum hydroxide (personal communication, Merlin Horn, 1978). Consequently, the sulfate concentration of the effluent waters is lowered considerably to 13 mg./l. Well 33A, however, located near the point of effluent discharge, exhibited 1200 mg./l sulfates.

CHLORIDE

Chloride is generally present in much lower concentrations in rocks than many of the other major constituents of natural water. Important sources, however, are associated with sedimentary rocks, particularly the evaporites. The chemical behavior of chloride in natural water is relatively inert compared to the other major ions. There are few oxidation-reduction reactions and no significant chemical complexing reactions which chloride enters into. In addition, chloride ions are not significantly adsorbed on mineral surfaces. For these reasons, chloride is commonly used as a tracer in groundwater.

Chloride concentrations in groundwater in the vicinity of the Columbia Energy Center typically range between 0.5 mg./l and 30 mg./l. The highest concentrations in monitoring wells tended to be located adjacent to U. S. Highway 51 where the use of road salt has resulted in the percolation of chloride into the groundwater. Monitoring Wells 51A and 51B located in a low area north of Murray Road along U. S. Highway 51, yielded chloride concentrations in excess of 200 mg./l. Two other wells, 52A and 19, also located along U. S. Highway 51, yielded values of 30 mg./l and 42.5 mg./l chloride, respectively.

Within the proposed site boundaries, the chloride concentration averaged 7.1 mg./l. Excluding the few wells adjacent to U. S. Highway 51 exhibiting elevated concentrations, no other significant trends in the occurrence of chloride were observed.

SUMMARY

In summary, the groundwater in the vicinity of the proposed disposal site exhibited a somewhat alkaline pH. In lowland areas, the pH was typically below 7.0, probably a result of the presence of acidic organic soils.

Specific conductance within the proposed site averaged 465 umhos/cm. Conductivities up to 2600 umhos/cm were observed, however, in the vicinity of the coal storage area, the present ash disposal pond and ash pond effluent channel where infiltration of water from these sources is occurring into the groundwater system.

The groundwater typically exhibited relatively low iron concentrations although, locally, concentrations in excess of drinking water standards were observed in about 20% of the wells. The occurrence of the higher iron concentrations appears to be related to the presence of organic soils.

Groundwater at the proposed site also tended to exhibit high calculated hardness (216 mg./l) based on average observed values for calcium (42 mg./l) and magnesium (27 mg./l). Dissolution of limestone and dolomite rocks in the glacial drift are the probable sources of these elements in the groundwater.

Enrichment of sulfate in groundwater has occurred as a result of leaching of pyrite (FeS_2) minerals from the coal storage area where concentrations up to 1200 mg./l were observed. The depth of this enrichment appears to extend beyond the maximum depth into the aquifer investigated. Sulfate concentrations decreased rapidly away from the coal storage area to an average of 12 mg./l within the proposed site boundaries. Other local sources of sulfate in groundwater appear to be related to the present ash settling pond.

The concentration of chloride within the proposed site averaged 7.1 mg./l. Higher levels were generally observed in wells adjacent to U. S. Highway 51 where the infiltration of road salt has locally raised chloride concentrations.

The above interpretations are based on one round of water quality sampling only and should be considered as preliminary in nature. High sulfate and chloride concentrations observed at greater depths may be a temporary condition resulting from contamination of spoil backfill materials with coal dust or salt, respectively, during installation of the monitoring well. Future sampling of these monitoring wells will help to distinguish short term contamination from actual conditions existing in the aquifer.

APPENDIX F
WATER QUALITY DATA

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
1A	7.6	550	17.	6.5	52	37	<0.1
1B	8.05	460	16.	10.5	39	31	<0.1
2	7.8	527	14.	2.5	45	32	<0.1
3A	7.5	548	13.	2.5	58	36	<0.1
3B	8.1	506	14.	7.0	50	34	<0.1
4	7.8	580	10.	4.0	59	34	<0.1
5	6.3	560	210.	12.5	13	29	10
16	7.6	408	12.	1.5	42	28	<0.1
17	6.45	350	30.	16.5	16	13	0.6
18	6.45	380	4.	4.5	33	22	5.7
19	7.9	570	10.	42.5	44	24	<0.1
20	8.0	340	10.	5.0	36	24	<0.1
21	6.9	220	20.	4.5	23	10	0.1
24A	7.45	775	18.	6.0	76	52	0.1
24B	7.85	440	15.	6.0	43	31	0.1
25	8.1	300	10.	2.5	29	20	<0.1
26A	7.2	2100	900	17.0	140	48	1.5
26B	7.5	2600	1100	16.5	43	7.0	0.2
27	7.15	400	6.	8.0	23	18	<0.1
28A	7.75	500	3.	0.5	48	31	<0.1
28B	7.6	480	4.	3.5	39	28	<0.1
29A	7.8	330	16.	1.5	33	21	0.5
30A	6.75	920	64.	11.0	38	30	26
30B	7.6	770	210	21.0	37	19	<0.1
33A	8.2	2500	1200	24.0	83	50	<0.1
33B	7.9	390	22.	6.5	31	27	0.2
34A	7.7	680	140.	10.0	58	45	0.1
34B	7.7	1700	660	15.0	48	22	<0.1
35	6.8	740	<1.0	4.0	66	33	2.9
36	6.8	740	<1.0	3.5	53	35	6.1
37A	7.7	460	9.	4.0	48	31	0.8
37B	7.5	630	73.	7.5	71	35	<0.1
39A	7.5	1800	350	22.0	180	100	0.1
39B	7.9	330	560	20.5	31	22	0.1
40A	8.0	630	140	8.5	43	29	<0.1
40B	8.1	330	17.	3.0	31	22	<0.1
41	6.8	590	16.	11.0	58	27	9.3

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
42	7.4	2400	900	17.5	50	12	0.5
44	6.9	490	<1.	16.5	39	23	11
45	7.6	390	14.	3.0	40	25	<0.1
46A	7.3	1100	21.	15.5	140	82	<0.1
46B	7.8	470	25.	17.5	40	26	<0.1
47	6.6	1200	3.	8.0	140	40	16
48A	7.3	620	15.	8.0	62	37	<0.1
48B	7.1	520	22.	20.0	43	29	0.2
49	7.15	730	6.	3.5	75	41	<0.1
50A	7.6	520	28.	15.5	51	34	<0.1
50B	7.5	410	21.	18.0	31	21	<0.1
51A	6.1	1850	8.	205.	65	40	<0.1
51B	7.2	1250	23.	275.	57	36	21
52A	7.7	450	16.	30.5	36	17	<0.1
52B	7.4	430	40.	17.5	32	20	<0.1
53	7.75	450	27.	10.5	39	28	<0.1
54A	7.8	350	12.	4.0	34	21	0.1
54B	7.55	390	15.	5.5	40	24	0.1
55B	7.9	340	23.	17.5	32	22	0.1
56	7.8	450	22.	9.5	43	28	0.1
57	7.85	380	17.	7.0	38	24	0.1
M-6	7.0	1160	5.	7.0	150	91	2.3
Cooling Lake	8.3	370	31.	18.0	34	21	<0.1
Ash Pond Effluent	7.45	1380	13.	4.0	28	1.2	3.7
Ash Pond Drainage	11.4	1510	520.	23.5	29	0.2	<0.1
Ditch (A) Drainage	7.8	500	21.	7.0	43	29	<0.1
Ditch (B)	9.05	1780	750	14.0	42	5.4	<0.1

DEC 19 1979

APPENDICES TO

SUPPLEMENTARY FEASIBILITY STUDY REPORT
AND PRELIMINARY ENGINEERING CONCEPTS
COLUMBIA SITE
WISCONSIN POWER AND LIGHT COMPANY
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

D. N. R. APPROVED

DATE 9/3/80
Nile Ostenso, Hydro

APPENDIX I

WATER QUALITY DATA - DECEMBER 1978

WATER QUALITY DATA


12/78

C 7134

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
1A	7.3	530	30	3.1	54	35	<0.1	-
1B	7.0	470	67	6.1	49	30	<0.1	-
2	7.25	458	91	<.5	48	24	<0.1	-
3A	7.0	560	36	<.5	61	31	<0.1	-
3B	7.15	530	52	35.7	37	33	<0.1	-
4	7.2	750	69	5.8	49	30	<0.1	-
5	6.35	1,650	670	14.1	14	13	1.7	-
16	6.9	390	69	1.0	49	23	<0.1	-
17	5.55	295	57	16.3	14	8.6	0.2	-
18	5.9	430	10	4.2	47	21	1.1	-
19	7.4	765	75	4.2	51	28	<0.1	-
20	7.4	380	26	1.6	39	26	<0.1	-
21	5.7	250	54	10.4	15	8.3	0.2	-
24A	7.2	730	36	1.6	65	42	<0.1	-
24B	7.2	470	10	7.3	42	28	<0.1	-
25	7.0	335	29	7.8	39	21	0.2	-
26A	7.4	2,250	650	12.6	32	8.6	<0.1	-
26B	6.8	2,530	840	20.8	49	18	<0.1	-
27	6.9	410	24	4.2	40	24	0.4	-
28A	7.2	500	61	0.5	45	28	<0.1	-
28B	7.0	465	6	2.1	39	26	0.1	-
29A	7.1	410	24	3.6	31	22	0.1	-
30A	5.8	1,140	15	<0.5	97	56	38	-
30B	6.65	835	160	14.6	37	20	<0.1	-
33A	7.8	1,970	830	16.7	21	8.9	<0.1	-
33B	7.5	380	31	7.3	24	27	<0.1	-
34A	7.25	560	46	4.2	53	33	<0.1	-
34B	8.5	1,575	730	21.9	28	29	0.1	-
35	6.7	545	61	3.6	60	26	1.0	-
36	6.4	515	5.0	2.6	43	24	4.8	-
37A	7.05	438	30	3.7	50	28	<0.1	-
37B	6.7	325	18	7.3	1.0	0.5	<0.1	-
39A	6.35	1,260	33	13.6	70	7.6	0.1	-
39B	6.7	385	25	4.2	30	21	<0.1	<.05
40A	7.35	483	40	<0.5	48	24	<0.1	-
40B	7.25	343	4	4.2	21	14	<0.1	-
41	6.1	640	54	19.8	43	32	<0.1	-


WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
42	7.15	2,050	910	15.6	23	7.5	0.1	-
44	6.15	710	6	0.5	56	27	3.5	-
45	7.2	420	32	1.0	44	26	<0.1	-
46A	7.0	560	93	<0.5	130	75	<0.1	<0.05
46B	6.5	1,290	170	20.8	46	30	<0.1	<0.05
47	7.3	958	120	<0.5	110	48	<0.1	-
48A	6.15	640	59	<0.5	42	51	<0.1	<0.05
48B	6.8	450	23	5.2	40	27	<0.1	<0.05
49	7.0	880	26	2.1	93	58	0.1	-
50A	7.4	660	25	17.7	60	36	<0.1	-
50B	7.1	405	16	17.7	38	23	<0.1	-
51A	7.0	1,170	57	135	66	31	<0.1	-
51B	7.3	1,410	22	330	46	39	<0.1	-
52A	7.0	370	110	18.5	35	10	<0.1	-
52B	7.0	595	43	52.5			0.1	-
53	Frozen							
54A	7.5	345	10	1.0	36	22	<0.1	<0.05
54B	Frozen							
55B	7.3	505	26	15.6	52	29	<0.1	<0.05
56	Frozen							
57	Frozen							
M-6								
58	6.55	1,265	140*	<0.5	110	65	0.1	-
59	6.8	925	40	<0.5	86	60	<0.1	-
60	7.2	1,510	54	4.7	130	85	<0.1	-
61A	6.85	590	39	30.2	58	31	<0.1	-
61B	7.2	505	6	13.5	48	29	<0.1	-
62	6.7	1,517	72	178	120	53	<0.1	-
64	6.9	670	100	26.8	63	36	0.8	-
65	7.2	830	57	17.8	78	50	<0.1	-
66	6.5	680	55	40	66	24	3.6	-

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
67	7.0	560	100	1.0	57	32	1.0	-
68A	7.6	440	32	2.1	40	27	<0.1	-
68B	7.2	400	36	1.0	42	25	<0.1	-
70A	7.5	440	20	<0.5	27	37	<0.1	-
70B	7.3	520	25	5.2	51	34	<0.1	-
72A	6.45	860	11	<0.5	100	41	1.8	-
72B	8.4	230	45	<0.5	17	19	<0.1	-
M-4	7.6	864	180	26.1	20	11	<0.1	-
MM-4			2	2.6	14	21	0.9	0.39
Cooling Lake at 1	7.7	355	36	13.6	31	21.2	<0.1	-
Ash Pond at 2	11.4	3,210	1,100	22.9	34	<0.1	<0.1	-
Ash Pond at 3	8.7	725	34	21.9	48	16	<0.1	-
Ash Pond Effluent at 4	6.7	3,090	1,400	25.0	39	0.4	<0.1	-
Drainage Ditch at 5	7.2	730	74	33.9	56	38	<0.1	-
Drainage Ditch at 6	7.35	2,750	640	18.8	34	7.5	<0.1	-
Drainage Ditch at 7	8.05	1,780	740	27.1	31	0.2	<0.1	-




Appendix C
Long-Term Concentration Trend Plots


Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-33A and MW-33AR - Boron ($\mu\text{g/l as B}$)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW34A - Boron ($\mu\text{g/l}$ as B)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-302 and MW-85 - Boron ($\mu\text{g/l}$ as B)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-33 and MW-33AR - Chloride (mg/l as Cl)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW34A - Chloride (mg/l as Cl)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-33 and MW-33AR - Sulfate (mg/l as SO4)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-34A - Sulfate (mg/l as SO4)



Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-85 and MW-302 - Sulfate (mg/l as SO₄)




Appendix D
Historical Groundwater Flow Maps



- LEGEND**
- PROPERTY LINE
 - EXISTING RAILROAD TRACKS
 - EXISTING GROUND CONTOUR
 - CONTOUR DEPRESSION
 - EXISTING PAVED ROAD
 - EXISTING UNPAVED ROAD
 - EXISTING FENCE
 - EXISTING BUILDING
 - EXISTING SPOT ELEVATION
 - TREES AND/OR BRUSH
 - WETLAND AREA
 - EDGE OF WATER
 - HC 1 WATER SUPPLY WELL
 - MW61A WATER TABLE WELL
 - MW61B PIEZOMETER
 - ABANDONED WATER TABLE WELL
 - ABANDONED PIEZOMETER
 - 801 STAFF GAUGE
 - ALS-1 LYSEMETER
 - DESIGN MANAGEMENT ZONE
 - PROPERTY LINE
 - O.S. OPEN STORAGE
 - O.H. OVERHEAD STRUCTURE
 - E.P.S. ELECTRICAL POWER STATION
 - T TANK
 - W WALL
 - (785.31) WATER TABLE ELEVATION (FT.-MSL)
(N.M. = NOT MEASURED)
 - 786 GROUNDWATER CONTOUR LINE
(FT. INTERVAL - FT. M.S.L.)
(DASHED WHERE INFERRED)
 - GROUNDWATER FLOW DIRECTION


- NOTES**
1. BASE MAP IS PROVIDED BY WISCONSIN POWER & LIGHT CO. AND IS BASED ON PHOTOS TAKEN ON APRIL 6, 1995 BY AERO-METRIC ENGINEERING, SHEBOYGAN, WI.
 2. HORIZONTAL DATUM IS BASED ON THE WISCONSIN STATE PLANE COORDINATE SYSTEM, SOUTH ZONE - DATUM NAD 83/01.
 3. VERTICAL DATUM IS REFERENCED TO U.S.G.S. MEAN SEA LEVEL (MSL). TOPOGRAPHIC CONTOUR INTERVAL IS TWO FEET.
 4. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER & LIGHT CO. IN DECEMBER 1994 & NOVEMBER 1996.
 5. THE LOCATION OF THE DESIGN MANAGEMENT ZONE DEMARCATION LINE IS APPROXIMATE.
 6. WATER ELEVATION USED TO PREPARE THIS MAP WERE MEASURED ON OCTOBER 24, 2002.
 7. THE WATER LEVEL AT MW 33A AND MW 33B COULD NOT BE MEASURED DURING OCTOBER 2002 DUE TO AN OBSTRUCTION IN THE WELL CASING.



PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY
 SHEET TITLE: WATER TABLE MAP (OCTOBER 2002)
 DRAWN BY: defoe | SCALE: 1"=200' | PROJ. NO. 3024.28
 CHECKED BY: JMR | FILE NO. WATERTBL.PLT
 APPROVED BY: JCD | DATE PRINTED: | FIGURE 3
 DATE: JANUARY 2003

3.			
2.			
1.			
NO. BY DATE	REVISION		APP'D.
PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY			
SHEET TITLE: WATER TABLE MAP (OCTOBER 2002)			
DRAWN BY: defoe	SCALE: 1"=200'	PROJ. NO. 3024.28	
CHECKED BY: JMR	FILE NO. WATERTBL.PLT		
APPROVED BY: JCD	DATE PRINTED:	FIGURE 3	
DATE: JANUARY 2003			

744 Heartland Trail
 Madison, WI 53717-1934
 P.O. Box 8923
 Madison, WI 53708-8923
 Phone: 608-831-4444



Appendix F2
April 2021 Detection Monitoring

Alternative Source Demonstration April 2021 Detection Monitoring

Dry Ash Disposal Facility, Modules 1-3
Columbia Energy Center
Pardeeville, Wisconsin

Prepared for:



SCS ENGINEERS

25221067.00 | October 13, 2021

2830 Dairy Drive
Madison, WI 53718-6751
608-224-2830

Table of Contents

Section	Page
PE Certification	iii
1.0 Introduction	1
1.1 §257.94(e)(2) Alternative Source Demonstration Requirements	1
1.2 Site Information and Map	1
1.3 Statistically Significant Increases Identified	2
1.4 Overview of Alternative Source Demonstration	2
2.0 Background	3
2.1 Regional Geology and Hydrogeology	3
2.1.1 Regional Information	3
2.1.2 Site Information	3
2.2 CCR Rule Monitoring System	3
2.3 Other Monitoring Wells.....	4
3.0 Methodology and Analysis Review	4
3.1 Sampling and Field Analysis	4
3.2 Laboratory Analysis Review	4
3.3 Statistical Evaluation Review.....	5
3.4 Summary of Methodology and Analysis Review Findings	5
4.0 Alternative Sources	5
4.1 Potential Causes of SSI.....	5
4.1.1 Natural Variation	5
4.1.2 Man-Made Alternative Sources	5
4.2 Lines of Evidence	6
4.2.1 Pre-Landfill Water Quality	6
4.2.2 Long-Term Concentration Trends	6
4.2.3 Groundwater Flow Direction Changes.....	7
4.2.4 Chloride and Boron Leachate Concentrations.....	8
5.0 Alternative Source Demonstration Conclusions	8
6.0 Site Groundwater Monitoring Recommendations	8
7.0 References	8

Tables

Table 1.	Groundwater Analytical Results Summary – April 2021 Event
Table 2.	Historical Analytical Results for Parameters with SSIs
Table 3.	Groundwater Elevation – State Monitoring Program and CCR Well Network
Table 4.	Analytical Results – Lysimeters and Leachate Pond

Figures

- Figure 1. Site Location Map
- Figure 2. Site Plan and Monitoring Well Locations
- Figure 3. Water Table Map – April 2021

Appendices

- Appendix A Trend Plots for CCR Wells
- Appendix B MW-1A/MW-1AR Boring Log and Well Construction Forms
- Appendix C Feasibility Study Water Quality Information
- Appendix D Long-Term Concentration Trend Plots
- Appendix E Historical Groundwater Flow Maps

I:\25221067.00\Deliverables\2021 April ASD MOD 1-3 LF\211013_COL_1-3 LF_Apr21 ASD_Final.docx

[This page left blank intentionally]

1.0 INTRODUCTION

This Alternative Source Demonstration (ASD) was prepared to support compliance with the groundwater monitoring requirements of the “Coal Combustion Residuals (CCR) Final Rule” published by the U.S. Environmental Protection Agency (U.S. EPA) in the *Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule*, dated April 17, 2015 (U.S. EPA, 2015), and subsequent amendments. Specifically, this report was prepared to fulfill the requirements of 40 CFR 257.94(e)(2). The applicable sections of the Rule are provided below in *italics*.

1.1 §257.94(E)(2) ALTERNATIVE SOURCE DEMONSTRATION REQUIREMENTS

The owner and operator may demonstrate that a source other than the CCR Unit caused the statistically significant increase over background levels for a constituent or that the statistically significant increase resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality. The owner or operator must complete the written demonstration within 90 days of detecting a statistically significant increase over background levels.

An ASD is completed when there are exceedances of one or more benchmarks established within the groundwater monitoring program. The ASD is completed to determine if any other sources are likely causes of the identified exceedance(s) of established benchmark(s) at the site. This ASD was performed in response to results indicating a statistically significant increase (SSI) over background levels during detection monitoring under the CCR Rule.

This ASD report is evaluating the SSIs observed in the statistical evaluation of the April 2021 detection monitoring event at the Columbia Energy Center (COL) Dry Ash Disposal Facility, Modules 1-3 CCR Units. The first ASD was prepared for this facility evaluating the SSIs observed in the statistical evaluation of the October 2017 detection monitoring event (SCS Engineers [SCS], 2018). The October 2017 ASD and subsequent semiannual updates have concluded that several lines of evidence demonstrated that SSIs reported for boron, chloride, and sulfate concentrations in the downgradient monitoring wells were likely due to man-made sources other than the CCR Units and/or naturally occurring constituents in the alluvial aquifer.

As discussed in more detail in **Section 4.2** of this ASD, the findings for the April 2021 monitoring event were consistent with those for the previous events.

1.2 SITE INFORMATION AND MAP

The COL site is located at W8375 Murray Road, Pardeeville, Columbia County, Wisconsin (**Figure 1**). The COL site is an active coal-burning generating station, which has been burning coal and disposing of CCR on site since the mid-1970s. The layout of the site is shown on **Figure 2**. The COL property includes two areas of CCR storage and disposal. These are the Dry Ash Disposal Facility (ADF) and the Ash Ponds Facility. This ASD will evaluate the conditions at the site for Modules 1-3 of the ADF only. The ADF is operated under the Wisconsin Department of Natural Resources (WDNR) License No. 3025.

The groundwater monitoring system monitors the following CCR Unit:

- COL Dry ADF – Modules 1-3 (existing CCR Landfill)

Modules 1-3 were previously described as separate existing CCR landfills, although they are contiguous and are managed as a single landfill by the facility and by the WDNR. Wisconsin Power and Light Company (WPL) recently clarified that Modules 1-3 are one existing CCR landfill under the federal CCR Rule, and this report reflects WPL's clarification.

A map showing the CCR Units and all background (or upgradient) and downgradient monitoring wells with identification numbers for the CCR groundwater monitoring program and the state monitoring program is provided as **Figure 2**. Separate monitoring systems have been established for the other CCR Units at COL, which include Module 4 of the COL ADF, the primary ash pond, and the secondary ash pond.

1.3 STATISTICALLY SIGNIFICANT INCREASES IDENTIFIED

SSIs were identified by comparing the monitoring results to Upper Prediction Limits (UPLs) established in accordance with 40 CFR 257.93(f)(3) and the statistical method previously selected for the CCR Unit. The UPLs are based on an interwell approach using two background monitoring wells: MW-84A and MW-301. The interwell UPLs were calculated based on a 1-of-2 resampling approach. Resampling was completed in June 2021 for pH at MW-33AR and MW-34A. The UPLs and results for the April 2021 monitoring event, including the June resample, are summarized in the attached **Table 1**.

The April 2021 SSIs include the following parameters and wells:

- Boron: MW-33AR, MW-34A, MW-302
- Chloride: MW-33AR
- Sulfate: MW-33AR, MW-34A, MW-302

Field pH exceeded the UPL in the April 2021 samples from MW-33AR and MW-34A, but not in the June 2021 resamples; therefore, there is no SSI under the 1-of-2 resampling approach. Concentration trends for the parameters with SSIs are shown in **Appendix A**.

1.4 OVERVIEW OF ALTERNATIVE SOURCE DEMONSTRATION

This ASD report includes:

- Background information (**Section 2.0**)
- Evaluation of potential that SSIs are due to methodology or analysis (**Section 3.0**)
- Evaluation of potential that SSIs are due to natural sources or man-made sources other than the CCR Units (**Section 4.0**)
- ASD conclusions (**Section 5.0**)
- Monitoring recommendations (**Section 6.0**)

The CCR Rule constituent results from background and compliance sampling for parameters with SSIs are provided in **Table 2**. The laboratory reports for the April 2021 detection monitoring event will be included in the 2021 Annual Groundwater Monitoring and Corrective Action Report due in January 2022. Complete laboratory reports for the background monitoring events and the previous

detection monitoring events were included in previous annual groundwater monitoring and corrective action reports.

2.0 BACKGROUND

To provide context for the ASD evaluation, the following background information is provided in this section of the report, prior to the ASD evaluation sections:

- Geologic and hydrogeologic setting
- CCR Rule monitoring system
- Other monitoring wells

A more detailed discussion of the background information for the site is provided in the ASD for the October 2017 event (SCS, 2018).

2.1 REGIONAL GEOLOGY AND HYDROGEOLOGY

2.1.1 Regional Information

For the purposes of groundwater monitoring, the surficial sand and gravel aquifer is considered the uppermost aquifer, as defined under 40 CFR 257.53. Immediately underlying the surficial sand and gravel aquifer is the Cambrian-Ordovician sandstone aquifer.

Additional details on the regional geology and hydrogeology were provided in the October 2017 ASD (SCS, 2018).

2.1.2 Site Information

Soils at the site are primarily sand to a depth of approximately 50 to 100 feet, and overlie sandstone bedrock. Soils encountered during the site feasibility study for the COL ADF were described as generally sandy with interbedded silty clay lenses up to 20 feet thick (Warzyn, 1978). During drilling of CCR wells MW-301 and MW-302, the unconsolidated materials were identified as consisting primarily of silty sand. Boring logs for previously installed monitoring wells MW-33AR, MW-34A, MW-84A, MW-1AR, and M-4R show silty sand and sand as the primary unconsolidated materials at these locations. All CCR monitoring wells are screened within the unconsolidated sand unit.

Shallow groundwater at the site generally flows to the north and west across the existing landfill Modules 1-3 area, then generally flows west toward the Wisconsin River. A groundwater flow map for April 2021 is shown on **Figure 3**. The groundwater elevation data for the CCR monitoring wells and state monitoring program wells are provided in **Table 3**.

2.2 CCR RULE MONITORING SYSTEM

The groundwater monitoring system established in accordance with the CCR Rule consists of two upgradient (background) monitoring wells and three downgradient monitoring wells. The background wells include MW-301 and MW-84A. The downgradient wells include MW-302, MW-33AR, and MW-34A. The CCR Rule wells are installed within the sand and gravel aquifer. Well depths range from approximately 29 to 45 feet, measured from the top of the well casing.

Existing state monitoring well MW-1AR was included as a supplemental well in the April 2021 monitoring event to provide additional evaluation to the northeast of the CCR Unit. The well depth for

MW-1AR is 44.4 feet and it was installed in November 1994. The MW-1A boring log and MW-1AR well construction form are provided in **Appendix B**.

2.3 OTHER MONITORING WELLS

Additional groundwater monitoring wells currently exist at COL as part of the monitoring systems developed for the state monitoring program and for the other CCR Units.

Monitoring wells for the state monitoring program are installed in the unconsolidated sand and gravel unit, which is the uppermost aquifer as defined under 40 CFR 257.53. This shallow monitoring system includes water table wells and mid-depth piezometers. Well depths range from approximately 14 to 76 feet, measured from the top of the well casing.

3.0 METHODOLOGY AND ANALYSIS REVIEW

To evaluate the potential that an SSI is due to a source other than the regulated CCR Unit, SCS used a two-step evaluation process. First, the sample collection, field and laboratory analysis, and statistical evaluation were reviewed to identify any potential error or analysis that led to exceedance of the benchmark. Second, potential alternative sources, including natural variation and man-made sources other than the CCR Unit, were evaluated. This section of the report provides the findings of the methodology and analysis review. **Section 4.0** of the report addresses the potential alternative sources.

3.1 SAMPLING AND FIELD ANALYSIS

Field notes and sampling results were reviewed to determine if any sampling error may have caused or contributed to the observed SSIs. Potential field sampling errors or issues could include mislabeling of samples, improper sample handling, missed holding times, cross contamination during sampling, or other field error. Field blank sample results were also reviewed for any indication of potential contamination from sampling equipment or containers. Based on the review of the field notes and results, SCS did not identify any indication that the SSI concentrations were due to a sampling error.

SCS did not identify any issues with the sampling procedures or field analysis based on review of the data and field notes. Because boron, chloride, and sulfate are laboratory parameters, there is little potential for a field analysis error to contribute to an SSI.

3.2 LABORATORY ANALYSIS REVIEW

The laboratory reports for the April 2021 detection monitoring event were reviewed to determine if any laboratory analysis error or issue may have caused or contributed to an observed SSI for boron, chloride, or sulfate. The laboratory report review included reviewing the laboratory quality control flags and narrative, verifying that correct methods were used and desired detection limits were achieved, and checking the field and laboratory blank sample results.

Based on the review of the laboratory reports, SCS did not identify any indication that the SSIs were due to a laboratory analysis error. There were no laboratory quality control flags or issues identified in the laboratory report that affect the usability of the data for detection monitoring.

Time series plots of the SSI constituent analytical data were also reviewed for any anomalous results that might indicate a possible sampling or laboratory error (e.g., dilution error or incorrect sample

labeling). The time series plots are provided in **Appendix A**. The concentrations observed are similar to historical concentrations.

3.3 STATISTICAL EVALUATION REVIEW

The review of the statistical results and methods included a quality control check of the following:

- Input analytical data vs. laboratory analytical reports
- Statistical method and process for each SSI

Based on the review of the statistical evaluation, SCS did not identify any errors or issues in the statistical evaluation that caused or contributed to the determination of interwell SSIs for the April 2021 detection monitoring event.

3.4 SUMMARY OF METHODOLOGY AND ANALYSIS REVIEW FINDINGS

In summary, there were no changes to the SSI determinations for the April 2021 monitoring event based on the methodology and analysis review. No errors or issues causing or contributing to the reported SSIs were identified.

4.0 ALTERNATIVE SOURCES

This section of the report discusses the potential alternative sources for the boron, chloride, and sulfate SSIs at the downgradient monitoring wells; identifies the most likely alternative source(s); and presents the lines of evidence indicating that an alternative source is the most likely cause of the observed SSIs.

4.1 POTENTIAL CAUSES OF SSI

4.1.1 Natural Variation

The statistical analysis was completed using an interwell approach, comparing the April 2021 detection monitoring results to the UPLs calculated based on sampling of the background wells (MW-84A and MW-301). If concentrations of a constituent that is naturally present in the aquifer vary spatially, then the potential exists that the downgradient concentrations may be higher than upgradient concentrations due to natural variation. Previous monitoring results for boron, chloride, and sulfate at COL Modules 1-3 landfill are shown in **Table 2**.

Although natural variation is present in the shallow aquifer, it does not appear likely that natural variation is the primary source causing the boron, chloride, and sulfate SSIs.

4.1.2 Man-Made Alternative Sources

Man-made alternative sources that could potentially contribute to the boron, chloride, and sulfate SSIs could include the closed ash pond landfill, the active and inactive ash ponds, the former ash pond effluent ditch, the coal storage area, road salt use, railroad operations, or other plant operations.

Based on the groundwater flow directions and on previous investigations at the site, the former ash pond effluent ditch appears to be the most likely cause of the boron and/or sulfate SSIs for wells

MW-33AR, MW-34A, and MW-302. The ash pond effluent ditch also likely contributed to the chloride SSIs at MW-33AR.

4.2 LINES OF EVIDENCE

The lines of evidence indicating that the SSIs for boron, chloride, and sulfate in compliance wells MW-33AR, MW-34A, and MW-302, relative to the background wells, are due to an alternative source include:

1. Elevated concentrations of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located, before the landfill was constructed.
2. Monitoring performed under the state program documents that the concentrations of boron, chloride, and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation.
3. Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west and/or north.
4. The increased and variable chloride results for well MW-33AR in the last 2 years have not correlated with an increase in boron, as would be expected for a CCR leachate source; therefore, an alternative source is more likely.

4.2.1 Pre-Landfill Water Quality

Elevated concentrations of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located, before the landfill was constructed. Groundwater monitoring performed in 1977 and 1978 as part of the Feasibility Study for the landfill permitting showed that wells located along the west side of the future landfill footprint, where the current compliance wells are located, had elevated results for sulfate, chloride, and specific conductance.

The 1978 Feasibility Study (Warzyn, 1978) for the dry ADF discusses the influence of the ash pond effluent ditch on groundwater west of the proposed site. The former ash pond effluent ditch, shown on **Figure 2**, carried effluent from the ash ponds located north of the plant, and flowed south between the west side of the current landfill and the substation. Groundwater monitoring in December 1977 indicated that sulfate was present at 1,200 milligrams per liter (mg/L) in MW-33A, which was located near the point where the ash pond effluent discharged from a culvert into the effluent ditch. The sulfate concentration at this well decreased to 830 mg/L in the December 1978 sampling (Warzyn, 1979). Current concentrations of sulfate in this area, while above background, are much lower. The April 2021 sulfate result for MW-33AR (installed to replace MW-33A) was 94.3 mg/L, for MW-34A was 59.3 mg/L, and for MW-302 was 36.9 mg/L.

Selected text and tables from the 1978 Feasibility Study and the 1979 Supplementary Feasibility Study Report are included in **Appendix C**.

4.2.2 Long-Term Concentration Trends

Monitoring performed under the state program documents that the concentrations of boron and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation. Routine groundwater monitoring for the COL ADF began after the Plan

of Operation was approved and prior to initial CCR disposal. The earliest data available from the WDNR Groundwater Environmental Monitoring System (GEMS) database is from September 1984. Initial placement of CCR in test plots in Module 1 of the ADF was approved in October 1984 and CCR disposal began sometime after that. Therefore, the initial groundwater monitoring results in the GEMS database represent pre-disposal conditions for the landfill.

The earliest historic monitoring data show that before CCR disposal in the landfill began, concentrations of boron and sulfate were significantly higher than current concentrations in the area west of the landfill where the compliance wells are located. Graphs of historical concentrations are provided in **Appendix D**. Results for compliance well MW-33AR are plotted with results from well MW-33A. MW-33AR was a replacement well for MW-33A at a slightly different location and depth. The well screen was installed approximately 10 feet higher in MW-33AR than in MW-33A, intersecting the water table, which may explain the increase in concentration that occurred with the well replacement. Results for compliance well MW-302 are plotted with results from monitoring well MW-85, which was located near the current MW-302 location (see **Figure 2**) and was monitored from September 1984 through September 1995.

The recent boron concentrations are consistent with generally decreasing or stable historical concentrations at MW-33AR and MW-34A (**Appendix A** and **Appendix D**). Recent boron concentrations at MW-302 have been variable, but remain well below the concentrations observed in samples from MW-85 prior to CCR disposal in the landfill.

4.2.3 Groundwater Flow Direction Changes

Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west. The 1978 Feasibility Study report states that the southern 2/3 of the proposed fill area (including the area of the active CCR landfill phases) exhibits a southeast and southerly groundwater flow direction, toward an agricultural drainage ditch southeast and south of the landfill area. The 1981 Plan of Operation indicates that flow in the landfill area is to the east-southeast. A water table map prepared by RMT, based on October 2002 water level measurements, shows flow under the landfill generally to the east and northeast from a groundwater high near the effluent ditch and Wisconsin Pollutant Discharge Elimination System (WPDES) pond between the landfill and the substation. The 1981 and 2002 water table maps are provided in **Appendix E**.

Under current conditions, groundwater flow below the active landfill area is generally to the north, west, and northwest. The flow changes with time reflect the termination of discharge to the ash pond effluent ditch in the mid-2000s. When discharge via this ditch was active, the ditch was a source of recharge to the groundwater and created a high groundwater area with flow moving away from the ditch to the east. After discharge to the ditch was terminated, water levels in this area decreased significantly and the groundwater flow direction changed.

With the changes in groundwater flow, historically impacted groundwater moved in alternating directions. While the effluent ditch was active, impacted groundwater likely moved eastward past the current compliance wells, as indicated by the long-term concentration data. Although the compliance wells are downgradient from the landfill under current flow conditions, the observed groundwater impacts may be residual from the past when the wells were downgradient from the effluent ditch.

4.2.4 Chloride and Boron Leachate Concentrations

The chloride results for well MW-33AR increased beginning in 2016, peaked in April 2018 and April 2019, decreased significantly in April 2020, and have remained relatively consistent since then (**Table 2** and **Appendix A**). Over the same time period, boron concentrations at MW-33AR have followed a steady gradual decreasing trend. The lack of correlation with boron indicates the source of the increase and subsequent decrease in chloride is not likely the CCR landfill. Sampling of the landfill leachate pond and the lysimeters indicates that boron and chloride concentrations are generally both elevated in leachate (**Table 4**); therefore, a leachate source would tend to influence concentrations of both parameters. Furthermore, the peak chloride concentrations in the groundwater samples from MW-33AR in 2018 and 2019 exceeded the chloride concentrations measured in the leachate at that time (**Table 4**), indicating the leachate was not the source of chloride at this location (**Table 2** and **Table 4**). An alternative man-made source, such as road salt, is a more likely source of chloride than the CCR Unit.

5.0 ALTERNATIVE SOURCE DEMONSTRATION CONCLUSIONS

The lines of evidence discussed above regarding the SSIs reported for boron, chloride, and sulfate concentrations in downgradient monitoring wells MW-33AR, MW-34A, and/or MW-302 demonstrate that the SSIs are likely primarily due to sources other than the CCR Units. Boron, sulfate, and chloride concentrations were elevated prior to disposal of CCR in the landfill and are associated with historical discharges from the ash ponds via the effluent ditch located west of the landfill. Elevated chloride concentrations detected at well MW-33AR appear likely to be related to an alternative non-CCR source, such as salt.

6.0 SITE GROUNDWATER MONITORING RECOMMENDATIONS

In accordance with section 257.94(e)(2) of the CCR Rule, the COL Modules 1-3 CCR Units may continue with detection monitoring based on this ASD. The ASD report will be included in the 2021 Annual Report due January 31, 2022.

7.0 REFERENCES

SCS Engineers, 2018, Alternative Source Demonstration, October 2017 Detection Monitoring, Columbia Energy Center Dry Ash Disposal Facility, April 2018.

U.S. EPA, 2015, Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule, April 2015.

Warzyn Engineering, Inc., 1978, Feasibility Study, Proposed Fly Ash and/or Scrubber Sludge Disposal Facility – Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Warzyn Engineering, Inc., 1979, and Preliminary Engineering Concepts, Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Tables

- 1 Groundwater Analytical Results Summary – April 2021 Event
- 2 Historical Analytical Results for Parameters with SSIs
- 3 Groundwater Elevation – State Monitoring Program and CCR Well Network
- 4 Analytical Results – Lysimeters and Leachate Pond

**Table 1. Groundwater Analytical Results Summary - April 2021 Event
Columbia Landfill MOD 1-3 / SCS Engineers Project #25221067.00**

Parameter Name	UPL	Background Wells		Compliance Wells					
		MW-84A	MW-301	MW-33AR		MW-34A		MW-302	MW-1AR
		4/14/20210	4/14/2021	4/13/2021	6/11/2021	4/13/2021	6/11/2021	4/13/2021	4/14/2021
Appendix III									
Boron, ug/L	35.6	14.3	22.2	473	--	203	--	521	16.1
Calcium, ug/L	129,000	69,100	117,000 P6	51,600	--	61,600	--	82,400	85500
Chloride, mg/L	6.2	4.4	1.5 J	26.9	--	2.3	--	1.4 J	1.5 J
Fluoride, mg/L	DQ	<0.095	<0.095	<0.095	--	<0.095	--	<0.095	<0.095
Field pH, Std. Units	7.78	7.34	6.66	8.78	7.71	7.93	7.61	7.51	7.52
Sulfate, mg/L	30.3	1.4 J	8.5	94.3	--	59.3	--	36.9	4.4 M0
Total Dissolved Solids, mg/L	514	328	472	362	--	290	--	370	318

4.4 Blue shaded cell indicates the compliance well result exceeds the UPL (background) and the Limit of Quantitation (LOQ).

Abbreviations:

UPL = Upper Prediction Limit

DQ = Double Qualification

SSI = Statistically Significant Increase

LOQ = Limit of Quantitation

LOD = Limit of Detection

µg/L = micrograms per liter

mg/L = milligrams per liter

-- = Not Measured

Lab Notes:

J = Estimated concentration at or above the LOD and below the LOQ.

P6 = Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

M0 = Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits

1. An individual result above the UPL does not constitute an SSI above background. See the accompanying report text for identification of statistically significant results.
2. Interwell UPLs calculated based on results from background wells MW-84A and MW-301. Interwell UPLs based on 1-of-2 retesting approach. UPLs updated in January 2020 based on background well results through October 2019.

Created by:	<u>NDK</u>	Date:	<u>5/17/2021</u>
Last revision by:	<u>NDK</u>	Date:	<u>6/14/2021</u>
Checked by:	<u>RM</u>	Date:	<u>6/14/2021</u>
Scientist/Proj Mgr QA/QC:	<u>TK</u>	Date:	<u>9/23/2021</u>

**Table 2. Historical Analytical Results for Parameters with SSIs
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Background	MW-301	12/22/2015	26.5	3.70 J	9.30
		4/5/2016	25.2	4.00	15.3
		7/8/2016	23.6	3.50 J	15.0
		10/13/2016	30.6	2.20	13.9
		12/29/2016	32.8	2.00 J	12.3 J
		1/25/2017	32.6	1.50 J	6.50
		4/11/2017	28.8	2.00	10.3
		6/6/2017	21.3	3.50	17.1
		8/8/2017	30.6	5.50	31.6
		10/23/2017	34.3	4.00	27.5
		4/25/2018	24.3	2.30	8.60
		8/8/2018	22.8	-	-
		10/22/2018	27.8	3.20	19.2
		4/3/2019	26.9	2.90 J, B	5.30 J
		10/9/2019	35.9	1.70	8.40
		5/29/2020	21.3	2.00 J	11.5 J
		10/8/2020	28.8	3.4	25.1
	4/13/2021	22.2	1.5 J	8.5	
	MW-84A	12/22/2015	11.9	4.90	4.90
		4/5/2016	14.0	4.70	4.30
		7/8/2016	14.7	5.10	3.70 J
		7/28/2016	-	-	-
		10/13/2016	11.1	4.30	2.60 J
		12/29/2016	14.7	4.70	2.70 J
		1/25/2017	16.1	4.60	3.00
		4/11/2017	12.9	4.90	2.80 J
		6/6/2017	14.8	5.50	2.70 J
		8/8/2017	22.9	5.50	2.00 J
		10/24/2017	13.8	5.10	2.20 J
		4/25/2018	25.0	4.80	2.80 J
		8/8/2018	12.8	--	--
		10/22/2018	10.1 J	4.20	1.60 J
		4/3/2019	13.6	3.60 B	1.40 J
10/9/2019		12.0	3.90	1.30 J	
5/29/2020	10.0	3.70	1.50 J		
10/8/2020	9.7 J	4.30	1.3 J		
4/13/2021	14.3	4.40	1.4 J		

**Table 2. Historical Analytical Results for Parameters with SSIs
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-302	12/22/2015	80.0	4.20	37.4
		4/5/2016	78.8	4.10	55.6
		7/7/2016	134	3.10 J	35.4
		10/13/2016	132	1.10 J	64.7
		12/29/2016	106	1.20 J	56.4
		1/25/2017	149	1.60 J	61.6
		4/11/2017	322	1.60 J	81.3
		6/6/2017	671	3.50	84.6
		8/8/2017	833	4.50	79.0
		10/24/2017	691	6.90	78.4
		4/24/2018	1,950	15.0	109
		9/21/2018	203	1.70 J	30.0
		10/22/2018	296	1.80 J	26.9
		4/2/2019	254	1.50 J	25.2
		10/9/2019	246	1.10 J	16.7
		5/29/2020	611	1.20 J	34.6
		10/8/2020	648	1.1 J	36.5
	4/13/2021	521	1.4 J	36.9	
	MW-33AR	12/21/2015	954	10.6	96.2
		4/5/2016	813	12.5	91.5
		7/7/2016	794	12.5	99.2
		10/13/2016	827	52.5	124
		12/29/2016	812	39.6	132
		1/25/2017	763	41.4	133
		4/11/2017	760	47.1	139
		6/6/2017	692	68.1	151
		8/7/2017	697	105	164
		10/24/2017	678	119	175
		4/24/2018	601	188	163
		9/21/2018	683	32.6	124
		10/22/2018	682	14.4	112
		4/2/2019	568	229	201
		10/8/2019	548	153	182
5/28/2020		566	15.9	104	
10/8/2020	569	27.3	97.4		
4/13/2021	473	26.9	94.3		

**Table 2. Historical Analytical Results for Parameters with SSIs
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-34A	12/21/2015	230	4.90	69.9
		4/5/2016	220	5.10	71.6
		7/7/2016	216	5.60	63.4
		7/28/2016	-	-	-
		10/13/2016	212	6.80	54.8
		12/29/2016	224	7.10	63.9
		1/25/2017	214	7.20	71.2
		4/11/2017	214	6.20	87.6
		6/6/2017	201	7.80	106
		8/7/2017	205	7.40	105
		10/24/2017	208	7.60	98.0
		4/24/2018	209	8.20	144
		9/21/2018	241	17.1	141
		10/22/2018	233	19.9	123
		4/4/2019	204	18.7	70.4
		10/8/2019	207	57.9	39.8
		5/28/2020	210	3.90	44.4
		10/8/2020	213	2.10	58.7
	4/13/2021	203	2.30	59.3	
	MW-1AR	4/14/2021	16.1	1.5 J	4.4 M0

Abbreviations:

µg/L = micrograms per liter or parts per billion (ppb)

mg/l = milligrams per liter or parts per million (ppm)

J = Estimated value below the laboratory's limit of quantitation

B = Analyte was detected in the associated Method Blank.

M0 = matrix spike recovery and/or matrix spike duplicate recovery outside of laboratory control limits

Notes:

- (1) Analytical laboratory reports provided in the Annual Groundwater Monitoring and Corrective Action Reports.
- (2) MW-1AR was added to the sampling network in 2021 to provide additional evaluation of site conditions in the CCR unit

Created by: NDK
 Last revision by: RM
 Scientist Check: JR

Date: 3/19/2020
 Date: 6/24/2021
 Date: 6/29/2021

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25221067.00**

	Well Number	MW-1AR	MW-4	MW-5R	MW-33AR	MW-33BR	MW-34A	MW-34B	MW-37A	MW-83	MW-84A	MW-84B	MW-86	MW-91AR	MW-91B	MW-92A	MW-92B	LS-1	LS-3R	LH-2	LH-3	LH-4
		Top of Casing Elevation (feet amsl)	822.55	819.74	805.44	808.29	808.39	805.95	806.05	813.04	807.96	814.28	814.26	824.79	809.03	808.45	808.47	808.41				
	Screen Length (ft)																					
	Total Depth (ft from top of casing)	44.40	39.58	25.97	31.08	57.50	35.43	56.95	31.80	25.42	40.21	52.02	45.43	32.90	52.38	28.94	51.75	17.42	17.10	19.90		
	Top of Well Screen Elevation (ft)	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	NM	NM	NM		
	Measurement Date																					
Dry Ash Facility (Facility ID #03025)	October 2, 2012	783.41	783.70	784.96	782.38	782.23	783.03	782.99	782.66	dry	783.84	783.94	783.81	784.09	783.90	784.49	784.06				dry	--
	April 15, 2013	785.44	784.02	786.09	784.16	784.14	784.74	784.79	783.87	784.49	785.83	785.76	785.22	785.14	785.01	785.75	785.34	NM	dry	dry	dry	--
	October 8, 2013													785.66	785.42	785.97	785.52	NM	NM	NM	--	--
	October 15, 2013	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.66	785.42	785.97	785.52					
	April 14, 2014	784.95	784.09	785.63	783.74	783.91	784.63	784.70	783.45	783.73	785.58	785.52	784.96	785.04	784.96	785.99	785.54	NM	dry	achate depth = 0.2 ft	--	--
	October 2-3, 2014	785.03	785.39	786.08	784.37	784.28	784.57	784.54	784.56	dry	785.24	785.18	785.19	785.47	785.28	785.75	785.33	NM	dry	achate depth = 0.3 ft	--	--
	April 13-14, 2015	783.96	783.63	785.25	783.01	782.74	783.65	783.95	782.87	dry	784.43	784.51	784.17	784.48	784.37	785.07	784.66	dry	--	dry	--	--
	October 6-7, 2015	784.28	784.44	785.72	783.68	783.33	784.05	784.02	783.66	dry	784.80	784.76	784.66	784.89	784.70	785.20	784.76	broken	dry	achate depth = 14.8'	--	--
	April 4-6, 2016	785.82	aband	787.02	785.29	785.07	785.63	785.67	784.76	785.43	786.37	786.26	785.89	786.05	785.95	786.61	786.21	broken	dry	15.9'	--	--
	October 11-13, 2016	786.64	aband	788.00	787.36	786.46	786.45	786.32	786.40	786.81	787.22	787.11	786.96	787.17	786.81	787.68	787.25	liquid depth = 3.5'	dry	0.8"	1.4"	--
	April 10-13, 2017	786.96	aband	788.13	786.39	785.99	786.30	786.28	786.34	786.23	787.16	787.06	786.96	787.24	787.03	787.90	787.60	liquid depth = 3.0'	dry	-0.3	1.4"	--
	October 3-5, 2017	785.48	aband	786.66	784.51	784.22	784.67	784.63	784.86	784.29	NM	786.49	785.58	786.08	785.83	786.47	786.02	liquid depth = 2.7'	dry	NM	NM	--
	October 9-10, 2017	NM	aband	NM	NM	NM	NM	NM	NM	NM	785.56 ⁽⁶⁾	NM	NM	NM	NM	NM	NM	liquid depth = 2.7'	NM	NM	1.4" ⁽⁵⁾	1.6" ⁽⁵⁾
	February 21, 2018	783.97	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	784.68	784.46	NM	NM	NM	NM	NM	NM	NM
	April 23-25, 2018	783.99	aband	785.36	783.09	786.36	781.77	780.79	783.28	783.32	785.88	784.91	782.54	784.71	784.53	785.23	784.81	liquid depth = 2.7'	NM	NM	NM	NM
	October 23-25, 2018	788.25	aband	789.71	788.77	787.96	787.88	787.73	787.62	788.26	788.32	788.19	788.21	788.59	788.31	789.32	788.87	dry	liquid depth = 4.6'	4	4	--
	April 1-4, 2019	787.05	aband	788.64	786.63	786.54	786.82	786.92	786.47	786.78	787.35	787.34	787.16	787.45	787.18	788.04	787.63	liquid depth = 3.9'	dry	--	--	--
	October 7-9, 2019	787.26	aband	789.23	788.26	787.64	787.92	787.74	786.77	788.90	787.79	787.73	787.44	787.78	787.62	788.63	788.17	liquid depth = 3.8'	dry	-0.1"	11.7"	13.1"
	May 27-28, 2020	786.92	aband	788.34	786.01	785.75	785.98	785.99	786.22	786.03	787.02	786.99	786.94	787.26	787.05	787.86	787.47	liquid depth = 3.8'	dry	-0.1	2.4	2.4
	October 7-8, 2020	785.95	aband	787.76	785.91	785.45	785.70	785.68	785.52	785.72	786.10	786.06	786.10	786.55	786.33	786.85	786.38	liquid depth = 3.8'	dry	-0.1	2.7	2.4
	February 25, 2021	NM	aband	NM	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	-0.1	2.7
April 14, 2021	785.11	aband	787.29	784.27	784.05	784.77	784.77	784.46	c	785.84	785.81	785.60	785.86	785.69	786.47	786.06	liquid depth = 3.7'			--	0.2333	0.2167
June 11, 2021	NM	aband	NM	784.19	NM	784.66	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	--	--	--	--	--
	Bottom of Well Elevation (ft)	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	NM	NM	NM	NM	

	Well Number	M-3	M-4R	MW-39A	MW-39B	MW-48A	MW-48B	MW-57	MW-59	MW-216R	MW-217	MW-220RR	SG-1	SG-2	SG-3	SG-4
		Top of Casing Elevation (feet amsl)	788.23	806.10	809.62	809.50	828.86	828.84	786.29	815.48	814.21	791.55	792.90	792.06	795.25	808.60
	Screen Length (ft)															
	Total Depth (ft from top of casing)	16.90	25.55	34.80	76.07	51.88	75.80	14.40	38.50	37.85	37.37	18.96	--	--	--	--
	Top of Well Screen Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--
	Measurement Date															
Ash Pond Facility (Facility ID #02325)	October 2, 2012	780.13	786.76	781.49	781.34	782.03	781.93	780.58	779.88	781.91	780.95	780.55	789.14	793.85	dry	dry
	April 15, 2013	785.16	788.39	783.97	784.00	783.77	783.78	784.69	783.66	784.09	784.75	785.02	789.5 ⁽¹⁾	NM	dry	dry
	October 8, 2013	781.22	786.67	NM	NM	783.69	783.58	NM	NM	783.39	782.27	782.36	789.5 ⁽¹⁾	791.33	dry	dry
	October 15, 2013	NM	NM	782.94	782.81	NM	NM	782.47	783.49	NM	NM	NM	NM	NM	NM	NM
	April 14, 2014	786.04	788.96	783.57	783.68	783.56	783.57	785.51	783.41	783.73	785.25	785.87	788.90	dry	dry	dry
	October 1-3, 2014	781.16	787.55	783.42	783.32	784.05	783.94	782.32	783.55	783.79	782.63	783.03	NM	dry	dry	dry
	April 13-14, 2015	783.08	786.83	782.77	782.68	782.80	782.82	782.81	782.83	782.93	783.34	783.42	789.3	791.70	dry	dry
	October 6-7, 2015	780.66	786.12	782.97	782.81	783.10	783.01	781.82	783.25	783.18	781.95	782.26	788.48	791.58	dry	dry
	April 4-6, 2016	784.21	789.09	785.27	785.27	784.79	784.76	783.21	784.97	785.68	785.02	784.36	NM	793.40	dry	dry
	October 11-13, 2016	781.88	787.88	785.75	785.52	785.73	785.61	783.12	786.51	786.16	783.75	784.09	788.32	792.52	dry	dry
	April 10-13, 2017	782.94	787.95	785.44	785.20	785.82	785.69	782.77	786.09	785.95	784.29	784.09	788.31	793.85	dry	dry
	October 3-5, 2017	780.93	787.04	783.35	783.18	784.30	784.19	782.37	784.23	783.89	782.48	782.61	788.3	793.45	dry	dry
	April 23-25, 2018	782.89	790.43	782.86	782.87	783.14	783.09	783.04	783.02	783.23	783.26	783.45	788.38	>795.25	dry	dry
	October 23-25, 2018	782.95	788.47	787.12	786.88	787.12	786.99	783.48	787.73	787.49	784.90	784.52	787.76	793.25	dry	dry
	April 1-4, 2019	785.68	789.44	786.28	786.31	786.56	786.45	785.27	787.39	786.53	786.33	785.46	788.40	794.60	dry	dry
	October 7-9, 2019	785.33	790.65	787.10	787.02	786.68	786.65	785.29	786.68	787.07	786.01	785.42	748.48	795.20	dry	dry
	May 27-29, 2020	781.80	787.73	785.12	784.92	785.74	785.59	783.11	785.89	785.60	783.41	783.89	748.48	>795.25	dry	dry
	October 7-8 & 17, 2020	781.42	787.74	784.74	784.64	785.03	784.96	782.83	785.43	785.10	783.06	783.49	788.34	793.32	dry	NM
April 12, 2021	782.30	786.34	783.66	783.65	784.13	784.08	782.79	784.08	783.97	783.15	783.49	788.03	793.45	below gauge	dry	
	Bottom of Well Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25221067.00**

Well Number	MW-301	MW-302	MW-303	MW-304	MW-305	M-4R	MW-33AR	MW-34A	MW-84A	MW-306	MW-307	MW-308	MW-309	MW-310	MW-311
Top of Casing Elevation (feet amsl)	806.89	813.00	811.52	805.42	806.32	806.10	808.29	805.95	814.28	807.63	806.89	806.9	813.27	813.62	809.74
Screen Length (ft)	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10
Total Depth (ft from top of casing)	29.40	33.6	35.80	25.7	25.6	39.58	31.08	35.43	40.21	27	26.5	28	37.67	38.41	36.19
Top of Well Screen Elevation (ft)	787.49	789.40	785.72	789.72	790.72	776.52	787.21	780.52	784.07	790.63	790.39	788.90	785.60	785.21	783.55
Measurement Date													--	--	--
December 21-22, 2015	NM	784.78	784.11	786.13	788.96	787.58	783.77	783.50	785.31	--	--	--	--	--	--
April 4-5, 2016	786.78	785.81	785.48	788.08	789.61	789.09	785.29	785.63	786.37	--	--	--	--	--	--
July 7-8, 2016	786.31	786.28	784.60	787.36	789.26	787.43	785.19	785.05	785.89	--	--	--	--	--	--
July 28, 2016	NM	NM	784.35	NM	NM	NM	NM	784.86	785.61	--	--	--	--	--	--
October 11-13, 2016	787.64	787.76	786.18	788.18	789.78	787.88	787.36	786.45	787.22	--	--	--	--	--	--
December 29, 2016	787.37	787.05	NM	NM	NM	NM	785.66	785.72	786.63	--	--	--	--	--	--
January 25-26, 2017	787.27	786.89	785.28	789.34	789.36	789.64	785.88	785.98	786.70	785.50	785.36	785.73	--	--	--
April 10 & 11, 2017	787.89	787.55	786.00	788.22	789.57	787.95	786.39	786.30	787.16	786.22	785.64	786.51	--	--	--
June 6, 2017	788.25	788.37	786.49	788.58	789.79	787.83	787.27	786.66	787.63	786.85	786.07	786.46	--	--	--
August 7-9, 2017	787.34	787.55	785.42	789.52	789.30	788.54	786.11	785.81	786.68	785.69	785.19	785.37	--	--	--
October 23-24, 2017	785.89	785.94	783.92	788.97	788.14	788.00	784.13	784.50	785.32	783.97	784.79	784.17	--	--	--
February 21, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.19	783.05	783.02
March 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.10	783.10	783.00
April 23-25, 2018	785.29	784.37	783.27	789.69	787.67	790.43	783.09	781.77	785.88	783.24	783.65	782.65	783.07	782.97	781.83
May 24, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.79	785.09	NM	785.45	785.97	786.11
June 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.03	786.64	786.47
July 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.27	786.35	786.55
August 7, 2018	787.06	NM	785.20	788.25	788.56	787.63	NM	NM	786.55	NM	NM	NM	NM	NM	NM
August 22, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.54	785.40	785.46
September 21, 2018	NM	788.37	786.50	NM	NM	NM	787.90	787.01	NM	NM	NM	NM	787.08	787.24	787.66
October 22-24, 2018	788.98	789.16	787.51	789.05	790.04	788.47	788.77	787.88	788.32	787.66	786.57	787.81	787.99	788.18	788.64
April 1-4, 2019	787.04	787.56	786.52	789.72	790.07	789.44	786.63	786.82	787.35	786.72	786.71	787.53	786.30	786.38	786.38
June 12, 2019	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	787.25	NM
June 19, 2019	NM	NM	786.81	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM
October 7-9, 2019	788.47	788.31	787.02	790.41	790.36	790.65	NM	NM	NM	787.47	786.99	787.18	787.26	787.94	787.64
December 13, 2019	--	--	--	--	--	--	--	--	--	787.03	785.68	786.43	--	--	--
December 23, 2019	--	--	--	--	--	--	--	--	--	--	--	--	--	775.22	--
January 17, 2020	--	--	785.58	--	--	--	--	--	--	--	--	--	--	--	--
February 3, 2020	787.24	NM	NM	NM	NM	NM	NM	NM	786.50	785.77	785.57	786.48	NM	NM	NM
May 27-29, 2020	787.77	787.29	785.56	789.30	787.78	787.73	786.01	785.98	787.02	785.77	785.35	786.28	785.98	785.81	785.85
June 30, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.18	NM	NM
August 6, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.93	NM	NM
October 7-8, 2020	786.53	786.74	785.16	788.52	787.96	787.74	785.91	785.70	786.10	785.39	784.71	785.68	785.47	785.56	785.83
December 11, 2020	--	--	--	--	788.19	--	--	--	--	--	--	--	785.26	785.26	--
February 25, 2021	--	--	784.27	--	788.36	--	--	784.75	--	--	--	--	--	--	--
April 12, 2021	786.50	785.77	784.07	787.99	788.11	786.34	784.27	784.77	785.84	784.32	784.21	785.55	784.29	784.24	784.15
June 11, 2021	NM	NM	NM	NM	NM	NM	784.19	784.66	NM	NM	NM	NM	784.20	784.05	NM
Bottom of Well Elevation (ft)	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	780.63	780.39	778.90	775.60	775.21	773.55

CCR Rule Wells

Notes:
 NM = not measured
 Created by: MDB Date: 5/6/2013
 Last revision by: RM Date: 6/11/2021
 Checked by: JR Date: 6/14/2021

- (1) The elevation for SG-1 is read off of the staff gauge (rather than measured from the top of the gauge).
- (2) SG-2 could not be located during the April 2013 event.
- (3) SG-3 could not be located during the October 2013 event. SG-1 could not be safely accessed during the October 2013 event.
- (4) LH-2 measurements are given as leachate depth, measured by a transducer.
- (5) LH-2 and LH-3 measurements were collected by WPL staff on October 9, 2017.
- (6) The depth to water at MW-84A was not measured prior to purging for sampling during the October 3-5 sampling event. The level was allowed to return to static and was measured on 10/10/2017.
- (7) BC = Brian Clepper; NS= Nate Sievers - Columbia Site employees.

I:\25221067.00\Deliverables\2021 April ASD MOD 1-3 LF\Tables\Table 3 - Groundwater Elevation Summary.xls\levels

**Table 4. Analytical Results - Lysimeters and Leachate Pond
Columbia Dry Ash Disposal Facility
SCS Engineers Project #25221067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LS-1	2015-Apr	DRY	--	--	--
	2015-Oct	BROKEN	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	--	6530	12.3	789
	2017-Apr	--	6510	20.7 J	814
	2017-Oct	--	6200	14.2 J	764
	2018-Apr	--	5920	16.0 J	856
	2018-Oct	DRY	--	--	--
	2019-Apr	--	5,640	22.0 J	911
	2019-Oct	--	6,180	19.2 J	861
	2020-May	--	6,180	25.4 J	1,040
	2020-Oct	--	5,640	27.2 J	950
	2021-Apr	--	6,010	21.1 J	976
LS-3R	2015-Apr	--	6480	20.6 B	807
	2015-Oct	DRY	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	DRY	--	--	--
	2017-Apr	DRY	--	--	--
	2017-Oct	DRY	--	--	--
	2018-Apr	DRY	--	--	--
	2018-Oct	--	6180	26.2 J	841
	2019-Apr	DRY	--	--	--
	2019-Oct	DRY	--	--	--
	2020-May	DRY	--	--	--
	2020-Oct	DRY	--	--	--
	2021-Apr	DRY	--	--	--

**Table 4. Analytical Results - Lysimeters and Leachate Pond
Columbia Dry Ash Disposal Facility
SCS Engineers Project #25221067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LP-1	2015-Apr	--	4060	27.8	734
	2015-Oct	--	4,300	37.1	820
	2016-Apr	--	1,830	26.8	416
	2016-Oct	--	4,610	71.5	835
	2017-Apr	--	2,690	66.3	587
	2017-Oct	--	4,970	91.7	739
	2018-Apr	--	2,060	63.2	634
	2018-Oct	--	2,630	151	907
	2019-Apr	--	570	35.1	249
	2019-Oct	--	1,270	63.9	602
	2020-May	--	2,460	179	952
	2020-Oct	--	2,710	243	1,160
	2021-Apr	--	3,340	319	1,180

Abbreviations:

µg/L = micrograms per liter

mg/L = milligrams per liter

-- = not analyzed

µmhos/cm = micromhos/centimeter

Notes:

B = Analyte was detected in the associated method blank.


J = Estimated concentration at or above the LOD and below the LOQ.

Created by: TLC Date: 12/1/2014
 Last revision by: RM Date: 6/24/2021
 Checked by: JR Date: 6/24/2021

I:\25221067.00\Deliverables\2021 April ASD MOD 1-3 LF\Tables\[Table 4 - Leachate_2015-Apr 2021 ASD.xlsx]Lys LP1 App III

Figures


- 1 Site Location Map
- 2 Site Plan and Monitoring Well Locations
- 3 Water Table Map – April 2021



POYNETTE QUADRANGLE
 WISCONSIN-COLUMBIA CO.
 7.5 MINUTE SERIES (TOPOGRAPHIC)
 2018
 SCALE: 1" = 2,000'




CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954		SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER PARDEEVILLE, WI		ENGINEER	SITE LOCATION MAP	
	PROJECT NO.	25220067.00		DRAWN BY:	BSS		SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	FIGURE
	DRAWN:	12/02/2019		CHECKED BY:	MDB			1
REVISED:	01/10/2020	APPROVED BY:	TK 04/10/2020					




- LEGEND
- EXISTING MAJOR CONTOUR (10' INTERVAL)
 - EXISTING MINOR CONTOUR (2' CONTOUR)
 - x - EXISTING FENCELINE
 - ||||| EXISTING TRACKS
 - ==== EXISTING PAVED ROAD
 - EXISTING UNPAVED ROAD
 - . . - EDGE OF WATER
 - APPROVED LIMITS OF WASTE (DRY ASH LANDFILL)
 - . . - CONSTRUCTED LIMITS OF WASTE (DRY ASH LANDFILL)
 - ⊕ WATER SUPPLY WELL
 - ⊙ STAFF GAUGE
 - ⊕ WATER TABLE WELL
 - ⊕ PIEZOMETER
 - ⊗ SURFACE WATER SAMPLE LOCATION
 - ⊠ LYSIMETER
 - ⊕ ABANDONED WATER TABLE WELL
 - ⊕ ABANDONED PIEZOMETER
 - ⚡ LEACHATE HEADWELL
 - CCR UNIT
 - ⊕ CCR MONITORING WELL
 - ⊕ CCR BACKGROUND MONITORING WELL

- NOTES:
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, MAY 2019 AND SEPTEMBER 2020.
 2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
 3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
 4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
 5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
 6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
 7. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH DISPOSAL FACILITY ARE: MW-301 AND MW-84A.



PROJECT NO. 25220067.00	DRAWN BY: BSS/ZTW	ENGINEER	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULE 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	SITE PLAN AND MONITORING WELL LOCATIONS	FIGURE
DRAWN: 12/02/2019	CHECKED BY: TK								
REVISED: 01/05/2021	APPROVED BY: TK 01/28/2021								2




- LEGEND**
- EXISTING MAJOR CONTOUR (10' INTERVAL)
 - EXISTING MINOR CONTOUR (2' CONTOUR)
 - x - x - EXISTING FENCE LINE
 - ||||| EXISTING TRACKS
 - ==== EXISTING PAVED ROAD
 - EXISTING UNPAVED ROAD
 - - - - - EDGE OF WATER
 - APPROVED LIMITS OF WASTE (DRY ASH LANDFILL)
 - · · — CONSTRUCTED LIMITS OF WASTE (DRY ASH LANDFILL)
 - ▲ WATER SUPPLY WELL
 - STAFF GAUGE
 - WATER TABLE WELL
 - ⊕ PIEZOMETER
 - ⊗ SURFACE WATER SAMPLE LOCATION
 - ⊠ LYSIMETER
 - ⊖ ABANDONED WATER TABLE WELL
 - ⊖ ABANDONED PIEZOMETER
 - ↖ LEACHATE HEADWELL
 - CCR UNIT
 - CCR MONITORING WELL
 - CCR BACKGROUND MONITORING WELL
 - 787.62 WATER TABLE ELEVATION
 - [788.87] POTENTIOMETRIC SURFACE ELEVATION (NOT CONTOURED)
 - (795.20) SURFACE WATER ELEVATION (NOT CONTOURED)
 - WATER TABLE CONTOUR
 - APPROXIMATE GROUNDWATER FLOW DIRECTION

- NOTES:**
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, AND MAY 2019.
 2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
 3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
 4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
 5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
 6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
 7. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON APRIL 12-14, 2021.
 8. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.

PROJECT NO.	25221067.00	DRAWN BY:	KP	<p>SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830</p>	<p>CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954</p>	<p>SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULE 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI</p>	<p>FIGURE 3</p>
DRAWN:	06/29/2021	CHECKED BY:	NDK				
REVISED:	06/29/2021	APPROVED BY:	TK 9/23/2021				

Appendix A
Trend Plots for CCR Wells

Boron



Time Series Analysis Run 6/25/2021 8:22 AM View: MOD 1-3 LF


Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

Time Series

Constituent: Boron (ug/L) Analysis Run 6/25/2021 8:23 AM View: MOD 1-3 LF
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			954	217.5 (D)		
12/22/2015	26.5	80			11.9	
4/5/2016	25.2	78.8	813	220	14	
7/7/2016		134	794	216		
7/8/2016	23.6				14.7	
10/13/2016	30.6	132	827	212	11.1	
12/29/2016	32.8	106	812	224	14.7	
1/25/2017	32.6	149	763	214	16.1	
4/11/2017	28.8	322	760	214	12.9	
6/6/2017	21.3	671	692	201	14.8	
8/7/2017			697	205		
8/8/2017	30.6	833			22.9	
10/23/2017	34.3					
10/24/2017		691	678	208	13.8	
4/24/2018		1950	601	209		
4/25/2018	24.3				25	
8/8/2018	22.8				12.8	
9/21/2018		203	683	241		
10/22/2018		296	682	233		
10/24/2018	27.8				10.1 (J)	
4/2/2019	26.9	254	568	204		
4/3/2019					13.6	
10/8/2019			548	207		
10/9/2019	35.9	246			12	
2/3/2020	27.9				15.7	
5/28/2020			566	210		
5/29/2020	21.3	611			10	
10/8/2020	28.8	648	569	213	9.7 (J)	
4/13/2021		521	473	203		
4/14/2021	22.2				14.3	16.1

Chloride



Time Series Analysis Run 6/25/2021 8:22 AM View: MOD 1-3 LF


Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

Time Series

Constituent: Chloride (mg/L) Analysis Run 6/25/2021 8:23 AM View: MOD 1-3 LF
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			10.6	4.85 (D)		
12/22/2015	3.7 (J)	4.2			4.9	
4/5/2016	4	4.1	12.5	5.1	4.7	
7/7/2016		3.1 (J)	12.5	5.6		
7/8/2016	3.5 (J)				5.1	
10/13/2016	2.2	1.1 (J)	52.5	6.8	4.3	
12/29/2016	2 (J)	1.2 (J)	39.6	7.1	4.7	
1/25/2017	1.5 (J)	1.6 (J)	41.4	7.2	4.6	
4/11/2017	2	1.6 (J)	47.1	6.2	4.9	
6/6/2017	3.5	3.5	68.1	7.8	5.5	
8/7/2017			105	7.4		
8/8/2017	5.5	4.5			5.5	
10/23/2017	4					
10/24/2017		6.9	119	7.6	5.1	
4/24/2018		15	188	8.2		
4/25/2018	2.3				4.8	
8/8/2018	5.2				4.9	
9/21/2018		1.7 (J)	32.6	17.1		
10/22/2018		1.8 (J)	14.4	19.9		
10/24/2018	3.2				4.2	
4/2/2019	0.79 (J)	1.5 (J)	229	18.7		
4/3/2019					3.6	
10/8/2019			153	57.9		
10/9/2019	1.7 (J)	1.1 (J)			3.9	
2/3/2020	1.3 (J)				3.7	
5/28/2020			15.9	3.9		
5/29/2020	2 (J)	1.2 (J)			3.7	
10/8/2020	3.4	1.1 (J)	27.3	2.1	4.3	
4/13/2021		1.4 (J)	26.9	2.3		
4/14/2021	1.5 (J)				4.4	1.5 (J)

Sulfate



Time Series Analysis Run 6/25/2021 8:22 AM View: MOD 1-3 LF
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

Time Series

Constituent: Sulfate (mg/L) Analysis Run 6/25/2021 8:23 AM View: MOD 1-3 LF
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			96.2	70.6 (D)		
12/22/2015	9.3	37.4			4.9	
4/5/2016	15.3	55.6	91.5	71.6	4.3	
7/7/2016		35.4	99.2	63.4		
7/8/2016	15				3.7 (J)	
10/13/2016	13.9	64.7	124	54.8	2.6 (J)	
12/29/2016	12.3 (J)	56.4	132	63.9	2.7 (J)	
1/25/2017	6.5	61.6	133	71.2	3	
4/11/2017	10.3	81.3	139	87.6	2.8 (J)	
6/6/2017	17.1	84.6	151	106	2.7 (J)	
8/7/2017			164	105		
8/8/2017	31.6	79			2 (J)	
10/23/2017	27.5					
10/24/2017		78.4	175	98	2.2 (J)	
4/24/2018		109	163	144		
4/25/2018	8.6				2.8 (J)	
8/8/2018	21.6				1.9 (J)	
9/21/2018		30	124	141		
10/22/2018		26.9	112	123		
10/24/2018	19.2				1.6 (J)	
4/2/2019	4.4	25.2	201	70.4		
4/3/2019					1.4 (J)	
10/8/2019			182	39.8		
10/9/2019	8.4	16.7			1.3 (J)	
2/3/2020	7.2				<2.2 (U)	
5/28/2020			104	44.4		
5/29/2020	11.5	34.6			1.5 (J)	
10/8/2020	25.1	36.5	97.4	58.7	1.3 (J)	
4/13/2021		36.9	94.3	59.3		
4/14/2021	8.5				1.4 (J)	4.4

Appendix B

MW-1A/MW-1AR Boring Log and Well Construction Forms

All abandonment work shall be performed in accordance with the provisions of Chapters NR 111, NR 112 or NR 141, Wis. Adm. Code, whichever is applicable. Also, see instructions on back.

(1) GENERAL INFORMATION		(2) FACILITY NAME	
Well/Drillhole/Borehole Location MW-1A	County Columbia	Original Well Owner (If Known) Wisconsin Power & Light	Present Well Owner Wisconsin Power & Light
SW 1/4 of SE 1/4 of Sec 27; T.12N; R.9 (if applicable)		Street or Route 222 W. Washington	
Gov't Lot	Grid Number	City, State, Zip Code Madison, WI 53701	
Grid Location 542,650 ft. <input checked="" type="checkbox"/> N. <input type="checkbox"/> S., 2,156,500ft. <input checked="" type="checkbox"/> E. <input type="checkbox"/> W.		Facility Well No. and/or Name (If Applicable)	
Civil Town Name Town of Pacific		WI Unique Well No.	
Street Address of Well Murray Road		Reason For Abandonment Well replacement	
City, Village Portage		Date of Abandonment 11/15/94	

WELL/DRILLHOLE/BOREHOLE INFORMATION

(3) Original Well/Drillhole/Borehole Construction Completed On (Date) <u>6/16/77</u> <input checked="" type="checkbox"/> Monitoring Well Construction Report Available? <input type="checkbox"/> Water Well <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Drillhole <input type="checkbox"/> Borehole Construction Type: <input checked="" type="checkbox"/> Drilled <input type="checkbox"/> Driven (Sandpoint) <input type="checkbox"/> Dug <input type="checkbox"/> Other (Specify) _____ Formation Type: <input checked="" type="checkbox"/> Unconsolidated Formation <input type="checkbox"/> Bedrock Total Well Depth (ft.) <u>45.8</u> Casing Diameter (ins.) <u>2.0</u> (From ground surface) Casing Depth (ft.) <u>35.8</u> Was Well Annular Space Grouted? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Unknown If Yes, To What Depth? _____ Feet	(4) Depth to Water (Feet) <u>36.5</u> Pump & Piping Removed? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Not Applicable Liner(s) Removed? <input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Not Applicable Screen Removed? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Not Applicable Casing Left in Place? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If No, Explain <u>Casing was drilled out to</u> Was Casing Cut Off Below Surface? <input type="checkbox"/> Yes <input type="checkbox"/> No Did Sealing Material Rise to Surface? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Did Material Settle After 24 Hours? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, Was Hole Retopped? <input type="checkbox"/> Yes <input type="checkbox"/> No
	(5) Required Method of Placing Sealing Material <input checked="" type="checkbox"/> Conductor Pipe-Gravity <input type="checkbox"/> Conductor Pipe-Pumped <input type="checkbox"/> Dump Bailer <input type="checkbox"/> Other (Explain)
	(6) Sealing Materials <input type="checkbox"/> Neat Cement Grout <input type="checkbox"/> Sand-Cement (Concrete) Grout <input type="checkbox"/> Concrete <input type="checkbox"/> Clay-Sand Slurry <input type="checkbox"/> Bentonite-Sand Slurry <input checked="" type="checkbox"/> Chipped Bentonite For monitoring wells and monitoring well boreholes only <input type="checkbox"/> Bentonite Pellets <input checked="" type="checkbox"/> Granular Bentonite <input type="checkbox"/> Bentonite-Cement Grout

(7) Sealing Material Used	From (Ft.)	To (Ft.)	No. Yards, Sacks Sealant or Volume	Mix Ratio or Mud Weight
Granular bentonite	Surface	18.0	6-50# Bags	Dry
Chipped bentonite	18.0	48.0	7-50# Bags	Dry

(8) Comments:

(9) Name of Person or Firm Doing Sealing Work RMT, Inc.		(10) FOR DNR OR COUNTY USE ONLY	
Signature of Person Doing Work <i>Richard L. ...</i>	Date Signed 11/28/94	Date Received/Inspected	District/County
Street or Route 744 Heartland Trail	Telephone Number (608) 831-4444	Reviewer/Inspector	<input type="checkbox"/> Complying Work <input type="checkbox"/> Noncomplying Work
City, State, Zip Code Madison, WI 53717		Follow-up Necessary	

Facility/Project Name WP&L Columbia - Dry Ash	Local Grid Location of Well <input type="checkbox"/> N. <input type="checkbox"/> E. _____ ft. <input type="checkbox"/> S. _____ ft. <input type="checkbox"/> W.	Well Name MW-1AR
Facility License, Permit or Monitoring Number 03025	Grid Origin Location Lat. _____ Long. _____ or St. Plane <u>542,635</u> ft. N, <u>2,156,555</u> ft. E.	Wis. Unique Well Number _____ DNR Well Number _____
Type of Well: Water Table Observation Well <input checked="" type="checkbox"/> 11 Piezometer <input type="checkbox"/> 12	Section Location of Waste/Source <input checked="" type="checkbox"/> E. <input type="checkbox"/> W.	Date Well Installed <u>11</u> / <u>15</u> / <u>94</u> MM DD YY
Distance Well is From Waste/Source Boundary ft.	Location of Well Relative to Waste/Source U <input type="checkbox"/> Upgradient S <input type="checkbox"/> Sidegradient D <input type="checkbox"/> Downgradient N <input checked="" type="checkbox"/> Not Known	Well Installed By: (Persons' Name and Firm) <u>Frank Badula</u> <u>Environmental & Foundation Drilling, Inc.</u>
Is Well A Point of Enforcement Std. Application? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		

- A. Protective pipe, top elevation 822.47 ft. MSL
- B. Well casing, top elevation 822.55 ft. MSL
- C. Land surface elevation 820.1 ft. MSL
- D. Surface seal, bottom 819.6 ft. MSL or 0.5 ft.

12. USCS classification of soil near screen:
 GP GM GC GW SW SP
 SM SC ML MH CL CH
 Bedrock


13. Sieve analysis attached? Yes No

14. Drilling method used: Rotary 50
 Hollow Stem Auger 41
 Other

15. Drilling fluid used: Water 02 Air 01
 Drilling Mud 03 None 99

16. Drilling additives used? Yes No
 Describe _____

17. Source of water (attach analysis):



- E. Bentonite seal, top 800.1 ft. MSL or 20.0 ft.
- F. Fine sand, top 792.1 ft. MSL or 28.0 ft.
- G. Filter pack, top 790.1 ft. MSL or 30.0 ft.
- H. Screen joint, top 788.1 ft. MSL or 32.0 ft.
- I. Well bottom 778.1 ft. MSL or 42.0 ft.
- J. Filter pack, bottom 777.1 ft. MSL or 43.0 ft.
- K. Borehole, bottom 777.1 ft. MSL or 43.0 ft.
- L. Borehole, diameter 8.3 in.
- M. O.D. well casing 2.2 in.
- N. I.D. well casing 2.03 in.

- 1. Cap and lock? Yes No
- 2. Protective cover pipe:
 a. Inside diameter: 5.0 in.
 b. Length: 7.0 ft.
 c. Material: Flush Mount Steel 04
 Other
 d. Additional protection? Yes No
 If yes, describe: _____
- 3. Surface seal: Bentonite 30
 Concrete 01
 Other
- 4. Material between well casing and protective pipe:
 Bentonite 30
 Annular space seal
 Other
- 5. Annular space seal:
 a. Granular Bentonite 33
 b. Lbs/gal mud weight... Bentonite-sand slurry 35
 c. Lbs/gal mud weight... Bentonite slurry 31
 d. % Bentonite... Bentonite-cement grout 50
 e. 400 lb volume added for any of the above
 f. How installed: Tremie 01
 Tremie pumped 02
 Gravity 08
- 6. Bentonite seal:
 a. Bentonite granules 33
 b. 1/4 in. 3/8 in. 1/2 in. Bentonite pellets 32
 c. Other
- 7. Fine sand material: Manufacturer, product name, mesh size
 a. Silica sand _____
 b. Volume added 50 lb
- 8. Filter pack material: Manufacturer, product, mesh size
 a. Badger Mining #30
 b. Volume added 250 lb
- 9. Well casing: Flush threaded PVC schedule 40 23
 Flush threaded PVC schedule 80 24
 Other
- 10. Screen Material: PVC
 a. Screen type: Factory cut 11
 Continuous slot 01
 Other
 b. Manufacturer Northern Air
 c. Slot size: 0.010 in.
 d. Slotted length: 9.6 ft.
- 11. Backfill material (below filter pack): None 14
 Other

I hereby certify that the information on this form is true and correct to the best of my knowledge.
 Signature Frank Badula Firm RMT, Inc.

Please complete both sides of this form and return to the appropriate DNR office listed at the top of this form as required by chs. 144, 147 and 160, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with ch. 144, Wis. Stats., failure to file this form may result in a forfeiture of not less than \$10, nor more than \$5,000 for each day of violation. In accordance with ch. 147, Wis. Stats., failure to file this form may result in a forfeiture of not more than \$10,000 for each day of violation. NOTE: Shaded areas are for DNR use only. See instructions for more information including where the completed form should be sent.

Route to: Solid Waste Haz. Waste Wastewater
Env. Response & Repair Underground Tanks Other

Facility/Project Name WP&L Columbia - Dry Ash	County Name Columbia	Well Name MW-1AR	
Facility License, Permit or Monitoring Number 03025	County Code	Wis. Unique Well Number	DNR Well Number

<p>1. Can this well be purged dry? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No</p> <p>2. Well development method</p> <table style="width:100%;"> <tr><td>surged with bailer and bailed</td><td><input type="checkbox"/> 41</td></tr> <tr><td>surged with bailer and pumped</td><td><input checked="" type="checkbox"/> 61</td></tr> <tr><td>surged with block and bailed</td><td><input type="checkbox"/> 42</td></tr> <tr><td>surged with block and pumped</td><td><input type="checkbox"/> 62</td></tr> <tr><td>surged with block, bailed and pumped</td><td><input type="checkbox"/> 70</td></tr> <tr><td>compressed air</td><td><input type="checkbox"/> 20</td></tr> <tr><td>bailed only</td><td><input type="checkbox"/> 10</td></tr> <tr><td>pumped only</td><td><input type="checkbox"/> 51</td></tr> <tr><td>pumped slowly</td><td><input type="checkbox"/> 50</td></tr> <tr><td>Other _____</td><td><input type="checkbox"/> <input checked="" type="checkbox"/></td></tr> </table> <p>3. Time spent developing well ... 1 2 0 min.</p> <p>4. Depth of well (from top of well casing) ... 4 5 5 ft.</p> <p>5. Inside diameter of well ... 2 0 3 in.</p> <p>6. Volume of water in filter pack and well casing ... 8 7 gal.</p> <p>7. Volume of water removed from well ... 5 0 0 gal.</p> <p>8. Volume of water added (if any) ... 0 0 gal.</p> <p>9. Source of water added _____</p> <p>10. Analysis performed on water added? <input type="checkbox"/> Yes <input type="checkbox"/> No (if yes, attach results)</p>	surged with bailer and bailed	<input type="checkbox"/> 41	surged with bailer and pumped	<input checked="" type="checkbox"/> 61	surged with block and bailed	<input type="checkbox"/> 42	surged with block and pumped	<input type="checkbox"/> 62	surged with block, bailed and pumped	<input type="checkbox"/> 70	compressed air	<input type="checkbox"/> 20	bailed only	<input type="checkbox"/> 10	pumped only	<input type="checkbox"/> 51	pumped slowly	<input type="checkbox"/> 50	Other _____	<input type="checkbox"/> <input checked="" type="checkbox"/>	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:30%;"></td> <td style="width:35%; text-align: center;">Before Development</td> <td style="width:35%; text-align: center;">After Development</td> </tr> <tr> <td>11. Depth to Water (from top of well casing)</td> <td>a. ... 3 4 4 ft.</td> <td>... 3 7 5 ft.</td> </tr> <tr> <td>Date</td> <td>b. $\frac{11}{m} / \frac{17}{d} / \frac{94}{y}$</td> <td>$\frac{11}{m} / \frac{17}{d} / \frac{94}{y}$</td> </tr> <tr> <td>Time</td> <td>c. ... 1 0 : 0 0 <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.</td> <td>... 1 2 : 0 0 <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.</td> </tr> <tr> <td>12. Sediment in well bottom</td> <td>... 0 0 inches</td> <td>... 0 0 inches</td> </tr> <tr> <td>13. Water clarity</td> <td>Clear <input type="checkbox"/> 10 Turbid <input checked="" type="checkbox"/> 15 (Describe)</td> <td>Clear <input type="checkbox"/> 20 Turbid <input checked="" type="checkbox"/> 25 (Describe)</td> </tr> <tr> <td colspan="3">Fill in if drilling fluids were used and well is at solid waste facility:</td> </tr> <tr> <td>14. Total suspended solids</td> <td>..... mg/l</td> <td>..... mg/l</td> </tr> <tr> <td>15. COD</td> <td>..... mg/l</td> <td>..... mg/l</td> </tr> </table>		Before Development	After Development	11. Depth to Water (from top of well casing)	a. ... 3 4 4 ft.	... 3 7 5 ft.	Date	b. $\frac{11}{m} / \frac{17}{d} / \frac{94}{y}$	$\frac{11}{m} / \frac{17}{d} / \frac{94}{y}$	Time	c. ... 1 0 : 0 0 <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.	... 1 2 : 0 0 <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.	12. Sediment in well bottom	... 0 0 inches	... 0 0 inches	13. Water clarity	Clear <input type="checkbox"/> 10 Turbid <input checked="" type="checkbox"/> 15 (Describe)	Clear <input type="checkbox"/> 20 Turbid <input checked="" type="checkbox"/> 25 (Describe)	Fill in if drilling fluids were used and well is at solid waste facility:			14. Total suspended solids mg/l mg/l	15. COD mg/l mg/l
surged with bailer and bailed	<input type="checkbox"/> 41																																															
surged with bailer and pumped	<input checked="" type="checkbox"/> 61																																															
surged with block and bailed	<input type="checkbox"/> 42																																															
surged with block and pumped	<input type="checkbox"/> 62																																															
surged with block, bailed and pumped	<input type="checkbox"/> 70																																															
compressed air	<input type="checkbox"/> 20																																															
bailed only	<input type="checkbox"/> 10																																															
pumped only	<input type="checkbox"/> 51																																															
pumped slowly	<input type="checkbox"/> 50																																															
Other _____	<input type="checkbox"/> <input checked="" type="checkbox"/>																																															
	Before Development	After Development																																														
11. Depth to Water (from top of well casing)	a. ... 3 4 4 ft.	... 3 7 5 ft.																																														
Date	b. $\frac{11}{m} / \frac{17}{d} / \frac{94}{y}$	$\frac{11}{m} / \frac{17}{d} / \frac{94}{y}$																																														
Time	c. ... 1 0 : 0 0 <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.	... 1 2 : 0 0 <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.																																														
12. Sediment in well bottom	... 0 0 inches	... 0 0 inches																																														
13. Water clarity	Clear <input type="checkbox"/> 10 Turbid <input checked="" type="checkbox"/> 15 (Describe)	Clear <input type="checkbox"/> 20 Turbid <input checked="" type="checkbox"/> 25 (Describe)																																														
Fill in if drilling fluids were used and well is at solid waste facility:																																																
14. Total suspended solids mg/l mg/l																																														
15. COD mg/l mg/l																																														

16. Additional comments on development:

Well developed by: Person's Name and Firm
Name: Frank Badula
Firm: Environmental & Foundation Drilling, Inc.

I hereby certify that the above information is true and correct to the best of my knowledge.
Signature: *Richard L. Galt*
Print Initials: RCC
Firm: RMT, Inc.

NOTE: Shaded areas are for DNR use only. See instructions for more information including a list of county codes.

FACILITY NAME
Wisconsin Power and Light Co. - Dry Ash

SAMPLING REQUIRED (ONE) YES NO

POINT (ONE) CAN BE SAMPLED CANNOT BE SAMPLED

COMMON NAME OF SAMPLING POINT
mw 1A

PREVIOUS COMMON NAME OF SAMPLING POINT

TYPE OF POINT (ONE)

1 (G) GROUND WATER
11 MONITOR WELL
12 PIEZOMETER
13 PRIVATE WELL
14 LYSIMETER
15 SPRING
16 RESISTIVITY PROBE

2 (L) LEACHATE
21 FLOW OR SEEP
22 POND
23 COLLECTION SYSTEM

3 (S) SURFACE WATER
31 UPSTREAM
32 MID-SITE
33 DOWNSTREAM
34 RUN-OFF
35 IMPOUNDED

POINT LOCATION
2156, 500 FT. (-)
542, 450 FT. (-)

DATE POINT ESTABLISHED
06/16/77
MON DAY YEAR

FROM GRID ORIGIN BENCHMARK

6 COMMENTS ABOUT SAMPLING POINTS:

Well depth - 45.8' Gradient from landfill - inside perimeter of module 4
Geologic formation of well screen - sand filter around PVC pipe (slotted)
Location of well seals / materials used - bentonite seal above screen

WELL DESCRIPTION	REQUIRED SAMPLING (MG/L except as noted)
	NO. PARAMETERS MONTHS OF REQUIRED SAMPLING
PIPE DIAMETER <u>2.00</u> INCHES	<input checked="" type="checkbox"/> 00410 ALKALINITY (AS CA CO ₃) 1-2-3-4-5-6-7-8-9-10-11-12
PIPE TOP ELEVATION <u>821.67</u> FEET <input checked="" type="checkbox"/> MSL <input type="checkbox"/> SITE	<input type="checkbox"/> 00310 BOD (5 DAY) 1-2-3-4-5-6-7-8-9-10-11-12
GROUND SURFACE ELEVATION <u>820.90</u> FEET <input checked="" type="checkbox"/> MSL <input type="checkbox"/> SITE	<input type="checkbox"/> 00916 CALCIUM 1-2-3-4-5-6-7-8-9-10-11-12
TYPE OF CASING (ONE) <input checked="" type="checkbox"/> 1 PLASTIC <input type="checkbox"/> 2 STEEL	<input type="checkbox"/> 00307 CHLORIDES 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00340 COD 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00872 CONDUCTIVITY (SU) 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00277 COPPER (DISSOLVED) 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00900 HARDNESS (AS CA CO ₃) 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01046 IRON (DISSOLVED) 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00348 MAGNESIUM 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00620 NITRATES (AS NO ₃) 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00640 NITROGEN (TOTAL INORGANIC N) 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00400 PH (SU) 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00129 PHENOLS 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00929 SODIUM 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00945 SULFATES 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00360 TOTAL DIS. SOLIDS 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00842 WATER ELEVATION (FT. MSL) 1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00275 ZINC (DISSOLVED) 1-2-3-4-5-6-7-8-9-10-11-12
	NO. PARAMETERS (OTHERS) MONTHS
	<input checked="" type="checkbox"/> 01022 Boreon 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> Color 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> odor 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> Turbidity 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01002 Arsenic, Tot 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01007 Barium, Tot 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00312 Cadmium, Tot 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00273 Chromium, Diss. 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00240 Lead, Diss 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00126 Mercury, Tot 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00270 Selenium, Tot 1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01077 Silver, Tot 1-2-3-4-5-6-7-8-9-10-11-12

7 COMMENTS ABOUT REQUIRED SAMPLING:

Avg. vol. of water to be bailed:

Groundwater flow - westerly direction

Warzyn Engineering Inc.

Log of soil borings

Drawing No. C71342

Date 8-26-77

BROWN

B #1
MW #1A

830

825

820

815

810

805

800

795

790

785

780

16
16
40
50
60
32
39
60
58
37
26
17
37

1' DARK BROWN
SILTY SAND TOPSOIL


Red. brown fine-medium
sand, some silt

Brown fine med. sand
trace to little silt
occasional gravel,
occasional uniform
medium sand

Light brown fine
sand, trace to little
silt.

Brown silty-fine
medium sand
occasional
gravel.

OCCASIONAL
SILT SILT



▽ 27.11.85

24.11.85

24.11.85

28

B#1A&B

U.S.H. 51

850

820

810

800

790

780

770

No legend available...

Scale:

Horizontal 1" = 100'

Vertical 1" = 10'

Fill
fine to med. sand
medium to coarse sand and gravel

fine to medium sand

0/82/11

		1-20-78	Drawing No. 7134-11	
NO.	BY	DATE	REVISION	AF



WARZYN ENGINEERING INC.
 MADISON Consulting Engineers WISCONSIN

GEOLOGIC CROSS SECTIONS

PROPOSED ASH AND/OR SCRUBBER SLUDGE DISPOSAL FACIL
 COLUMBIA SITE
 WISCONSIN POWER & LIGHT COMPANY
 PART OF SECTIONS 27, B, 34, T12N, R9E
 COLUMBIA COUNTY, WISCONSIN

WELL


DRAWN TCP	CHECKED RJK	SCALE AS SHOWN	SHEET 8 OF 13
APPROVED RJK		DATE 1-20-78	DRAWING



TYPICAL MONITORING WELL DETAIL

NOT TO SCALE

			Date - 1-20-78	Drawing No. 7134-9	
			Warzyn Engineering Inc.		



Appendix C
Feasibility Study Water Quality Information

1370



FEASIBILITY STUDY
PROPOSED FLY ASH AND/OR SCRUBBER SLUDGE
DISPOSAL FACILITY-COLUMBIA SITE
WISCONSIN POWER AND LIGHT COMPANY
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

Jan 78

C 7134

conceivable that groundwater flow in the area north of Murray Road may be altered such that contaminants derived from the present ash settling basin might be diverted southerly towards the homes along Murray Road. These questions would have to be addressed in greater detail, consistent with the goals of Wisconsin Power and Light Company.

WATER QUALITY

During the first two weeks of December, 1977, 64 water samples were obtained from surface waters and groundwater monitoring wells at the Columbia Energy Center. The purpose of the sampling was to assess background water quality in the vicinity of the proposed disposal site. The sampling stations included 59 monitoring wells, the cooling lake, ash settling pond, the drainage ditch carrying the ash pond discharge waters and the agricultural drainage ditch along the southern boundary of the site. Due to the large number of sampling stations, the analyses were limited to pH, specific conductance, iron, calcium, magnesium, sulfate and chloride. The analytical data is contained in Appendix F and is discussed below.

pH

Most groundwaters found in the United States have pH values ranging from around 6.0 to 8.5. The pH of a water represents the result of a number of interrelated chemical equilibria. This equilibria can be altered shortly after sampling by gains or losses of carbon dioxide, the oxidation of ferrous iron and numerous other chemical reactions. Thus, pH measurements must be taken shortly after obtaining the sample. For this study, the pH of samples was determined immediately upon return to the laboratory.

Within the proposed site boundaries at the Columbia Energy Center, pH values ranged between 6.3 and 8.1 and averaged 7.5. Typically, the lower pH values were observed in the lowland areas and wetlands, probably as a result of acidic organic soils. The pH of water in the ash disposal settling pond and the cooling lake was 11.4 and 8.3, respectively.

SPECIFIC CONDUCTANCE

Specific conductance, or conductivity, is the ability of a substance to conduct an electric current. The conductance determination is correlative with the dissolved-solids concentration. Conductivity, however, is temperature dependent and thus requires the reference of specific conductance measurements to a standard temperature. The values discussed here are referred to 25°C.

The specific conductance of groundwater in the study area ranged from 220 umhos/cm to a maximum of 2600 umhos/cm. The highest conductivity readings were observed in monitoring wells located along the coal storage area and the drainage ditch carrying the ash pond discharge where values up to 2600 umhos/cm were measured. The conductivity of the ash pond effluent was 1380 umhos/cm. This data appears to confirm earlier speculation of infiltration of effluent from the ash pond discharge channel and from the coal storage area into the groundwater. Conductance within the proposed site boundaries averaged approximately 465 umhos/cm.

Conductivity in the ash disposal settling pond was measured at 1510 umhos/cm. Shallow monitoring wells M-6 and 39A, located adjacent to the pond also exhibited elevated values of 1160 umhos/cm and 1800 umhos/cm, respectively.


High conductivities were also observed along U. S. Highway 51 at monitoring wells 51A and 51B. The chloride data, discussed below, indicates infiltration of road salt has probably occurred at this location.

Specific conductance measurements obtained in the vicinity of the proposed disposal site are shown on Drawing C 7134-15.

IRON

The element iron is an abundant element found in most rocks and soil. It generally occurs as sulfides and oxides in igneous and metamorphic rocks and as iron oxide and hydroxide cementing materials in coarse-grained sedimentary rocks.

Ferrous iron is unstable in the presence of oxygen where it is bound to hydroxide anions as $2\text{Fe}(\text{OH})_3$.



If subjected to a strong reducing environment, such as a marsh, the reaction is reversed and iron goes back into solution. The amount which dissolves is related to a number of variables including the velocity with which water moves through this environment.

The U. S. Public Health Service recommends an iron concentration of less than 0.3 mg/l in water used for drinking and culinary purposes. Laundry and porcelain tend to be stained when concentrations reach 0.5 to 1.0 mg/l. At this level it can also be tasted.

The presence of iron under the proposed disposal area in the majority of cases was below the detection limit of 0.1 mg/l. In monitoring wells 5 and 18, located in or near the central marsh area, iron increased to 10 mg/l and 5.7 mg/l, respectively. In the southern marsh, monitoring wells exhibited concentrations between 0.5 mg/l and 6.1 mg/l. Although the iron concentration in the cooling lake was below the detection limit, down-gradient wells 44 and 30A located on the cooling lake dike yielded values of 11 mg/l and 26 mg/l iron respectively. Boring logs indicated trace amounts of organic material at the base of the dike which is probably the reason for the high concentrations observed. At the same location, iron in well 30B installed to a depth of 100 feet below the surface was below 0.1 mg/l. Thus, the occurrence of high iron concentrations in this area appears restricted to groundwater in the upper portion of the aquifer where organic material is present and conditions are favorable for the dissolution of iron.

The ash pond discharge in the drainage ditch paralleling the west site boundary showed an iron concentration of 3.7 mg/l. Shallow monitoring wells 33A and 34A adjacent to the ditch indicated less than 0.1 mg/l iron.

North of Murray Road the iron concentration in monitoring wells in the marsh and uplands were typically less than 0.1 mg/l. Although the ash basin had less than 0.1 mg/l iron, several wells along cross-section F-F' showed anomalously high values (#M6-2.3 mg/l; #47-16 mg/l; #51B-21 mg/l).

CALCIUM

Calcium, because of its relative abundance and mobility, is the principle cation in most natural fresh water. Calcium is a constituent of many rock types but is found in greatest quantities in waters leaching deposits of limestone and dolomite. In sandstone and other detrital rock, calcium carbonate is a common cement between grains.

Monitoring wells located within the site boundaries exhibited calcium concentrations between 30 mg/l and 66 mg/l and averaged about 42 mg/l. Similar to iron, the concentrations of calcium in monitoring wells along cross-section F-F' were anomalously high, up to 150 mg/l calcium. Water table wells along the drainage ditch carrying the ash pond discharge averaged 83 mg/l while the ash pond effluent contained 28 mg/l. Generally the amount of calcium in groundwater decreased with depth. Nested monitoring wells typically showed somewhat lower concentrations of calcium in the deeper wells.

MAGNESIUM

As a relatively abundant element on the earth's crust, the principle sources of magnesium in natural waters are considered to be ferromagnesian minerals in igneous rocks and magnesium carbonate in carbonate rocks (limestone and dolomite). Waters in which magnesium is the predominant cation are somewhat unusual. Like calcium, magnesium imparts the property of hardness to water and is, therefore, of concern to industrial users.

Generally, concentrations of magnesium were 1/3 to 1/2 of the calcium levels. Magnesium concentrations within the site boundaries ranged between 10 mg/l and 36 mg/l and averaged 27 mg/l. Similar to calcium and iron, higher magnesium values were observed, in general, north of Murray Road and especially in monitoring wells along cross-section F-F'.



SULFATE

Sulphur is widely distributed in reduced form in both igneous and sedimentary rocks as metallic sulfides and when present in sufficient concentrations, constitutes ore of economic importance. During weathering processes with aerated water, the sulfides are oxidized to sulfate ions and are dissolved into water. Pyrite (FeS_2) crystals often occur in sedimentary rocks and are particularly associated with biogenic deposits such as coal which were deposited under strongly reducing conditions.

The concentrations of sulfate in groundwater in the vicinity of the proposed disposal site ranged from less than 1 mg./l to 1,200 mg./l of sulfate. (Refer to Drawing C 7134-15.) Typically, within the site boundaries concentrations averaged approximately 12 mg./l. Near the coal storage area, however, significant increases were observed. Observation wells 26A, 26B, and 42 exhibited concentrations between 900 and 1100 mg./l. The depth of sulfate enrichment in groundwater, near the coal pile, appears to extend to considerable depths, indicated by relatively high sulfate concentrations in Well 26B sealed 100 feet below ground surface. The oxidation of pyrite minerals in the coal leaching into the groundwater is probably the major source of the high concentrations observed.

Sulfate concentrations in the ash disposal settling pond were 520 mg./l. In the ditch carrying the ash pond discharge, the effluent is treated with sulfuric acid which results in precipitation of barium sulfate and aluminum hydroxide (personal communication, Merlin Horn, 1978). Consequently, the sulfate concentration of the effluent waters is lowered considerably to 13 mg./l. Well 33A, however, located near the point of effluent discharge, exhibited 1200 mg./l sulfates.

CHLORIDE

Chloride is generally present in much lower concentrations in rocks than many of the other major constituents of natural water. Important sources, however, are associated with sedimentary rocks, particularly the evaporites. The chemical behavior of chloride in natural water is relatively inert compared to the other major ions. There are few oxidation-reduction reactions and no significant chemical complexing reactions which chloride enters into. In addition, chloride ions are not significantly adsorbed on mineral surfaces. For these reasons, chloride is commonly used as a tracer in groundwater.

Chloride concentrations in groundwater in the vicinity of the Columbia Energy Center typically range between 0.5 mg./l and 30 mg./l. The highest concentrations in monitoring wells tended to be located adjacent to U. S. Highway 51 where the use of road salt has resulted in the percolation of chloride into the groundwater. Monitoring Wells 51A and 51B located in a low area north of Murray Road along U. S. Highway 51, yielded chloride concentrations in excess of 200 mg./l. Two other wells, 52A and 19, also located along U. S. Highway 51, yielded values of 30 mg./l and 42.5 mg./l chloride, respectively.

Within the proposed site boundaries, the chloride concentration averaged 7.1 mg./l. Excluding the few wells adjacent to U. S. Highway 51 exhibiting elevated concentrations, no other significant trends in the occurrence of chloride were observed.

SUMMARY

In summary, the groundwater in the vicinity of the proposed disposal site exhibited a somewhat alkaline pH. In lowland areas, the pH was typically below 7.0, probably a result of the presence of acidic organic soils.

Specific conductance within the proposed site averaged 465 umhos/cm. Conductivities up to 2600 umhos/cm were observed, however, in the vicinity of the coal storage area, the present ash disposal pond and ash pond effluent channel where infiltration of water from these sources is occurring into the groundwater system.

The groundwater typically exhibited relatively low iron concentrations although, locally, concentrations in excess of drinking water standards were observed in about 20% of the wells. The occurrence of the higher iron concentrations appears to be related to the presence of organic soils.

Groundwater at the proposed site also tended to exhibit high calculated hardness (216 mg./l) based on average observed values for calcium (42 mg./l) and magnesium (27 mg./l). Dissolution of limestone and dolomite rocks in the glacial drift are the probable sources of these elements in the groundwater.

Enrichment of sulfate in groundwater has occurred as a result of leaching of pyrite (FeS_2) minerals from the coal storage area where concentrations up to 1200 mg./l were observed. The depth of this enrichment appears to extend beyond the maximum depth into the aquifer investigated. Sulfate concentrations decreased rapidly away from the coal storage area to an average of 12 mg./l within the proposed site boundaries. Other local sources of sulfate in groundwater appear to be related to the present ash settling pond.

The concentration of chloride within the proposed site averaged 7.1 mg./l. Higher levels were generally observed in wells adjacent to U. S. Highway 51 where the infiltration of road salt has locally raised chloride concentrations.

The above interpretations are based on one round of water quality sampling only and should be considered as preliminary in nature. High sulfate and chloride concentrations observed at greater depths may be a temporary condition resulting from contamination of spoil backfill materials with coal dust or salt, respectively, during installation of the monitoring well. Future sampling of these monitoring wells will help to distinguish short term contamination from actual conditions existing in the aquifer.

APPENDIX F
WATER QUALITY DATA

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
1A	7.6	550	17.	6.5	52	37	<0.1
1B	8.05	460	16.	10.5	39	31	<0.1
2	7.8	527	14.	2.5	45	32	<0.1
3A	7.5	548	13.	2.5	58	36	<0.1
3B	8.1	506	14.	7.0	50	34	<0.1
4	7.8	580	10.	4.0	59	34	<0.1
5	6.3	560	210.	12.5	13	29	10
16	7.6	408	12.	1.5	42	28	<0.1
17	6.45	350	30.	16.5	16	13	0.6
18	6.45	380	4.	4.5	33	22	5.7
19	7.9	570	10.	42.5	44	24	<0.1
20	8.0	340	10.	5.0	36	24	<0.1
21	6.9	220	20.	4.5	23	10	0.1
24A	7.45	775	18.	6.0	76	52	0.1
24B	7.85	440	15.	6.0	43	31	0.1
25	8.1	300	10.	2.5	29	20	<0.1
26A	7.2	2100	900	17.0	140	48	1.5
26B	7.5	2600	1100	16.5	43	7.0	0.2
27	7.15	400	6.	8.0	23	18	<0.1
28A	7.75	500	3.	0.5	48	31	<0.1
28B	7.6	480	4.	3.5	39	28	<0.1
29A	7.8	330	16.	1.5	33	21	0.5
30A	6.75	920	64.	11.0	38	30	26
30B	7.6	770	210	21.0	37	19	<0.1
33A	8.2	2500	1200	24.0	83	50	<0.1
33B	7.9	390	22.	6.5	31	27	0.2
34A	7.7	680	140.	10.0	58	45	0.1
34B	7.7	1700	660	15.0	48	22	<0.1
35	6.8	740	<1.0	4.0	66	33	2.9
36	6.8	740	<1.0	3.5	53	35	6.1
37A	7.7	460	9.	4.0	48	31	0.8
37B	7.5	630	73.	7.5	71	35	<0.1
39A	7.5	1800	350	22.0	180	100	0.1
39B	7.9	330	560	20.5	31	22	0.1
40A	8.0	630	140	8.5	43	29	<0.1
40B	8.1	330	17.	3.0	31	22	<0.1
41	6.8	590	16.	11.0	58	27	9.3

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
42	7.4	2400	900	17.5	50	12	0.5
44	6.9	490	<1.	16.5	39	23	11
45	7.6	390	14.	3.0	40	25	<0.1
46A	7.3	1100	21.	15.5	140	82	<0.1
46B	7.8	470	25.	17.5	40	26	<0.1
47	6.6	1200	3.	8.0	140	40	16
48A	7.3	620	15.	8.0	62	37	<0.1
48B	7.1	520	22.	20.0	43	29	0.2
49	7.15	730	6.	3.5	75	41	<0.1
50A	7.6	520	28.	15.5	51	34	<0.1
50B	7.5	410	21.	18.0	31	21	<0.1
51A	6.1	1850	8.	205.	65	40	<0.1
51B	7.2	1250	23.	275.	57	36	21
52A	7.7	450	16.	30.5	36	17	<0.1
52B	7.4	430	40.	17.5	32	20	<0.1
53	7.75	450	27.	10.5	39	28	<0.1
54A	7.8	350	12.	4.0	34	21	0.1
54B	7.55	390	15.	5.5	40	24	0.1
55B	7.9	340	23.	17.5	32	22	0.1
56	7.8	450	22.	9.5	43	28	0.1
57	7.85	380	17.	7.0	38	24	0.1
M-6	7.0	1160	5.	7.0	150	91	2.3
Cooling Lake	8.3	370	31.	18.0	34	21	<0.1
Ash Pond Effluent	7.45	1380	13.	4.0	28	1.2	3.7
Ash Pond Drainage	11.4	1510	520.	23.5	29	0.2	<0.1
Ditch (A) Drainage	7.8	500	21.	7.0	43	29	<0.1
Ditch (B)	9.05	1780	750	14.0	42	5.4	<0.1

DEC 19 1979

APPENDICES TO

SUPPLEMENTARY FEASIBILITY STUDY REPORT
AND PRELIMINARY ENGINEERING CONCEPTS
COLUMBIA SITE
WISCONSIN POWER AND LIGHT COMPANY
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

D. N. R. APPROVED

DATE 9/3/80
Nile Ostenso, Hydro

APPENDIX I

WATER QUALITY DATA - DECEMBER 1978

WATER QUALITY DATA


12/76

C 7134

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
1A	7.3	530	30	3.1	54	35	<0.1	-
1B	7.0	470	67	6.1	49	30	<0.1	-
2	7.25	458	91	<.5	48	24	<0.1	-
3A	7.0	560	36	<.5	61	31	<0.1	-
3B	7.15	530	52	35.7	37	33	<0.1	-
4	7.2	750	69	5.8	49	30	<0.1	-
5	6.35	1,650	670	14.1	14	13	1.7	-
16	6.9	390	69	1.0	49	23	<0.1	-
17	5.55	295	57	16.3	14	8.6	0.2	-
18	5.9	430	10	4.2	47	21	1.1	-
19	7.4	765	75	4.2	51	28	<0.1	-
20	7.4	380	26	1.6	39	26	<0.1	-
21	5.7	250	54	10.4	15	8.3	0.2	-
24A	7.2	730	36	1.6	65	42	<0.1	-
24B	7.2	470	10	7.3	42	28	<0.1	-
25	7.0	335	29	7.8	39	21	0.2	-
26A	7.4	2,250	650	12.6	32	8.6	<0.1	-
26B	6.8	2,530	840	20.8	49	18	<0.1	-
27	6.9	410	24	4.2	40	24	0.4	-
28A	7.2	500	61	0.5	45	28	<0.1	-
28B	7.0	465	6	2.1	39	26	0.1	-
29A	7.1	410	24	3.6	31	22	0.1	-
30A	5.8	1,140	15	<0.5	97	56	38	-
30B	6.65	835	160	14.6	37	20	<0.1	-
33A	7.8	1,970	830	16.7	21	8.9	<0.1	-
33B	7.5	380	31	7.3	24	27	<0.1	-
34A	7.25	560	46	4.2	53	33	<0.1	-
34B	8.5	1,575	730	21.9	28	29	0.1	-
35	6.7	545	61	3.6	60	26	1.0	-
36	6.4	515	5.0	2.6	43	24	4.8	-
37A	7.05	438	30	3.7	50	28	<0.1	-
37B	6.7	325	18	7.3	1.0	0.5	<0.1	-
39A	6.35	1,260	33	13.6	70	7.6	0.1	-
39B	6.7	385	25	4.2	30	21	<0.1	<.05
40A	7.35	483	40	<0.5	48	24	<0.1	-
40B	7.25	343	4	4.2	21	14	<0.1	-
41	6.1	640	54	19.8	43	32	<0.1	-


WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
42 <i>near old well</i>	7.15	2,050	910	15.6	23	7.5	0.1	-
44 <i>near old well</i>	6.15	710	6	0.5	56	27	3.5	-
45 <i>near old well</i>	7.2	420	32	1.0	44	26	<0.1	-
46A <i>near old well</i>	7.0	560	93	<0.5	130	75	<0.1	<0.05
46B <i>near old well</i>	6.5	1,290	170	20.8	46	30	<0.1	<0.05
47 <i>near old well</i>	7.3	958	120	<0.5	110	48	<0.1	-
48A <i>near old well</i>	6.15	640	59	<0.5	42	51	<0.1	<0.05
48B <i>near old well</i>	6.8	450	23	5.2	40	27	<0.1	<0.05
49 <i>near old well</i>	7.0	880	26	2.1	93	58	0.1	-
50A <i>near old well</i>	7.4	660	25	17.7	60	36	<0.1	-
50B <i>near old well</i>	7.1	405	16	17.7	38	23	<0.1	-
51A <i>near old well</i>	7.0	1,170	57	135	66	31	<0.1	-
51B <i>near old well</i>	7.3	1,410	22	330	46	39	<0.1	-
52A <i>near old well</i>	7.0	370	110	18.5	35	10	<0.1	-
52B <i>near old well</i>	7.0	595	43	52.5			0.1	-
53	Frozen							
54A <i>near old well</i>	7.5	345	10	1.0	36	22	<0.1	<0.05
54B <i>near old well</i>	Frozen							
55B <i>near old well</i>	7.3	505	26	15.6	52	29	<0.1	<0.05
56 <i>near old well</i>	Frozen							
57 <i>near old well</i>	Frozen							
M-6								
58 <i>near old well</i>	6.55	1,265	140*	<0.5	110	65	0.1	-
59 <i>near old well</i>	6.8	925	40	<0.5	86	60	<0.1	-
60 <i>near old well</i>	7.2	1,510	54	4.7	130	85	<0.1	-
61A <i>near old well</i>	6.85	590	39	30.2	58	31	<0.1	-
61B <i>near old well</i>	7.2	505	6	13.5	48	29	<0.1	-
62 <i>Insect Hydrant</i>	6.7	1,517	72	178	120	53	<0.1	-
64 <i>near old well</i>	6.9	670	100	26.8	63	36	0.8	-
65 <i>near old well</i>	7.2	830	57	17.8	78	50	<0.1	-
66 <i>near old well</i>	6.5	680	55	40	66	24	3.6	-

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
67	7.0	560	100	1.0	57	32	1.0	-
68A	7.6	440	32	2.1	40	27	<0.1	-
68B	7.2	400	36	1.0	42	25	<0.1	-
70A	7.5	440	20	<0.5	27	37	<0.1	-
70B	7.3	520	25	5.2	51	34	<0.1	-
72AZ	6.45	860	11	<0.5	100	41	1.8	-
72B	8.4	230	45	<0.5	17	19	<0.1	-
M-4	7.6	864	180	26.1	20	11	<0.1	-
MM-4			2	2.6	14	21	0.9	0.39
Cooling Lake at 1	7.7	355	36	13.6	31	21.2	<0.1	-
Ash Pond at 2	11.4	3,210	1,100	22.9	34	<0.1	<0.1	-
Ash Pond at 3	8.7	725	34	21.9	48	16	<0.1	-
Ash Pond Effluent at 4	6.7	3,090	1,400	25.0	39	0.4	<0.1	-
Drainage Ditch at 5	7.2	730	74	33.9	56	38	<0.1	-
Drainage Ditch at 6	7.35	2,750	640	18.8	34	7.5	<0.1	-
Drainage Ditch at 7	8.05	1,780	740	27.1	31	0.2	<0.1	-




Appendix D
Long-Term Concentration Trend Plots


Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-302 and MW-85 - Boron ($\mu\text{g/l}$ as B)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-33A and MW-33AR - Boron ($\mu\text{g/l}$ as B)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW34A - Boron ($\mu\text{g/l}$ as B)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW34A - Chloride (mg/l as Cl)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-33 and MW-33AR - Chloride (mg/l as Cl)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-33 and MW-33AR - Sulfate (mg/l as SO4)




Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-34A - Sulfate (mg/l as SO4)



Wisconsin Power & Light Company
Columbia Dry Ash Disposal Facility
MW-85 and MW-302 - Sulfate (mg/l as SO4)





Appendix E
Historical Groundwater Flow Maps



- LEGEND**
- PROPOSED PROJECT AREA
 - ⊕ 720.29 OBSERVATION WELL LOCATION, NUMBER, AND WATER TABLE ELEVATION
 - ⊕ BORING LOCATION AND NUMBER
 - WETLANDS
 - TOPOGRAPHIC CONTOURS (CONTOUR INTERVAL: 20FT.)
 - PRIVATE RESIDENCES (ASSUMED LOCATIONS OF PRIVATE WATER SUPPLY WELLS)
 - ▣ COMMERCIAL BUILDINGS (ASSUMED LOCATIONS OF POSSIBLE PUBLIC WATER SUPPLY WELLS)
 - SURFACE WATERS (STREAMS OR DRAINAGE DITCHES); ARROWS INDICATE DIRECTION OF FLOW
 - OTHER BUILDINGS (GARAGES, BARN, ETC.)
 - ⊕ HIGH CAPACITY WELLS
 - 790- WATER TABLE CONTOURS (CONTOUR INTERVAL: 1 FT.)
 - ➔ DIRECTION OF GROUNDWATER FLOW


NO.	BY	DATE	REVISION	APPD.
WATER TABLE CONTOUR MAP 2/4/81				
PLAN OF OPERATION - ASH DISPOSAL FACILITY COLUMBIA SITE WISCONSIN POWER & LIGHT COMPANY PART OF SECTIONS 27 & 34, T12N, R9E TOWN OF PACIFIC COLUMBIA CO. WISCONSIN				
DRAWN TDH		SCALE 1"=300'	SHEET 39 OF 39	
CHECKED RJK		DATE 2/10/81	DRAWING NO.	
APPROVED			C7134-94	
REFERENCE			PRINTED 8/3/88	





- LEGEND**
- PROPERTY LINE
 - EXISTING RAILROAD TRACKS
 - EXISTING GROUND CONTOUR
 - CONTOUR DEPRESSION
 - EXISTING PAVED ROAD
 - EXISTING UNPAVED ROAD
 - EXISTING FENCE
 - EXISTING BUILDING
 - EXISTING SPOT ELEVATION
 - TREES AND/OR BRUSH
 - WETLAND AREA
 - EDGE OF WATER
 - HC 1 WATER SUPPLY WELL
 - MW61A WATER TABLE WELL
 - MW61B PIEZOMETER
 - MW217 ABANDONED WATER TABLE WELL
 - MW220R ABANDONED PIEZOMETER
 - 801 STAFF GAUGE
 - ALS-1 LYSMETER
 - DESIGN MANAGEMENT ZONE
 - PROPERTY LINE
 - O.S. OPEN STORAGE
 - O.H. OVERHEAD STRUCTURE
 - E.P.S. ELECTRICAL POWER STATION
 - T TANK
 - W WALL
 - (785.31) WATER TABLE ELEVATION (FT.-MSL)
(N.M. = NOT MEASURED)
 - 786 GROUNDWATER CONTOUR LINE
(FT. INTERVAL - FT. M.S.L.)
(DASHED WHERE INFERRED)
 - GROUNDWATER FLOW DIRECTION

- NOTES**
1. BASE MAP IS PROVIDED BY WISCONSIN POWER & LIGHT CO. AND IS BASED ON PHOTOS TAKEN ON APRIL 6, 1995 BY AERO-METRIC ENGINEERING, SHEBOYGAN, WI.
 2. HORIZONTAL DATUM IS BASED ON THE WISCONSIN STATE PLANE COORDINATE SYSTEM, SOUTH ZONE - DATUM NAD 83/01.
 3. VERTICAL DATUM IS REFERENCED TO U.S.G.S. MEAN SEA LEVEL (MSL). TOPOGRAPHIC CONTOUR INTERVAL IS TWO FEET.
 4. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER & LIGHT CO. IN DECEMBER 1994 & NOVEMBER 1996.
 5. THE LOCATION OF THE DESIGN MANAGEMENT ZONE DEMARCATION LINE IS APPROXIMATE.
 6. WATER ELEVATION USED TO PREPARE THIS MAP WERE MEASURED ON OCTOBER 24, 2002.
 7. THE WATER LEVEL AT MW 33A AND MW 33B COULD NOT BE MEASURED DURING OCTOBER 2002 DUE TO AN OBSTRUCTION IN THE WELL CASING.



PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY
 SHEET TITLE: WATER TABLE MAP (OCTOBER 2002)
 DRAWN BY: defoe | SCALE: 1"=200' | PROJ. NO. 3024.28
 CHECKED BY: JMR | FILE NO. WATERTBL.PLT
 APPROVED BY: JCD | DATE PRINTED: | FIGURE 3
 DATE: JANUARY 2003

3.			
2.			
1.			
NO. BY DATE	REVISION		APP'D.
PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY			
SHEET TITLE: WATER TABLE MAP (OCTOBER 2002)			
DRAWN BY: defoe	SCALE: 1"=200'	PROJ. NO. 3024.28	
CHECKED BY: JMR	FILE NO. WATERTBL.PLT		
APPROVED BY: JCD	DATE PRINTED:	FIGURE 3	
DATE: JANUARY 2003			

144 Heartland Trail
 Madison, WI 53717-1934
 P.O. Box 8923
 Madison, WI 53708-8923
 Phone: 608-831-4444