

# 2023 Annual Groundwater Monitoring and Corrective Action Report

Columbia Energy Center  
Dry Ash Disposal Facility, Modules 1 through 3  
Pardeeville, Wisconsin

Prepared for:

Alliant Energy



**SCS ENGINEERS**

25223067.00 | January 31, 2024

2830 Dairy Drive  
Madison, WI 53718-6751  
608-224-2830

## OVERVIEW OF CURRENT STATUS

### Columbia Energy Center, Dry Ash Disposal Facility, Modules 1 through 3 2023 Annual Report

In accordance with §257.90(e)(6), this section at the beginning of the annual report provides an overview of the current status of groundwater monitoring and corrective action programs for the coal combustion residual (CCR) unit. The groundwater monitoring system for the Columbia Energy Center (COL) Dry Ash Disposal Facility Modules 1 through 3 monitors a single CCR unit. Supporting information is provided in the text of the annual report.

Category	Rule Requirement	Site Status
<b>Monitoring Status – Start of Year</b>	(i) At the start of the current annual reporting period, whether the CCR unit was operating under the detection monitoring program in §257.94 or the assessment monitoring program in §257.95;	Detection
<b>Monitoring Status – End of Year</b>	(ii) At the end of the current annual reporting period, whether the CCR unit was operating under the detection monitoring program in §257.94 or the assessment monitoring program in §257.95;	Detection
<b>Statistically Significant Increases (SSIs)</b>	(iii) If it was determined that there was an SSI over background for one or more constituents listed in appendix III to this part pursuant to §257.94(e):	
	(A) Identify those constituents listed in appendix III to this part and the names of the monitoring wells associated with such an increase; and	<u>October 2022</u> Boron: MW-33AR, MW-34A, MW-302 Chloride: MW-33AR Sulfate: MW-33AR, MW-34A, MW-302  <u>April 2023</u> Boron: MW-33AR, MW-34A, MW-302 Chloride: MW-33AR Field pH: MW-34A Sulfate: MW-33AR, MW-34A
	(B) Provide the date when the assessment monitoring program was initiated for the CCR unit.	Alternative Source Demonstrations prepared for October 2022 and April 2023 events during 2023. Assessment monitoring not required.



Category	Rule Requirement	Site Status
<b>Statistically Significant Levels (SSL) Above Groundwater Protection Standard (GPS)</b>	(iv) If it was determined that there was an SSL above the GPS for one or more constituents listed in appendix IV to this part pursuant to §257.95(g) include all of the following:	Not applicable – Appendix IV sampling not required
	(A) Identify those constituents listed in appendix IV to this part and the names of the monitoring wells associated with such an increase;	
	(B) Provide the date when the assessment of corrective measures was initiated for the CCR unit;	
	(C) Provide the date when the public meeting was held for the assessment of corrective measures for the CCR unit; and	
<b>Selection of Remedy</b>	(v) Whether a remedy was selected pursuant to §257.97 during the current annual reporting period, and if so, the date of remedy selection; and	Not applicable – Site is in detection monitoring
<b>Corrective Action</b>	(vi) Whether remedial activities were initiated or are ongoing pursuant to §257.98 during the current annual reporting period.	Not applicable – Site is in detection monitoring

## Table of Contents

Section	Page
<b>Overview of Current Status.....</b>	<b>i</b>
<b>1.0 Introduction.....</b>	<b>1</b>
<b>2.0 Background.....</b>	<b>1</b>
2.1 Geologic and Hydrogeologic Setting.....	1
2.1.1 Regional Information.....	1
2.1.2 Site Information.....	2
2.2 CCR Rule Monitoring System.....	2
<b>3.0 §257.90(e) Annual Report Requirements.....</b>	<b>2</b>
3.1 §257.90(e)(1) Site Map.....	3
3.2 §257.90(e)(2) Monitoring System Changes.....	3
3.3 §257.90(e)(3) Summary of Sampling Events.....	3
3.4 §257.90(e)(4) Monitoring Transition Narrative.....	4
3.5 §257.90(e)(5) Other Requirements.....	4
3.5.1 § 257.90(e) General Requirements.....	5
3.5.2 §257.94(d) Alternative Detection Monitoring Frequency.....	5
3.5.3 §257.94(e)(2) Alternative Source Demonstration for Detection Monitoring.....	5
3.5.4 §257.95(c) Alternative Assessment Monitoring Frequency.....	6
3.5.5 §257.95(d)(3) Assessment Monitoring Results and Standards.....	6
3.5.6 §257.95(g)(3)(ii) Alternative Source Demonstration for Assessment Monitoring..	6
3.5.7 §257.96(a) Extension of Time for Corrective Measures Assessment.....	6
3.6 §257.90(e)(6) Overview.....	6
<b>4.0 References.....</b>	<b>7</b>

### Tables

Table 1.	Groundwater Monitoring Well Network
Table 2.	CCR Rule Groundwater Samples Summary
Table 3.	Groundwater Elevation – State Monitoring Program and CCR Well Network
Table 4.	Horizontal Gradients and Flow Velocity
Table 5.	Groundwater Analytical Results Summary
Table 6.	Groundwater Field Data Summary

### Figures

Figure 1.	Site Location Map
Figure 2.	Site Plan and Monitoring Well Locations
Figure 3.	Water Table Map – April 2023
Figure 4.	Water Table Map – October 2023

## Appendices

Appendix A	Regional Hydrogeologic Information
Appendix B	Boring Logs and Well Construction Documentation
Appendix C	Laboratory Reports
Appendix D	Historical Monitoring Results
Appendix E	Alternative Source Demonstrations
	E1 October 2022 Detection Monitoring
	E2 April 2023 Detection Monitoring

I:\25223067.00\Deliverables\2023 - Fed CCR Annual Report - COL Mod 1-3\240131\_2023 Fed Annual Report - COL Mod 1-3\_Final.docx

## 1.0 INTRODUCTION

This 2023 Annual Groundwater Monitoring and Corrective Action Report was prepared to support compliance with the groundwater monitoring requirements of the Coal Combustion Residuals (CCR) Rule [40 Code of Federal Regulations (CFR) 257.50-107]. Specifically, this report was prepared to fulfill the requirements of 40 CFR 257.90(e). The applicable sections of the Rule are provided below in italics, followed by applicable information relative to the 2023 Annual Groundwater Monitoring and Corrective Action Report for the CCR Units. The site location is shown on **Figure 1**.

This report covers the period of groundwater monitoring from January 1, 2023, through December 31, 2023.

The groundwater monitoring system for the Columbia Energy Center (COL) Dry Ash Disposal Facility Modules 1 through 3 monitors a single CCR unit:

- COL Dry Ash Disposal Facility – Modules 1-3 (existing CCR Landfill)

The system is designed to detect monitored constituents at the waste boundary of Modules 1 through 3 of the COL Dry Ash Disposal Facility as required by 40 CFR 257.91(d). The groundwater monitoring system consists of two upgradient and three downgradient monitoring wells (**Table 1** and **Figure 2**). Separate groundwater monitoring systems evaluate groundwater conditions for Modules 4 through 6 and Modules 10 and 11 of the COL Dry Ash Disposal Facility.

## 2.0 BACKGROUND

To provide context for the required annual report information, the following background information is provided in this section of the report, prior to the required information:

- Geologic and hydrogeologic setting
- CCR Rule monitoring system

## 2.1 GEOLOGIC AND HYDROGEOLOGIC SETTING

### 2.1.1 Regional Information

For the purposes of groundwater monitoring, the surficial sand and gravel aquifer is considered to be the uppermost aquifer unit, as defined under 40 CFR 257.53, at the COL Ash Disposal Facility Modules 1 through 3. Immediately underlying the surficial sand and gravel aquifer is the Cambrian-Ordovician sandstone aquifer. A summary of the regional hydrogeologic stratigraphy is presented in **Appendix A**.

The sand and gravel aquifer is capable of producing sufficient water for industrial or municipal use in some parts of Columbia County and is capable of producing sufficient water for domestic use in many areas, including along the Wisconsin River near the Columbia Energy Center (Harr et al., 1978). A map showing expected well yields within the sand and gravel aquifer in Columbia County is included in **Appendix A**.

Regional groundwater flow in the site vicinity is generally west toward the Wisconsin River. A map showing the regional water table elevations is included with the regional hydrogeologic information in **Appendix A**.

## 2.1.2 Site Information

Soils at the site are primarily sand to a depth of approximately 50 to 100 feet and overlie sandstone bedrock. Soils encountered during the site feasibility study for the COL Ash Disposal Facility were described as generally sandy with interbedded silty clay lenses up to 20 feet thick (Warzyn Engineering, Inc., 1978). During drilling of CCR wells MW-301 and MW-302, the unconsolidated materials were identified as consisting primarily of silty sand and sand. Boring logs for previously installed monitoring wells MW-33AR, MW-34A, MW-84A, and M-4R show silty sand and sand as the primary unconsolidated materials at these locations. The boring logs for Ash Disposal Facility Modules 1 through 3 CCR monitoring wells are provided in **Appendix B**. All CCR monitoring wells are screened within the unconsolidated sand unit.

Shallow groundwater at the site generally flows to the north and west across the existing landfill area. The April 2023 water levels and apparent flow directions reflect the influence of a temporary dewatering system installed to lower groundwater levels in the area of the Primary Pond as part of the closure project for that CCR Unit. The water table elevations and groundwater flow directions for the April 2023 monitoring event are shown on **Figure 3**, and the water table elevations and groundwater flow directions for the October 2023 monitoring event are shown on **Figure 4**. The groundwater elevation data for the CCR monitoring wells are provided in **Table 3**. Calculated horizontal gradients and flow velocities for representative flow paths are provided in **Table 4**.

## 2.2 CCR RULE MONITORING SYSTEM

The groundwater monitoring system established in accordance with the CCR Rule consists of two upgradient (background) monitoring wells and three downgradient monitoring wells (**Table 1** and **Figure 2**). The background wells include MW-301 and MW-84A. The downgradient wells include MW-302, MW-33AR, and MW-34A. The CCR Rule wells are installed within the sand and gravel aquifer. Well depths range from approximately 29 to 43 feet, measured from the top of the well casing.

## 3.0 §257.90(e) ANNUAL REPORT REQUIREMENTS

**Annual groundwater monitoring and corrective action report.** *For existing CCR landfills and existing CCR surface impoundments, no later than January 31, 2018, and annually thereafter, the owner or operator must prepare an annual groundwater monitoring and corrective action report. For new CCR landfills, new CCR surface impoundments, and all lateral expansions of CCR units, the owner or operator must prepare the initial annual groundwater monitoring and corrective action report no later than January 31 of the year following the calendar year a groundwater monitoring system has been established for such CCR unit as required by this subpart, and annually thereafter. For the preceding calendar year, the annual report must document the status of the groundwater monitoring and corrective action program for the CCR unit, summarize key actions completed, describe any problems encountered, discuss actions to resolve the problems, and project key activities for the upcoming year. For purposes of this section, the owner or operator has prepared the annual report when the report is placed in the facility's operating record as required by § 257.105(h)(1). At a minimum, the annual groundwater monitoring and corrective action report must contain the following information, to the extent available:*

### **3.1 §257.90(e)(1) SITE MAP**

*A map, aerial image, or diagram showing the CCR unit and all background (or upgradient) and downgradient monitoring wells, to include the well identification numbers, that are part of the groundwater monitoring program for the CCR unit;*

A map of the site location is provided on **Figure 1**. A map showing the Dry Ash Disposal Facility Modules 1 through 3 and all background (or upgradient) and downgradient monitoring wells with identification numbers for the groundwater monitoring program is provided as **Figure 2**. Other CCR units are also shown on **Figure 2**.

### **3.2 §257.90(e)(2) MONITORING SYSTEM CHANGES**

*Identification of any monitoring wells that were installed or decommissioned during the preceding year, along with a narrative description of why those actions were taken;*

There were no monitoring system changes in 2023.

### **3.3 §257.90(e)(3) SUMMARY OF SAMPLING EVENTS**

*In addition to all the monitoring data obtained under §§ 257.90 through 257.98, a summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the detection monitoring or assessment monitoring programs;*

Two semiannual groundwater sampling events were completed in 2023 at the COL Dry Ash Disposal Modules 1 through 3 as part of ongoing detection monitoring.

Groundwater samples collected during the semiannual events in April and October 2023 were analyzed for Appendix III constituents. A summary including the number of groundwater samples that were collected for analysis for each background and downgradient well, the dates the samples were collected, and whether the sample was required by the detection or assessment monitoring program is included in **Table 2**.

The validation and evaluation of the October 2022 monitoring event data was completed and transmitted to WPL on March 2, 2023. The validation and evaluation of the April 2023 monitoring event data was completed and transmitted to WPL on August 24, 2023. The validation and evaluation of the October 2023 monitoring event data was in progress at the end of 2023 and will be transmitted to WPL in 2024; therefore, the October 2023 monitoring results and analytical report will be included in the 2024 annual report. The October 2023 groundwater elevation data are included in this report.

The sampling results for Appendix III parameters in October 2022 and April 2023 are summarized in **Table 5**. Field parameter results for the October 2022 and April 2023 sampling events are provided in **Table 6**. The analytical laboratory reports for October 2022 and April 2023 are provided in **Appendix C**. Historical results for each monitoring well through April 2023 are summarized in **Appendix D**.

The October 2022 analyses for the samples collected from background wells MW-84A and MW-301 are provided in two laboratory reports: an initial report and a reanalysis report. The reanalysis only affects Appendix IV parameters, which are not required for the Mod 1-3 LF CCR Unit, but are required

for other CCR Units at COL. The background well samples were reanalyzed for select metals because the original results were flagged for detections in the method blank sample and/or were not consistent with historical results. The reanalysis was completed within the method holding time, the metals were not detected in the method blank, and no other flags were applied to the results. Based on the quality control review, the reanalysis results were considered to be more accurate than the original analyses.

### **3.4 §257.90(e)(4) MONITORING TRANSITION NARRATIVE**

*A narrative discussion of any transition between monitoring programs (e.g., the date and circumstances for transitioning from detection monitoring to assessment monitoring in addition to identifying the constituent(s) detected at a statistically significant increase over background levels);*

There were no transitions between monitoring programs during 2023. The COL Dry Ash Disposal Facility, Modules 1 through 3, remained in the detection monitoring program.

In 2023, the monitoring results for the October 2022 and April 2023 monitoring events were evaluated for statistically significant increases (SSIs) in detection monitoring parameters relative to background. The comparison to background was based on a prediction limit approach, comparing the results to interwell upper prediction limits (UPLs) based on background monitoring results from the upgradient wells (MW-84A and MW-301). The interwell UPLs were most recently updated in January 2020 using background data collected through October 2019. The January 2020 statistical analysis was included as an appendix in the 2021 Annual Groundwater Monitoring Report. The Unified Guidance for Statistical Analysis of Groundwater Monitoring Data at Resource Conservation and Recovery Act (RCRA) Facilities (U.S. Environmental Protection Agency [U.S. EPA], 2009; Section 5.3.1) recommends periodic updating of background for both intrawell and interwell analyses. For semiannual monitoring, an update interval of 2 to 3 years is recommended. The next UPL update is planned for 2024.

For the October 2022 and April 2023 events, SSIs for boron, chloride, and sulfate were identified.

Alternative source demonstrations (ASDs) were completed for the October 2022 and April 2023 events, demonstrating that sources other than the CCR unit were the likely cause of the observed concentrations of boron, chloride, and sulfate. The ASD reports are provided in **Appendix E**.

### **3.5 §257.90(e)(5) OTHER REQUIREMENTS**

*Other information required to be included in the annual report as specified in §§ 257.90 through 257.98.*

Additional potentially applicable requirements for the annual report, and the location of the requirement within the Rule, are provided in the following sections. For each cited section of the Rule, the portion referencing the annual report requirement is provided below in italics, followed by applicable information relative to the 2023 Annual Groundwater Monitoring and Corrective Action Report for the CCR Units.



### 3.5.1 § 257.90(e) General Requirements

*For the preceding calendar year, the annual report must document the status of the groundwater monitoring and corrective action program for the CCR unit, summarize key actions completed, describe any problems encountered, discuss actions to resolve the problems, and project key activities for the upcoming year.*

**Status of Groundwater Monitoring and Corrective Action Program:** The groundwater monitoring and corrective action program was in detection monitoring throughout 2023.

#### **Summary of Key Actions Completed:**

- Statistical evaluation and determination of SSIs for the October 2022 and April 2023 monitoring events.
- ASD reports for the SSIs identified from the October 2022 and April 2023 monitoring events.
- Two semiannual groundwater sampling and analysis events (April and October 2023).

**Description of Any Problems Encountered:** No problems were encountered for Mod 1-3 in 2023.

**Discussion of Actions to Resolve the Problems:** Not applicable.

#### **Projection of Key Activities for the Upcoming Year (2024):**

- Statistical evaluation and determination of any SSIs for the October 2023 and April 2024 monitoring events.
- If an SSI is determined, then within 90 days either:
  - Complete ASD (if applicable), or
  - Establish an assessment monitoring program.
- Two semiannual groundwater sampling and analysis events (April and October 2024).

### 3.5.2 §257.94(d) Alternative Detection Monitoring Frequency

*The owner or operator must include the demonstration providing the basis for the alternative monitoring frequency and the certification by a qualified professional engineer in the annual groundwater monitoring and corrective action report required by § 257.90(e).*

Not applicable. No alternative detection monitoring frequency has been proposed.

### 3.5.3 §257.94(e)(2) Alternative Source Demonstration for Detection Monitoring

*The owner or operator must also include the demonstration in the annual groundwater monitoring and corrective action report required by § 257.90(e), in addition to the certification by a qualified professional engineer.*



The ASD reports prepared to address the SSIs observed for the October 2022 and April 2023 sampling events are provided in **Appendix E**. The ASD reports are certified by a qualified professional engineer.

### **3.5.4 §257.95(c) Alternative Assessment Monitoring Frequency**

*The owner or operator must include the demonstration providing the basis for the alternative monitoring frequency and the certification by a qualified professional engineer in the annual groundwater monitoring and corrective action report required by § 257.90(e).*

Not applicable. Assessment monitoring has not been initiated.

### **3.5.5 §257.95(d)(3) Assessment Monitoring Results and Standards**

*Include the recorded concentrations required by paragraph (d)(1) of this section, identify the background concentrations established under § 257.94(b), and identify the groundwater protection standards established under paragraph (d)(2) of this section in the annual groundwater monitoring and corrective action report required by § 257.90(e).*

Not applicable. Assessment monitoring has not been initiated.

### **3.5.6 §257.95(g)(3)(ii) Alternative Source Demonstration for Assessment Monitoring**

*The owner or operator must also include the demonstration in the annual groundwater monitoring and corrective action report required by § 257.90(e), in addition to the certification by a qualified professional engineer.*

Not applicable. Assessment monitoring has not been initiated.

### **3.5.7 §257.96(a) Extension of Time for Corrective Measures Assessment**

*The assessment of corrective measures must be completed within 90 days, unless the owner or operator demonstrates the need for additional time to complete the assessment of corrective measure due to site-specific conditions or circumstances. The owner or operator must obtain a certification from a qualified professional engineer attesting that the demonstration is accurate. The 90-day deadline to complete the assessment of corrective measures may be extended for longer than 60 days. The owner or operator must also include the demonstration in the annual groundwater monitoring and corrective action report required by § 257.90(e), in addition to the certification by a qualified professional engineer.*

Not applicable. Corrective measures assessment has not been initiated.

## **3.6 §257.90(E)(6) OVERVIEW**

*A section at the beginning of the annual report that provides an overview of the current status of groundwater monitoring and corrective action programs for the CCR unit.*

The specific requirements for the overview under §257.90(e)(6) are listed and the information is provided at the beginning of this report, before the Table of Contents.

## 4.0 REFERENCES

Harr, C.A., L.C. Trotta, and R.G. Borman, 1978, "Ground-Water Resources and Geology of Columbia County, Wisconsin," University of Wisconsin-Extension Geological and Natural History Survey Information Circular Number 37, 1978.

U.S. Environmental Protection Agency (U.S. EPA), 2009, Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities, Unified Guidance, EPA 530-R-09-007, March 2009.

Warzyn Engineering, Inc., 1978, Feasibility Study, Proposed Fly Ash and/or Scrubber Sludge Disposal Facility – Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

[This page left blank intentionally.]

## Tables

- 1 Groundwater Monitoring Well Network
- 2 CCR Rule Groundwater Samples Summary
- 3 Groundwater Elevation – State Monitoring Program  
and CCR Well Network
- 4 Horizontal Gradients and Flow Velocity
- 5 Groundwater Analytical Results Summary
- 6 Groundwater Field Data Summary

**Table 1. Groundwater Monitoring Well Network  
Columbia Energy Center Dry Ash Disposal Facility - Modules 1-3  
SCS Engineers Project #25223067.00**

<b>Monitoring Well</b>	<b>Location in Monitoring Network</b>	<b>Role in Monitoring Network</b>
MW-84A	Upgradient	Background
MW-301	Upgradient	Background
MW-302	Downgradient	Compliance
MW-34A	Downgradient	Compliance
MW-33AR	Downgradient	Compliance

**Note:**

1, Monitoring well MW-1AR was abandoned in 2022 because it was within the footprint of the pending MOD 10-11 expansion area. The monitoring network certification was updated with the abandonment of MW-1AR in October 2022.

Created by: NDK  
 Last revision by: NLB  
 Checked by: BLR

Date: 9/19/2022  
 Date: 11/29/2023  
 Date: 12/1/2023

**Table 2. CCR Rule Groundwater Samples Summary  
Columbia Energy Center Dry Ash Disposal Facility, Modules 1-3  
SCS Engineers Project #25223067.00**

Sample Dates	Compliance Wells			Background Wells	
	MW-302	MW-34A	MW-33AR	MW-84A	MW-301
4/26-27/2023	D	D	D	D	D
10/11/2023	D	D	D	D	D
Total Samples	2	2	2	2	2

Abbreviations:

D = Required by Detection Monitoring Program

Created by: <u>NLB</u>	Date: <u>11/29/2023</u>
Last revision by: <u>NLB</u>	Date: <u>11/29/2023</u>
Checked by: <u>RM</u>	Date: <u>12/12/2023</u>

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network  
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25223067.00**

Well Number	MW-1AR	MW-4	MW-5R	MW-33AR	MW-33BR	MW-34A	MW-34B	MW-37A	MW-83	MW-84A	MW-84B	MW-86	MW-91AR	MW-91B	MW-92A	MW-92B	MW-93A	MW-93B	MW-312
<b>Top of Casing Elevation (feet amsl)</b>	822.55	819.74	805.44	808.29	808.39	805.95	806.05	813.04	807.96	814.28	814.26	824.79	809.03	808.45	808.47	808.41	827.89	827.71	826.79
<b>Screen Length (ft)</b>																	10	5	10
<b>Total Depth (ft from top of casing)</b>	44.40	39.58	25.97	31.08	57.50	35.43	56.95	31.80	25.42	40.21	52.02	45.43	32.90	52.38	28.94	51.75	50.7	82.5	52.5
<b>Top of Well Screen Elevation (ft)</b>	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	787.19	750.21	784.29
<b>Measurement Date</b>																			
October 2, 2012	783.41	783.70	784.96	782.38	782.23	783.03	782.99	782.66	dry	783.84	783.94	783.81	784.09	783.90	784.49	784.06	NI	NI	NI
April 15, 2013	785.44	784.02	786.09	784.16	784.14	784.74	784.79	783.87	784.49	785.83	785.76	785.22	785.14	785.01	785.75	785.34	NI	NI	NI
October 8, 2013													785.66	785.42	785.97	785.52	NI	NI	NI
October 15, 2013	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.66	785.42	785.97	785.52	NI	NI
April 14, 2014	784.95	784.09	785.63	783.74	783.91	784.63	784.70	783.45	783.73	785.58	785.52	784.96	785.04	784.96	785.99	785.54	NI	NI	NI
October 2-3, 2014	785.03	785.39	786.08	784.37	784.28	784.57	784.54	784.56	dry	785.24	785.18	785.19	785.47	785.28	785.75	785.33	NI	NI	NI
April 13-14, 2015	783.96	783.63	785.25	783.01	782.74	783.65	783.95	782.87	dry	784.43	784.51	784.17	784.48	784.37	785.07	784.66	NI	NI	NI
October 6-7, 2015	784.28	784.44	785.72	783.68	783.33	784.05	784.02	783.66	dry	784.80	784.76	784.66	784.89	784.70	785.20	784.76	NI	NI	NI
April 4-6, 2016	785.82	aband	787.02	785.29	785.07	785.63	785.67	784.76	785.43	786.37	786.26	785.89	786.05	785.95	786.61	786.21	NI	NI	NI
October 11-13, 2016	786.64	aband	788.00	787.36	786.46	786.45	786.32	786.40	786.81	787.22	787.11	786.96	787.17	786.81	787.68	787.25	NI	NI	NI
April 10-13, 2017	786.96	aband	788.13	786.39	785.99	786.30	786.28	786.34	786.23	787.16	787.06	786.96	787.24	787.03	787.90	787.60	NI	NI	NI
October 3-5, 2017	785.48	aband	786.66	784.51	784.22	784.67	784.63	784.86	784.29	NM	786.49	785.58	786.08	785.83	786.47	786.02	NI	NI	NI
October 9-10, 2017	NM	aband	NM	NM	NM	NM	NM	NM	NM	785.56 <sup>(6)</sup>	NM	NM	NM	NM	NM	NM	NI	NI	NI
February 21, 2018	783.97	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	784.68	784.46	NM	NM	NI	NI	NI
April 23-25, 2018	783.99	aband	785.36	783.09	786.36	781.77	780.79	783.28	783.32	785.88	784.91	782.54	784.71	784.53	785.23	784.81	NI	NI	NI
October 23-25, 2018	788.25	aband	789.71	788.77	787.96	787.88	787.73	787.62	788.26	788.32	788.19	788.21	788.59	788.31	789.32	788.87	NI	NI	NI
April 1-4, 2019	787.05	aband	788.64	786.63	786.54	786.82	786.92	786.47	786.78	787.35	787.34	787.16	787.45	787.18	788.04	787.63	NI	NI	NI
October 7-9, 2019	787.26	aband	789.23	788.26	787.64	787.92	787.74	786.77	788.90	787.79	787.73	787.44	787.78	787.62	788.63	788.17	NI	NI	NI
May 27-28, 2020	786.92	aband	788.34	786.01	785.75	785.98	785.99	786.22	786.03	787.02	786.99	786.94	787.26	787.05	787.86	787.47	NI	NI	NI
October 7-8, 2020	785.95	aband	787.76	785.91	785.45	785.70	785.68	785.52	785.72	786.10	786.06	786.10	786.55	786.33	786.85	786.38	NI	NI	NI
February 25, 2021	NM	aband	NM	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI
April 14, 2021	778.12	aband	787.29	784.27	784.05	784.77	784.77	784.46	c	785.84	785.81	785.60	785.86	785.69	786.47	786.06	NI	NI	NI
June 11, 2021	NM	aband	NM	784.19	NM	784.66	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI
October 11-12, 14, 2021	784.47	aband	786.78	783.73	783.60	784.42	784.41	783.88	783.87	784.96	784.88	784.79	785.14	784.94	785.55	785.11	NI	NI	NI
October 17, 2021	NM	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI
April 1, 2022	aband	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM
April 11-13, 2022	aband	aband	785.52	783.27	783.45	784.30	784.42	783.26	783.78	785.02	785.00	784.70	784.83	784.72	785.45	785.02	783.99	783.97	783.73
October 24-28, 2022	aband	aband	785.43	781.94	781.61	783.61	783.61	782.28	dry	784.57	784.54	784.38	784.64	784.47	785.05	784.62	783.74	782.76	783.50
February 20-23, 2023	aband	aband	NM	783.57	NM	784.48	NM	NM	NM	785.25	NM	NM	NM	NM	NM	NM	NM	NM	NM
March 27-28, 2023	aband	aband	NM	784.52	NM	785.23	NM	NM	NM	786.21	NM	NM	NM	NM	NM	NM	NM	NM	NM
April 24-27, 2023	aband	aband	787.76	785.79	785.35	786.22	786.12	784.99	786.05	786.97	786.86	786.67	786.76	786.59	787.53	787.11	785.87	785.85	785.55
May 16, 2023	aband	aband	787.79	785.64	785.25	786.06	786.05	785.39	785.77	786.88	786.79	786.74	786.95	786.75	787.47	787.05	786.23	786.21	785.97
May 30-31, 2023	aband	aband	NM	785.23	NM	785.70	NM	NM	NM	786.57	NM	NM	NM	NM	NM	NM	NM	NM	NM
October 9-11, 2023	aband	aband	785.33	782.57	782.39	783.55	783.40	782.94	dry	784.39	784.31	784.24	784.63	784.36	784.89	784.36	783.86	783.59	783.69
<b>Bottom of Well Elevation (ft)</b>	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	777.19	745.21	774.29

Dry Ash Facility (Facility ID #03025)

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network  
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25223067.00**

Well Number	M-3	M-4R	MW-39A	MW-39B	MW-48A	MW-48B	MW-57	MW-59	MW-216R	MW-217	MW-220RR
	<b>Top of Casing Elevation (feet amsl)</b>	788.23	806.10	809.62	809.50	828.86	828.84	786.29	815.48	814.21	791.55
<b>Screen Length (ft)</b>											
<b>Total Depth (ft from top of casing)</b>	16.90	25.55	34.80	76.07	51.88	75.80	14.40	38.50	37.85	37.37	18.96
<b>Top of Well Screen Elevation (ft)</b>	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94
<b>Measurement Date</b>											
October 2, 2012	780.13	786.76	781.49	781.34	782.03	781.93	780.58	779.88	781.91	780.95	780.55
April 15, 2013	785.16	788.39	783.97	784.00	783.77	783.78	784.69	783.66	784.09	784.75	785.02
October 8, 2013	781.22	786.67	NM	NM	783.69	783.58	NM	NM	783.39	782.27	782.36
October 15, 2013	NM	NM	782.94	782.81	NM	NM	782.47	783.49	NM	NM	NM
April 14, 2014	786.04	788.96	783.57	783.68	783.56	783.57	785.51	783.41	783.73	785.25	785.87
October 1-3, 2014	781.16	787.55	783.42	783.32	784.05	783.94	782.32	783.55	783.79	782.63	783.03
April 13-14, 2015	783.08	786.83	782.77	782.68	782.80	782.82	782.81	782.83	782.93	783.34	783.42
October 6-7, 2015	780.66	786.12	782.97	782.81	783.10	783.01	781.82	783.25	783.18	781.95	782.26
April 4-6, 2016	784.21	789.09	785.27	785.27	784.79	784.76	783.21	784.97	785.68	785.02	784.36
October 11-13, 2016	781.88	787.88	785.75	785.52	785.73	785.61	783.12	786.51	786.16	783.75	784.09
April 10-13, 2017	782.94	787.95	785.44	785.20	785.82	785.69	782.77	786.09	785.95	784.29	784.09
October 3-5, 2017	780.93	787.04	783.35	783.18	784.30	784.19	782.37	784.23	783.89	782.48	782.61
April 23-25, 2018	782.89	790.43	782.86	782.87	783.14	783.09	783.04	783.02	783.23	783.26	783.45
October 23-25, 2018	782.95	788.47	787.12	786.88	787.12	786.99	783.48	787.73	787.49	784.90	784.52
April 1-4, 2019	785.68	789.44	786.28	786.31	786.56	786.45	785.27	787.39	786.53	786.33	785.46
October 7-9, 2019	785.33	790.65	787.10	787.02	786.68	786.65	785.29	786.68	787.07	786.01	785.42
May 27-29, 2020	781.80	787.73	785.12	784.92	785.74	785.59	783.11	785.89	785.60	783.41	783.89
<b>Bottom of Well Elevation (ft)</b>	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94

Ash Pond Facility (Facility ID #02325)





**Table 4. Horizontal Gradients and Flow Velocity  
Columbia Energy Center Dry Ash Disposal Facility - Modules 1-3  
SCS Engineers Project #25223067.00  
January - December 2023**

Flow Path A - North					
Sampling Dates	h1 (ft)	h2 (ft)	Δl (ft)	Δh/Δl (ft/ft)	V (ft/d)
4/24-27/2023	787.00	786.00	611	0.0016	0.042

Flow Path A - Northwest					
Sampling Dates	h1 (ft)	h2 (ft)	Δl (ft)	Δh/Δl (ft/ft)	V (ft/d)
4/24-27/2023	787.00	786.00	815	0.0012	0.031
10/9-11/2023	785.00	783.00	1035	0.0019	0.049

Wells	K Values (cm/sec)	K Values (ft/d)
MW-34A	N/A	N/A
MW-302	3.22E-02	91.2
MW-33AR	4.01E-04	1.1
Geometric Mean	3.59E-03	10.2

Assumed Porosity, n
0.40

Groundwater flow velocity equation:  $V = [K*(\Delta h/\Delta l)] / n$

ft = feet

ft/d = feet per day

K = hydraulic conductivity

n = effective porosity

V = groundwater flow velocity

h1, h2 = point interpreted groundwater elevation at locations 1 and 2

Δl = distance between location 1 and 2

Δh/Δl = hydraulic gradient

**Note:**

1. See Figures 3 and 4 for velocity calculation flow path locations.

Created by: RM  
 Last revision by: RM  
 Checked by: NLB

Date: 1/2/2024  
 Date: 1/2/2024  
 Date: 1/2/2024

**Table 5. Groundwater Analytical Results Summary**  
**Columbia Energy Center Dry Ash Disposal Facility - Modules 1-3 / SCS Engineers Project #25223067.00**

Parameter Name	UPL Method	UPL	Background Wells				Compliance Wells					
			MW-84A		MW-301		MW-33AR		MW-34A		MW-302	
			10/27/2022	4/27/2023	10/17/2022	4/27/2023	10/27/2022	4/24/2023	10/27/2022	4/26/2023	10/27/2022	4/27/2023
Groundwater Elevation (ft above msl)			784.57	786.97	784.91	787.57	781.94	785.79	783.61	786.22	784.62	786.87
<b>Appendix III</b>												
Boron, ug/L	P	35.6	12.2	10.3	37.5	20.1	586	532	264	220	374	541
Calcium, ug/L	NP	129,000	78,400	68,600	62,800	P6 120,000	77,000	55,300	87,300	49,600	91,200	66,500
Chloride, mg/L	P	6.2	3.4	3.0	2.3	1.5	J 40.5	19.0	2.2	2.0	2.1	1.3
Fluoride, mg/L	DQ	DQ	<0.095	<0.095	<0.095	M0 <0.095	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095
Field pH, Std. Units	P	7.78	7.31	7.01	6.80	6.65	7.54	7.61	7.53	7.53	7.25	7.36
Sulfate, mg/L	P	30.3	1.1	J 1.3	J 11.6	12.3	153	104	169	48.4	30.3	36.6
Total Dissolved Solids, mg/L	NP	514	302	326	282	526	440	394	436	302	348	352

4.4 Blue shaded cell indicates the compliance well result exceeds the UPL (background) and the Limit of Quantitation (LOQ).

**Abbreviations:**

mg/L = milligrams per liter  
 ug/L = micrograms per liter  
 SSI = Statistically Significant Increase  
 -- = Not Measured

GPS = Groundwater Protection Standard  
 UPL = Upper Prediction Limit  
 NP = Nonparametric UPL with 1-of-2 retesting  
 P = Parametric UPL with 1-of-2 retesting

LOD = Limit of Detection  
 LOQ = Limit of Quantitation  
 DQ = Double Quantification

J = Estimated concentration at or above the LOD and below the LOQ.  
 P6 = Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.  
 M0 = Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits

**Notes:**

1. An individual result above the UPL does not constitute an SSI above background. See the accompanying report text for identification of statistically significant results.
2. Interwell UPLs calculated based on results from background wells MW-84A and MW-301. Interwell UPLs based on 1-of-2 retesting approach. UPLs updated in January 2020 based on background well results through October 2019.
3. Interwell UPLs calculated based on results from background wells MW-84 and MW-301.

Created by:	<u>NDK</u>	Date:	<u>9/19/2022</u>
Last revision by:	<u>NLB</u>	Date:	<u>7/31/2023</u>
Checked by:	<u>BLR</u>	Date:	<u>8/2/2023</u>
Scientist/Proj Mgr QA/QC:	<u>TK</u>	Date:	<u>12/28/2023</u>

**Table 6. Groundwater Field Data Summary**  
**Columbia Energy Center Dry Ash Disposal Facility - Modules 1-3 / SCS Engineers Project #25223067.00**


Well	Sample Date	Groundwater Elevation (feet)	Field Temperature (deg C)	Field pH (Std. Units)	Oxygen, Dissolved (mg/L)	Field Specific Conductance (umhos/cm)	Field Oxidation Potential (mV)	Turbidity (NTU)
MW-84A	10/27/2022	784.57	11.7	7.31	8.31	585	40	0.00
	4/27/2023	786.97	10.7	7.01	9.37	557	103	0.72
MW-301	10/27/2022	784.91	10.8	6.80	0.10	508	81	0.00
	4/27/2023	787.57	8.0	6.65	6.50	857	95	0.00
MW-302	10/27/2022	784.62	11.6	7.25	8.60	616	38	0.00
	4/27/2023	786.87	9.7	7.36	10.91	605	145	1.82
MW-33AR	10/27/2022	781.94	12.7	7.54	8.91	737	101	0.00
	4/27/2023	785.79	10.2	7.61	11.71	609	177	0.20
MW-34A	10/27/2022	783.61	12.6	7.53	8.46	648	39	1.76
	4/26/2023	786.22	10.9	7.53	9.87	466	124	2.11

Created by: RM  
 Last revision by: BLR  
 Checked by: RM

Date: 12/11/2023  
 Date: 12/11/2023  
 Date: 12/12/2023

## Figures

- 1 Site Location Map
- 2 Site Plan and Monitoring Well Locations
- 3 Water Table Map – April 2023
- 4 Water Table Map – October 2023



POYNETTE QUADRANGLE  
 WISCONSIN-COLUMBIA CO.  
 7.5 MINUTE SERIES (TOPOGRAPHIC)  
 2018  
 SCALE: 1" = 2,000'




CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954		SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER PARDEEVILLE, WI		ENGINEER	SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830		SITE LOCATION MAP	
	PROJECT NO.	25220067.00		DRAWN BY:	BSS		FIGURE	1		
	DRAWN:	12/02/2019		CHECKED BY:	MDB					
REVISED:	01/10/2020	APPROVED BY:	TK 04/10/2020							

I:\25220067.00\Drawings\ASD Mod 1-3 LF\Site Location Map.dwg, 4/12/2020 7:05:09 PM










PROJECT NO.	25223067.00	DRAWN BY:	KP	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULES 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	WATER TABLE MAP APRIL 2023	FIGURE
DRAWN:	10/12/2023	CHECKED BY:	NLB					3
REVISED:	01/09/2024	APPROVED BY:	TK 1/29/2024					


I:\25223067.00\Drawings\Modules 1-3\Water Table Map-April 2023.dwg, 1/22/2024 9:27:17 AM





PROJECT NO.	25223067.00	DRAWN BY:	KP	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULES 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	WATER TABLE MAP OCTOBER 2023	FIGURE
DRAWN:	11/13/2023	CHECKED BY:	NLB					4
REVISED:	01/09/2024	APPROVED BY:	TK 1/10/2024					

I:\25223067.00\Drawings\Modules 1-3\Water Table Map-October 2023.dwg, 1/9/2024 10:33:50 AM



Appendix A  
Regional Hydrogeologic Information

**Table COL-3. Regional Hydrogeologic Stratigraphy  
Columbia Energy Center / SCS Engineers Project #25215053**

Approximate Age	Hydrogeologic Unit	General Thickness (feet)	Name of Rock Unit*	Predominant Lithology
Quaternary (0-1 million years old)	Surficial Aquifer	0 to 300+	Holocene & Pleistocene Deposits	<ul style="list-style-type: none"> <li>• Unconsolidated clay, silt, sand, gravel, cobbles, boulders, and organic matter</li> </ul>
Ordovician (460 to 490 million years old)	Sandstone Aquifer	0 to 800+	Galena Decorah Platteville St. Peter Prairie du Chien	<ul style="list-style-type: none"> <li>• Dolomite and shaley dolomite</li> <li>• Sandstone</li> </ul>
Cambrian (490 to 500 million years old)			Trempeleau Franconia Galesville Eau Claire Mt. Simon	<ul style="list-style-type: none"> <li>• Sandstone</li> </ul>
Precambrian (more than 1 billion years old)	Used for domestic supply in some areas	--	Precambrian	<ul style="list-style-type: none"> <li>• Igneous and metamorphic rocks</li> </ul>



\*This nomenclature and classification of rock units in this report are those of the Wisconsin Geological and Natural History Survey and do not necessarily coincide with those accepted by the U.S. Geological Survey.

Sources:

Harr, C.A., L.C. Trotta, and R.G. Borman, "Ground-Water Resources and Geology of Columbia County, Wisconsin," University of Wisconsin-Extension Geological and Natural History Survey Information Circular Number 37, 1978.  
 Wisconsin Geological and Natural History Survey, Bedrock Stratigraphic Units in Wisconsin, UW Extension Educational Series 51, ISSN: 1052-2115, 2011.


I:\25215053\Reports\Report 3 - Columbia\Tables\Table\_2\_Regional\_Hydrogeologic\_Stratigraphy.doc





EXPLANATION

Probable well yields




Boundary of saturated sand-and-gravel aquifer

Figure 9. Probably well yields from the sand-and-gravel aquifer.

Source: Harr, C.A., L.C. Trotta, and R.G. Borman, "Ground-Water Resources and Geology of Columbia County, Wisconsin," University of Wisconsin-Extension Geological and Natural History Survey Information Circular Number 37, 1978.  
 02/26/2024 - Classification: Internal - ECRM13238672

# Generalized water-table elevation in Columbia County, Wisconsin



## Appendix B


### Boring Logs and Well Construction Documentation

Route To: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name <b>Alliant Energy - Columbia</b>		License/Permit/Monitoring Number <b>03025</b>		Boring Number <b>MW-33AR</b>	
Boring Drilled By: Name of crew chief (first, last) and Firm <b>Ryan Fisher Boart Longyear</b>		Date Drilling Started <b>4/9/2003</b>		Date Drilling Completed <b>4/9/2003</b>	
Drilling Method <b>4 1/4" HSA</b>		WI Unique Well No. <b>PE223</b>		DNR Well ID No. <b>138</b>	
Common Well Name <b>MW-33AR</b>		Final Static Water Level <b>Feet MSL</b>		Surface Elevation <b>805.4 Feet MSL</b>	
Borehole Diameter <b>8.0 inches</b>		Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/> ) or Boring Location <input checked="" type="checkbox"/>		Local Grid Location	
State Plane <b>542,663 N, 2,123,584 E S/C/N</b>		Lat _____ "		<input type="checkbox"/> N <input type="checkbox"/> E	
<b>NE 1/4 of SW 1/4 of Section 27, T 12 N, R 9 E</b>		Long _____ "		Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W	
Facility ID <b>111049180</b>		County <b>Columbia</b>		County Code <b>11</b>	
				Civil Town/City/ or Village <b>Pacific</b>	

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties						RQD/ Comments
									Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200		
			2.5 5.0 7.5 10.0 12.5 15.0 17.5 20.0 22.5 25.0 27.5	<b>Blind drilled to 29 feet. See log of MW-33BR for lithology.</b>	SM										
				<b>End of boring at 29 feet.</b>											

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature  Firm **RMT, Inc.** Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.



Route To: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name <b>Alliant Energy - Columbia</b>		License/Permit/Monitoring Number <b>03025</b>		Boring Number <b>MW-33BR</b>	
Boring Drilled By: Name of crew chief (first, last) and Firm <b>Ryan Fisher Boart Longyear</b>		Date Drilling Started <b>4/8/2003</b>	Date Drilling Completed <b>4/9/2003</b>	Drilling Method <b>4 1/4" HSA</b>	
WI Unique Well No. <b>PE224</b>	DNR Well ID No. <b>140</b>	Common Well Name <b>MW-33BR</b>	Final Static Water Level <b>785.3 Feet MSL</b>	Surface Elevation <b>805.3 Feet MSL</b>	Borehole Diameter <b>8.0 inches</b>
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/> ) or Boring Location <input checked="" type="checkbox"/> State Plane <b>542,660 N, 2,123,585 E S/C/N</b> <b>NE 1/4 of SW 1/4 of Section 27, T 12 N, R 9 E</b>			Local Grid Location Lat _____ " <input type="checkbox"/> N <input type="checkbox"/> E Long _____ " Feet <input type="checkbox"/> S Feet <input type="checkbox"/> W		
Facility ID <b>111049180</b>	County <b>Columbia</b>	County Code <b>11</b>	Civil Town/City/ or Village <b>Pacific</b>		

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments	
									Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200		
AUGER	60		1												
1 SS	24	4 4 4 4	5	<b>SILTY SAND (SM), 85% fine to medium sand, 15% fines, nonplastic, 10YR 5/4 yellowish brown, no odor, moist.</b>	SM										
2 SS	24	3 5 5 5	10												
			11												
			12												
			13												
			14												
			15												

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature *R. M. C.* Firm **RMT, Inc.** Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

WDNR\_SBL\_98 03024WDPRY.GPJ WI\_DNR98.GDT 7/18/03



Boring Number **MW-33BR** Use only as an attachment to Form 4400-122.

Page 2 of 3

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Alt. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	
3 SS	24	4 5 4 5	16 17 18 19											
4 SS	24	4 3 4 4	20 21 22 23 24	Same as above, but wet.	SM									
5 SS	24	50/0	25 26 27 28 29	Hit a rock, auger through.										
6 SS	24	8 20 19 27	30 31 32 33 34	<b>SILTY SAND WITH GRAVEL (SM),</b> 70% fine to medium sand, 15% gravel, 15% fines, nonplastic, 10YR 4/3 brown, wet, dense.										
7 SS	24	10 17 19 24	35 36 37 38 39 40		SM									

WDNR\_SBL\_98\_03024WDYR.GPJ WI\_DNR98.GDT 7/18/03

Boring Number **MW-33BR** Use only as an attachment to Form 4400-122.

Page **3** of **3**

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Att. & Recovered (in)								Compressive Strength	Moisture Content	Liquid Limit	Plasticity Index	P 200	
8 SS	24	18 20 28 39	18 41	Same as above.										
9 SS	24	27 50/2	45 46		SM									
10 SS	24	7 50/1	53 54	<b>WEATHERED SANDSTONE, 95% poorly graded medium sand, 5% fines, white to brown, well sorted and rounded, poorly cemented.</b>										
			56	<b>End of boring at 56 feet.</b>										

WDNR\_SBL\_98 03024WDYR.GPJ WJ\_DNR98.GDT 7/18/03

Route To: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

**MONITORING WELL CONSTRUCTION**  
Form 4400-113A Rev. 7-98

Facility/Project Name Alliant Energy - Columbia	Local Grid Location of Well ft. <input type="checkbox"/> N. <input type="checkbox"/> S. <input type="checkbox"/> E. <input type="checkbox"/> W.	Well Name MW-33AR
Facility License, Permit or Monitoring No. 03025	Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/> ) or Well Location <input checked="" type="checkbox"/> Lat. " ' " Long. " ' " or	Wis. Unique Well No. PE223 DNR Well Number 138
Facility ID 111049180	St. Plane 542,663 ft. N, 2,123,584 ft. E. S/C/N	Date Well Installed 04/09/2003
Type of Well Well Code 71/dw	Section Location of Waste/Source NE 1/4 of SW 1/4 of Sec. 27, T. 12 N, R. 9 <input checked="" type="checkbox"/> E <input type="checkbox"/> W	Well Installed By: (Person's Name and Firm) R. Fischer
Distance from Waste/Source 500 ft.	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input checked="" type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	Gov. Lot Number Boart Longyear

A. Protective pipe, top elevation 808.09 ft. MSL  Yes  No

B. Well casing, top elevation 808.29 ft. MSL

C. Land surface elevation 805.4 ft. MSL

D. Surface seal, bottom 804.4 ft. MSL or 1.0 ft.

12. USCS classification of soil near screen:  
GP  GM  GC  GW  SW  SP   
SM  SC  ML  MH  CL  CH   
Bedrock


13. Sieve analysis attached?  Yes  No

14. Drilling method used: Rotary  50  
Hollow Stem Auger  41  
Other

15. Drilling fluid used: Water  02 Air  01  
Drilling Mud  03 None  99

16. Drilling additives used?  Yes  No  
Describe \_\_\_\_\_

17. Source of water (attach analysis, if required):  
\_\_\_\_\_



1. Cap and lock?  Yes  No

2. Protective cover pipe:  
a. Inside diameter: 4.0 in.  
b. Length: 7.0 ft.  
c. Material: Steel  04  
Other

d. Additional protection?  Yes  No  
If yes, describe: \_\_\_\_\_

3. Surface seal: Bentonite  30  
Concrete  01  
Other

4. Material between well casing and protective pipe: Bentonite  30  
Other

5. Annular space seal: a. Granular/Chipped Bentonite  33  
b.        Lbs/gal mud weight . . . Bentonite-sand slurry  35  
c. 10.5 Lbs/gal mud weight . . . Bentonite slurry  31  
d.        % Bentonite . . . Bentonite-cement grout  50  
e. 3.5 Ft<sup>3</sup> volume added for any of the above  
f. How installed: Tremie  01  
Tremie pumped  02  
Gravity  08

6. Bentonite seal: a. Bentonite granules  33  
b.  1/4 in.  3/8 in.  1/2 in. Bentonite chips  32  
c.        Other

7. Fine sand material: Manufacturer, product name & mesh size  
a. #7 Badger  
b. Volume added 0.5 ft<sup>3</sup>

8. Filter pack material: Manufacturer, product name & mesh size  
a. #40 Badger  
b. Volume added 4.5 ft<sup>3</sup>

9. Well casing: Flush threaded PVC schedule 40  23  
Flush threaded PVC schedule 80  24  
Other

10. Screen material: PVC  
a. Screen Type: Factory cut  11  
Continuous slot  01  
Other

b. Manufacturer Boart Longyear  
c. Slot size: 0.010 in.  
d. Slotted length: 10.0 ft.

11. Backfill material (below filter pack): None  14  
Other

E. Bentonite seal, top 794.4 ft. MSL or 11.0 ft.

F. Fine sand, top 789.4 ft. MSL or 16.0 ft.

G. Filter pack, top 788.4 ft. MSL or 17.0 ft.

H. Screen joint, top 787.4 ft. MSL or 18.0 ft.

I. Well bottom 777.4 ft. MSL or 28.0 ft.

J. Filter pack, bottom 776.4 ft. MSL or 29.0 ft.

K. Borehole, bottom 776.4 ft. MSL or 29.0 ft.

L. Borehole, diameter 8.0 in.

M. O.D. well casing 2.37 in.

N. I.D. well casing 2.06 in.

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature R. M. Ch Firm RMT, Inc. Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.



# LOG OF TEST BORING

Project Wisconsin Power & Light  
 Location Columbia Generating Station

Boring No. MW-84A  
 Surface Elevation 813.4  
 Job No. C 7134  
 Sheet 1 of 1

1409 EMIL STREET • P.O. BOX 9538, MADISON, WIS. 53715 • TEL. (608) 257-4848

SAMPLE						VISUAL CLASSIFICATION and Remarks	SOIL PROPERTIES				
No.	Type	Recovery ↓	Moisture ↓	N	Depth		q <sub>s</sub>	W	LL	PL	D
						Dark Brown Silty SAND (SM)					
					5	Brown Fine to Medium SAND, Little Silt, Trace to Little Gravel and Boulders (SM)					
					10						
					15						
					20						
					25						
					30						
					35						
					40						
							End Boring at 37'				
							Well Installed at 37'				

## WATER LEVEL OBSERVATIONS

## GENERAL NOTES

While Drilling \_\_\_\_\_  
 Upon Completion of Drilling \_\_\_\_\_  
 Time After Drilling \_\_\_\_\_  
 Depth to Water \_\_\_\_\_  
 Depth to Cave In \_\_\_\_\_

10/5/83 10/5/83  
 Start \_\_\_\_\_ Complete \_\_\_\_\_  
 Crew Chief JVS Rig B-40  
 Drilling Method ED 0-37'

Route To: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name <b>Alliant Energy - Columbia</b>	County <b>Columbia</b>	Well Name <b>MW-33AR</b>	
Facility License, Permit or Monitoring Number <b>03025</b>	County Code <b>11</b>	Wis. Unique Well Number <b>PE223</b>	DNR Well Number <b>138</b>

1. Can this well be purged dry?  Yes  No

2. Well development method:
- surged with bailer and bailed  4 1
  - surged with bailer and pumped  6 1
  - surged with block and bailed  4 2
  - surged with block and pumped  6 2
  - surged with block, bailed, and pumped  7 0
  - compressed air  2 0
  - bailed only  1 0
  - pumped only  5 1
  - pumped slowly  5 0
  - other \_\_\_\_\_  \_\_\_\_\_

3. Time spent developing well **60 min.**

4. Depth of well (from top of well casing) **31.3 ft.**

5. Inside diameter of well **2.06 in.**

6. Volume of water in filter pack and well casing **6.0 gal.**

7. Volume of water removed from well **35.0 gal.**

8. Volume of water added (if any) **0.0 gal.**

9. Source of water added \_\_\_\_\_

10. Analysis performed on water added?  Yes  No  
(If yes, attach results)

17. Additional comments on development:  
**Pumped dry 3 times.**

	Before Development	After Development
11. Depth to Water (from top of well casing)	a. <b>23.47 ft.</b>	<b>23.62 ft.</b>
Date	b. <b>4/10/2003</b>	<b>4/10/2003</b>
Time	c. <b>08:50</b> <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.	<b>11:50</b> <input checked="" type="checkbox"/> a.m. <input type="checkbox"/> p.m.
12. Sediment in well bottom	<b>0.0 inches</b>	<b>0.0 inches</b>
13. Water clarity (Describe)	Clear <input type="checkbox"/> 1 0 <b>Opaque, brown</b>	Clear <input type="checkbox"/> 2 0 <b>Slight, tan</b>

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids **72 mg/l**

15. COD **mg/l**

16. Well developed by: Person's Name and Firm

**Peter M. Chase**  
**RMT, Inc.**

Facility Address or Owner/Responsible Party Address

Name: **Peter M. Chase**

Firm: **RMT, Inc.**

Street: **744 Heartland Tr.**

City/State/Zip: **Madison, WI 53717**

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: 

Print Name: **Peter M. Chase**

Firm: **RMT, Inc.**

NOTE: See instructions for more information including a list of county codes and well type codes.



FACILITY NAME  
Wisconsin Power and Light Co. Dry Ash

SAMPLING REQUIRED (✓ ONE)  YES  NO  
POINT (✓ ONE)  CAN BE SAMPLED  CANNOT BE SAMPLED

COMMON NAME OF SAMPLING POINT  
mw 34A

PREVIOUS COMMON NAME OF SAMPLING POINT

FACILITY ID NO.

POINT ID NO.

TYPE OF POINT (✓ ONE)

1 (G) GROUND WATER  
11  MONITOR WELL  
12  PIEZOMETER  
13  PRIVATE WELL  
14  LYSIMETER  
15  SPRING  
16  RESISTIVITY PROBE

2 (L) LEACHATE  
21  FLOW OR SEEP  
22  POND  
23  COLLECTION SYSTEM

3 (S) SURFACE WATER  
31  UPSTREAM  
32  MID-SITE  
33  DOWNSTREAM  
34  RUN-OFF  
35  IMPOUNDED

POINT LOCATION  
2,155 . 200 FT. (+)  E. (-)  W.  
541 . 742 FT. (+)  N. (-)  S.

FROM  GRID ORIGIN  BENCHMARK

DATE POINT ESTABLISHED  
09/28/77  
MON DAY YEAR

COMMENTS ABOUT SAMPLING POINTS:

Well depth - 30.6' Gradient from landfill - down gradient

Geologic formation of well screen - sand

Location of well seals/materials used - bentonite seal above well screen

WELL DESCRIPTION	REQUIRED SAMPLING (MG/L except as noted)		
	NO.	PARAMETERS	MONTHS OF REQUIRED SAMPLING
PIPE DIAMETER <u>2 . 0 0</u> INCHES	<input checked="" type="checkbox"/> 00410	ALKALINITY (AS CA CO <sub>3</sub> )	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00310	BOD (5 DAY)	1-2-3-4-5-6-7-8-9-10-11-12
PIPE TOP ELEVATION <u>806 . 0 0</u> FEET <input checked="" type="checkbox"/> MSL <input type="checkbox"/> SITE	<input type="checkbox"/> 00916	CALCIUM	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00307	CHLORIDES	1-2-3-4-5-6-7-8-9-10-11-12
GROUND SURFACE ELEVATION <u>802 . 7 0</u> FEET <input checked="" type="checkbox"/> MSL <input type="checkbox"/> SITE	<input type="checkbox"/> 00340	COD	1-2-3-4-5-6-7-8-9-10-11-12
TYPE OF CASING (✓ ONE)	<input checked="" type="checkbox"/> 00872	CONDUCTIVITY (SU)	1-2-3-4-5-6-7-8-9-10-11-12
<input checked="" type="checkbox"/> 1 PLASTIC <input type="checkbox"/> 2 STEEL	<input type="checkbox"/> 00277	COPPER (DISSOLVED)	1-2-3-4-5-6-7-8-9-10-11-12
COMMENTS ABOUT REQUIRED SAMPLING	<input checked="" type="checkbox"/> 00900	HARDNESS (AS CA CO <sub>3</sub> )	1-2-3-4-5-6-7-8-9-10-11-12
<u>Avg. vol. of water to be bailed:</u>	<input checked="" type="checkbox"/> 01046	IRON (DISSOLVED)	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00348	MAGNESIUM	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00620	NITRATES (AS NO <sub>3</sub> )	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00640	NITROGEN (TOTAL INORGANIC N)	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00400	PH (SU)	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00129	PHENOLS	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00929	SOLIUM	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00945	SULFATES	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00360	TOTAL DIS. SOLIDS	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00842	WATER ELEVATION (FT. MSL)	1-2-3-4-5-6-7-8-9-10-11-12
	<input type="checkbox"/> 00275	ZINC (DISSOLVED)	1-2-3-4-5-6-7-8-9-10-11-12
	NO.	PARAMETERS (OTHERS)	MONTHS
<u>Groundwater flow - westerly</u>	<input checked="" type="checkbox"/> 01022	Boran	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/>	Color	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/>	Odor	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/>	Turbidity	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01002	Arsenic	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01007	Barium	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00312	Cadmium	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00273	Chromium	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00240	Lead	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00126	Mercury	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 00270	Selenium	1-2-3-4-5-6-7-8-9-10-11-12
	<input checked="" type="checkbox"/> 01077	Silver	1-2-3-4-5-6-7-8-9-10-11-12



SUBSTATION

ASH POND  
DISCHARGE  
DRAINAGE DITCH  
ERR  
B\*34A&B

medium to  
coarse sand  
and gravel

fill-  
fine to  
medium  
sand

fine to  
medium  
sand

dstone

Scale:

Horizontal 1" = 100'


Vertical 1" = 10'

No legend available

Warzyn Engineering Inc.  
Geologic Cross Sections

Drawing No. C7134-11

Date 1-20-78



TYPICAL MONITORING WELL DETAIL

NOT TO SCALE

Date - 1-20-78 Drawing No. 7134-9

Warzyn Engineering Inc.

WELL DETAIL INFORMATION SHEET

JOB NO. C 7134

BORING NO. MW-84A


DATE 10/5/83

Elev. 814.57 Steel  
Elev. 814.32 PVC CHIEF JS

LOCATION WP&L-Columbia Generating Station

Elev. 813.4

All depth measurements of well detail assumed to be from ground surface unless otherwise indicated.



- ① DEPTH TO BOTTOM OF BOREHOLE  
37 FEET
- ② LENGTH OF WELL POINT, WELL SCREEN, OR SLOTTED PIPE 10 FEET
- ③ TOTAL LENGTH OF SOLID PIPE 29 FEET @ 2 IN. DIAMETER
- ④ HEIGHT OF WELL CASING ABOVE GROUND 2 FEET
- ⑤ TYPE OF FILTER MATERIAL AROUND WELL POINT OR SLOTTED PIPE Flint Sand
- ⑥ DEPTH OF LOWER OR BOTTOM SEAL 3 FEET
- ⑦ DEPTH OF UPPER OR TOP SEAL 0 FEET
- ⑧ TYPE OF BACKFILL Spoils (Sand)
- ⑨ PROTECTIVE CASING YES NO  
HEIGHT ABOVE GROUND 2'
- LOCKING CAP YES NO
- ⑩ CONCRETE CAP YES NO

WATER LEVEL CHECKS

\* From top of casing, if protective casing higher take measurement from top of protective casing.

BORING #	DATE	TIME	DEPTH TO WATER	REMARKS
84A	10/7/83	3 days	21'	
84B	10/7/83	3 days	19'6"	






Route To: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name <b>WPL-Columbia</b> SCS#: 25215135.00		License/Permit/Monitoring Number		Boring Number <b>MW-301</b>	
Boring Drilled By: Name of crew chief (first, last) and Firm <b>Kevin Durst Badger State Drilling</b>			Date Drilling Started <b>11/11/2015</b>	Date Drilling Completed <b>11/11/2015</b>	Drilling Method <b>hollow stem auger</b>
WI Unique Well No. <b>VY701</b>	DNR Well ID No.	Common Well Name	Final Static Water Level <b>Feet</b>	Surface Elevation <b>803.69 Feet</b>	Borehole Diameter <b>8.5 in.</b>
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/> ) or Boring Location <input checked="" type="checkbox"/>			Local Grid Location		
State Plane <b>541562.2 N, 2025001.0 E</b> S/C/N			Lat <b>° ' "</b>	<input type="checkbox"/> N <input type="checkbox"/> E	
1/4 of 1/4 of Section <b>27, T 12 N, R 9 E</b>			Long <b>° ' "</b>	<input type="checkbox"/> S <input type="checkbox"/> W	
Facility ID		County <b>Columbia</b>	County Code <b>11</b>	Civil Town/City/ or Village <b>Portage</b>	

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments			
									Pocket Penetration (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200				
S1	21	7 6 9 10	1 2	SILTY SAND, yellowish brown (10YR 5/6), fine to medium grained.													
S2	20	6 7 9 10	3 4	Same as above except, 10YR 5/4 (top section), 10YR 3/6 (bottom section), trace gravel.													
S3	22	7 6 9 6	5 6 7	Same as above except, 10YR 3/4 (bottom), 10YR 5/4 (top), trace little roots and sticks, trace gravel.	SM												
S4	21	4 5 6 5	8 9	Same as above except, 10YR (top), 10YR 4/6 (bottom), trace clay at bottom.													
S5	18	2 2 4 5	10 11	Same as above except, fine to coarse grained sand, little gravel, trace clay in top half, 10YR 3/6.													
S6	20	2 3 3 3	12 13 14	Same as above except, 10YR 6/8.													

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature 	Firm <b>SCS Engineers</b> 2830 Dairy Drive Madison, WI 53711	Tel: (608) 224-2830 Fax:
--	---	-----------------------------

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.

Boring Number **MW-301**

Use only as an attachment to Form 4400-122.

Page **2** of **2**

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	U S C S	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments							
Number and Type	Length Att. & Recovered (in)								Pocket Penetration (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200								
S7	20	5 4 4 3	16 17	SILTY SAND, yellowish brown (10YR 5/6), fine to medium grained.																	
S8	20	2 4 4 5	18 19 20																	M	
S9	23	4 4 3 6	21 22																	SM	W
S10	21	3 2 4 10	23 24 25																	W	
			26 27 28	End of boring at 28 ft bgs.																	



Route To: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name <b>WPL-Columbia</b>		SCS#: 25215135.00		License/Permit/Monitoring Number	Boring Number <b>MW-302</b>	
Boring Drilled By: Name of crew chief (first, last) and Firm <b>Kevin Durst Badger State Drilling</b>				Date Drilling Started <b>11/11/2015</b>	Date Drilling Completed <b>11/12/2015</b>	Drilling Method <b>hollow stem auger</b>
WI Unique Well No. <b>VY702</b>	DNR Well ID No.	Common Well Name		Final Static Water Level <b>Feet</b>	Surface Elevation <b>809.93 Feet</b>	Borehole Diameter <b>8.5 in.</b>
Local Grid Origin <input type="checkbox"/> (estimated: <input type="checkbox"/> ) or Boring Location <input checked="" type="checkbox"/> State Pla <b>541964.7 N, 2123849 E</b> S/C/N				Local Grid Location		
1/4 of		1/4 of Section <b>27, T 12 N, R 9 E</b>		Lat _____ "	Long _____ "	Feet <input type="checkbox"/> N <input type="checkbox"/> E Feet <input type="checkbox"/> S <input type="checkbox"/> W
Facility ID		County <b>Columbia</b>	County Code <b>11</b>	Civil Town/City/ or Village <b>Portage</b>		

Sample Number and Type	Length Att. & Recovered (in)	Blow Counts	Depth in Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	USCS	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments			
									Pocket Penetration (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200				
S1	12	10 13 17 16	1 2	SILTY SAND, fine to medium grained, trace gravel, 10YR 5/6.													
S2	12	10 12 8 6	4 5	Same as above except, large gravel at bottom, trace to little gravel.													
S3	20	2 4 4 5	7	Same as above except, 10YR 4/6.	SM												
S4	23	3 3 4 5	9 10	Same as above except, 10YR 5/8.													
S5	20	3 3 3 4	12	Same as above except, 10YR 6/6.													
S6	20	3 4 4 7	14 15	POORLY GRADED SAND, 10YR 6/6.	SP												

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature <i>[Signature]</i> for Zach Watson	Firm <b>SCS Engineers</b> 2830 Dairy Drive Madison, WI 53711	Tel: (608) 224-2830 Fax:
---	--	-----------------------------

This form is authorized by Chapters 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats. Completion of this form is mandatory. Failure to file this form may result in forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on this form is not intended to be used for any other purpose. NOTE: See instructions for more information, including where the completed form should be sent.



Boring Number **MW-302**

Use only as an attachment to Form 4400-122.

Page **2** of **2**

Sample		Blow Counts	Depth In Feet	Soil/Rock Description And Geologic Origin For Each Major Unit	U S C S	Graphic Log	Well Diagram	PID/FID	Soil Properties					RQD/ Comments
Number and Type	Length Att. & Recovered (in)								Pocket Penetration (tsf)	Moisture Content	Liquid Limit	Plasticity Index	P 200	
S7	20	6 8 10 12	16 17	POORLY GRADED SAND, light tan 10YR 8/3.						M				
S8	20	5 6 8 8	19 20		SP					M				
S9	19	3 3 3 2	21 22							M				
S10	20	3 3 8 8	23 24 25	SILTY SAND, 10YR 5/6. POORLY GRADED SAND, 10YR 8/3.	SM					W				
S11	23	5 9 12 12	26 27	Same as above except, light tan 10YR 6/6.						W				
			28 29 30 31 32 33 34 35		SP									
			35	End of boring at 35 ft bgs.										

Route to: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name Alliant-Columbia	County Name Columbia	Well Name MW-301	
Facility License, Permit or Monitoring Number	County Code 11	Wis. Unique Well Number VY701	DNR Well ID Number

1. Can this well be purged dry?  Yes  No

2. Well development method

- surged with bailer and bailed  4 1
- surged with bailer and pumped  6 1
- surged with block and bailed  4 2
- surged with block and pumped  6 2
- surged with block, bailed and pumped  7 0
- compressed air  2 0
- bailed only  1 0
- pumped only  5 1
- pumped slowly  5 0
- Other

3. Time spent developing well \_\_\_\_\_ 120 min.

4. Depth of well (from top of well casing) \_\_\_\_\_ 29 . 4 ft.

5. Inside diameter of well \_\_\_\_\_ 2 . 00 in.

6. Volume of water in filter pack and well casing \_\_\_\_\_ 7 . 6 gal.

7. Volume of water removed from well \_\_\_\_\_ 84 . 0 gal.

8. Volume of water added (if any) \_\_\_\_\_ gal.

9. Source of water added \_\_\_\_\_

10. Analysis performed on water added?  Yes  No  
(If yes, attach results)

	Before Development	After Development
11. Depth to Water (from top of well casing)	a. _____ 21 . 72 ft.	_____ 21 . 77 ft.
Date	b. _____ 12 / _____ 02 / _____ 2015	_____ 12 / _____ 02 / _____ 2015
Time	c. _____ 08 : 30 <input checked="" type="checkbox"/> a.m. _____ p.m.	_____ 10 : 30 <input checked="" type="checkbox"/> a.m. _____ p.m.
12. Sediment in well bottom	_____ 0 . inches	_____ 0 . inches
13. Water clarity	Clear <input type="checkbox"/> 1 0 Turbid <input checked="" type="checkbox"/> 1 5 (Describe)	Clear <input checked="" type="checkbox"/> 2 0 Turbid <input type="checkbox"/> 2 5 (Describe)

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids \_\_\_\_\_ mg/l \_\_\_\_\_ mg/l

15. COD \_\_\_\_\_ mg/l \_\_\_\_\_ mg/l

16. Well developed by: Name (first, last) and Firm  
First Name: Gary Last Name: Sterkel  
Firm: SCS ENGINEERS

17. Additional comments on development:

Name and Address of Facility Contact /Owner/Responsible Party

First Name: Nate Last Name: Sievers

Facility/Firm: Wisconsin Power and Light

Street: W8375 Murray Rd.

City/State/Zip: Pardeville, WI 53954

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: *[Handwritten Signature]* for Gary Sterkel

Print Name: Gary Sterkel

Firm: SCS ENGINEERS

NOTE: See instructions for more information including a list of county codes and well type codes.

Route to: Watershed/Wastewater  Waste Management   
Remediation/Redevelopment  Other

Facility/Project Name Alliant - Columbia	County Name Columbia	Well Name MW-302	
Facility License, Permit or Monitoring Number	County Code 11	Wis. Unique Well Number VY702	DNR Well ID Number

1. Can this well be purged dry?  Yes  No
2. Well development method
- surged with bailer and bailed  4 1
  - surged with bailer and pumped  6 1
  - surged with block and bailed  4 2
  - surged with block and pumped  6 2
  - surged with block, bailed and pumped  7 0
  - compressed air  2 0
  - bailed only  1 0
  - pumped only  5 1
  - pumped slowly  5 0
  - Other
3. Time spent developing well \_\_\_\_\_ 120 min.
4. Depth of well (from top of well casing) \_\_\_\_\_ 33 . 6 ft.
5. Inside diameter of well \_\_\_\_\_ 2 . 00 in.
6. Volume of water in filter pack and well casing \_\_\_\_\_ 5 . 4 gal.
7. Volume of water removed from well \_\_\_\_\_ 60 . 0 gal.
8. Volume of water added (if any) \_\_\_\_\_ gal.
9. Source of water added \_\_\_\_\_
10. Analysis performed on water added?  Yes  No  
(If yes, attach results)

	Before Development	After Development
11. Depth to Water (from top of well casing)	a. _____ 28 . 37 ft.	_____ 28 . 41 ft.
Date	b. _____ 12 / _____ 02 / _____ 2015	_____ 12 / _____ 02 / _____ 2015
Time	c. _____ 02 : 00 <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.	_____ 04 : 00 <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.
12. Sediment in well bottom	_____ 0 . inches	_____ 0 . inches
13. Water clarity	Clear <input type="checkbox"/> 1 0 Turbid <input checked="" type="checkbox"/> 1 5 (Describe)	Clear <input checked="" type="checkbox"/> 2 0 Turbid <input type="checkbox"/> 2 5 (Describe)
Fill in if drilling fluids were used and well is at solid waste facility:		
14. Total suspended solids	_____ mg/l	_____ mg/l
15. COD	_____ mg/l	_____ mg/l
16. Well developed by: Name (first, last) and Firm		
First Name: Gary	Last Name: Sterkel	
Firm: SCS ENGINEERS		

17. Additional comments on development:

Name and Address of Facility Contact /Owner/Responsible Party

First Name: Nate Last Name: Sievers  
Name: \_\_\_\_\_ Name: \_\_\_\_\_

Facility/Firm: Wisconsin Power and Light

Street: W8375 Murray Rd.

City/State/Zip: Pardeeville, WI 53954

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: *Gary Sterkel* for SCS.

Print Name: Gary Sterkel

Firm: SCS ENGINEERS

NOTE: See instructions for more information including a list of county codes and well type codes.



State of Wisconsin  
Department of Natural Resources

Route to:  Watershed/Wastewater  Waste Management   
 Remediation/Redevelopment  Other

MONITORING WELL CONSTRUCTION  
Form 4400-113A Rev. 7-98

Facility/Project Name WPL-Columbia	Local Grid Location of Well _____ ft. <input type="checkbox"/> N. _____ ft. <input type="checkbox"/> E. _____ ft. <input type="checkbox"/> S. _____ ft. <input type="checkbox"/> W.	Well Name MW-301
Facility License, Permit or Monitoring No.	Local Grid Origin _____ (estimated: <input type="checkbox"/> ) or Well Location _____ Lat. _____ " Long. _____ or _____	Wis. Unique Well No. <u>VY701</u> DNR Well ID No. _____
Facility ID	St. Plane <u>541562.2</u> ft. N, <u>2125001</u> ft. E. S/C/N	Date Well Installed <u>11</u> / <u>11</u> / <u>2015</u> m m d d y y y y
Type of Well Well Code <u>11</u> / MW	Section Location of Waste/Source SW <u>1/4</u> of SE <u>1/4</u> of Sec. <u>27</u> , T. <u>12</u> N, R. <u>9</u> <input checked="" type="checkbox"/> E <input type="checkbox"/> W	Well Installed By: Name (first, last) and Firm <u>Kevin Duerst</u> <u>Badger State Drilling</u>
Distance from Waste/Source _____ ft.	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	Gov. Lot Number _____

A. Protective pipe, top elevation <u>807</u> <u>16</u> ft. MSL	1. Cap and lock? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
B. Well casing, top elevation <u>806</u> <u>89</u> ft. MSL	2. Protective cover pipe: a. Inside diameter: <u>6</u> in. b. Length: <u>5</u> ft. c. Material: Steel <input checked="" type="checkbox"/> 04 Other <input type="checkbox"/>
C. Land surface elevation <u>803</u> <u>69</u> ft. MSL	d. Additional protection? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No If yes, describe: <u>bumper posts</u>
D. Surface seal, bottom <u>791</u> <u>69</u> ft. MSL or <u>12</u> ft.	3. Surface seal: Bentonite <input checked="" type="checkbox"/> 30 Concrete <input type="checkbox"/> 01 Other <input type="checkbox"/>
12. USCS classification of soil near screen: GP <input type="checkbox"/> GM <input type="checkbox"/> GC <input type="checkbox"/> GW <input type="checkbox"/> SW <input type="checkbox"/> SP <input type="checkbox"/> SM <input checked="" type="checkbox"/> SC <input type="checkbox"/> ML <input type="checkbox"/> MH <input type="checkbox"/> CL <input type="checkbox"/> CH <input type="checkbox"/> Bedrock <input type="checkbox"/>	4. Material between well casing and protective pipe: Bentonite <input checked="" type="checkbox"/> 30 <u>Bentonite to grade, sand above</u> Other <input type="checkbox"/>
13. Sieve analysis performed? <input type="checkbox"/> Yes <input type="checkbox"/> No	5. Annular space seal: a. Granular/Chipped Bentonite <input type="checkbox"/> 33 b. _____ Lbs/gal mud weight . . . Bentonite-sand slurry <input type="checkbox"/> 35 c. _____ Lbs/gal mud weight . . . . . Bentonite slurry <input type="checkbox"/> 31 d. _____ % Bentonite . . . . . Bentonite-cement grout <input type="checkbox"/> 50 e. _____ Ft <sup>3</sup> volume added for any of the above
14. Drilling method used: Rotary <input type="checkbox"/> 50 Hollow Stem Auger <input checked="" type="checkbox"/> 41 Other <input type="checkbox"/>	f. How installed: Tremie <input type="checkbox"/> 01 Tremie pumped <input type="checkbox"/> 02 Gravity <input type="checkbox"/> 08
15. Drilling fluid used: Water <input type="checkbox"/> 02 Air <input type="checkbox"/> 01 Drilling Mud <input type="checkbox"/> 03 None <input checked="" type="checkbox"/> 99	6. Bentonite seal: a. Bentonite granules <input type="checkbox"/> 33 b. <input type="checkbox"/> 1/4 in. <input checked="" type="checkbox"/> 3/8 in. <input type="checkbox"/> 1/2 in. Bentonite chips <input checked="" type="checkbox"/> 32 c. <u>4</u> ft <sup>3</sup> Other <input type="checkbox"/>
16. Drilling additives used? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7. Fine sand material: Manufacturer, product name & mesh size a. <u>RW Sidley Inc. #7</u> <input type="checkbox"/> b. Volume added <u>0.5</u> ft <sup>3</sup>
Describe _____	8. Filter pack material: Manufacturer, product name & mesh size a. <u>RW Sidley #5</u> <input type="checkbox"/> b. Volume added <u>2</u> ft <sup>3</sup>
17. Source of water (attach analysis, if required): _____	9. Well casing: Flush threaded PVC schedule 40 <input checked="" type="checkbox"/> 23 Flush threaded PVC schedule 80 <input type="checkbox"/> 24 Other <input type="checkbox"/>
E. Bentonite seal, top <u>803</u> <u>69</u> ft. MSL or <u>0</u> ft.	10. Screen material: <u>PVC</u> a. Screen type: Factory cut <input checked="" type="checkbox"/> 11 Continuous slot <input type="checkbox"/> 01 Other <input type="checkbox"/>
F. Fine sand, top <u>791</u> <u>69</u> ft. MSL or <u>12</u> ft.	b. Manufacturer <u>Johnson</u> c. Slot size: <u>0.01</u> in. d. Slotted length: <u>10</u> ft.
G. Filter pack, top <u>789</u> <u>69</u> ft. MSL or <u>14</u> ft.	11. Backfill material (below filter pack): None <input type="checkbox"/> 14 <u>Native</u> Other <input checked="" type="checkbox"/>
H. Screen joint, top <u>787</u> <u>69</u> ft. MSL or <u>16</u> ft.	
I. Well bottom <u>777</u> <u>69</u> ft. MSL or <u>26</u> ft.	
J. Filter pack, bottom <u>776</u> <u>69</u> ft. MSL or <u>27</u> ft.	
K. Borehole, bottom <u>775</u> <u>69</u> ft. MSL or <u>28</u> ft.	
L. Borehole, diameter <u>8.5</u> in.	
M. O.D. well casing <u>2.4</u> in.	
N. I.D. well casing <u>2.0</u> in.	

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature [Signature] Firm SCS ENGINEERS, 2830 Dairy Drive, Madison, WI 53718-6751

Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.



State of Wisconsin  
Department of Natural Resources

Route to:  Watershed/Wastewater  Waste Management   
 Remediation/Redevelopment  Other

MONITORING WELL CONSTRUCTION  
Form 4400-113A Rev. 7-98

Facility/Project Name WPL-Columbia	Local Grid Location of Well _____ ft. <input type="checkbox"/> N. _____ ft. <input type="checkbox"/> E. _____ ft. <input type="checkbox"/> S. _____ ft. <input type="checkbox"/> W.	Well Name MW-302
Facility License, Permit or Monitoring No.	Local Grid Origin _____ (estimated: _____) or Well Location _____ Lat. _____ "Long. _____ or _____	Wis. Unique Well No. <u>VY702</u> DNR Well ID No. _____
Facility ID _____	St. Plane <u>541964.7</u> ft. N, <u>2123849</u> ft. E. S/C/N _____	Date Well Installed <u>11/12/2015</u> m m d d y y y y
Type of Well Well Code <u>11</u> / MW	Section Location of Waste/Source <u>SE</u> 1/4 of <u>SW</u> 1/4 of Sec. <u>27</u> , T. <u>12</u> N, R. <u>9</u> <input checked="" type="checkbox"/> E <input type="checkbox"/> W	Well Installed By: Name (first, last) and Firm <u>Kevin Duerst</u> <u>Badger State Drilling</u>
Distance from Waste/Source _____ ft.	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	
Enf. Stds. Apply <input type="checkbox"/>	Gov. Lot Number _____	


A. Protective pipe, top elevation <u>813.19</u> ft. MSL	1. Cap and lock? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
B. Well casing, top elevation <u>813.00</u> ft. MSL	2. Protective cover pipe: a. Inside diameter: <u>6</u> in. b. Length: <u>5</u> ft. c. Material: <u>steel</u> Steel <input type="checkbox"/> 04 Other <input type="checkbox"/>
C. Land surface elevation <u>809.93</u> ft. MSL	d. Additional protection? <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, describe: <u>yes, bumper posts</u>
D. Surface seal, bottom <u>793.53</u> ft. MSL or <u>16.4</u> ft.	3. Surface seal: <u>Bentonite</u> <input checked="" type="checkbox"/> 30 Concrete <input type="checkbox"/> 01 Other <input type="checkbox"/>
12. USCS classification of soil near screen: GP <input type="checkbox"/> GM <input type="checkbox"/> GC <input type="checkbox"/> GW <input type="checkbox"/> SW <input type="checkbox"/> SP <input checked="" type="checkbox"/> SM <input type="checkbox"/> SC <input type="checkbox"/> ML <input type="checkbox"/> MH <input type="checkbox"/> CL <input type="checkbox"/> CH <input type="checkbox"/> Bedrock <input type="checkbox"/>	4. Material between well casing and protective pipe: <u>Bentonite to grade, sand above</u> Bentonite <input checked="" type="checkbox"/> 30 Other <input type="checkbox"/>
13. Sieve analysis performed? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	5. Annular space seal: a. Granular/Chipped Bentonite <input type="checkbox"/> 33 b. _____ Lbs/gal mud weight . . . Bentonite-sand slurry <input type="checkbox"/> 35 c. _____ Lbs/gal mud weight . . . . . Bentonite slurry <input type="checkbox"/> 31 d. _____ % Bentonite . . . . . Bentonite-cement grout <input type="checkbox"/> 50 e. _____ Ft <sup>3</sup> volume added for any of the above
14. Drilling method used: Rotary <input type="checkbox"/> 50 Hollow Stem Auger <input checked="" type="checkbox"/> 41 Other <input type="checkbox"/>	f. How installed: Tremie <input type="checkbox"/> 01 Tremie pumped <input type="checkbox"/> 02 Gravity <input type="checkbox"/> 08
15. Drilling fluid used: Water <input type="checkbox"/> 02 Air <input type="checkbox"/> 01 Drilling Mud <input type="checkbox"/> 03 None <input checked="" type="checkbox"/> 99	6. Bentonite seal: a. Bentonite granules <input type="checkbox"/> 33 b. <input type="checkbox"/> 1/4 in. <input checked="" type="checkbox"/> 3/8 in. <input type="checkbox"/> 1/2 in. Bentonite chips <input type="checkbox"/> 32 c. <u>4.7</u> ft <sup>3</sup> Other <input type="checkbox"/>
16. Drilling additives used? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7. Fine sand material: Manufacturer, product name & mesh size a. <u>RW Sidley Inc. #7</u> <input type="checkbox"/>
Describe _____	b. Volume added <u>1</u> ft <sup>3</sup>
17. Source of water (attach analysis, if required): _____	8. Filter pack material: Manufacturer, product name & mesh size a. <u>RW Sidley #5</u> <input type="checkbox"/>
E. Bentonite seal, top <u>809.93</u> ft. MSL or <u>0</u> ft.	b. Volume added <u>2.5</u> ft <sup>3</sup>
F. Fine sand, top <u>793.53</u> ft. MSL or <u>16.4</u> ft.	9. Well casing: Flush threaded PVC schedule 40 <input checked="" type="checkbox"/> 23 Flush threaded PVC schedule 80 <input type="checkbox"/> 24 Other <input type="checkbox"/>
G. Filter pack, top <u>791.53</u> ft. MSL or <u>18.4</u> ft.	10. Screen material: <u>PVC</u>
H. Screen joint, top <u>789.53</u> ft. MSL or <u>20.4</u> ft.	a. Screen type: Factory cut <input checked="" type="checkbox"/> 11 Continuous slot <input type="checkbox"/> 01 Other <input type="checkbox"/>
I. Well bottom <u>779.53</u> ft. MSL or <u>30.4</u> ft.	b. Manufacturer <u>Johnson</u>
J. Filter pack, bottom <u>776.93</u> ft. MSL or <u>33</u> ft.	c. Slot size: <u>0.01</u> in.
K. Borehole, bottom <u>776.93</u> ft. MSL or <u>33</u> ft.	d. Slotted length: <u>10</u> ft.
L. Borehole, diameter <u>8.5</u> in.	11. Backfill material (below filter pack): <u>Native</u> None <input type="checkbox"/> 14 Other <input checked="" type="checkbox"/>
M. O.D. well casing <u>2 3/8</u> in.	
N. I.D. well casing <u>2</u> in.	

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature [Signature] Firm SCS ENGINEERS, 2830 Dairy Drive, Madison, WI 53718-6751

Please complete both Forms 4400-113A and 4400-113B and return them to the appropriate DNR office and bureau. Completion of these reports is required by chs. 160, 281, 283, 289, 291, 292, 293, 295, and 299, Wis. Stats., and ch. NR 141, Wis. Adm. Code. In accordance with chs. 281, 289, 291, 292, 293, 295, and 299, Wis. Stats., failure to file these forms may result in a forfeiture of between \$10 and \$25,000, or imprisonment for up to one year, depending on the program and conduct involved. Personally identifiable information on these forms is not intended to be used for any other purpose. NOTE: See the instructions for more information, including where the completed forms should be sent.





Appendix C  
Laboratory Reports

December 02, 2022

Meghan Blodgett  
SCS ENGINEERS  
2830 Dairy Drive  
Madison, WI 53718

RE: Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on October 29, 2022. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay
- Pace Analytical Services - Greensburg

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky  
dan.milewsky@pacelabs.com  
(920)469-2436  
Project Manager

Enclosures

cc: Matt Bizjack, Alliant Energy  
Sherren Clark, SCS Engineers  
Jenny Coughlin, Alliant Energy  
Tom Karwoski, SCS ENGINEERS  
Nicole Kron, SCS ENGINEERS  
Ryan Matzuk, SCS Engineers  
Jeff Maxted, ALLIANT ENERGY  
Marc Morandi, ALLIANT ENERGY



## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## CERTIFICATIONS

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

---

### **Pace Analytical Services Pennsylvania**

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601  
ANAB DOD-ELAP Rad Accreditation #: L2417  
Alabama Certification #: 41590  
Arizona Certification #: AZ0734  
Arkansas Certification  
California Certification #: 04222CA  
Colorado Certification #: PA01547  
Connecticut Certification #: PH-0694  
Delaware Certification  
EPA Region 4 DW Rad  
Florida/TNI Certification #: E87683  
Georgia Certification #: C040  
Florida: Cert E871149 SEKS WET  
Guam Certification  
Hawaii Certification  
Idaho Certification  
Illinois Certification  
Indiana Certification  
Iowa Certification #: 391  
Kansas/TNI Certification #: E-10358  
Kentucky Certification #: KY90133  
KY WW Permit #: KY0098221  
KY WW Permit #: KY0000221  
Louisiana DHH/TNI Certification #: LA180012  
Louisiana DEQ/TNI Certification #: 4086  
Maine Certification #: 2017020  
Maryland Certification #: 308  
Massachusetts Certification #: M-PA1457  
Michigan/PADEP Certification #: 9991

Missouri Certification #: 235  
Montana Certification #: Cert0082  
Nebraska Certification #: NE-OS-29-14  
Nevada Certification #: PA014572018-1  
New Hampshire/TNI Certification #: 297617  
New Jersey/TNI Certification #: PA051  
New Mexico Certification #: PA01457  
New York/TNI Certification #: 10888  
North Carolina Certification #: 42706  
North Dakota Certification #: R-190  
Ohio EPA Rad Approval: #41249  
Oregon/TNI Certification #: PA200002-010  
Pennsylvania/TNI Certification #: 65-00282  
Puerto Rico Certification #: PA01457  
Rhode Island Certification #: 65-00282  
South Dakota Certification  
Tennessee Certification #: 02867  
Texas/TNI Certification #: T104704188-17-3  
Utah/TNI Certification #: PA014572017-9  
USDA Soil Permit #: P330-17-00091  
Vermont Dept. of Health: ID# VT-0282  
Virgin Island/PADEP Certification  
Virginia/VELAP Certification #: 460198  
Washington Certification #: C868  
West Virginia DEP Certification #: 143  
West Virginia DHHR Certification #: 9964C  
Wisconsin Approve List for Rad  
Wyoming Certification #: 8TMS-L

---

### **Pace Analytical Services Green Bay**

1241 Bellevue Street, Green Bay, WI 54302  
Florida/NELAP Certification #: E87948  
Illinois Certification #: 200050  
Kentucky UST Certification #: 82  
Louisiana Certification #: 04168  
Minnesota Certification #: 055-999-334  
New York Certification #: 12064  
North Dakota Certification #: R-150

South Carolina Certification #: 83006001  
Texas Certification #: T104704529-21-8  
Virginia VELAP Certification ID: 11873  
Wisconsin Certification #: 405132750  
Wisconsin DATCP Certification #: 105-444  
USDA Soil Permit #: P330-21-00008  
Federal Fish & Wildlife Permit #: 51774A

---

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## SAMPLE SUMMARY

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40253965001	MW-301	Water	10/27/22 16:35	10/29/22 09:15
40253965002	MW-84A	Water	10/27/22 15:25	10/29/22 09:15

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### SAMPLE ANALYTE COUNT

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
40253965001	MW-301	EPA 6020B	KXS	14	PASI-G
		EPA 7470	AJT	1	PASI-G
			JXA	7	PASI-G
		EPA 903.1	JDZ	1	PASI-PA
		EPA 904.0	ZPC	1	PASI-PA
		Total Radium Calculation	JAL	1	PASI-PA
		SM 2540C	SRK	1	PASI-G
		EPA 9040	YER	1	PASI-G
		EPA 300.0	HMB	3	PASI-G
		40253965002	MW-84A	EPA 6020B	KXS
EPA 7470	AJT			1	PASI-G
	JXA			7	PASI-G
EPA 903.1	JDZ			1	PASI-PA
EPA 904.0	ZPC			1	PASI-PA
Total Radium Calculation	JAL			1	PASI-PA
SM 2540C	SRK			1	PASI-G
EPA 9040	YER			1	PASI-G
EPA 300.0	HMB			3	PASI-G

PASI-G = Pace Analytical Services - Green Bay  
PASI-PA = Pace Analytical Services - Greensburg

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

**Sample: MW-301**      **Lab ID: 40253965001**      Collected: 10/27/22 16:35      Received: 10/29/22 09:15      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Antimony	<0.15	ug/L	1.0	0.15	1	11/18/22 06:38	11/30/22 11:56	7440-36-0	
Arsenic	0.30J	ug/L	1.0	0.28	1	11/18/22 06:38	11/30/22 11:56	7440-38-2	
Barium	7.5	ug/L	2.3	0.70	1	11/18/22 06:38	12/01/22 17:45	7440-39-3	
Beryllium	<0.25	ug/L	1.0	0.25	1	11/18/22 06:38	12/01/22 17:45	7440-41-7	
Boron	37.5	ug/L	10.0	3.0	1	11/18/22 06:38	11/30/22 11:56	7440-42-8	
Cadmium	<0.15	ug/L	1.0	0.15	1	11/18/22 06:38	11/30/22 11:56	7440-43-9	
Calcium	62800	ug/L	2540	762	10	11/18/22 06:38	11/30/22 12:55	7440-70-2	P6
Chromium	<1.0	ug/L	3.4	1.0	1	11/18/22 06:38	11/30/22 11:56	7440-47-3	
Cobalt	0.46J	ug/L	1.0	0.12	1	11/18/22 06:38	11/30/22 11:56	7440-48-4	B
Lead	<0.24	ug/L	1.0	0.24	1	11/18/22 06:38	11/30/22 11:56	7439-92-1	
Lithium	0.37J	ug/L	1.0	0.22	1	11/18/22 06:38	11/30/22 11:56	7439-93-2	
Molybdenum	<0.44	ug/L	1.5	0.44	1	11/18/22 06:38	11/30/22 11:56	7439-98-7	
Selenium	<0.32	ug/L	1.1	0.32	1	11/18/22 06:38	11/30/22 11:56	7782-49-2	
Thallium	<0.14	ug/L	1.0	0.14	1	11/18/22 06:38	11/30/22 11:56	7440-28-0	
<b>7470 Mercury</b>									
Analytical Method: EPA 7470    Preparation Method: EPA 7470 Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	11/03/22 07:25	11/04/22 08:00	7439-97-6	
<b>Field Data</b>									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	6.80	Std. Units			1		10/27/22 16:35		
Field Specific Conductance	507.5	umhos/cm			1		10/27/22 16:35		
Oxygen, Dissolved	0.10	mg/L			1		10/27/22 16:35	7782-44-7	
REDOX	80.9	mV			1		10/27/22 16:35		
Turbidity	0.00	NTU			1		10/27/22 16:35		
Static Water Level	784.91	feet			1		10/27/22 16:35		
Temperature, Water (C)	10.8	deg C			1		10/27/22 16:35		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	282	mg/L	20.0	8.7	1		11/01/22 11:31		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.1	Std. Units	0.10	0.010	1		11/03/22 13:55		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	2.3	mg/L	2.0	0.43	1		11/12/22 13:03	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		11/14/22 12:02	16984-48-8	M0
Sulfate	11.6	mg/L	2.0	0.44	1		11/12/22 13:03	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

**Sample: MW-84A**      **Lab ID: 40253965002**      Collected: 10/27/22 15:25      Received: 10/29/22 09:15      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Antimony	0.29J	ug/L	1.0	0.15	1	11/18/22 06:38	11/30/22 13:25	7440-36-0	B
Arsenic	0.72J	ug/L	1.0	0.28	1	11/18/22 06:38	11/30/22 13:25	7440-38-2	
Barium	13.7	ug/L	2.3	0.70	1	11/18/22 06:38	12/01/22 18:14	7440-39-3	
Beryllium	<0.25	ug/L	1.0	0.25	1	11/18/22 06:38	12/01/22 18:14	7440-41-7	
Boron	12.2	ug/L	10.0	3.0	1	11/18/22 06:38	11/30/22 13:25	7440-42-8	
Cadmium	0.22J	ug/L	1.0	0.15	1	11/18/22 06:38	11/30/22 13:25	7440-43-9	B
Calcium	78400	ug/L	254	76.2	1	11/18/22 06:38	11/30/22 13:25	7440-70-2	
Chromium	2.2J	ug/L	3.4	1.0	1	11/18/22 06:38	11/30/22 13:25	7440-47-3	
Cobalt	0.25J	ug/L	1.0	0.12	1	11/18/22 06:38	11/30/22 13:25	7440-48-4	B
Lead	0.26J	ug/L	1.0	0.24	1	11/18/22 06:38	11/30/22 13:25	7439-92-1	
Lithium	0.41J	ug/L	1.0	0.22	1	11/18/22 06:38	11/30/22 13:25	7439-93-2	
Molybdenum	<0.44	ug/L	1.5	0.44	1	11/18/22 06:38	11/30/22 13:25	7439-98-7	
Selenium	<0.32	ug/L	1.1	0.32	1	11/18/22 06:38	11/30/22 13:25	7782-49-2	
Thallium	0.33J	ug/L	1.0	0.14	1	11/18/22 06:38	11/30/22 13:25	7440-28-0	B
<b>7470 Mercury</b>									
Analytical Method: EPA 7470    Preparation Method: EPA 7470 Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	11/03/22 07:25	11/04/22 08:02	7439-97-6	
<b>Field Data</b>									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	7.31	Std. Units			1		10/27/22 15:25		
Field Specific Conductance	585.2	umhos/cm			1		10/27/22 15:25		
Oxygen, Dissolved	8.31	mg/L			1		10/27/22 15:25	7782-44-7	
REDOX	39.9	mV			1		10/27/22 15:25		
Turbidity	0.00	NTU			1		10/27/22 15:25		
Static Water Level	784.57	feet			1		10/27/22 15:25		
Temperature, Water (C)	11.7	deg C			1		10/27/22 15:25		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	302	mg/L	20.0	8.7	1		11/01/22 11:32		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.4	Std. Units	0.10	0.010	1		11/03/22 13:56		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	3.4	mg/L	2.0	0.43	1		11/12/22 14:11	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		11/14/22 12:45	16984-48-8	
Sulfate	1.1J	mg/L	2.0	0.44	1		11/12/22 14:11	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

QC Batch: 430492      Analysis Method: EPA 7470  
QC Batch Method: EPA 7470      Analysis Description: 7470 Mercury  
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253965001, 40253965002

METHOD BLANK: 2479204      Matrix: Water

Associated Lab Samples: 40253965001, 40253965002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Mercury	ug/L	<0.066	0.20	11/04/22 07:30	

LABORATORY CONTROL SAMPLE: 2479205

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	ug/L	5	5.0	101	85-115	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2479206      2479207

Parameter	Units	40253959001		2479207		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result						
Mercury	ug/L	<0.066	5	5	5.0	4.8	100	95	85-115	5	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

QC Batch: 431884 Analysis Method: EPA 6020B  
QC Batch Method: EPA 3010A Analysis Description: 6020B MET  
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253965001, 40253965002

METHOD BLANK: 2487054 Matrix: Water

Associated Lab Samples: 40253965001, 40253965002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Antimony	ug/L	0.19J	1.0	11/30/22 12:41	
Arsenic	ug/L	<0.28	1.0	11/30/22 12:41	
Barium	ug/L	<0.70	2.3	12/01/22 17:30	
Beryllium	ug/L	<0.25	1.0	12/01/22 17:30	
Boron	ug/L	<3.0	10.0	11/30/22 12:41	
Cadmium	ug/L	0.20J	1.0	11/30/22 12:41	
Calcium	ug/L	<76.2	254	11/30/22 12:41	
Chromium	ug/L	<1.0	3.4	11/30/22 12:41	
Cobalt	ug/L	0.18J	1.0	11/30/22 12:41	
Lead	ug/L	<0.24	1.0	11/30/22 12:41	
Lithium	ug/L	<0.22	1.0	11/30/22 12:41	
Molybdenum	ug/L	<0.44	1.5	11/30/22 12:41	
Selenium	ug/L	<0.32	1.1	11/30/22 12:41	
Thallium	ug/L	0.18J	1.0	11/30/22 12:41	

LABORATORY CONTROL SAMPLE: 2487055

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	ug/L	250	270	108	80-120	
Arsenic	ug/L	250	261	104	80-120	
Barium	ug/L	250	242	97	80-120	
Beryllium	ug/L	250	262	105	80-120	
Boron	ug/L	250	253	101	80-120	
Cadmium	ug/L	250	264	105	80-120	
Calcium	ug/L	10000	10200	102	80-120	
Chromium	ug/L	250	254	102	80-120	
Cobalt	ug/L	250	249	99	80-120	
Lead	ug/L	250	259	104	80-120	
Lithium	ug/L	250	263	105	80-120	
Molybdenum	ug/L	250	255	102	80-120	
Selenium	ug/L	250	272	109	80-120	
Thallium	ug/L	250	259	104	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

Parameter	Units	MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2487056		2487056		2487057		% Rec	% Rec	% Rec	Limits	RPD	Max RPD	Qual
		40253965001	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec							
Antimony	ug/L	<0.15	250	250	268	263	107	105	75-125	2	20			
Arsenic	ug/L	0.30J	250	250	260	260	104	104	75-125	0	20			
Barium	ug/L	7.5	250	250	250	245	97	95	75-125	2	20			
Beryllium	ug/L	<0.25	250	250	268	265	107	106	75-125	1	20			
Boron	ug/L	37.5	250	250	295	282	103	98	75-125	5	20			
Cadmium	ug/L	<0.15	250	250	259	254	104	102	75-125	2	20			
Calcium	ug/L	62800	10000	10000	72700	69600	99	69	75-125	4	20	P6		
Chromium	ug/L	<1.0	250	250	251	247	100	99	75-125	1	20			
Cobalt	ug/L	0.46J	250	250	247	244	99	97	75-125	1	20			
Lead	ug/L	<0.24	250	250	260	257	104	103	75-125	1	20			
Lithium	ug/L	0.37J	250	250	272	255	109	102	75-125	6	20			
Molybdenum	ug/L	<0.44	250	250	256	255	102	102	75-125	0	20			
Selenium	ug/L	<0.32	250	250	271	267	108	107	75-125	1	20			
Thallium	ug/L	<0.14	250	250	258	257	103	103	75-125	1	20			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

QC Batch: 430299

Analysis Method: SM 2540C

QC Batch Method: SM 2540C

Analysis Description: 2540C Total Dissolved Solids

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253965001, 40253965002

METHOD BLANK: 2477981

Matrix: Water

Associated Lab Samples: 40253965001, 40253965002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	11/01/22 11:27	

LABORATORY CONTROL SAMPLE: 2477982

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	585	546	93	80-120	

SAMPLE DUPLICATE: 2477983

Parameter	Units	40253952003 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	658	652	1	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

QC Batch: 430502

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253965001, 40253965002

SAMPLE DUPLICATE: 2479241

Parameter	Units	40253453001 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.0	7.0	0	20	H6

SAMPLE DUPLICATE: 2479545

Parameter	Units	40253825003 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.4	7.4	0	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

QC Batch: 430807	Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0	Analysis Description: 300.0 IC Anions
	Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253965001, 40253965002

METHOD BLANK: 2480961 Matrix: Water

Associated Lab Samples: 40253965001, 40253965002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	11/12/22 12:34	
Fluoride	mg/L	<0.095	0.32	11/14/22 11:33	
Sulfate	mg/L	<0.44	2.0	11/12/22 12:34	

LABORATORY CONTROL SAMPLE: 2480962

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	19.4	97	90-110	
Fluoride	mg/L	2	1.9	97	90-110	
Sulfate	mg/L	20	19.4	97	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2480963 2480964

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40253965001 Result	Spike Conc.	Spike Conc.	Result								
Chloride	mg/L	2.3	20	20	24.1	24.2	109	110	90-110	1	15		
Fluoride	mg/L	<0.095	2	2	2.5	2.4	123	121	90-110	2	15	M0	
Sulfate	mg/L	11.6	20	20	32.8	33.1	106	107	90-110	1	15		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

**Sample: MW-301**      **Lab ID: 40253965001**      Collected: 10/27/22 16:35      Received: 10/29/22 09:15      Matrix: Water  
PWS:      Site ID:      Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
	Pace Analytical Services - Greensburg					
Radium-226	EPA 903.1	<b>-0.169 ± 0.429 (0.940)</b> <b>C:NA T:90%</b>	pCi/L	11/22/22 13:34	13982-63-3	
	Pace Analytical Services - Greensburg					
Radium-228	EPA 904.0	<b>0.00292 ± 0.343 (0.793)</b> <b>C:79% T:90%</b>	pCi/L	11/16/22 15:01	15262-20-1	
	Pace Analytical Services - Greensburg					
Total Radium	Total Radium Calculation	<b>0.00292 ± 0.772 (1.73)</b>	pCi/L	11/22/22 17:11	7440-14-4	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

**Sample: MW-84A**      **Lab ID: 40253965002**      Collected: 10/27/22 15:25      Received: 10/29/22 09:15      Matrix: Water  
PWS:      Site ID:      Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
Pace Analytical Services - Greensburg						
Radium-226	EPA 903.1	<b>0.267 ± 0.279 (0.393)</b> <b>C:NA T:96%</b>	pCi/L	11/22/22 13:34	13982-63-3	
Pace Analytical Services - Greensburg						
Radium-228	EPA 904.0	<b>0.406 ± 0.346 (0.700)</b> <b>C:82% T:96%</b>	pCi/L	11/16/22 15:01	15262-20-1	
Pace Analytical Services - Greensburg						
Total Radium	Total Radium Calculation	<b>0.673 ± 0.625 (1.09)</b>	pCi/L	11/22/22 17:11	7440-14-4	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL - RADIOCHEMISTRY

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

QC Batch: 544795

Analysis Method: EPA 903.1

QC Batch Method: EPA 903.1

Analysis Description: 903.1 Radium-226

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40253965001, 40253965002

METHOD BLANK: 2644705

Matrix: Water

Associated Lab Samples: 40253965001, 40253965002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-226	0.113 ± 0.314 (0.610) C:NA T:88%	pCi/L	11/22/22 12:52	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL - RADIOCHEMISTRY

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

QC Batch: 544797

Analysis Method: EPA 904.0

QC Batch Method: EPA 904.0

Analysis Description: 904.0 Radium 228

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40253965001, 40253965002

METHOD BLANK: 2644706

Matrix: Water

Associated Lab Samples: 40253965001, 40253965002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-228	0.565 ± 0.314 (0.566) C:89% T:88%	pCi/L	11/16/22 11:48	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## QUALIFIERS

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40253965

---

### DEFINITIONS

Act - Activity

Unc - Uncertainty: SDWA = 1.96 sigma count uncertainty, all other matrices = Expanded Uncertainty (95% confidence interval).

Gamma Spec = Expanded Uncertainty (95.4% Confidence Interval)

(MDC) - Minimum Detectable Concentration

Trac - Tracer Recovery (%)

Carr - Carrier Recovery (%)

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

### ANALYTE QUALIFIERS

B Analyte was detected in the associated method blank.

H6 Analysis initiated outside of the 15 minute EPA required holding time.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40253965

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40253965001	MW-301	EPA 3010A	431884	EPA 6020B	431956
40253965002	MW-84A	EPA 3010A	431884	EPA 6020B	431956
40253965001	MW-301	EPA 7470	430492	EPA 7470	430560
40253965002	MW-84A	EPA 7470	430492	EPA 7470	430560
40253965001	MW-301				
40253965002	MW-84A				
40253965001	MW-301	EPA 903.1	544795		
40253965002	MW-84A	EPA 903.1	544795		
40253965001	MW-301	EPA 904.0	544797		
40253965002	MW-84A	EPA 904.0	544797		
40253965001	MW-301	Total Radium Calculation	549026		
40253965002	MW-84A	Total Radium Calculation	549026		
40253965001	MW-301	SM 2540C	430299		
40253965002	MW-84A	SM 2540C	430299		
40253965001	MW-301	EPA 9040	430502		
40253965002	MW-84A	EPA 9040	430502		
40253965001	MW-301	EPA 300.0	430807		
40253965002	MW-84A	EPA 300.0	430807		


### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.





**Sample Condition Upon Receipt Form (SCUR)**

Project #: 
**WO# : 40253965**  
  
 40253965

**Client Name:** SCS Engineering  
**Courier:**  CS Logistics  Fed Ex  Speedee  UPS  Waltco  
 Client  Pace Other: \_\_\_\_\_

**Tracking #:** \_\_\_\_\_  
**Custody Seal on Cooler/Box Present:**  yes  no    **Seals intact:**  yes  no  
**Custody Seal on Samples Present:**  yes  no    **Seals intact:**  yes  no  
**Packing Material:**  Bubble Wrap  Bubble Bags  None  Other

**Thermometer Used** SR - 123    **Type of Ice:**  Wet  Blue  Dry  None  Meltwater Only

**Cooler Temperature**    **Uncorr:** 0    **ICorr:** 0.2

**Temp Blank Present:**  yes  no    **Biological Tissue is Frozen:**  yes  no

Temp should be above freezing to 6°C.  
 Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

**Person examining contents:**  
**Date:** 10/11/22 / **Initials:** SG  
**Labeled By Initials:** NK

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
<b>Sampler Name &amp; Signature</b> on COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- DI VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time: _____
<b>Short Hold Time Analysis (&lt;72hr):</b>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
<b>Rush Turn Around Time Requested:</b>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No    MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
Correct Type: <u>Pace Green Bay</u> , Pace IR, Non-Pace		
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis    Matrix: <u>5</u>		
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased): _____		

**Client Notification/ Resolution:** \_\_\_\_\_    If checked, see attached form for additional comments   
 Person Contacted: \_\_\_\_\_    Date/Time: \_\_\_\_\_  
 Comments/ Resolution: \_\_\_\_\_

**PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir**  
 Page 2 of 2



December 29, 2022

Meghan Blodgett  
SCS ENGINEERS  
2830 Dairy Drive  
Madison, WI 53718

RE: Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40255945

Dear Meghan Blodgett:


Enclosed are the analytical results for sample(s) received by the laboratory on December 14, 2022. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky  
dan.milewsky@pacelabs.com  
(920)469-2436  
Project Manager

Enclosures

cc: Matt Bizjack, Alliant Energy  
Sherren Clark, SCS Engineers  
Jenny Coughlin, Alliant Energy  
Tom Karwoski, SCS ENGINEERS  
Ryan Matzuk, SCS Engineers  
Jeff Maxted, ALLIANT ENERGY  
Marc Morandi, ALLIANT ENERGY



## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## CERTIFICATIONS

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40255945

---

### **Pace Analytical Services Green Bay**

1241 Bellevue Street, Green Bay, WI 54302

Florida/NELAP Certification #: E87948

Illinois Certification #: 200050

Kentucky UST Certification #: 82

Louisiana Certification #: 04168

Minnesota Certification #: 055-999-334

New York Certification #: 12064

North Dakota Certification #: R-150

South Carolina Certification #: 83006001

Texas Certification #: T104704529-21-8

Virginia VELAP Certification ID: 11873

Wisconsin Certification #: 405132750

Wisconsin DATCP Certification #: 105-444

USDA Soil Permit #: P330-21-00008

Federal Fish & Wildlife Permit #: 51774A

---

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### SAMPLE SUMMARY

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40255945

---

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40255945001	MW-301	Water	10/27/22 16:35	12/14/22 09:20
40255945002	MW-84A	Water	10/27/22 15:25	12/14/22 09:20

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### SAMPLE ANALYTE COUNT

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40255945

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40255945001	MW-301	EPA 6020B	KXS	1
40255945002	MW-84A	EPA 6020B	KXS	5

PASI-G = Pace Analytical Services - Green Bay

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40255945

---

**Sample: MW-301**      **Lab ID: 40255945001**      Collected: 10/27/22 16:35      Received: 12/14/22 09:20      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Cobalt	<b>0.52J</b>	ug/L	1.0	0.12	1	12/19/22 06:07	12/21/22 03:38	7440-48-4	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40255945

**Sample: MW-84A**      **Lab ID: 40255945002**      Collected: 10/27/22 15:25      Received: 12/14/22 09:20      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Antimony	<0.15	ug/L	1.0	0.15	1	12/19/22 06:07	12/21/22 03:46	7440-36-0	
Cadmium	<0.15	ug/L	1.0	0.15	1	12/19/22 06:07	12/21/22 03:46	7440-43-9	
Cobalt	<0.12	ug/L	1.0	0.12	1	12/19/22 06:07	12/21/22 03:46	7440-48-4	
Lead	<0.24	ug/L	1.0	0.24	1	12/19/22 06:07	12/21/22 03:46	7439-92-1	
Thallium	<0.14	ug/L	1.0	0.14	1	12/19/22 06:07	12/21/22 03:46	7440-28-0	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40255945

QC Batch: 434044	Analysis Method: EPA 6020B
QC Batch Method: EPA 3010A	Analysis Description: 6020B MET
	Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40255945001, 40255945002

METHOD BLANK: 2498851 Matrix: Water

Associated Lab Samples: 40255945001, 40255945002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Antimony	ug/L	<0.15	1.0	12/21/22 00:57	
Cadmium	ug/L	<0.15	1.0	12/21/22 00:57	
Cobalt	ug/L	<0.12	1.0	12/21/22 00:57	
Lead	ug/L	<0.24	1.0	12/21/22 00:57	
Thallium	ug/L	<0.14	1.0	12/21/22 00:57	

LABORATORY CONTROL SAMPLE: 2498852

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	ug/L	250	242	97	80-120	
Cadmium	ug/L	250	242	97	80-120	
Cobalt	ug/L	250	237	95	80-120	
Lead	ug/L	250	237	95	80-120	
Thallium	ug/L	250	228	91	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2498853 2498854

Parameter	Units	MS		MSD		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40255857001 Result	Spike Conc.	Spike Conc.	Result						
Antimony	ug/L	5.8J	250	250	256	247	100	96	75-125	4	20
Cadmium	ug/L	8.2J	250	250	250	246	97	95	75-125	2	20
Cobalt	ug/L	5.2J	250	250	247	242	97	95	75-125	2	20
Lead	ug/L	5.5J	250	250	250	245	98	96	75-125	2	20
Thallium	ug/L	2.9J	250	250	235	232	93	91	75-125	2	20

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## QUALIFIERS

Project: 25222067 COLUMBIA CCR BACKGRND

Pace Project No.: 40255945

---

### DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

**QUALITY CONTROL DATA CROSS REFERENCE TABLE**

Project: 25222067 COLUMBIA CCR BACKGRND  
Pace Project No.: 40255945

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40255945001	MW-301	EPA 3010A	434044	EPA 6020B	434141
40255945002	MW-84A	EPA 3010A	434044	EPA 6020B	434141

**REPORT OF LABORATORY ANALYSIS**

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.





December 02, 2022

Meghan Blodgett  
SCS ENGINEERS  
2830 Dairy Drive  
Madison, WI 53718

RE: Project: 25222067 COLUMBIA CCR MOD 1-3  
Pace Project No.: 40253963

Dear Meghan Blodgett:


Enclosed are the analytical results for sample(s) received by the laboratory on October 31, 2022. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky  
dan.milewsky@pacelabs.com  
(920)469-2436  
Project Manager

Enclosures

cc: Matt Bizjack, Alliant Energy  
Sherren Clark, SCS Engineers  
Jenny Coughlin, Alliant Energy  
Tom Karwoski, SCS ENGINEERS  
Nicole Kron, SCS ENGINEERS  
Ryan Matzuk, SCS Engineers  
Jeff Maxted, ALLIANT ENERGY  
Marc Morandi, ALLIANT ENERGY



## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## CERTIFICATIONS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

---

### **Pace Analytical Services Green Bay**

1241 Bellevue Street, Green Bay, WI 54302

Florida/NELAP Certification #: E87948

Illinois Certification #: 200050

Kentucky UST Certification #: 82

Louisiana Certification #: 04168

Minnesota Certification #: 055-999-334

New York Certification #: 12064

North Dakota Certification #: R-150

South Carolina Certification #: 83006001

Texas Certification #: T104704529-21-8

Virginia VELAP Certification ID: 11873

Wisconsin Certification #: 405132750

Wisconsin DATCP Certification #: 105-444

USDA Soil Permit #: P330-21-00008

Federal Fish & Wildlife Permit #: 51774A

---

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## SAMPLE SUMMARY

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40253963001	MW-302	Water	10/27/22 14:15	10/31/22 09:15
40253963002	MW-33AR	Water	10/27/22 12:50	10/31/22 09:15
40253963003	MW-34A	Water	10/27/22 11:25	10/31/22 09:15
40253963004	FIELD BLANK-MOD1-3LF	Water	10/27/22 12:50	10/31/22 09:15
40253963005	MW-312	Water	10/28/22 00:00	10/31/22 15:35
40253963006	MW-93B	Water	10/28/22 15:05	10/31/22 15:35

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### SAMPLE ANALYTE COUNT

Project: 25222067 COLUMBIA CCR MOD 1-3  
Pace Project No.: 40253963

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40253963001	MW-302	EPA 6020B	KXS	2
			JXA	7
		SM 2540C	SRK	1
		EPA 9040	YER	1
		EPA 300.0	HMB	3
40253963002	MW-33AR	EPA 6020B	KXS	2
			JXA	7
		SM 2540C	SRK	1
		EPA 9040	YER	1
		EPA 300.0	HMB	3
40253963003	MW-34A	EPA 6020B	KXS	2
			JXA	7
		SM 2540C	SRK	1
		EPA 9040	YER	1
		EPA 300.0	HMB	3
40253963004	FIELD BLANK-MOD1-3LF	EPA 6020B	KXS	2
			SM 2540C	SRK
		EPA 9040	YER	1
		EPA 300.0	HMB	3
		40253963005	MW-312	
40253963006	MW-93B		JXA	1

PASI-G = Pace Analytical Services - Green Bay

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

**Sample: MW-302**      **Lab ID: 40253963001**      Collected: 10/27/22 14:15      Received: 10/31/22 09:15      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Boron	<b>374</b>	ug/L	10.0	3.0	1	11/18/22 06:38	11/30/22 16:00	7440-42-8	
Calcium	<b>91200</b>	ug/L	254	76.2	1	11/18/22 06:38	11/30/22 16:00	7440-70-2	
<b>Field Data</b>									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	<b>7.25</b>	Std. Units			1		10/27/22 14:15		
Field Specific Conductance	<b>616.1</b>	umhos/cm			1		10/27/22 14:15		
Oxygen, Dissolved	<b>8.60</b>	mg/L			1		10/27/22 14:15	7782-44-7	
REDOX	<b>38.2</b>	mV			1		10/27/22 14:15		
Turbidity	<b>0.00</b>	NTU			1		10/27/22 14:15		
Static Water Level	<b>784.62</b>	feet			1		10/27/22 14:15		
Temperature, Water (C)	<b>11.6</b>	deg C			1		10/27/22 14:15		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	<b>348</b>	mg/L	20.0	8.7	1		11/01/22 11:29		
<b>9040 pH</b>									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	<b>7.4</b>	Std. Units	0.10	0.010	1		11/03/22 13:55		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	<b>2.1</b>	mg/L	2.0	0.43	1		11/12/22 14:26	16887-00-6	
Fluoride	<b>&lt;0.095</b>	mg/L	0.32	0.095	1		11/14/22 13:00	16984-48-8	
Sulfate	<b>30.3</b>	mg/L	2.0	0.44	1		11/12/22 14:26	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

**Sample: MW-33AR**      **Lab ID: 40253963002**      Collected: 10/27/22 12:50      Received: 10/31/22 09:15      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Boron	<b>586</b>	ug/L	10.0	3.0	1	11/18/22 06:38	11/30/22 16:07	7440-42-8	
Calcium	<b>77000</b>	ug/L	254	76.2	1	11/18/22 06:38	11/30/22 16:07	7440-70-2	
<b>Field Data</b>									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	<b>7.54</b>	Std. Units			1		10/27/22 12:50		
Field Specific Conductance	<b>737</b>	umhos/cm			1		10/27/22 12:50		
Oxygen, Dissolved	<b>8.91</b>	mg/L			1		10/27/22 12:50	7782-44-7	
REDOX	<b>101.2</b>	mV			1		10/27/22 12:50		
Turbidity	<b>0.00</b>	NTU			1		10/27/22 12:50		
Static Water Level	<b>781.94</b>	feet			1		10/27/22 12:50		
Temperature, Water (C)	<b>12.7</b>	deg C			1		10/27/22 12:50		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	<b>440</b>	mg/L	20.0	8.7	1		11/01/22 11:29		
<b>9040 pH</b>									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	<b>7.9</b>	Std. Units	0.10	0.010	1		11/03/22 13:55		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	<b>40.5</b>	mg/L	20.0	4.3	10		11/12/22 14:40	16887-00-6	
Fluoride	<b>&lt;0.095</b>	mg/L	0.32	0.095	1		11/14/22 13:14	16984-48-8	
Sulfate	<b>153</b>	mg/L	20.0	4.4	10		11/12/22 14:40	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

**Sample: MW-34A**      **Lab ID: 40253963003**      Collected: 10/27/22 11:25      Received: 10/31/22 09:15      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Boron	<b>264</b>	ug/L	10.0	3.0	1	11/18/22 06:38	11/30/22 16:14	7440-42-8	
Calcium	<b>87300</b>	ug/L	254	76.2	1	11/18/22 06:38	11/30/22 16:14	7440-70-2	
<b>Field Data</b>									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	<b>7.53</b>	Std. Units			1		10/27/22 11:25		
Field Specific Conductance	<b>648.0</b>	umhos/cm			1		10/27/22 11:25		
Oxygen, Dissolved	<b>8.46</b>	mg/L			1		10/27/22 11:25	7782-44-7	
REDOX	<b>38.8</b>	mV			1		10/27/22 11:25		
Turbidity	<b>1.76</b>	NTU			1		10/27/22 11:25		
Static Water Level	<b>783.61</b>	feet			1		10/27/22 11:25		
Temperature, Water (C)	<b>12.6</b>	deg C			1		10/27/22 11:25		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	<b>436</b>	mg/L	20.0	8.7	1		11/01/22 11:30		
<b>9040 pH</b>									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	<b>7.7</b>	Std. Units	0.10	0.010	1		11/03/22 13:55		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	<b>2.2</b>	mg/L	2.0	0.43	1		11/12/22 14:55	16887-00-6	
Fluoride	<b>&lt;0.095</b>	mg/L	0.32	0.095	1		11/14/22 13:28	16984-48-8	
Sulfate	<b>169</b>	mg/L	20.0	4.4	10		11/14/22 12:47	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR MOD 1-3  
Pace Project No.: 40253963

**Sample: FIELD BLANK-MOD1-3LF    Lab ID: 40253963004    Collected: 10/27/22 12:50    Received: 10/31/22 09:15    Matrix: Water**

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Boron	<3.0	ug/L	10.0	3.0	1	11/18/22 06:38	11/30/22 15:37	7440-42-8	
Calcium	<76.2	ug/L	254	76.2	1	11/18/22 06:38	11/30/22 15:37	7440-70-2	
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	<8.7	mg/L	20.0	8.7	1		11/01/22 11:30		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	6.2	Std. Units	0.10	0.010	1		11/03/22 13:55		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	<0.43	mg/L	2.0	0.43	1		11/12/22 15:10	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		11/14/22 13:43	16984-48-8	
Sulfate	<0.44	mg/L	2.0	0.44	1		11/12/22 15:10	14808-79-8	

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

---

**Sample: MW-312**      **Lab ID: 40253963005**      Collected: 10/28/22 00:00      Received: 10/31/22 15:35      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>Field Data</b>									
Analytical Method: Pace Analytical Services - Green Bay									
Static Water Level	<b>783.50</b>	feet			1		10/28/22 00:00		

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## ANALYTICAL RESULTS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

---

**Sample: MW-93B**      **Lab ID: 40253963006**      Collected: 10/28/22 15:05      Received: 10/31/22 15:35      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>Field Data</b>		Analytical Method: Pace Analytical Services - Green Bay							
Static Water Level	<b>782.76</b>	feet			1		10/28/22 15:05		

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR MOD 1-3  
Pace Project No.: 40253963

QC Batch:	431884	Analysis Method:	EPA 6020B
QC Batch Method:	EPA 3010A	Analysis Description:	6020B MET
		Laboratory:	Pace Analytical Services - Green Bay

Associated Lab Samples: 40253963001, 40253963002, 40253963003, 40253963004

METHOD BLANK: 2487054 Matrix: Water  
Associated Lab Samples: 40253963001, 40253963002, 40253963003, 40253963004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Boron	ug/L	<3.0	10.0	11/30/22 12:41	
Calcium	ug/L	<76.2	254	11/30/22 12:41	

LABORATORY CONTROL SAMPLE: 2487055

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Boron	ug/L	250	253	101	80-120	
Calcium	ug/L	10000	10200	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2487056 2487057

Parameter	Units	40253965001		2487056		2487057		% Rec Limits	RPD	Max RPD	Qual
		Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec				
Boron	ug/L	37.5	250	250	295	282	103	98	75-125	5	20
Calcium	ug/L	62800	10000	10000	72700	69600	99	69	75-125	4	20 P6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



**QUALITY CONTROL DATA**

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

QC Batch: 430502

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253963001, 40253963002, 40253963003, 40253963004

SAMPLE DUPLICATE: 2479241

Parameter	Units	40253453001 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.0	7.0	0	20	H6

SAMPLE DUPLICATE: 2479545

Parameter	Units	40253825003 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.4	7.4	0	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

**REPORT OF LABORATORY ANALYSIS**

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25222067 COLUMBIA CCR MOD 1-3  
Pace Project No.: 40253963

QC Batch: 430807 Analysis Method: EPA 300.0  
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions  
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40253963001, 40253963002, 40253963003, 40253963004

METHOD BLANK: 2480961 Matrix: Water  
Associated Lab Samples: 40253963001, 40253963002, 40253963003, 40253963004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	11/12/22 12:34	
Fluoride	mg/L	<0.095	0.32	11/14/22 11:33	
Sulfate	mg/L	<0.44	2.0	11/12/22 12:34	

LABORATORY CONTROL SAMPLE: 2480962

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	19.4	97	90-110	
Fluoride	mg/L	2	1.9	97	90-110	
Sulfate	mg/L	20	19.4	97	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2480963 2480964

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40253965001 Result	Spike Conc.	Spike Conc.	Result								
Chloride	mg/L	2.3	20	20	24.1	24.2	109	110	90-110	1	15		
Fluoride	mg/L	<0.095	2	2	2.5	2.4	123	121	90-110	2	15	M0	
Sulfate	mg/L	11.6	20	20	32.8	33.1	106	107	90-110	1	15		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## QUALIFIERS

Project: 25222067 COLUMBIA CCR MOD 1-3

Pace Project No.: 40253963

---

### DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

### ANALYTE QUALIFIERS

H6 Analysis initiated outside of the 15 minute EPA required holding time.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25222067 COLUMBIA CCR MOD 1-3  
Pace Project No.: 40253963

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40253963001	MW-302	EPA 3010A	431884	EPA 6020B	431956
40253963002	MW-33AR	EPA 3010A	431884	EPA 6020B	431956
40253963003	MW-34A	EPA 3010A	431884	EPA 6020B	431956
40253963004	FIELD BLANK-MOD1-3LF	EPA 3010A	431884	EPA 6020B	431956
40253963001	MW-302				
40253963002	MW-33AR				
40253963003	MW-34A				
40253963005	MW-312				
40253963006	MW-93B				
40253963001	MW-302	SM 2540C	430299		
40253963002	MW-33AR	SM 2540C	430299		
40253963003	MW-34A	SM 2540C	430299		
40253963004	FIELD BLANK-MOD1-3LF	SM 2540C	430299		
40253963001	MW-302	EPA 9040	430502		
40253963002	MW-33AR	EPA 9040	430502		
40253963003	MW-34A	EPA 9040	430502		
40253963004	FIELD BLANK-MOD1-3LF	EPA 9040	430502		
40253963001	MW-302	EPA 300.0	430807		
40253963002	MW-33AR	EPA 300.0	430807		
40253963003	MW-34A	EPA 300.0	430807		
40253963004	FIELD BLANK-MOD1-3LF	EPA 300.0	430807		

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.





**Sample Condition Upon Receipt Form (SCUR)**

Project #: \_\_\_\_\_

**WO#: 40253963**



40253963

**Client Name:** SCS Engineering

**Courier:**  CS Logistics  Fed Ex  Speedee  UPS  Waltco  
 Client  Pace Other: \_\_\_\_\_

**Tracking #:** \_\_\_\_\_

**Custody Seal on Cooler/Box Present:**  yes  no    **Seals intact:**  yes  no

**Custody Seal on Samples Present:**  yes  no    **Seals intact:**  yes  no

**Packing Material:**  Bubble Wrap  Bubble Bags  None  Other

**Thermometer Used** SR-119    **Type of Ice:**  Wet  Blue  Dry  None     Meltwater Only

**Cooler Temperature**    Uncorr: 1    ICorr: 0.5

**Temp Blank Present:**  yes  no    **Biological Tissue is Frozen:**  yes  no

Temp should be above freezing to 6°C.  
 Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

<b>Person examining contents:</b>	
Date: <u>10/3/22</u>	Initials: <u>SG</u>
Labeled By Initials: <u>NK</u>	

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
<b>Sampler Name &amp; Signature on COC:</b>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- DI VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time:
<b>Short Hold Time Analysis (&lt;72hr):</b>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
<b>Rush Turn Around Time Requested:</b>	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No    MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
Correct Type: <u>Pace Green Bay</u> , Pace IR, Non-Pace		
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis    Matrix: <u>W</u>		
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased): _____		

**Client Notification/ Resolution:** \_\_\_\_\_ If checked, see attached form for additional comments

Person Contacted: \_\_\_\_\_ Date/Time: \_\_\_\_\_

Comments/ Resolution: \_\_\_\_\_

**PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample log**

Page 2 of 2

02/26/2024 - Classification: Internal - ECRM13238672

May 26, 2023

Meghan Blodgett  
SCS ENGINEERS  
2830 Dairy Drive  
Madison, WI 53718

RE: Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on April 28, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay
- Pace Analytical Services - Greensburg

Revised Report: REDOX has been added to the field data list for MW-84A.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Dan Milewsky  
dan.milewsky@pacelabs.com  
(920)469-2436  
Project Manager

Enclosures

cc: Matt Bizjack, Alliant Energy  
Natalie Burris, SCS ENGINEERS  
Sherren Clark, SCS Engineers  
Jenny Coughlin, Alliant Energy  
Tom Karwoski, SCS ENGINEERS  
Ryan Matzuk, SCS Engineers  
Jeff Maxted, ALLIANT ENERGY



## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



## CERTIFICATIONS

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

---

### Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601  
ANAB DOD-ELAP Rad Accreditation #: L2417  
Alabama Certification #: 41590  
Arizona Certification #: AZ0734  
Arkansas Certification  
California Certification #: 04222CA  
Colorado Certification #: PA01547  
Connecticut Certification #: PH-0694  
Delaware Certification  
EPA Region 4 DW Rad  
Florida/TNI Certification #: E87683  
Georgia Certification #: C040  
Florida: Cert E871149 SEKS WET  
Guam Certification  
Hawaii Certification  
Idaho Certification  
Illinois Certification  
Indiana Certification  
Iowa Certification #: 391  
Kansas/TNI Certification #: E-10358  
Kentucky Certification #: KY90133  
KY WW Permit #: KY0098221  
KY WW Permit #: KY0000221  
Louisiana DHH/TNI Certification #: LA180012  
Louisiana DEQ/TNI Certification #: 4086  
Maine Certification #: 2017020  
Maryland Certification #: 308  
Massachusetts Certification #: M-PA1457  
Michigan/PADEP Certification #: 9991

Missouri Certification #: 235  
Montana Certification #: Cert0082  
Nebraska Certification #: NE-OS-29-14  
Nevada Certification #: PA014572018-1  
New Hampshire/TNI Certification #: 297617  
New Jersey/TNI Certification #: PA051  
New Mexico Certification #: PA01457  
New York/TNI Certification #: 10888  
North Carolina Certification #: 42706  
North Dakota Certification #: R-190  
Ohio EPA Rad Approval: #41249  
Oregon/TNI Certification #: PA200002-010  
Pennsylvania/TNI Certification #: 65-00282  
Puerto Rico Certification #: PA01457  
Rhode Island Certification #: 65-00282  
South Dakota Certification  
Tennessee Certification #: 02867  
Texas/TNI Certification #: T104704188-17-3  
Utah/TNI Certification #: PA014572017-9  
USDA Soil Permit #: P330-17-00091  
Vermont Dept. of Health: ID# VT-0282  
Virgin Island/PADEP Certification  
Virginia/VELAP Certification #: 460198  
Washington Certification #: C868  
West Virginia DEP Certification #: 143  
West Virginia DHHR Certification #: 9964C  
Wisconsin Approve List for Rad  
Wyoming Certification #: 8TMS-L

### Pace Analytical Services Green Bay

1241 Bellevue Street, Green Bay, WI 54302  
Florida/NELAP Certification #: E87948  
Illinois Certification #: 200050  
Kentucky UST Certification #: 82  
Louisiana Certification #: 04168  
Minnesota Certification #: 055-999-334  
New York Certification #: 12064  
North Dakota Certification #: R-150

South Carolina Certification #: 83006001  
Texas Certification #: T104704529-21-8  
Virginia VELAP Certification ID: 11873  
Wisconsin Certification #: 405132750  
Wisconsin DATCP Certification #: 105-444  
USDA Soil Permit #: P330-21-00008  
Federal Fish & Wildlife Permit #: 51774A

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



## SAMPLE SUMMARY

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40261460001	MW-301	Water	04/27/23 12:20	04/28/23 08:40
40261460002	MW-84A	Water	04/27/23 14:05	04/28/23 08:40

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### SAMPLE ANALYTE COUNT

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
40261460001	MW-301	EPA 6020B	TXW	14	PASI-G
		EPA 7470	AJT	1	PASI-G
			LB	7	PASI-G
		EPA 903.1	JLJ	1	PASI-PA
		EPA 904.0	VAL	1	PASI-PA
		Total Radium Calculation	JAL	1	PASI-PA
		SM 2540C	HNT	1	PASI-G
		EPA 9040	SRK	1	PASI-G
		EPA 300.0	HMB	3	PASI-G
		40261460002	MW-84A	EPA 6020B	TXW
EPA 7470	AJT			1	PASI-G
	LB			7	PASI-G
EPA 903.1	JLJ			1	PASI-PA
EPA 904.0	VAL			1	PASI-PA
Total Radium Calculation	JAL			1	PASI-PA
SM 2540C	HNT			1	PASI-G
EPA 9040	SRK			1	PASI-G
EPA 300.0	HMB			3	PASI-G

PASI-G = Pace Analytical Services - Green Bay

PASI-PA = Pace Analytical Services - Greensburg

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

**Sample: MW-301**      **Lab ID: 40261460001**      Collected: 04/27/23 12:20      Received: 04/28/23 08:40      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Antimony	<0.15	ug/L	1.0	0.15	1	05/01/23 06:24	05/15/23 08:01	7440-36-0	
Arsenic	<0.28	ug/L	1.0	0.28	1	05/01/23 06:24	05/15/23 08:01	7440-38-2	
Barium	9.8	ug/L	2.3	0.70	1	05/01/23 06:24	05/15/23 08:01	7440-39-3	
Beryllium	<0.25	ug/L	1.0	0.25	1	05/01/23 06:24	05/15/23 08:01	7440-41-7	
Boron	20.1	ug/L	10.0	3.0	1	05/01/23 06:24	05/15/23 08:01	7440-42-8	
Cadmium	<0.15	ug/L	1.0	0.15	1	05/01/23 06:24	05/15/23 08:01	7440-43-9	
Calcium	120000	ug/L	254	76.2	1	05/01/23 06:24	05/15/23 08:01	7440-70-2	
Chromium	<1.0	ug/L	3.4	1.0	1	05/01/23 06:24	05/15/23 08:01	7440-47-3	
Cobalt	<0.12	ug/L	1.0	0.12	1	05/01/23 06:24	05/15/23 08:01	7440-48-4	
Lead	<0.24	ug/L	1.0	0.24	1	05/01/23 06:24	05/15/23 08:01	7439-92-1	
Lithium	0.62J	ug/L	1.0	0.22	1	05/01/23 06:24	05/15/23 08:01	7439-93-2	
Molybdenum	<0.44	ug/L	1.5	0.44	1	05/01/23 06:24	05/15/23 08:01	7439-98-7	
Selenium	<0.32	ug/L	1.1	0.32	1	05/01/23 06:24	05/15/23 08:01	7782-49-2	
Thallium	<0.14	ug/L	1.0	0.14	1	05/01/23 06:24	05/15/23 08:01	7440-28-0	
<b>7470 Mercury</b>									
Analytical Method: EPA 7470    Preparation Method: EPA 7470 Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	05/08/23 10:55	05/09/23 09:00	7439-97-6	M0
<b>Field Data</b>									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	6.65	Std. Units			1		04/27/23 12:20		
Field Specific Conductance	857.0	umhos/cm			1		04/27/23 12:20		
Oxygen, Dissolved	6.50	mg/L			1		04/27/23 12:20	7782-44-7	
REDOX	95.3	mV			1		04/27/23 12:20		
Turbidity	0.00	NTU			1		04/27/23 12:20		
Static Water Level	787.57	feet			1		04/27/23 12:20		
Temperature, Water (C)	8.0	deg C			1		04/27/23 12:20		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	526	mg/L	20.0	8.7	1		05/01/23 10:51		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	6.9	Std. Units	0.10	0.010	1		05/02/23 16:48		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	1.5J	mg/L	2.0	0.43	1		05/12/23 16:00	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		05/12/23 16:00	16984-48-8	
Sulfate	12.3	mg/L	2.0	0.44	1		05/12/23 16:00	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

**Sample: MW-84A**      **Lab ID: 40261460002**      Collected: 04/27/23 14:05      Received: 04/28/23 08:40      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Antimony	<0.15	ug/L	1.0	0.15	1	05/01/23 06:24	05/15/23 08:08	7440-36-0	
Arsenic	<0.28	ug/L	1.0	0.28	1	05/01/23 06:24	05/15/23 08:08	7440-38-2	
Barium	12.6	ug/L	2.3	0.70	1	05/01/23 06:24	05/15/23 08:08	7440-39-3	
Beryllium	<0.25	ug/L	1.0	0.25	1	05/01/23 06:24	05/15/23 08:08	7440-41-7	
Boron	10.3	ug/L	10.0	3.0	1	05/01/23 06:24	05/15/23 08:08	7440-42-8	
Cadmium	<0.15	ug/L	1.0	0.15	1	05/01/23 06:24	05/15/23 08:08	7440-43-9	
Calcium	68600	ug/L	254	76.2	1	05/01/23 06:24	05/15/23 08:08	7440-70-2	
Chromium	1.7J	ug/L	3.4	1.0	1	05/01/23 06:24	05/15/23 08:08	7440-47-3	
Cobalt	<0.12	ug/L	1.0	0.12	1	05/01/23 06:24	05/15/23 08:08	7440-48-4	
Lead	<0.24	ug/L	1.0	0.24	1	05/01/23 06:24	05/15/23 08:08	7439-92-1	
Lithium	0.71J	ug/L	1.0	0.22	1	05/01/23 06:24	05/15/23 08:08	7439-93-2	
Molybdenum	<0.44	ug/L	1.5	0.44	1	05/01/23 06:24	05/15/23 08:08	7439-98-7	
Selenium	<0.32	ug/L	1.1	0.32	1	05/01/23 06:24	05/15/23 08:08	7782-49-2	
Thallium	<0.14	ug/L	1.0	0.14	1	05/01/23 06:24	05/15/23 08:08	7440-28-0	
<b>7470 Mercury</b>									
Analytical Method: EPA 7470    Preparation Method: EPA 7470 Pace Analytical Services - Green Bay									
Mercury	<0.066	ug/L	0.20	0.066	1	05/08/23 10:55	05/09/23 09:12	7439-97-6	
<b>Field Data</b>									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	7.01	Std. Units			1		04/27/23 14:05		
Field Specific Conductance	556.6	umhos/cm			1		04/27/23 14:05		
Field Oxidation Potential	103.4	mV			1		04/27/23 14:05		
Oxygen, Dissolved	9.37	mg/L			1		04/27/23 14:05	7782-44-7	
Turbidity	0.72	NTU			1		04/27/23 14:05		
Static Water Level	786.97	feet			1		04/27/23 14:05		
Temperature, Water (C)	10.7	deg C			1		04/27/23 14:05		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	326	mg/L	20.0	8.7	1		05/01/23 10:51		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	7.6	Std. Units	0.10	0.010	1		05/02/23 16:52		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	3.0	mg/L	2.0	0.43	1		05/12/23 16:59	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		05/12/23 16:59	16984-48-8	
Sulfate	1.3J	mg/L	2.0	0.44	1		05/12/23 16:59	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

QC Batch: 444256 Analysis Method: EPA 7470  
QC Batch Method: EPA 7470 Analysis Description: 7470 Mercury  
Laboratory: Pace Analytical Services - Green Bay  
Associated Lab Samples: 40261460001, 40261460002

METHOD BLANK: 2550653 Matrix: Water  
Associated Lab Samples: 40261460001, 40261460002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Mercury	ug/L	<0.066	0.20	05/09/23 08:56	

LABORATORY CONTROL SAMPLE: 2550654

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Mercury	ug/L	5	5.5	110	85-115	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2550655 2550656

Parameter	Units	40261460001		2550656		MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result						
Mercury	ug/L	<0.066	5	5	5.8	5.9	115	119	85-115	3	20 M0

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

QC Batch: 443628 Analysis Method: EPA 6020B  
QC Batch Method: EPA 3010A Analysis Description: 6020B MET  
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40261460001, 40261460002

METHOD BLANK: 2547530 Matrix: Water

Associated Lab Samples: 40261460001, 40261460002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Antimony	ug/L	<0.15	1.0	05/11/23 17:42	
Arsenic	ug/L	<0.28	1.0	05/11/23 17:42	
Barium	ug/L	<0.70	2.3	05/11/23 17:42	
Beryllium	ug/L	<0.25	1.0	05/11/23 17:42	
Boron	ug/L	<3.0	10.0	05/11/23 17:42	
Cadmium	ug/L	<0.15	1.0	05/11/23 17:42	
Calcium	ug/L	<76.2	254	05/11/23 17:42	
Chromium	ug/L	<1.0	3.4	05/11/23 17:42	
Cobalt	ug/L	<0.12	1.0	05/11/23 17:42	
Lead	ug/L	<0.24	1.0	05/11/23 17:42	
Lithium	ug/L	<0.22	1.0	05/11/23 17:42	
Molybdenum	ug/L	<0.44	1.5	05/11/23 17:42	
Selenium	ug/L	<0.32	1.1	05/11/23 17:42	
Thallium	ug/L	<0.14	1.0	05/11/23 17:42	

LABORATORY CONTROL SAMPLE: 2547531

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Antimony	ug/L	250	250	100	80-120	
Arsenic	ug/L	250	255	102	80-120	
Barium	ug/L	250	234	94	80-120	
Beryllium	ug/L	250	233	93	80-120	
Boron	ug/L	250	220	88	80-120	
Cadmium	ug/L	250	254	102	80-120	
Calcium	ug/L	10000	10200	102	80-120	
Chromium	ug/L	250	241	96	80-120	
Cobalt	ug/L	250	241	96	80-120	
Lead	ug/L	250	241	96	80-120	
Lithium	ug/L	250	237	95	80-120	
Molybdenum	ug/L	250	245	98	80-120	
Selenium	ug/L	250	257	103	80-120	
Thallium	ug/L	250	227	91	80-120	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

Parameter	Units	2547532		2547533		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40261434001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result								
Antimony	ug/L	0.52J	250	250	268	263	107	105	75-125	2	20		
Arsenic	ug/L	12.4	250	250	264	262	100	100	75-125	1	20		
Barium	ug/L	128	250	250	405	384	111	102	75-125	5	20		
Beryllium	ug/L	0.83J	250	250	261	259	104	103	75-125	1	20		
Boron	ug/L	43.8	250	250	309	302	106	103	75-125	2	20		
Cadmium	ug/L	0.56J	250	250	249	243	99	97	75-125	3	20		
Calcium	ug/L	147000	10000	10000	163000	156000	157	94	75-125	4	20	P6	
Chromium	ug/L	30.1	250	250	279	274	100	98	75-125	2	20		
Cobalt	ug/L	19.2	250	250	257	254	95	94	75-125	1	20		
Lead	ug/L	26.6	250	250	280	274	102	99	75-125	2	20		
Lithium	ug/L	23.9	250	250	277	276	101	101	75-125	0	20		
Molybdenum	ug/L	1.3J	250	250	246	241	98	96	75-125	2	20		
Selenium	ug/L	1.9J	250	250	267	264	106	105	75-125	1	20		
Thallium	ug/L	0.44J	250	250	250	251	100	100	75-125	0	20		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

QC Batch: 443675      Analysis Method: SM 2540C  
QC Batch Method: SM 2540C      Analysis Description: 2540C Total Dissolved Solids  
Laboratory: Pace Analytical Services - Green Bay  
Associated Lab Samples: 40261460001, 40261460002

METHOD BLANK: 2547666      Matrix: Water  
Associated Lab Samples: 40261460001, 40261460002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	05/01/23 10:47	

LABORATORY CONTROL SAMPLE: 2547667

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	582	552	95	80-120	

SAMPLE DUPLICATE: 2547668

Parameter	Units	40261457001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	448	464	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

QC Batch: 443847

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40261460001, 40261460002

SAMPLE DUPLICATE: 2548305

Parameter	Units	40261459003 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.3	7.3	0	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

**QUALITY CONTROL DATA**

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

QC Batch: 444310	Analysis Method: EPA 300.0
QC Batch Method: EPA 300.0	Analysis Description: 300.0 IC Anions
	Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40261460001, 40261460002

METHOD BLANK: 2550800 Matrix: Water

Associated Lab Samples: 40261460001, 40261460002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	05/12/23 14:40	
Fluoride	mg/L	<0.095	0.32	05/12/23 14:40	
Sulfate	mg/L	<0.44	2.0	05/12/23 14:40	

LABORATORY CONTROL SAMPLE: 2550801

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	19.5	98	90-110	
Fluoride	mg/L	2	2.0	101	90-110	
Sulfate	mg/L	20	19.7	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2550802 2550803

Parameter	Units	MS		MSD		MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
		40261459001 Result	Spike Conc.	Spike Conc.	Conc.								
Chloride	mg/L	2.3	20	20	22.6	22.7	102	102	90-110	0	15		
Fluoride	mg/L	<0.095	2	2	2.1	2.1	105	104	90-110	0	15		
Sulfate	mg/L	11.0	20	20	31.5	31.5	103	103	90-110	0	15		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

**REPORT OF LABORATORY ANALYSIS**

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

**Sample: MW-301**      **Lab ID: 40261460001**      Collected: 04/27/23 12:20      Received: 04/28/23 08:40      Matrix: Water  
PWS:      Site ID:      Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
Pace Analytical Services - Greensburg						
Radium-226	EPA 903.1	<b>0.000 ± 0.387 (0.805)</b> <b>C:NA T:99%</b>	pCi/L	05/18/23 14:53	13982-63-3	
Pace Analytical Services - Greensburg						
Radium-228	EPA 904.0	<b>0.417 ± 0.322 (0.623)</b> <b>C:80% T:87%</b>	pCi/L	05/15/23 15:22	15262-20-1	
Pace Analytical Services - Greensburg						
Total Radium	Total Radium Calculation	<b>0.417 ± 0.709 (1.43)</b>	pCi/L	05/22/23 12:45	7440-14-4	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS - RADIOCHEMISTRY

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

**Sample: MW-84A**      **Lab ID: 40261460002**      Collected: 04/27/23 14:05      Received: 04/28/23 08:40      Matrix: Water  
PWS:      Site ID:      Sample Type:

Parameters	Method	Act ± Unc (MDC) Carr Trac	Units	Analyzed	CAS No.	Qual
Pace Analytical Services - Greensburg						
Radium-226	EPA 903.1	<b>0.000 ± 0.365 (0.772)</b> <b>C:NA T:95%</b>	pCi/L	05/18/23 15:08	13982-63-3	
Pace Analytical Services - Greensburg						
Radium-228	EPA 904.0	<b>0.326 ± 0.316 (0.647)</b> <b>C:79% T:93%</b>	pCi/L	05/15/23 15:22	15262-20-1	
Pace Analytical Services - Greensburg						
Total Radium	Total Radium Calculation	<b>0.326 ± 0.681 (1.42)</b>	pCi/L	05/22/23 12:45	7440-14-4	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL - RADIOCHEMISTRY

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

QC Batch: 585758

Analysis Method: EPA 904.0

QC Batch Method: EPA 904.0

Analysis Description: 904.0 Radium 228

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40261460001, 40261460002

METHOD BLANK: 2845167

Matrix: Water

Associated Lab Samples: 40261460001, 40261460002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-228	0.356 ± 0.319 (0.642) C:76% T:89%	pCi/L	05/15/23 15:19	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL - RADIOCHEMISTRY

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

QC Batch: 585757

Analysis Method: EPA 903.1

QC Batch Method: EPA 903.1

Analysis Description: 903.1 Radium-226

Laboratory: Pace Analytical Services - Greensburg

Associated Lab Samples: 40261460001, 40261460002

METHOD BLANK: 2845166

Matrix: Water

Associated Lab Samples: 40261460001, 40261460002

Parameter	Act ± Unc (MDC) Carr Trac	Units	Analyzed	Qualifiers
Radium-226	-0.0428 ± 0.195 (0.397) C:NA T:94%	pCi/L	05/18/23 14:53	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## QUALIFIERS

Project: 25223067 COLUMBIA CCR BCKGRND

Pace Project No.: 40261460

---

### DEFINITIONS

Act - Activity

Unc - Uncertainty: SDWA = 1.96 sigma count uncertainty, all other matrices = Expanded Uncertainty (95% confidence interval).

Gamma Spec = Expanded Uncertainty (95.4% Confidence Interval)

(MDC) - Minimum Detectable Concentration

Trac - Tracer Recovery (%)

Carr - Carrier Recovery (%)

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

DL - Adjusted Method Detection Limit.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

### ANALYTE QUALIFIERS

H6 Analysis initiated outside of the 15 minute EPA required holding time.

M0 Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25223067 COLUMBIA CCR BCKGRND  
Pace Project No.: 40261460

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40261460001	MW-301	EPA 3010A	443628	EPA 6020B	443733
40261460002	MW-84A	EPA 3010A	443628	EPA 6020B	443733
40261460001	MW-301	EPA 7470	444256	EPA 7470	444285
40261460002	MW-84A	EPA 7470	444256	EPA 7470	444285
40261460001	MW-301				
40261460002	MW-84A				
40261460001	MW-301	EPA 903.1	585757		
40261460002	MW-84A	EPA 903.1	585757		
40261460001	MW-301	EPA 904.0	585758		
40261460002	MW-84A	EPA 904.0	585758		
40261460001	MW-301	Total Radium Calculation	589747		
40261460002	MW-84A	Total Radium Calculation	589747		
40261460001	MW-301	SM 2540C	443675		
40261460002	MW-84A	SM 2540C	443675		
40261460001	MW-301	EPA 9040	443847		
40261460002	MW-84A	EPA 9040	443847		
40261460001	MW-301	EPA 300.0	444310		
40261460002	MW-84A	EPA 300.0	444310		

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.







Sample Condition Upon Receipt Form (SCUR)

Project #: \_\_\_\_\_

Client Name: SLS Engineers

WO#: **40261460**

Courier:  CS Logistics  Fed Ex  Speedee  UPS  Walto  
 Client  Pace Other: \_\_\_\_\_



Tracking #: \_\_\_\_\_

Custody Seal on Cooler/Box Present:  yes  no Seals intact:  yes  no

Custody Seal on Samples Present:  yes  no Seals intact:  yes  no

Packing Material:  Bubble Wrap  Bubble Bags  None  Other

Thermometer Used SR - 9 Type of Ice: Wet Blue Dry None  Meltwater Only

Cooler Temperature Uncorr: 1.0 / Corr: 2.0

Temp Blank Present:  yes  no Biological Tissue is Frozen:  yes  no

Person examining contents:  
 Date: 4/28/23 Initials: SG  
 Labeled By Initials: mit

Temp should be above freezing to 6°C.  
 Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- DI VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time:
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
Correct Type: <u>Pace Green Bay</u> Pace IR, Non-Pace		
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	12. <u>002 same "1045"</u>
-Includes date/time/ID/Analysis Matrix: <u>W3</u>		<u>4/28/23 SG</u>
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution: \_\_\_\_\_ If checked, see attached form for additional comments

Person Contacted: \_\_\_\_\_ Date/Time: \_\_\_\_\_

Comments/ Resolution: chart used white out on bottle types 4/28/23 SG

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir

May 16, 2023

Meghan Blodgett  
SCS ENGINEERS  
2830 Dairy Drive  
Madison, WI 53718

RE: Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

Dear Meghan Blodgett:

Enclosed are the analytical results for sample(s) received by the laboratory on April 28, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Tod Noltemeyer for  
Dan Milewsky  
dan.milewsky@pacelabs.com  
(920)469-2436  
Project Manager

Enclosures

cc: Matt Bizjack, Alliant Energy  
Natalie Burris, SCS ENGINEERS  
Sherren Clark, SCS Engineers  
Jenny Coughlin, Alliant Energy  
Tom Karwoski, SCS ENGINEERS  
Ryan Matzuk, SCS Engineers  
Jeff Maxted, ALLIANT ENERGY



## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## CERTIFICATIONS

Project: 25223067 COLUMBIA CCR MOD1-3

Pace Project No.: 40261462

---

### **Pace Analytical Services Green Bay**

1241 Bellevue Street, Green Bay, WI 54302

Florida/NELAP Certification #: E87948

Illinois Certification #: 200050

Kentucky UST Certification #: 82

Louisiana Certification #: 04168

Minnesota Certification #: 055-999-334

New York Certification #: 12064

North Dakota Certification #: R-150

South Carolina Certification #: 83006001

Texas Certification #: T104704529-21-8

Virginia VELAP Certification ID: 11873

Wisconsin Certification #: 405132750

Wisconsin DATCP Certification #: 105-444

USDA Soil Permit #: P330-21-00008

Federal Fish & Wildlife Permit #: 51774A

---

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## SAMPLE SUMMARY

Project: 25223067 COLUMBIA CCR MOD1-3

Pace Project No.: 40261462

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40261462001	MW-302	Water	04/27/23 11:40	04/28/23 08:40
40261462002	MW-33AR	Water	04/27/23 10:30	04/28/23 08:40
40261462003	MW-34A	Water	04/26/23 10:20	04/28/23 08:40
40261462004	FIELD BLANK-MOD1-3LF	Water	04/27/23 11:00	04/28/23 08:40

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### SAMPLE ANALYTE COUNT

Project: 25223067 COLUMBIA CCR MOD1-3

Pace Project No.: 40261462

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40261462001	MW-302	EPA 6020B	KXS	2
			LB	7
		SM 2540C	HNT	1
		EPA 9040	SRK	1
		EPA 300.0	HMB	3
40261462002	MW-33AR	EPA 6020B	KXS	2
			LB	7
		SM 2540C	HNT	1
		EPA 9040	SRK	1
		EPA 300.0	HMB	3
40261462003	MW-34A	EPA 6020B	KXS	2
			LB	7
		SM 2540C	HNT	1
		EPA 9040	SRK	1
		EPA 300.0	HMB	3
40261462004	FIELD BLANK-MOD1-3LF	EPA 6020B	KXS	2
		SM 2540C	HNT	1
		EPA 9040	SRK	1
		EPA 300.0	HMB	3

PASI-G = Pace Analytical Services - Green Bay

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25223067 COLUMBIA CCR MOD1-3

Pace Project No.: 40261462

**Sample: MW-302**      **Lab ID: 40261462001**      Collected: 04/27/23 11:40      Received: 04/28/23 08:40      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A									
Pace Analytical Services - Green Bay									
Boron	<b>541</b>	ug/L	10.0	3.0	1	05/02/23 05:28	05/10/23 23:13	7440-42-8	
Calcium	<b>66500</b>	ug/L	254	76.2	1	05/02/23 05:28	05/10/23 23:13	7440-70-2	
<b>Field Data</b>									
Analytical Method:									
Pace Analytical Services - Green Bay									
Field pH	<b>7.36</b>	Std. Units			1		04/27/23 11:40		
Field Specific Conductance	<b>605.2</b>	umhos/cm			1		04/27/23 11:40		
Oxygen, Dissolved	<b>10.91</b>	mg/L			1		04/27/23 11:40	7782-44-7	
REDOX	<b>144.7</b>	mV			1		04/27/23 11:40		
Turbidity	<b>1.82</b>	NTU			1		04/27/23 11:40		
Static Water Level	<b>786.87</b>	feet			1		04/27/23 11:40		
Temperature, Water (C)	<b>9.7</b>	deg C			1		04/27/23 11:40		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C									
Pace Analytical Services - Green Bay									
Total Dissolved Solids	<b>352</b>	mg/L	20.0	8.7	1		05/01/23 10:51		
<b>9040 pH</b>									
Analytical Method: EPA 9040									
Pace Analytical Services - Green Bay									
pH at 25 Degrees C	<b>7.7</b>	Std. Units	0.10	0.010	1		05/02/23 16:55		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0									
Pace Analytical Services - Green Bay									
Chloride	<b>1.3J</b>	mg/L	2.0	0.43	1		05/12/23 17:58	16887-00-6	
Fluoride	<b>&lt;0.095</b>	mg/L	0.32	0.095	1		05/12/23 17:58	16984-48-8	
Sulfate	<b>36.6</b>	mg/L	2.0	0.44	1		05/12/23 17:58	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### ANALYTICAL RESULTS

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

**Sample: MW-33AR**      **Lab ID: 40261462002**      Collected: 04/27/23 10:30      Received: 04/28/23 08:40      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Boron	<b>532</b>	ug/L	10.0	3.0	1	05/02/23 05:28	05/10/23 23:20	7440-42-8	
Calcium	<b>55300</b>	ug/L	254	76.2	1	05/02/23 05:28	05/10/23 23:20	7440-70-2	
<b>Field Data</b>									
Analytical Method: Pace Analytical Services - Green Bay									
Field pH	<b>7.61</b>	Std. Units			1		04/27/23 10:30		
Field Specific Conductance	<b>609.3</b>	umhos/cm			1		04/27/23 10:30		
Oxygen, Dissolved	<b>11.71</b>	mg/L			1		04/27/23 10:30	7782-44-7	
REDOX	<b>176.7</b>	mV			1		04/27/23 10:30		
Turbidity	<b>0.20</b>	NTU			1		04/27/23 10:30		
Static Water Level	<b>785.79</b>	feet			1		04/27/23 10:30		
Temperature, Water (C)	<b>10.2</b>	deg C			1		04/27/23 10:30		
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	<b>394</b>	mg/L	20.0	8.7	1		05/01/23 10:52		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	<b>7.8</b>	Std. Units	0.10	0.010	1		05/02/23 16:56		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	<b>19.0</b>	mg/L	2.0	0.43	1		05/12/23 18:13	16887-00-6	
Fluoride	<b>&lt;0.095</b>	mg/L	0.32	0.095	1		05/12/23 18:13	16984-48-8	
Sulfate	<b>104</b>	mg/L	10.0	2.2	5		05/15/23 11:46	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### ANALYTICAL RESULTS

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

**Sample: MW-34A**      **Lab ID: 40261462003**      Collected: 04/26/23 10:20      Received: 04/28/23 08:40      Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>		Analytical Method: EPA 6020B Preparation Method: EPA 3010A Pace Analytical Services - Green Bay							
Boron	<b>220</b>	ug/L	10.0	3.0	1	05/02/23 05:28	05/10/23 23:28	7440-42-8	
Calcium	<b>49600</b>	ug/L	254	76.2	1	05/02/23 05:28	05/10/23 23:28	7440-70-2	
<b>Field Data</b>		Analytical Method: Pace Analytical Services - Green Bay							
Field pH	<b>7.53</b>	Std. Units			1		04/26/23 10:20		
Field Specific Conductance	<b>465.8</b>	umhos/cm			1		04/26/23 10:20		
Oxygen, Dissolved	<b>9.87</b>	mg/L			1		04/26/23 10:20	7782-44-7	
REDOX	<b>124.4</b>	mV			1		04/26/23 10:20		
Turbidity	<b>2.11</b>	NTU			1		04/26/23 10:20		
Static Water Level	<b>786.22</b>	feet			1		04/26/23 10:20		
Temperature, Water (C)	<b>10.9</b>	deg C			1		04/26/23 10:20		
<b>2540C Total Dissolved Solids</b>		Analytical Method: SM 2540C Pace Analytical Services - Green Bay							
Total Dissolved Solids	<b>302</b>	mg/L	20.0	8.7	1		05/01/23 10:52		
<b>9040 pH</b>		Analytical Method: EPA 9040 Pace Analytical Services - Green Bay							
pH at 25 Degrees C	<b>7.8</b>	Std. Units	0.10	0.010	1		05/02/23 17:03		H6
<b>300.0 IC Anions</b>		Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay							
Chloride	<b>2.0</b>	mg/L	2.0	0.43	1		05/12/23 18:28	16887-00-6	
Fluoride	<b>&lt;0.095</b>	mg/L	0.32	0.095	1		05/12/23 18:28	16984-48-8	
Sulfate	<b>48.4</b>	mg/L	2.0	0.44	1		05/12/23 18:28	14808-79-8	

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## ANALYTICAL RESULTS

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

**Sample: FIELD BLANK-MOD1-3LF**    **Lab ID: 40261462004**    Collected: 04/27/23 11:00    Received: 04/28/23 08:40    Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
<b>6020B MET ICPMS</b>									
Analytical Method: EPA 6020B    Preparation Method: EPA 3010A Pace Analytical Services - Green Bay									
Boron	<3.0	ug/L	10.0	3.0	1	05/02/23 05:28	05/10/23 19:48	7440-42-8	
Calcium	<76.2	ug/L	254	76.2	1	05/02/23 05:28	05/10/23 19:48	7440-70-2	
<b>2540C Total Dissolved Solids</b>									
Analytical Method: SM 2540C Pace Analytical Services - Green Bay									
Total Dissolved Solids	<8.7	mg/L	20.0	8.7	1		05/01/23 10:52		
<b>9040 pH</b>									
Analytical Method: EPA 9040 Pace Analytical Services - Green Bay									
pH at 25 Degrees C	6.4	Std. Units	0.10	0.010	1		05/02/23 17:16		H6
<b>300.0 IC Anions</b>									
Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay									
Chloride	<0.43	mg/L	2.0	0.43	1		05/12/23 18:43	16887-00-6	
Fluoride	<0.095	mg/L	0.32	0.095	1		05/12/23 18:43	16984-48-8	
Sulfate	<0.44	mg/L	2.0	0.44	1		05/12/23 18:43	14808-79-8	

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

QC Batch: 443772 Analysis Method: EPA 6020B  
QC Batch Method: EPA 3010A Analysis Description: 6020B MET  
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

METHOD BLANK: 2547952 Matrix: Water  
Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Boron	ug/L	<3.0	10.0	05/10/23 19:11	
Calcium	ug/L	<76.2	254	05/10/23 19:11	

LABORATORY CONTROL SAMPLE: 2547953

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Boron	ug/L	250	225	90	80-120	
Calcium	ug/L	10000	9600	96	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2547954 2547955

Parameter	Units	40261411001		2547954		2547955		% Rec Limits	RPD	Max RPD	Qual
		Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec				
Boron	ug/L	32.0	250	250	249	245	87	85	75-125	2	20
Calcium	ug/L	91800	10000	10000	104000	105000	124	132	75-125	1	20 P6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

QC Batch: 443675 Analysis Method: SM 2540C  
QC Batch Method: SM 2540C Analysis Description: 2540C Total Dissolved Solids  
Laboratory: Pace Analytical Services - Green Bay  
Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

METHOD BLANK: 2547666 Matrix: Water  
Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Total Dissolved Solids	mg/L	<8.7	20.0	05/01/23 10:47	

LABORATORY CONTROL SAMPLE: 2547667

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Total Dissolved Solids	mg/L	582	552	95	80-120	

SAMPLE DUPLICATE: 2547668

Parameter	Units	40261457001 Result	Dup Result	RPD	Max RPD	Qualifiers
Total Dissolved Solids	mg/L	448	464	4	10	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR MOD1-3

Pace Project No.: 40261462

QC Batch: 443847

Analysis Method: EPA 9040

QC Batch Method: EPA 9040

Analysis Description: 9040 pH

Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

SAMPLE DUPLICATE: 2548305

Parameter	Units	40261459003 Result	Dup Result	RPD	Max RPD	Qualifiers
pH at 25 Degrees C	Std. Units	7.3	7.3	0	20	H6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



### QUALITY CONTROL DATA

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

QC Batch: 444310 Analysis Method: EPA 300.0  
QC Batch Method: EPA 300.0 Analysis Description: 300.0 IC Anions  
Laboratory: Pace Analytical Services - Green Bay  
Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

METHOD BLANK: 2550800 Matrix: Water  
Associated Lab Samples: 40261462001, 40261462002, 40261462003, 40261462004

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<0.43	2.0	05/12/23 14:40	
Fluoride	mg/L	<0.095	0.32	05/12/23 14:40	
Sulfate	mg/L	<0.44	2.0	05/12/23 14:40	

LABORATORY CONTROL SAMPLE: 2550801

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	20	19.5	98	90-110	
Fluoride	mg/L	2	2.0	101	90-110	
Sulfate	mg/L	20	19.7	99	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2550802 2550803

Parameter	Units	40261459001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chloride	mg/L	2.3	20	20	22.6	22.7	102	102	90-110	0	15	
Fluoride	mg/L	<0.095	2	2	2.1	2.1	105	104	90-110	0	15	
Sulfate	mg/L	11.0	20	20	31.5	31.5	103	103	90-110	0	15	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

## QUALIFIERS

Project: 25223067 COLUMBIA CCR MOD1-3

Pace Project No.: 40261462

---

### DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

### ANALYTE QUALIFIERS

H6 Analysis initiated outside of the 15 minute EPA required holding time.

P6 Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

## REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.

### QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 25223067 COLUMBIA CCR MOD1-3  
Pace Project No.: 40261462

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40261462001	MW-302	EPA 3010A	443772	EPA 6020B	443833
40261462002	MW-33AR	EPA 3010A	443772	EPA 6020B	443833
40261462003	MW-34A	EPA 3010A	443772	EPA 6020B	443833
40261462004	FIELD BLANK-MOD1-3LF	EPA 3010A	443772	EPA 6020B	443833
40261462001	MW-302				
40261462002	MW-33AR				
40261462003	MW-34A				
40261462001	MW-302	SM 2540C	443675		
40261462002	MW-33AR	SM 2540C	443675		
40261462003	MW-34A	SM 2540C	443675		
40261462004	FIELD BLANK-MOD1-3LF	SM 2540C	443675		
40261462001	MW-302	EPA 9040	443847		
40261462002	MW-33AR	EPA 9040	443847		
40261462003	MW-34A	EPA 9040	443847		
40261462004	FIELD BLANK-MOD1-3LF	EPA 9040	443847		
40261462001	MW-302	EPA 300.0	444310		
40261462002	MW-33AR	EPA 300.0	444310		
40261462003	MW-34A	EPA 300.0	444310		
40261462004	FIELD BLANK-MOD1-3LF	EPA 300.0	444310		

### REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,  
without the written consent of Pace Analytical Services, LLC.



Effective Date: 8/16/2022

Client Name: SCS Engineers  
 All containers needing preservation have been checked and noted below.

Sample Preservation Receipt Form  
 Project # 40261462

Yes  No  N/A  
 Lab Lot# of pH paper: 1000702 Lab Std #/ID of preservation (if pH adjusted):

Initial when completed: SG Date/Time:

Pace Lab #	Glass						Plastic						Vials					Jars				General				VOA Vials (>6mm) *	H2SO4 pH ≤2	NaOH+Zn Act pH ≥9	NaOH pH ≥12	HNO3 pH ≤2	pH after adjusted	Volume (mL)									
	AG1U	BG1U	AG1H	AG4S	AG5U	AG2S	BG3U	BP1U	BP3U	BP3B	BP3N	BP3S	BP2Z	VG9C	DG9T	VG9U	VG9H	VG9M	VG9D	JG9U	JG9U	WG9U	WPFU	SP5T	ZPLC								GN 1	GN 2							
001																																									
002																																									2.5 / 5
003																																									2.5 / 5
004																																									2.5 / 5
005																																									2.5 / 5
006																																									2.5 / 5
007																																									2.5 / 5
008																																									2.5 / 5
009																																									2.5 / 5
010																																									2.5 / 5
011																																									2.5 / 5
012																																									2.5 / 5
013																																									2.5 / 5
014																																									2.5 / 5
015																																									2.5 / 5
016																																									2.5 / 5
017																																									2.5 / 5
018																																									2.5 / 5
019																																									2.5 / 5
020																																									2.5 / 5

*4/28/23 SG*

Exceptions to preservation check: VOA, Coliform, TOC, TOX, TOH, O&G, WI DRO, Phenolics, Other: \_\_\_\_\_  
 Headspace in VOA Vials (>6mm):  Yes  No  N/A \*If yes look in headspace column


AG1U	1 liter amber glass	BP1U	1 liter plastic unpres	VG9C	40 mL clear ascorbic w/ HCl	JG9U	4 oz amber jar unpres
BG1U	1 liter clear glass	BP3U	250 mL plastic unpres	DG9T	40 mL amber Na Thio	JG9U	9 oz amber jar unpres
AG1H	1 liter amber glass HCL	BP3B	250 mL plastic NaOH	VG9U	40 mL clear vial unpres	WG9U	4 oz clear jar unpres
AG4S	125 mL amber glass H2SO4	BP3N	250 mL plastic HNO3	VG9H	40 mL clear vial HCL	WPFU	4 oz plastic jar unpres
AG5U	100 mL amber glass unpres	BP3S	250 mL plastic H2SO4	VG9M	40 mL clear vial MeOH	SP5T	120 mL plastic Na Thiosulfate
AG2S	500 mL amber glass H2SO4	BP2Z	500 mL plastic NaOH + Zn	VG9D	40 mL clear vial DI	ZPLC	ziploc bag
BG3U	250 mL clear glass unpres					GN 1	
						GN 2	

Sample Condition Upon Receipt Form (SCUR)

Client Name: SLS Engineers  
 Courier:  CS Logistics  Fed Ex  Speedee  UPS  Walco  
 Client  Pace Other: \_\_\_\_\_

Project #: \_\_\_\_\_

**WO# : 40261462**



40261462

Tracking #: \_\_\_\_\_  
 Custody Seal on Cooler/Box Present:  yes  no Seals intact:  yes  no  
 Custody Seal on Samples Present:  yes  no Seals intact:  yes  no  
 Packing Material:  Bubble Wrap  Bubble Bags  None  Other  
 Thermometer Used SR - 9 Type of Ice:  Wet  Blue  Dry  None  Meltwater Only

Cooler Temperature Uncorr: 1.0 / Corr: 2.0  
 Temp Blank Present:  yes  no Biological Tissue is Frozen:  yes  no

Person examining contents:  
 Date: 4/28/23 Initials: SG  
 Labeled By Initials: mt


Temp should be above freezing to 6°C.  
 Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	5.
- DI VOA Samples frozen upon receipt	<input type="checkbox"/> Yes <input type="checkbox"/> No	Date/Time
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7.
Sufficient Volume:		8.
For Analysis: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No MS/MSD: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A		
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	9.
Correct Type: <u>Pace Green Bay</u> ; Pace IR, Non-Pace		
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix: <u>W3</u>		<u>004 BP3N7P "FB MOD 1-4" 4/28/23</u> <u>004 BP3U57P "Fdd/blk MOD1" SG</u>
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution: \_\_\_\_\_ If checked, see attached form for additional comments   
 Person Contacted: \_\_\_\_\_ Date/Time: \_\_\_\_\_  
 Comments/ Resolution: \_\_\_\_\_

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir  
 Page 2 of 2





# Appendix D

## Historical Monitoring Results

# Single Location

Name: WPL - Columbia

Location ID: MW-33AR

Number of Sampling Dates: 23

Parameter Name	Units	12/21/2015	4/5/2016	7/7/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/7/2017	10/24/2017	4/24/2018	9/21/2018	10/22/2018	4/2/2019	10/8/2019	5/28/2020	10/8/2020	4/13/2021	6/11/2021	10/12/2021	4/12/2022	10/27/2022	4/27/2023
Boron	ug/L	954	813	794	827	812	763	760	692	697	678	601	683	682	568	548	566	569	473	--	564	558	586	532
Calcium	ug/L	50000	48900	50500	79000	63100	57500	66800	80700	84800	98200	99800	--	66900	131000	121000	58400	57100	51600	--	53700	80000	77000	55300
Chloride	mg/L	10.6	12.5	12.5	52.5	39.6	41.4	47.1	68.1	105	119	188	32.6	14.4	229	153	15.9	27.3	26.9	--	22.6	59	40.5	19
Fluoride	mg/L	<0.2	<0.2	<0.2	<0.5	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.1	<0.1	<0.1	<0.095	<0.095	<0.095	--	<0.095	<0.095	<0.095	<0.095
Field pH	Std. Units	7.87	8.08	7.68	8.23	7.63	8.62	8.19	7.78	7.47	7.81	7.74	8.16	7.69	7.72	7.74	7.59	7.7	8.78	7.71	7.59	7.6	7.54	7.61
Sulfate	mg/L	96.2	91.5	99.2	124	132	133	139	151	164	175	163	124	112	201	182	104	97.4	94.3	--	96.4	155	153	104
Total Dissolved Solids	mg/L	356	354	364	456	440	426	446	492	598	606	692	466	388	784	634	376	270	362	--	374	506	440	394
Antimony	ug/L	0.14	0.11	0.18	0.79	0.11	0.12	<0.073	<0.15	0.35	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Arsenic	ug/L	0.46	0.38	0.52	1.2	0.32	0.45	0.31	0.36	0.59	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Barium	ug/L	25.8	24.8	26.8	47.7	37.8	33.8	35.1	37.7	42.4	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Beryllium	ug/L	<0.13	<0.13	<0.13	0.28	<0.13	<0.13	<0.13	<0.18	0.19	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Cadmium	ug/L	<0.089	<0.089	0.11	0.66	<0.089	<0.089	<0.089	<0.081	0.22	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Chromium	ug/L	2.3	2.1	1.9	2.2	1.9	2	2.4	1.5	1.7	--	2.2	--	--	2.4	--	--	--	--	--	--	--	--	--
Cobalt	ug/L	<0.036	<0.036	0.13	0.68	0.039	0.065	<0.036	<0.085	0.23	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Lead	ug/L	<0.04	<0.04	0.14	0.73	<0.04	0.046	<0.04	<0.2	0.35	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Lithium	ug/L	1.3	1.3	1.1	2.8	1.4	1.3	1.2	1.4	1.4	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Mercury	ug/L	<0.1	<0.1	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Molybdenum	ug/L	4.7	4.1	4.4	2.4	3.8	3.6	3	1.3	2.1	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Selenium	ug/L	2.2	2	2.1	2.9	2	2.3	2.3	1.9	2.4	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Thallium	ug/L	<0.14	<0.14	0.17	0.76	<0.14	<0.14	<0.14	<0.14	0.31	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Total Radium	pCi/L	0.76	0.852	1.79	1.01	1.53	0.556	0.313	0.829	1.12	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Radium-226	pCi/L	0.202	0.709	0.835	-0.209	0.834	0.314	0.166	0.3	0.426	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Radium-228	pCi/L	0.558	0.143	0.951	1.01	0.698	0.242	0.147	0.529	0.698	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Field Specific Conductance	umhos/cm	607	417.6	583.4	1255	702	797	1165	689	823	804	1079	632	618.4	1312	1102	633.4	623.5	622	609	623.2	847	737	609.3
Oxygen, Dissolved	mg/L	10.6	9.67	3.82	9.98	9.41	6.46	9.98	10.7	8.1	9.5	3	10.33	9.88	10.22	12.19	10.35	9.31	10.11	11.42	--	9.62	8.91	11.71
Field Oxidation Potential	mV	269	176	39.9	67.7	73.5	193.9	833	101.5	152.1	191	33.8	2.9	136.9	129	165.1	199.4	160.4	125.3	85.3	90	198.2	101.2	176.7
Groundwater Elevation	feet	783.77	763.29	785.19	787.36	785.66	785.88	786.39	787.27	786.11	784.13	783.09	787.9	788.77	786.63	788.26	786.01	785.91	784.27	784.19	783.73	783.27	781.94	785.79
Temperature	deg C	11.6	10.1	11.9	13.2	12.2	11.3	10.3	10.9	12.3	12.5	10.9	13.8	13.6	10.3	12.8	10.7	13.8	9.8	12.7	13.5	10.6	12.7	10.2
Turbidity	NTU	--	1.37	0.57	0.45	0.44	0.23	0.45	0.68	0.32	3.24	0.61	3.79	4.69	2.71	2.13	0	0	0.63	0	0	0	0	0.2
pH at 25 Degrees C	Std. Units	7.8	7.8	7.7	7.6	7.6	7.6	8	7.8	7.4	7.7	7.7	7.8	7.8	7.6	7.6	7.6	7.8	7.8	--	8	7.7	7.9	7.8

**Single Location**

Name: WPL - Columbia

Location ID: MW-34A		Number of Sampling Dates: 25																								
Parameter Name	Units	12/21/2015	4/5/2016	7/7/2016	7/28/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/7/2017	10/24/2017	4/24/2018	9/21/2018	10/22/2018	4/2/2019	10/8/2019	5/28/2020	10/8/2020	2/25/2021	4/13/2021	6/11/2021	10/12/2021	4/12/2022	10/27/2022	4/26/2023
Boron	ug/L	230/205	220	216	--	212	224	214	214	201	205	208	209	241	233	204	207	210	213	--	203	--	212	237	264	220
Calcium	ug/L	65300/65200	63500	60000	--	55600	62800	58900	66300	66900	67300	69600	69600	--	70100	67500	78800	58700	61300	--	61600	--	58100	77000	87300	49600
Chloride	mg/L	4.9/4.8	5.1	5.6	--	6.8	7.1	7.2	6.2	7.8	7.4	7.6	8.2	17.1	19.9	18.7	57.9	3.9	2.1	--	2.3	--	1.9	2.2	2.2	2
Fluoride	mg/L	<0.2/<0.2	<0.2	<0.2	--	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.1	<0.1	<0.1	<0.095	<0.095	--	<0.095	--	<0.095	<0.095	<0.095	<0.095
Field pH	Std. Units	7.91	7.92	7.52	7.4	8.19	7.43	7.71	8.03	7.57	7.39	7.67	7.8	8.12	7.64	7.73	7.79	7.4	7.81	7.57	7.93	7.61	7.68	8.34	7.53	7.53
Sulfate	mg/L	69.9/71.3	71.6	63.4	--	54.8	63.9	71.2	87.6	106	105	98	144	141	123	70.4	39.8	44.4	58.7	--	59.3	--	56.1	146	169	48.4
Total Dissolved Solids	mg/L	300/324	298	304	--	288	242	310	330	366	358	340	412	460	392	310	314	284	306	--	290	--	278	402	436	302
Antimony	ug/L	<0.073/<0.073	<0.073	<0.073	--	0.59	<0.073	<0.073	<0.073	<0.15	<0.15	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Arsenic	ug/L	0.2/0.2	0.35	0.26	--	0.87	0.23	0.36	0.29	<0.28	0.36	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Barium	ug/L	15.8/11.1	9.1	9.4	--	9.9	9.5	8.9	11.6	9.9	10.2	--	--	--	--	--	--	10.2	--	--	--	--	--	--	--	--
Beryllium	ug/L	<0.13/<0.13	<0.13	<0.13	--	0.28	<0.13	<0.13	<0.13	<0.18	<0.18	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Cadmium	ug/L	<0.089/<0.089	<0.089	<0.089	--	0.51	<0.089	<0.089	<0.089	<0.081	0.089	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Chromium	ug/L	2.5/2.2	2	2.2	--	2.2	1.8	1.8	2.4	1.7	1.5	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Cobalt	ug/L	0.29/0.13	0.048	0.16	--	0.53	<0.036	<0.036	0.18	<0.085	0.13	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Lead	ug/L	0.38/0.18	0.046	0.18	--	0.61	0.049	<0.04	0.18	<0.2	<0.2	--	0.61	0.049	<0.04	0.18	<0.2	<0.2	--	--	--	--	--	--	--	--
Lithium	ug/L	0.7/0.64	0.4	0.56	--	0.8	0.51	0.46	0.57	0.45	0.62	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Mercury	ug/L	<0.1/<0.1	<0.1	<0.13	--	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Molybdenum	ug/L	1.1/1.1	1.1	1.1	--	1.7	1.1	1	1.1	0.93	1.1	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Selenium	ug/L	0.77/1	0.78	0.71	--	1.2	0.45	0.82	1.2	0.77	1.2	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Thallium	ug/L	<0.14/<0.14	<0.14	<0.14	--	0.68	<0.14	<0.14	<0.14	<0.14	0.24	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Total Radium	pCi/L	0.689 /0.696	0.869	--	0.788	0.602	0.509	0.477	0.215	0.373	0.348	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Radium-226	pCi/L	0.585 /0.198	0.869	--	-0.132	0.256	-0.235	0.477	0	-0.29	0.0539	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Radium-228	pCi/L	0.104 /0.498	-0.021	--	0.788	0.346	0.509	-0.459	0.215	0.373	0.294	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Field Specific Conductance	umhos/cm	517	386.9	494.3	503.6	819	490	470.9	843	499.1	510.6	454	581.4	578	607.7	531.7	572.9	459	464.2	--	472.6	472.7	478.1	577	648	465.8
Oxygen, Dissolved	mg/L	10	9.38	3.96	5.11	10.33	9.9	9.83	9.96	10.27	8.02	9.9	2.45	10.54	10.62	10.22	11.71	10.12	9.88	--	10.47	11.77	10.1	7.82	8.46	9.87
Field Oxidation Potential	mV	255	163.5	28.8	130.8	77.5	72.9	17.9	82.5	109.3	144.8	207	38.3	-2.6	118.8	104.4	150.9	198.5	143.2	--	118.8	73.4	72.6	112.6	38.8	124.4
Groundwater Elevation	feet	783.5	795.16	785.05	784.86	786.45	785.72	785.98	786.3	786.66	785.81	784.5	781.77	787.01	787.88	786.82	787.92	785.98	785.7	--	784.77	784.66	784.42	784.3	783.61	786.22
Temperature	deg C	11.7	10.9	10.8	10.9	12.2	12.3	12.3	11	11	11.5	11.7	11	12.45	12.7	10.6	13.4	11.1	12.9	--	10.3	12.2	13	11.4	12.6	10.9
Turbidity	NTU	--	4.08	6.3	4.96	2.27	0.95	2.09	15.96	3.7	2.68	14.34	2.72	24.9	9.32	64.77	52.88	84.51	55	--	36.34	9.72	21.13	4.39	1.76	2.11
pH at 25 Degrees C	Std. Units	7.7/7.7	7.7	7.4	--	7.6	7.4	7.3	7.9	7.7	7.8	7.7	7.7	7.7	7.7	7.7	7.7	7.6	7.7	--	7.8	--	7.8	7.8	7.7	7.8

# Single Location

Name: WPL - Columbia

Location ID: MW-84A		Number of Sampling Dates: 24																							
Parameter Name	Units	12/22/2015	4/5/2016	7/8/2016	7/28/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/8/2017	10/24/2017	4/25/2018	8/8/2018	10/24/2018	4/3/2019	10/9/2019	2/3/2020	5/29/2020	10/8/2020	4/14/2021	10/14/2021	4/13/2022	10/27/2022	4/27/2023
Boron	ug/L	11.9	14	14.7	--	11.1	14.7	16.1	12.9	14.8	22.9	13.8	25	12.8	10.1	13.6	12	15.7	10	9.7	14.3	11.1	10.5	12.2	10.3
Calcium	mg/L	74000	72200	67600	--	74000	76000	70800	73200	76100	74900	77500	76600	76000	74000	80100	73500	72700	77600	69200	69100	75300	75100	78400	68600
Chloride	mg/L	4.9	4.7	5.1	--	4.3	4.7	4.6	4.9	5.5	5.5	5.1	4.8	4.9	4.2	3.6	3.9	3.7	3.7	4.3	4.4	3.5	5.2	3.4	3
Fluoride	mg/L	<0.2	<0.2	<0.2	--	<0.1	<0.1	0.12	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095
Field pH	Std. Units	7.6	7.61	7.45	7.34	7.91	7.25	6.99	7.8	7.28	7.23	7.68	7.45	7.38	7.24	7.03	7.23	7.51	7.34	7.49	7.34	7.42	7.34	7.31	7.01
Sulfate	mg/L	4.9	4.3	3.7	--	2.6	2.7	3	2.8	2.7	2	2.2	2.8	1.9	1.6	1.4	1.3	<2.2	1.5	1.3	1.4	1.3	1.4	1.1	1.3
Total Dissolved Solids	mg/L	316	322	316	--	324	316	328	342	344	342	314	328	372	330	318	310	316	340	320	328	326	334	302	326
Antimony	ug/L	<0.073	0.084	0.1	--	<0.073	<0.073	<0.073	<0.073	<0.15	<0.15	--	<0.15	<0.15	<0.15	<0.15	<0.15	--	<0.15	<0.15	0.55	<0.15	<0.15	<0.15	<0.15
Arsenic	ug/L	0.15	0.29	0.14	--	0.35	0.19	0.35	<0.099	<0.28	0.28	--	<0.28	<0.28	0.33	<0.28	0.46	0.38	0.34	0.49	0.91	0.41	0.31	0.72	<0.28
Barium	ug/L	15.3	12.7	12.2	--	14.2	18.4	13.8	14.1	13.4	14	--	14.6	13.7	14.5	14.7	13.2	14	13.9	12.6	13.4	12.9	13.5	13.7	12.6
Beryllium	ug/L	<0.13	<0.13	<0.13	--	<0.13	<0.13	<0.13	<0.13	<0.18	<0.18	--	<0.18	<0.18	<0.18	<0.18	<0.25	--	<0.25	<0.25	0.47	<0.25	<0.25	<0.25	<0.25
Cadmium	ug/L	<0.089	<0.089	<0.089	--	<0.089	<0.089	<0.089	<0.089	<0.081	<0.081	--	<0.081	--	<0.15	<0.15	<0.15	--	<0.15	<0.15	0.53	<0.15	<0.15	<0.15	<0.15
Chromium	ug/L	2.5	1.9	1.8	--	2	2	1.9	2.4	2	1.6	--	2.4	1.5	1.6	1.8	1.6	1.6	1.7	1.6	2.6	1.9	2.2	2.2	1.7
Cobalt	ug/L	0.095	<0.036	0.053	--	<0.036	<0.036	<0.036	<0.036	<0.085	<0.085	--	<0.085	<0.085	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	0.52	0.12	<0.12	<0.12	<0.12
Lead	ug/L	0.16	<0.04	0.39	--	0.049	0.11	<0.04	0.041	<0.2	<0.2	--	<0.2	--	<0.24	<0.24	<0.24	--	<0.24	<0.24	0.55	<0.24	<0.24	<0.24	<0.24
Lithium	ug/L	0.72	0.44	0.5	--	0.56	0.56	0.56	0.55	0.46	0.58	--	0.5	0.4	0.49	0.56	0.52	0.58	0.4	0.39	1	0.28	0.36	0.41	0.71
Mercury	ug/L	<0.1	<0.1	<0.13	--	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	<0.13	--	<0.084	<0.084	<0.084	--	<0.084	<0.066	<0.066	<0.093	<0.066	<0.066	<0.066
Molybdenum	ug/L	<0.07	<0.07	0.073	--	0.12	<0.07	<0.07	<0.07	<0.44	<0.44	--	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	0.62	<0.44	<0.44	<0.44	<0.44
Selenium	ug/L	<0.21	<0.21	<0.21	--	<0.21	<0.21	<0.21	<0.21	<0.32	<0.32	--	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32	0.48	<0.32	<0.32	<0.32	<0.32
Thallium	ug/L	<0.14	<0.14	<0.14	--	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	--	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	0.66	0.19	<0.14	<0.14	<0.14
Total Radium	pCi/L	0.593	0.0809	--	1.37	0.825	0.404	1.39	0.0929	0.676	0.509	--	0.526	0.529	0.62	0.681	0.247	0.1	0.395	0.39	0.285	0.243	0.611	0.673	0.326
Radium-226	pCi/L	0.156	-0.088	--	-0.058	0.132	0.168	0.624	0.0768	0.27	0.242	--	0.155	-0.203	0.313	0.199	0.247	0.1	0.368	0	-0.289	0	0.254	0.267	0
Radium-228	pCi/L	0.437	0.0809	--	1.37	0.693	0.236	0.766	0.0161	0.406	0.267	--	0.371	0.529	0.307	0.482	-0.024	-0.153	0.0273	0.39	0.285	0.243	0.357	0.406	0.326
Field Specific Conductance	umhos/cm	599	427	574.8	579.3	1002	578.2	489	948	535.3	557.2	491	581.7	617.1	609	637.2	614.1	618.4	613.7	610.1	610.9	598.9	600.2	585.2	556.6
Oxygen, Dissolved	mg/L	9.7	9.37	3.78	5.11	9.61	8.94	6.48	9.28	9.46	7.5	9.3	3.94	8.84	10.01	9.49	11.36	8.43	9.81	9.39	9.8	9.25	9.33	8.31	9.37
Field Oxidation Potential	mV	154	165.1	139.9	138.3	82.7	87	192.9	102	123.6	204.7	210	53.3	142.7	71.5	103.4	181.7	121.5	135	153.2	95.6	89.7	200.6	39.9	103.4
Groundwater Elevation	feet	785.31	786.3	785.89	785.61	787.22	786.63	786.7	787.16	787.63	786.68	785.32	785.88	786.55	788.32	787.35	787.79	786.5	787.02	786.1	785.84	784.96	785.02	784.57	786.97
Temperature	deg C	10.4	10.2	11.3	11	11.5	10.8	10.9	10.6	11.3	11.2	11.1	10.2	12	11.6	10.2	11.8	10.3	10.6	11.9	10.2	12.5	9.9	11.7	10.7
Turbidity	NTU	--	0.86	2.75	0.17	0.3	0.25	0.33	0.04	0.56	0.08	2.93	0.81	0.71	3.79	1.9	2.41	1.23	2.15	0	2.45	3.41	0	0	0.72
pH at 25 Degrees C	Std. Units	7.5	7.4	7.4	--	7.3	7.4	7.3	7.7	7.6	7.4	7.6	7.6	7.4	7.5	7.4	7.5	7.4	7.6	7.6	7.6	7.8	7.6	7.4	7.6

# Single Location

Name: WPL - Columbia


Location ID: MW-301																								
Number of Sampling Dates: 23																								
Parameter Name	Units	12/22/2015	4/5/2016	7/8/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/8/2017	10/23/2017	4/25/2018	8/8/2018	10/24/2018	4/2/2019	10/9/2019	2/3/2020	5/29/2020	10/8/2020	4/14/2021	10/14/2021	4/13/2022	10/27/2022	4/27/2023
Boron	ug/L	26.5	25.2	23.6	30.6	32.8	32.6	28.8	21.3	30.6	34.3	24.3	22.8	27.8	26.9	35.9	27.9	21.3	28.8	22.2	31.4	28.7	37.5	20.1
Calcium	ug/L	126000	115000	108000	118000	129000	124000	120000	111000	108000	87200	112000	105000	101000	126000	114000	113000	112000	93000	117000	67800	97300	62800	120000
Chloride	mg/L	3.7	4	3.5	2.2	2	1.5	2	3.5	5.5	4	2.3	5.2	3.2	0.79	1.7	1.3	2	3.4	1.5	2.7	1.9	2.3	1.5
Fluoride	mg/L	<0.2	<0.2	<0.2	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095
Field pH	Std. Units	6.85	7.01	6.87	7.28	6.63	7.1	7.11	6.7	6.75	7.37	6.76	6.91	6.79	6.62	6.67	6.89	6.73	6.95	6.66	7.01	6.6	6.8	6.65
Sulfate	mg/L	9.3	15.3	15	13.9	12.3	6.5	10.3	17.1	31.6	27.5	8.6	21.6	19.2	4.4	8.4	7.2	11.5	25.1	8.5	17.4	12.7	11.6	12.3
Total Dissolved Solids	mg/L	478	486	464	490	444	514	502	458	462	362	464	502	424	462	418	462	452	412	472	334	422	282	526
Antimony	ug/L	0.15	0.094	0.13	<0.073	0.4	<0.073	<0.073	<0.15	<0.15	--	<0.15	0.36	<0.15	0.32	<0.15	--	<0.15	0.33	<0.15	<0.15	0.31	<0.15	<0.15
Arsenic	ug/L	0.26	0.26	0.19	0.24	0.4	0.13	0.18	<0.28	<0.28	--	<0.28	0.45	<0.28	0.4	0.42	<0.28	0.33	0.62	<0.28	0.35	0.47	0.3	<0.28
Barium	ug/L	20.2	11.1	11.6	15.6	15	13.5	13.2	11.3	11.8	--	9.3	10.2	11.5	11.8	10	10.9	9.8	9.4	8.9	7.7	7.8	7.5	9.8
Beryllium	ug/L	<0.13	<0.13	<0.13	<0.13	0.19	<0.13	<0.13	<0.18	<0.18	--	<0.18	0.37	<0.18	0.28	<0.25	--	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25
Cadmium	ug/L	<0.089	<0.089	<0.089	<0.089	0.32	<0.089	<0.089	<0.081	<0.081	--	<0.081	--	<0.15	0.21	<0.15	--	<0.15	0.19	<0.15	<0.15	0.3	<0.15	<0.15
Chromium	ug/L	2.1	0.58	0.59	<0.39	0.7	0.53	0.7	2.3	<1	--	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1
Cobalt	ug/L	1.4	0.25	0.22	0.041	0.38	0.071	0.064	0.13	0.12	--	<0.085	0.28	<0.12	0.35	<0.12	0.17	<0.12	0.29	<0.12	0.34	0.32	0.52	<0.12
Lead	ug/L	0.9	0.077	0.48	<0.04	0.34	<0.04	<0.04	<0.2	<0.2	--	<0.2	--	<0.24	0.3	<0.24	--	<0.24	0.25	<0.24	<0.24	3.1	<0.24	<0.24
Lithium	ug/L	1.3	0.58	0.69	0.6	0.87	0.67	0.68	0.62	0.6	--	0.55	0.85	0.52	0.9	0.61	0.67	0.47	0.46	0.58	0.46	0.56	0.37	0.62
Mercury	ug/L	<0.1	<0.1	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	<0.13	--	<0.084	<0.084	<0.084	--	<0.084	<0.066	<0.066	<0.093	<0.066	<0.066	<0.066
Molybdenum	ug/L	0.35	0.15	0.14	0.12	0.38	<0.07	<0.07	<0.44	<0.44	--	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44	<0.44
Selenium	ug/L	0.3	0.21	0.39	<0.21	0.26	<0.21	<0.21	<0.32	<0.32	--	<0.32	0.71	<0.32	0.49	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32	<0.32
Thallium	ug/L	<0.14	<0.14	<0.14	<0.14	0.48	<0.14	<0.14	<0.14	<0.14	--	<0.14	0.3	<0.14	0.48	<0.14	<0.14	<0.14	0.3	<0.14	0.17	0.32	<0.14	<0.14
Total Radium	pCi/L	1.31	1.11	0.89	0.631	1.01	2.42	1.35	1.3	1.74	--	0.882	0.0351	0.652	0.552	0.701	0.502	0.193	0.38	1.16	0.172	0.179	0.00292	0.417
Radium-226	pCi/L	0.655	0.294	0.404	-0.067	0.108	1.46	0.513	0.287	1.09	--	0.122	-0.06	0.247	0	0.252	0.136	0	0.0511	0.418	0.172	0	-0.169	0
Radium-228	pCi/L	0.651	0.82	0.486	0.631	0.905	0.964	0.833	1.01	0.647	--	0.76	0.0351	0.405	0.552	0.449	0.366	0.193	0.329	0.739	-0.0327	0.179	0.00292	0.417
Field Specific Conductance	umhos/cm	897	573	796	1464	859	1018	1354	698.4	691.7	561	774	799	767	883	801	868	797	760	857	597.2	747	507.5	857
Oxygen, Dissolved	mg/L	1.7	2.71	1.47	1.99	1.34	1.24	1.44	1.81	1.43	1.1	2.35	2.14	2.49	2.2	1.67	1.07	2	1.22	3.9	0.25	2.47	0.1	6.5
Field Oxidation Potential	mV	135	123.7	133.9	100.8	95.8	226.1	100.9	115.1	187.4	204	74.3	126.5	77.9	152.1	173	132.3	118.7	183.9	102.9	57.8	207.5	80.9	95.3
Groundwater Elevation	feet	785.56	768.12	786.31	787.64	787.37	787.27	787.89	788.25	787.34	785.89	785.29	787.06	788.98	787.04	788.47	787.24	787.77	786.53	786.5	785.28	785.44	784.91	787.57
Temperature	deg C	9.7	7.7	10	11.2	10.1	8.8	7.7	8.9	10.2	11.1	7.4	10.6	11.1	7.5	11.3	8.5	8.1	11	7.4	11.1	7.1	10.8	8
Turbidity	NTU	--	1.52	3.89	0.59	0.74	0.42	0.1	0.22	0.18	1.52	1.12	0.46	3.3	2.02	2.12	1.41	0	0	2.41	3.21	0	0	0
pH at 25 Degrees C	Std. Units	7	7	6.8	6.8	6.9	6.9	7.1	7	7	7.3	7	7	7.1	6.8	7	6.8	7	7.2	6.9	7.3	7	7.1	6.9

# Single Location

Name: WPL - Columbia

Location ID: MW-302																									
Number of Sampling Dates: 23																									
Parameter Name	Units	12/22/2015	4/5/2016	7/7/2016	10/13/2016	12/29/2016	1/25/2017	4/11/2017	6/6/2017	8/8/2017	10/24/2017	4/24/2018	9/21/2018	10/22/2018	4/2/2019	10/9/2019	5/29/2020	10/8/2020	4/13/2021	10/14/2021	4/12/2022	10/27/2022	4/27/2023	8/31/2023	
Boron	ug/L	80	78.8	134	132	106	149	322	671	833	691	1950	203	296	254	246	611	648	521	495	389	374	541	--	
Calcium	ug/L	68800	65900	66900	71700	76100	75400	79600	88900	87100	94400	110000	--	56900	62400	61400	90500	80600	82400	84100	91600	91200	66500	--	
Chloride	mg/L	4.2	4.1	3.1	1.1	1.2	1.6	1.6	3.5	4.5	6.9	15	1.7	1.8	1.5	1.1	1.2	1.1	1.4	1.3	0.79	2.1	1.3	--	
Fluoride	mg/L	<0.2	<0.2	<0.2	<0.1	<0.1	0.13	<0.1	<0.1	<0.1	<0.1	<0.1	--	<0.1	<0.1	<0.1	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095	<0.095	--	
Field pH	Std. Units	7.63	7.7	7.29	7.72	7.12	8.21	7.63	7.16	7.04	8.23	7.21	7.74	7.22	7.32	7.08	7.2	7.21	7.51	7.07	7.21	7.25	7.36	7.33	
Sulfate	mg/L	37.4	55.6	35.4	64.7	56.4	61.6	81.3	84.6	79	78.4	109	30	26.9	25.2	16.7	34.6	36.5	36.9	37.8	22.1	30.3	36.6	--	
Total Dissolved Solids	mg/L	312	312	344	360	330	384	436	466	470	446	598	280	288	290	274	404	378	370	394	398	348	352	--	
Antimony	ug/L	0.17	0.092	0.2	0.14	0.14	0.17	<0.073	<0.15	<0.15	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Arsenic	ug/L	<0.099	0.17	0.23	0.2	<0.099	0.24	<0.099	<0.28	<0.28	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Barium	ug/L	14.3	9.7	14.6	16.4	16.9	17.8	20.3	22	22.2	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Beryllium	ug/L	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.18	<0.18	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Cadmium	ug/L	<0.089	<0.089	0.14	<0.089	<0.089	<0.089	<0.089	<0.081	<0.081	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Chromium	ug/L	2.3	3.3	2.7	1.7	2.4	2.6	2.7	2.3	2	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Cobalt	ug/L	0.11	0.11	0.2	<0.036	0.079	0.083	0.08	<0.085	<0.085	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Lead	ug/L	0.1	0.084	0.24	<0.04	0.073	0.075	0.047	<0.2	<0.2	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Lithium	ug/L	17.1	13.7	4.5	3	3.3	3.2	2.7	2.2	2.4	--	--	--	--	--	--	--	--	--	--	--	--	--	3.3	
Mercury	ug/L	<0.1	<0.1	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	<0.13	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Molybdenum	ug/L	8.9	8	2.4	1.6	1.6	1.6	1.5	1.3	1.6	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Selenium	ug/L	2.8	2.7	1.8	1.2	2	1.6	2.5	2	2.4	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Thallium	ug/L	<0.14	<0.14	0.24	<0.14	<0.14	<0.14	<0.14	<0.14	<0.14	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Total Radium	pCi/L	0.184	0.505	1.21	0.4	0.252	2.6	0.555	1.45	0.731	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Radium-226	pCi/L	0.184	0.1	-0.358	0.208	-0.103	1.37	0.077	0.649	0.193	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Radium-228	pCi/L	-0.028	0.405	1.21	0.192	0.252	1.23	0.478	0.802	0.538	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
Field Specific Conductance	umhos/cm	566	383.6	578	1006	588.9	726	1114	641.8	679	596	894	461	507.6	538.6	515.4	694.7	643.1	661.3	663.7	677.1	616.1	605.2	566.8	
Oxygen, Dissolved	mg/L	6.8	9.7	3.7	9.37	8.5	6.22	9.53	9.91	7.4	8.7	2.8	9.82	9.34	9.65	11.38	10	9.21	9.92	8.07	8.74	8.6	10.91	11.98	
Field Oxidation Potential	mV	132	198.6	80	96.3	88.9	223.4	107.4	130.4	191.1	220	49.1	56	135.1	126.7	134.5	169.2	152.7	127	149.1	197.1	38.2	144.7	259	
Groundwater Elevation	feet	784.78	778.91	786.28	787.76	787.05	786.89	787.55	788.37	787.55	785.94	784.37	788.37	789.16	787.56	788.31	787.29	786.74	785.77	785.09	784.42	784.62	786.87	785.3	
Temperature	deg C	10.6	9.8	11.2	12.2	11.1	10.4	9.5	10.1	11.4	11.4	10.7	12.45	13.1	9.8	12.6	9.8	11.8	9.6	11.5	9.5	11.6	9.7	11.9	
Turbidity	NTU	--	9.69	2.08	0.81	1.78	1.26	1.68	1.9	0.83	2.61	3.42	5.26	5.23	9.72	2.01	2.88	0	2.6	2.54	3.92	0	1.82	3.87	
pH at 25 Degrees C	Std. Units	7.5	7.6	7.3	7.2	7.1	7.8	7.6	7.5	7.4	7.2	7.4	7.4	7.3	7.4	7.4	7.4	7.6	7.4	7.7	7.4	7.4	7.7	--	





Appendix E  
Alternative Source Demonstrations

# E1 October 2022 Detection Monitoring Alternative Source Demonstration

# Alternative Source Demonstration October 2022 Detection Monitoring

Dry Ash Disposal Facility, Modules 1-3  
Columbia Energy Center  
Pardeeville, Wisconsin

Prepared for:



**SCS ENGINEERS**

25223067.00 | May 31, 2023

2830 Dairy Drive  
Madison, WI 53718-6751  
608-224-2830

## Table of Contents

Section	Page
<b>PE Certification</b> .....	<b>iii</b>
<b>1.0 Introduction</b> .....	<b>1</b>
1.1 §257.94(e)(2) Alternative Source Demonstration Requirements .....	1
1.2 Site Information and Map .....	1
1.3 Statistically Significant Increases Identified .....	2
1.4 Overview of Alternative Source Demonstration.....	2
<b>2.0 Background</b> .....	<b>3</b>
2.1 Regional Geology and Hydrogeology .....	3
2.1.1 Regional Information .....	3
2.1.2 Site Information .....	3
2.2 CCR Rule Monitoring System .....	3
2.3 Other Monitoring Wells.....	4
<b>3.0 Methodology and Analysis Review</b> .....	<b>4</b>
3.1 Sampling and Field Analysis .....	4
3.2 Laboratory Analysis Review .....	4
3.3 Statistical Evaluation Review.....	5
3.4 Summary of Methodology and Analysis Review Findings .....	5
<b>4.0 Alternative Sources</b> .....	<b>5</b>
4.1 Potential Causes of SSI.....	5
4.1.1 Natural Variation .....	5
4.1.2 Man-Made Alternative Sources .....	5
4.2 Lines of Evidence .....	6
4.2.1 Pre-Landfill Water Quality .....	6
4.2.2 Long-Term Concentration Trends .....	7
4.2.3 Groundwater Flow Direction Changes.....	7
4.2.4 Chloride and Boron Concentrations .....	8
<b>5.0 Alternative Source Demonstration Conclusions</b> .....	<b>8</b>
<b>6.0 Site Groundwater Monitoring Recommendations</b> .....	<b>8</b>
<b>7.0 References</b> .....	<b>8</b>

### Tables

Table 1.	Groundwater Analytical Results Summary – October 2022 Event
Table 2.	Historical Analytical Results for Parameters with SSIs
Table 3.	Groundwater Elevation – State Monitoring Program and CCR Well Network
Table 4.	Analytical Results – Lysimeters and Leachate Pond

## Figures



- Figure 1. Site Location Map
- Figure 2. Site Plan and Monitoring Well Locations
- Figure 3. Water Table Map – October 2022

## Appendices

- Appendix A Trend Plots for CCR Wells
- Appendix B Feasibility Study Water Quality Information
- Appendix C Long-Term Concentration Trend Plots
- Appendix D Historical Groundwater Flow Maps

I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\230531\_COL\_1-3 LF\_Oct22 ASD\_Final.docx

# PE CERTIFICATION

	<p>I, Sherren Clark, hereby certify that the information in this alternative source demonstration is accurate and meets the requirements of 40 CFR 257.94(e)(2). This certification is based on my review of the groundwater data and related site information available for the Columbia Energy Center Dry Ash Disposal Facility. I am a duly licensed Professional Engineer under the laws of the State of Wisconsin.</p>
	
	<p>5/31/2023</p>
	<p>(signature) <span style="float: right;">(date)</span></p>
	<p>Sherren Clark, PE (printed or typed name)</p> <p>License number E-29863</p> <p>My license renewal date is July 31, 2024.</p> <p>Pages or sheets covered by this seal: Alternative Source Demonstration, October 2022 Detection Monitoring, Dry Ash Disposal Facility, Modules 1-3, Columbia Energy Center, Pardeeville, Wisconsin</p>

[This page left blank intentionally]



## 1.0 INTRODUCTION

This Alternative Source Demonstration (ASD) was prepared to support compliance with the groundwater monitoring requirements of the “Coal Combustion Residuals (CCR) Final Rule” published by the U.S. Environmental Protection Agency (U.S. EPA) in the *Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule*, dated April 17, 2015 (U.S. EPA, 2015), and subsequent amendments. Specifically, this report was prepared to fulfill the requirements of 40 CFR 257.94(e)(2). The applicable sections of the Rule are provided below in *italics*.

### 1.1 §257.94(E)(2) ALTERNATIVE SOURCE DEMONSTRATION REQUIREMENTS

*The owner and operator may demonstrate that a source other than the CCR Unit caused the statistically significant increase over background levels for a constituent or that the statistically significant increase resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality. The owner or operator must complete the written demonstration within 90 days of detecting a statistically significant increase over background levels.*

An ASD is completed when there are exceedances of one or more benchmarks established within the groundwater monitoring program to determine if any other sources are likely causes of the identified exceedance(s) of established benchmark(s) at the site. This ASD was performed in response to results indicating a statistically significant increase (SSI) over background levels during detection monitoring under the CCR Rule.

This ASD report evaluates the SSIs observed in the statistical evaluation of the October 2022 detection monitoring event at the Columbia Energy Center (COL) Dry Ash Disposal Facility (ADF), Modules 1-3 CCR Unit. The first ASD was prepared for this facility evaluating the SSIs observed in the statistical evaluation of the October 2017 detection monitoring event (SCS Engineers [SCS], 2018). The October 2017 ASD and subsequent semiannual updates have provided several lines of evidence demonstrating that SSIs reported for boron, chloride, field pH, and sulfate concentrations in the downgradient monitoring wells were likely due to man-made sources other than the CCR Units and/or naturally occurring constituents in the alluvial aquifer.

As discussed in more detail in **Section 4.2** of this ASD, the findings for the October 2022 monitoring event were consistent with those for the previous events.

### 1.2 SITE INFORMATION AND MAP

The COL site is located at W8375 Murray Road, Pardeeville, Columbia County, Wisconsin (**Figure 1**). The COL site is an active coal-burning generating station, which has been burning coal and disposing of CCR on-site since the mid-1970s. The layout of the site is shown on **Figure 2**. The COL property includes two areas of CCR storage and disposal. These are the ADF and the Ash Ponds Facility. This ASD will evaluate the conditions at the site for Modules 1-3 of the ADF only. The ADF is operated under the Wisconsin Department of Natural Resources (WDNR) License No. 3025.

The groundwater monitoring system monitors the following CCR Unit:

- COL Dry ADF – Modules 1-3 (existing CCR Landfill)

Modules 1-3 were originally described as separate existing CCR landfills, although they are contiguous and are managed as a single landfill by the facility and by the WDNR. Wisconsin Power and Light Company (WPL) subsequently clarified that Modules 1-3 are one existing CCR landfill under the federal CCR Rule, and this report reflects WPL's clarification.

A map showing the CCR Unit and all background (or upgradient) and downgradient monitoring wells with identification numbers for the CCR groundwater monitoring program and the state monitoring program is provided as **Figure 2**. Separate monitoring systems have been established for the other CCR Units at COL, which include Modules 4-6 of the COL ADF, the primary ash pond, and the secondary ash pond.

### 1.3 STATISTICALLY SIGNIFICANT INCREASES IDENTIFIED

SSIs were identified by comparing the monitoring results to Upper Prediction Limits (UPLs) established in accordance with 40 CFR 257.93(f)(3) and the statistical method previously selected for the CCR Unit. The UPLs are based on an interwell approach using two background monitoring wells: MW-84A and MW-301. The interwell UPLs were calculated based on a 1-of-2 resampling approach. The UPLs and results for the October 2022 monitoring event are summarized in **Table 1**.

The October 2022 SSIs include the following parameters and wells:

- Boron: MW-33AR, MW-34A, MW-302
- Chloride: MW-33AR
- Sulfate: MW-33AR, MW-34A, MW-302

Concentration trends for the parameters with SSIs are shown in **Appendix A**.

### 1.4 OVERVIEW OF ALTERNATIVE SOURCE DEMONSTRATION

This ASD report includes:

- Background information (**Section 2.0**).
- Evaluation of potential that SSIs are due to methodology or analysis (**Section 3.0**).
- Evaluation of potential that SSIs are due to natural sources or man-made sources other than the CCR Units (**Section 4.0**).
- ASD conclusions (**Section 5.0**).
- Monitoring recommendations (**Section 6.0**).

The CCR Rule constituent results from background and compliance sampling for parameters with SSIs are provided in **Table 2**. The laboratory reports for the October 2022 detection monitoring event will be included in the 2023 Annual Groundwater Monitoring and Corrective Action Report to be completed in January 2024. Complete laboratory reports for the background monitoring events and the previous detection monitoring events were included in previous annual groundwater monitoring and corrective action reports.

## 2.0 BACKGROUND

To provide context for the ASD evaluation, the following background information is provided in this section of the report, prior to the ASD evaluation sections:

- Geologic and hydrogeologic setting
- CCR Rule monitoring system
- Other monitoring wells

A more detailed discussion of the background information for the site is provided in the ASD for the October 2017 event (SCS, 2018).

## 2.1 REGIONAL GEOLOGY AND HYDROGEOLOGY

### 2.1.1 Regional Information

For the purposes of groundwater monitoring, the surficial sand and gravel aquifer is considered the uppermost aquifer, as defined under 40 CFR 257.53. Immediately underlying the surficial sand and gravel aquifer is the Cambrian-Ordovician sandstone aquifer.

Additional details on the regional geology and hydrogeology were provided in the October 2017 ASD (SCS, 2018).

### 2.1.2 Site Information

Soils at the site are primarily sand to a depth of approximately 50 to 100 feet, and overlie sandstone bedrock. Soils encountered during the site feasibility study for the COL ADF were described as generally sandy with interbedded silty clay lenses up to 20 feet thick (Warzyn, 1978). During drilling of CCR wells MW-301 and MW-302, the unconsolidated materials were identified as consisting primarily of silty sand and sand. Boring logs for previously installed monitoring wells MW-33AR, MW-34A, MW-84A, and MW-1AR (abandoned) show silty sand and sand as the primary unconsolidated materials at these locations. All CCR monitoring wells are screened within the unconsolidated sand unit.

Shallow groundwater at the site generally flows to the north and west across the existing landfill Modules 1-3 area, then generally flows west toward the Wisconsin River. The groundwater flow map for October 2022 is shown on **Figure 3**. Historically, localized groundwater mounding was associated with the ash ponds, but the ash ponds are currently in the closure process. The October 2022 flow map shows temporary inward gradients in the vicinity of the Secondary Ash Pond due to dewatering activities. These temporary changes in flow do not affect groundwater flow directions in the vicinity of Mod 1-3. The groundwater elevation data for the CCR monitoring wells and state monitoring program wells are provided in **Table 3**.

## 2.2 CCR RULE MONITORING SYSTEM

The groundwater monitoring system established in accordance with the CCR Rule consists of two upgradient (background) monitoring wells and three downgradient monitoring wells (**Table 1** and **Figure 2**). The background wells include MW-301 and MW-84A. The downgradient wells include MW-302, MW-33AR, and MW-34A. MW-1AR was added to the monitoring program in 2021 as a supplemental well because monitoring data have indicated that the groundwater flow direction in this part of the site is sometimes to the northeast. MW-1AR was abandoned in 2022 because it was

within the footprint of the pending MOD 10-11 expansion area. The monitoring network certification was updated with the abandonment of MW-1AR in October 2022. Flow direction in this area of the site will continue to be monitored by additional wells in the State monitoring program, including new water level-only monitoring wells MW-312 and MW-93A, which will be part of the future Modules 10 and 11 monitoring well network. The CCR Rule wells are installed within the sand and gravel aquifer. Well depths range from approximately 29 to 51 feet, measured from the top of the well casing.

## **2.3 OTHER MONITORING WELLS**

Additional groundwater monitoring wells currently exist at COL as part of the monitoring systems developed for the state monitoring program and for the other CCR Units.

Monitoring wells for the state monitoring program are installed in the unconsolidated sand and gravel unit, which is the uppermost aquifer as defined under 40 CFR 257.53. This shallow monitoring system includes water table wells and mid-depth piezometers. Well depths range from approximately 14 to 76 feet, measured from the top of the well casing.

## **3.0 METHODOLOGY AND ANALYSIS REVIEW**

To evaluate the potential that an SSI is due to a source other than the regulated CCR Unit, SCS used a two-step evaluation process. First, the sample collection, field and laboratory analysis, and statistical evaluation were reviewed to identify any potential error or analysis that led to exceedance of the benchmark. Second, potential alternative sources, including natural variation and man-made sources other than the CCR Unit, were evaluated. This section of the report provides the findings of the methodology and analysis review. **Section 4.0** of the report addresses the potential alternative sources.

### **3.1 SAMPLING AND FIELD ANALYSIS**

Field notes and sampling results were reviewed to determine if any sampling error may have caused or contributed to the observed SSIs. Potential field sampling errors or issues could include mislabeling of samples, improper sample handling, missed holding times, cross-contamination during sampling, or other field error. Field blank sample results were also reviewed for any indication of potential contamination from sampling equipment or containers.

SCS did not identify any sampling errors for field data that may have caused or contributed to observed SSIs.

The October 2022 monitoring event was completed in accordance with the Sampling and Analysis Plan for the monitoring system.

### **3.2 LABORATORY ANALYSIS REVIEW**

The laboratory reports for the October 2022 detection monitoring event were reviewed to determine if any laboratory analysis error or issue may have caused or contributed to an observed SSI for boron, chloride, or sulfate. The laboratory report review included reviewing the laboratory quality control flags and narrative, verifying that correct methods were used and desired detection limits were achieved, and checking the field and laboratory blank sample results.

Based on the review of the laboratory reports, SCS did not identify any laboratory analysis issues that could have caused or contributed to the observed SSIs for boron, chloride, and sulfate.

Time series plots of the SSI constituent analytical data were also reviewed for any anomalous results that might indicate a possible sampling or laboratory error (e.g., dilution error or incorrect sample labeling). The time series plots are provided in **Appendix A**. The concentrations observed are similar to historical concentrations. The sulfate concentration at MW-34A was slightly higher than other recent results, but within the range of historical results (see Section 4.2.2) and does not appear to be an anomalous result due to sampling or laboratory error.

### **3.3 STATISTICAL EVALUATION REVIEW**

The review of the statistical results and methods included a quality control check of the following:

- Input analytical data vs. laboratory analytical reports
- Statistical method and process for each SSI

Based on the review of the statistical evaluation, SCS did not identify any errors or issues in the statistical evaluation that caused or contributed to the determination of interwell SSIs for the October 2022 detection monitoring event.

### **3.4 SUMMARY OF METHODOLOGY AND ANALYSIS REVIEW FINDINGS**

In summary, there were no changes to the SSI determinations for the October 2022 monitoring event based on the methodology and analysis review. No other errors or issues causing or contributing to the reported SSIs were identified.

## **4.0 ALTERNATIVE SOURCES**

This section of the report discusses the potential alternative sources for the boron, chloride, and sulfate SSIs at the downgradient monitoring wells; identifies the most likely alternative source(s); and presents the lines of evidence indicating that an alternative source is the most likely cause of the observed SSIs.

### **4.1 POTENTIAL CAUSES OF SSI**

#### **4.1.1 Natural Variation**

The statistical analysis was completed using an interwell approach, comparing the October 2022 detection monitoring results to the UPLs calculated based on the sampling of the background wells (MW-84A and MW-301). If concentrations of a constituent that is naturally present in the aquifer vary spatially, then the potential exists that the downgradient concentrations may be higher than upgradient concentrations due to natural variation. Previous monitoring results for boron, chloride, and sulfate at COL Modules 1-3 landfill are shown in **Table 2**.

Although natural variation is present in the shallow aquifer, it does not appear likely that natural variation is the primary source causing the boron, chloride, and sulfate SSIs.

#### **4.1.2 Man-Made Alternative Sources**

Man-made alternative sources that could potentially contribute to the boron, chloride, and sulfate SSIs could include the closed ash pond landfill, the active and inactive ash ponds, the former ash

pond effluent ditch, the coal storage area, road salt use, railroad operations, or other plant operations.

Based on the groundwater flow directions and on previous investigations at the site, the former ash pond effluent ditch appears to be the most likely cause of the boron and/or sulfate SSIs for wells MW-33AR, MW-34A, and MW-302. The ash pond effluent ditch, a non-CCR alternative source, also likely contributed to the chloride SSI at MW-33AR.

## 4.2 LINES OF EVIDENCE

The lines of evidence indicating that the SSIs for boron, chloride, and sulfate in compliance wells MW-33AR, MW-34A, and MW-302, relative to the background wells, are due to an alternative source include:

1. Elevated levels of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located before the landfill was constructed.
2. Monitoring performed under the state program documents that the concentrations of boron, chloride, and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation.
3. Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west and/or north.
4. The variations in chloride results for well MW-33AR since detection monitoring was initiated have not correlated with boron concentrations, as would be expected for a CCR leachate source; therefore, an alternative source is more likely.

### 4.2.1 Pre-Landfill Water Quality

Elevated levels of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located, before the landfill was constructed. Groundwater monitoring performed in 1977 and 1978 as part of the Feasibility Study for the landfill permitting showed that wells located along the west side of the future landfill footprint, where the current compliance wells are located, had elevated results for sulfate, chloride, and specific conductance. The 1978 Feasibility Study (Warzyn, 1978) for the dry ADF discusses the influence of the ash pond effluent ditch on groundwater west of the proposed site. The former ash pond effluent ditch carried effluent from the ash ponds located north of the plant, and flowed south between the west side of the current landfill and the substation. Groundwater monitoring in December 1977 indicated that sulfate was present at 1,200 milligrams per liter (mg/L) in MW-33A, which was located near the point where the ash pond effluent discharged from a culvert into the effluent ditch. The sulfate concentration at this well decreased to 830 mg/L in the December 1978 sampling (Warzyn, 1979). Current concentrations of sulfate in this area, while above background, are much lower. The October 2022 sulfate result for MW-33AR (installed to replace MW-33A) was 153 mg/L, for MW-34A was 169 mg/L, and for MW-302 was 30.3 mg/L (Table 1).

Selected text and tables from the 1978 Feasibility Study and the 1979 Supplementary Feasibility Study Report are included in **Appendix B**.



## 4.2.2 Long-Term Concentration Trends

Monitoring performed under the state program documents that the concentrations of boron and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation. Routine groundwater monitoring for the COL ADF began after the Plan of Operation was approved and prior to initial CCR disposal. The earliest data available from the WDNR Groundwater Environmental Monitoring System (GEMS) database is from September 1984. Initial placement of CCR in test plots in Module 1 of the ADF was approved in October 1984, and CCR disposal began sometime after that. Therefore, the initial groundwater monitoring results in the GEMS database represent pre-disposal conditions for the landfill.

The earliest historic monitoring data show that before CCR disposal in the landfill began, concentrations of boron and sulfate were significantly higher than current concentrations in the area west of the landfill where the compliance wells are located. Graphs of historical concentrations are provided in **Appendix C**. Results for compliance well MW-33AR are plotted with results from well MW-33A. MW-33AR was a replacement well for MW-33A at a slightly different location and depth. The well screen was installed approximately 10 feet higher in MW-33AR than in MW-33A, intersecting the water table, which may explain the increase in concentration that occurred with the well replacement. Results for compliance well MW-302 are plotted with results from monitoring well MW-85, which was located near the current MW-302 location (see **Figure 2**) and was monitored from September 1984 through September 1995.

The recent boron concentrations are consistent with generally decreasing or stable historical concentrations at MW-33AR and MW-34A (**Appendix A** and **Appendix C**). Recent boron concentrations at MW-302 have been variable, but remain well below the concentrations observed in samples from MW-85 prior to CCR disposal in the landfill.

## 4.2.3 Groundwater Flow Direction Changes

Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west. The 1978 Feasibility Study report states that the southern 2/3 of the proposed fill area (including the area of the active CCR landfill phases) exhibits a southeast and southerly groundwater flow direction, toward an agricultural drainage ditch southeast and south of the landfill area. The 1981 Plan of Operation indicates that flow in the landfill area is to the east-southeast. A water table map prepared by RMT, based on October 2002 water level measurements, shows flow under the landfill generally to the east and northeast from a groundwater high near the effluent ditch and Wisconsin Pollutant Discharge Elimination System (WPDES) pond between the landfill and the substation. The 1981 and 2002 water table maps are provided in **Appendix D**.

Under current conditions, groundwater flow below the active landfill area is generally to the north and northwest. The flow changes with time reflect the termination of discharge to the ash pond effluent ditch in the mid-2000s. When discharge via this ditch was active, the ditch was a source of recharge to the groundwater and created a high groundwater area with flow moving away from the ditch to the east. After discharge to the ditch was terminated, water levels in this area decreased significantly and the groundwater flow direction changed.

With the changes in groundwater flow, historically impacted groundwater moved in alternating directions. While the effluent ditch was active, impacted groundwater likely moved eastward past the current compliance wells, as indicated by the long-term concentration data. Although the compliance



wells on the west side of MOD 1-3 are downgradient from the landfill under current flow conditions, the observed groundwater impacts may be residual from the past when the wells were downgradient from the effluent ditch.

#### **4.2.4 Chloride and Boron Concentrations**

The chloride results for well MW-33AR increased beginning in 2016, peaked in April 2018 and April 2019, decreased significantly in May 2020, and have remained relatively consistent since then. A slight increase was observed in the sample collected during the April 2022 event, followed by a decrease for the October 2022 event. The 2022 concentrations were still significantly lower than the values observed in 2019 (**Table 2** and **Appendix A**). Over the same time period, boron concentrations at MW-33AR have been stable, following a long steady decreasing trend.

The lack of correlation with boron indicates the source of the increase and subsequent decrease in chloride is not likely the CCR landfill. Sampling of the landfill leachate pond and lysimeters LS-1 and LS-3R, located on the western and southern edges of MOD 1-3, indicates that boron and chloride concentrations are generally both higher than background (**Table 5**); therefore, a leachate source would tend to influence concentrations of both parameters. Furthermore, the peak chloride concentrations in the groundwater samples from MW-33AR in 2018 and 2019 exceeded the chloride concentrations measured in the leachate at that time, indicating the leachate was not the source of chloride at this location (**Table 2**, **Table 5**, and **Appendix A**). Recent samples from the leachate pond have shown increased concentrations of chloride, but this increase does not correlate with results at MW-33AR, which have decreased, or with chloride results from the lysimeters, which remain low. Based on the comparison of groundwater and leachate chloride results, an alternative man-made source, such as road salt, is a more likely source of chloride than the CCR Unit.

### **5.0 ALTERNATIVE SOURCE DEMONSTRATION CONCLUSIONS**

The lines of evidence discussed above regarding the SSIs reported for boron, chloride, and sulfate concentrations in downgradient monitoring wells MW-33AR, MW-34A, and/or MW-302 demonstrate that the SSIs are likely primarily due to sources other than the CCR Unit. Boron, sulfate, and chloride concentrations were elevated prior to disposal of CCR in the landfill and are associated with historical discharges from the ash ponds via the effluent ditch located west of the landfill. Elevated chloride concentrations detected at well MW-33AR appear likely to be related to an alternative non-CCR source, such as salt.

### **6.0 SITE GROUNDWATER MONITORING RECOMMENDATIONS**

In accordance with section 257.94(e)(2) of the CCR Rule, the COL Modules 1-3 CCR Units may continue with detection monitoring based on this ASD. The ASD report will be included in the 2023 Annual Report due January 31, 2024.

### **7.0 REFERENCES**

SCS Engineers, 2018, Alternative Source Demonstration, October 2017 Detection Monitoring, Columbia Energy Center Dry Ash Disposal Facility, April 2018.

U.S. EPA, 2015, Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule, April 2015.

Warzyn Engineering, Inc., 1978, Feasibility Study, Proposed Fly Ash and/or Scrubber Sludge Disposal Facility – Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Warzyn Engineering, Inc., 1979, and Preliminary Engineering Concepts, Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

## Tables

- 1 Groundwater Analytical Results Summary – October 2022 Event
- 2 Historical Analytical Results for Parameters with SSIs
- 3 Groundwater Elevation – State Monitoring Program and CCR Well Network
- 4 Analytical Results – Lysimeters and Leachate Pond

**Table 1. Groundwater Analytical Results Summary -  
Columbia Landfill MOD 1-3 / SCS Engineers Project #25223067.00**

Parameter Name	UPL Method	UPL	Background Wells			Compliance Wells		
			MW-84A	MW-301	MW-33AR	MW-34A	MW-302	
			10/27/2022	10/27/2022	10/27/2023	10/27/2022	10/27/2022	
<b>Appendix III</b>								
Boron, ug/L	P	35.6	12.2	37.5	586	264	374	
Calcium, ug/L	NP	129,000	78400	62800 P6	77000	87300	91200	
Chloride, mg/L	P	6.2	3.4	2.3	40.5	2.2	2.1	
Fluoride, mg/L	DQ	DQ	<0.095	<0.095 M0	<0.095	<0.095	<0.095	
Field pH, Std. Units	P	7.78	7.31	6.80	7.54	7.53	7.25	
Sulfate, mg/L	P	30.3	1.1 J	11.6	153	169	30.3	
Total Dissolved Solids, mg/L	NP	514	302	282	440	436	348	

4.4 Blue shaded cell indicates the compliance well result exceeds the UPL (background) and the Limit of Quantitation (LOQ).

**Abbreviations:**

UPL = Upper Prediction Limit  
 DQ = Double Qualification  
 SSI = Statistically Significant Increase  
 -- = Not Measured  
 µg/L = micrograms per liter

NP = Nonparametric UPL with 1-of-2 retesting  
 P = Parametric UPL with 1-of-2 retesting  
 LOQ = Limit of Quantitation  
 LOD = Limit of Detection  
 mg/L = milligrams per liter

J = Estimated concentration at or above the LOD and below the LOQ.  
 P6 = Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.  
 M0 = Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits

**Notes:**

1. An individual result above the UPL does not constitute an SSI above background. See the accompanying report text for identification of statistically significant results.
2. Interwell UPLs calculated based on results from background wells MW-84A and MW-301. Interwell UPLs based on 1-of-2 retesting approach. UPLs updated in January 2020 based on background well results through October 2019
3. Interwell UPLs calculated based on results from background wells MW-84 and MW-301.

Created by: <u>NDK</u>	Date: <u>5/17/2022</u>
Last revision by: <u>NLB</u>	Date: <u>4/25/2023</u>
Checked by: <u>RM</u>	Date: <u>5/1/2023</u>
Scientist/Proj Mgr QA/QC: <u>TK</u>	Date: <u>5/9/2023</u>

**Table 2. Historical Analytical Results for Parameters with SSIs  
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Background	MW-301	12/22/2015	26.5	3.70 J	9.30
		4/5/2016	25.2	4.00	15.3
		7/8/2016	23.6	3.50 J	15.0
		10/13/2016	30.6	2.20	13.9
		12/29/2016	32.8	2.00 J	12.3 J
		1/25/2017	32.6	1.50 J	6.50
		4/11/2017	28.8	2.00	10.3
		6/6/2017	21.3	3.50	17.1
		8/8/2017	30.6	5.50	31.6
		10/23/2017	34.3	4.00	27.5
		4/25/2018	24.3	2.30	8.60
		8/8/2018	22.8	--	--
		10/22/2018	27.8	3.20	19.2
		4/3/2019	26.9	2.90 J, B	5.30 J
		10/9/2019	35.9	1.70	8.40
		5/29/2020	21.3	2.00 J	11.5 J
		10/8/2020	28.8	3.40	25.1
		4/13/2021	22.2	1.50 J	8.5
	10/14/2021	31.4	2.70	17.4	
	4/13/2022	28.7	1.90 J	12.7	
	10/27/2022	37.5	2.3	11.6	
	MW-84A	12/22/2015	11.9	4.90	4.90
		4/5/2016	14.0	4.70	4.30
		7/8/2016	14.7	5.10	3.70 J
		7/28/2016	--	--	--
		10/13/2016	11.1	4.30	2.60 J
		12/29/2016	14.7	4.70	2.70 J
		1/25/2017	16.1	4.60	3.00
		4/11/2017	12.9	4.90	2.80 J
		6/6/2017	14.8	5.50	2.70 J
		8/8/2017	22.9	5.50	2.00 J
		10/24/2017	13.8	5.10	2.20 J
		4/25/2018	25.0	4.80	2.80 J
		8/8/2018	12.8	--	--
10/22/2018		10.1 J	4.20	1.60 J	
4/3/2019		13.6	3.60 B	1.40 J	
10/9/2019		12.0	3.90	1.30 J	
5/29/2020	10.0	3.70	1.50 J		
10/8/2020	9.7 J	4.30	1.30 J		
4/13/2021	14.3	4.40	1.40 J		
10/14/2021	11.1	3.50	17.4		
4/13/2022	10.5	5.20	1.40 J, MO		
10/27/2022	12.2	3.4	1.1 J		

**Table 2. Historical Analytical Results for Parameters with SSIs  
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-302	12/22/2015	80.0	4.20	37.4
		4/5/2016	78.8	4.10	55.6
		7/7/2016	134	3.10 J	35.4
		10/13/2016	132	1.10 J	64.7
		12/29/2016	106	1.20 J	56.4
		1/25/2017	149	1.60 J	61.6
		4/11/2017	322	1.60 J	81.3
		6/6/2017	671	3.50	84.6
		8/8/2017	833	4.50	79.0
		10/24/2017	691	6.90	78.4
		4/24/2018	1,950	15.0	109
		9/21/2018	203	1.70 J	30.0
		10/22/2018	296	1.80 J	26.9
		4/2/2019	254	1.50 J	25.2
		10/9/2019	246	1.10 J	16.7
		5/29/2020	611	1.20 J	34.6
		10/8/2020	648	1.10 J	36.5
		4/13/2021	521	1.40 J	36.9
		10/14/2021	495	1.30 J	37.8
	4/12/2022	389	0.79 J	22.1 M0	
	10/27/2022	374	2.1	30.3	
	MW-33AR	12/21/2015	954	10.6	96.2
		4/5/2016	813	12.5	91.5
		7/7/2016	794	12.5	99.2
		10/13/2016	827	52.5	124
		12/29/2016	812	39.6	132
		1/25/2017	763	41.4	133
		4/11/2017	760	47.1	139
		6/6/2017	692	68.1	151
		8/7/2017	697	105	164
		10/24/2017	678	119	175
		4/24/2018	601	188	163
		9/21/2018	683	32.6	124
		10/22/2018	682	14.4	112
4/2/2019		568	229	201	
10/8/2019		548	153	182	
5/28/2020	566	15.9	104		
10/8/2020	569	27.3	97.4		
4/13/2021	473	26.9	94.3		
6/11/2021	--	--	--		
10/12/2021	564	22.6	96.4		
4/12/2022	558	59.0	155		
10/27/2022	586	40.5	153		

**Table 2. Historical Analytical Results for Parameters with SSIs  
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-34A	12/21/2015	230	4.90	69.9
		4/5/2016	220	5.10	71.6
		7/7/2016	216	5.60	63.4
		7/28/2016	--	--	--
		10/13/2016	212	6.80	54.8
		12/29/2016	224	7.10	63.9
		1/25/2017	214	7.20	71.2
		4/11/2017	214	6.20	87.6
		6/6/2017	201	7.80	106
		8/7/2017	205	7.40	105
		10/24/2017	208	7.60	98.0
		4/24/2018	209	8.20	144
		9/21/2018	241	17.1	141
		10/22/2018	233	19.9	123
		4/4/2019	204	18.7	70.4
		10/8/2019	207	57.9	39.8
		5/28/2020	210	3.90	44.4
		10/8/2020	213	2.10	58.7
		4/13/2021	203	2.30	59.3
		6/11/2022	--	--	--
	10/12/2021	212	1.90 J, M0	56.1	
	4/12/2022	237	2.20	146	
	10/27/2022	264	2.20	169	
MW-1AR <sup>(2)</sup>	4/14/2021	16.1	1.50 J	4.40 M0	
	10/14/2021	12.4	1.20 J	3.10	

Abbreviations:

µg/L = micrograms per liter or parts per billion (ppb)

mg/l = milligrams per liter or parts per million (ppm)

J = Estimated value below the laboratory's limit of quantitation

B = Analyte was detected in the associated Method Blank.

M0 = matrix spike recovery and/or matrix spike duplicate recovery outside of laboratory control limits.

Notes:

(1) Analytical laboratory reports provided in the Annual Groundwater Monitoring and Corrective Action Reports.

(2) MW-1AR was added to the sampling network in 2021 to provide additional evaluation of site conditions in the CCR unit. MW-1AR was abandoned in March of 2022.

Created by: NDK  
 Last revision by: NLB  
 Scientist Check: RM

Date: 3/19/2020  
 Date: 4/25/2023  
 Date: 5/1/2023



**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network  
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25223067.00**

Dry Ash Facility (Facility ID #03025)	Well Number	MW-1AR	MW-4	MW-5R	MW-33AR	MW-33BR	MW-34A	MW-34B	MW-37A	MW-83	MW-84A	MW-84B	MW-86	MW-91AR	MW-91B	MW-92A	MW-92B	MW-93A	MW-93B	MW-312
	<b>Top of Casing Elevation (feet amsl)</b>	822.55	819.74	805.44	808.29	808.39	805.95	806.05	813.04	807.96	814.28	814.26	824.79	809.03	808.45	808.47	808.41	827.89	827.71	826.79
	<b>Screen Length (ft)</b>																	10	5	10
	<b>Total Depth (ft from top of casing)</b>	44.40	39.58	25.97	31.08	57.50	35.43	56.95	31.80	25.42	40.21	52.02	45.43	32.90	52.38	28.94	51.75	50.7	82.5	52.5
	<b>Top of Well Screen Elevation (ft)</b>	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	787.19	750.21	784.29
	<b>Measurement Date</b>																			
	October 2, 2012	783.41	783.70	784.96	782.38	782.23	783.03	782.99	782.66	dry	783.84	783.94	783.81	784.09	783.90	784.49	784.06	NI	NI	NI
	April 15, 2013	785.44	784.02	786.09	784.16	784.14	784.74	784.79	783.87	784.49	785.83	785.76	785.22	785.14	785.01	785.75	785.34	NI	NI	NI
	October 8, 2013													785.66	785.42	785.97	785.52	NI	NI	NI
	October 15, 2013	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.66	785.42	785.97	785.52	NI	NI	NI
	April 14, 2014	784.95	784.09	785.63	783.74	783.91	784.63	784.70	783.45	783.73	785.58	785.52	784.96	785.04	784.96	785.99	785.54	NI	NI	NI
	October 2-3, 2014	785.03	785.39	786.08	784.37	784.28	784.57	784.54	784.56	dry	785.24	785.18	785.19	785.47	785.28	785.75	785.33	NI	NI	NI
	April 13-14, 2015	783.96	783.63	785.25	783.01	782.74	783.65	783.95	782.87	dry	784.43	784.51	784.17	784.48	784.37	785.07	784.66	NI	NI	NI
	October 6-7, 2015	784.28	784.44	785.72	783.68	783.33	784.05	784.02	783.66	dry	784.80	784.76	784.66	784.89	784.70	785.20	784.76	NI	NI	NI
	April 4-6, 2016	785.82	aband	787.02	785.29	785.07	785.63	785.67	784.76	785.43	786.37	786.26	785.89	786.05	785.95	786.61	786.21	NI	NI	NI
	October 11-13, 2016	786.64	aband	788.00	787.36	786.46	786.45	786.32	786.40	786.81	787.22	787.11	786.96	787.17	786.81	787.68	787.25	NI	NI	NI
	April 10-13, 2017	786.96	aband	788.13	786.39	785.99	786.30	786.28	786.34	786.23	787.16	787.06	786.96	787.24	787.03	787.90	787.60	NI	NI	NI
	October 3-5, 2017	785.48	aband	786.66	784.51	784.22	784.67	784.63	784.86	784.29	NM	786.49	785.58	786.08	785.83	786.47	786.02	NI	NI	NI
	October 9-10, 2017	NM	aband	NM	NM	NM	NM	NM	NM	NM	785.56 <sup>(6)</sup>	NM	NM	NM	NM	NM	NM	NI	NI	NI
	February 21, 2018	783.97	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	784.68	784.46	NM	NM	NI	NI	NI
	April 23-25, 2018	783.99	aband	785.36	783.09	786.36	781.77	780.79	783.28	783.32	785.88	784.91	782.54	784.71	784.53	785.23	784.81	NI	NI	NI
	October 23-25, 2018	788.25	aband	789.71	788.77	787.96	787.88	787.73	787.62	788.26	788.32	788.19	788.21	788.59	788.31	789.32	788.87	NI	NI	NI
	April 1-4, 2019	787.05	aband	788.64	786.63	786.54	786.82	786.92	786.47	786.78	787.35	787.34	787.16	787.45	787.18	788.04	787.63	NI	NI	NI
	October 7-9, 2019	787.26	aband	789.23	788.26	787.64	787.92	787.74	786.77	788.90	787.79	787.73	787.44	787.78	787.62	788.63	788.17	NI	NI	NI
	May 27-28, 2020	786.92	aband	788.34	786.01	785.75	785.98	785.99	786.22	786.03	787.02	786.99	786.94	787.26	787.05	787.86	787.47	NI	NI	NI
	October 7-8, 2020	785.95	aband	787.76	785.91	785.45	785.70	785.68	785.52	785.72	786.10	786.06	786.10	786.55	786.33	786.85	786.38	NI	NI	NI
	February 25, 2021	NM	aband	NM	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI
	April 14, 2021	778.12	aband	787.29	784.27	784.05	784.77	784.77	784.46	c	785.84	785.81	785.60	785.86	785.69	786.47	786.06	NI	NI	NI
	June 11, 2021	NM	aband	NM	784.19	NM	784.66	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI
	October 11-12, 14, 2021	784.47	adand	786.78	783.73	783.60	784.42	784.41	783.88	783.87	784.96	784.88	784.79	785.14	784.94	785.55	785.11	NI	NI	NI
	October 17, 2021	NM	adand	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI
	April 1, 2022	aband	aband	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM
	April 11-13, 2022	aband	adand	785.52	783.27	783.45	784.30	784.42	783.26	783.78	785.02	785.00	784.70	784.83	784.72	785.45	785.02	783.99	783.97	783.73
	October 24-28, 2022	aband	aband	785.43	781.94	781.61	783.61	783.61	782.28	dry	784.57	784.54	784.38	784.64	784.47	785.05	784.62	783.74	782.76	783.50
	<b>Bottom of Well Elevation (ft)</b>	778.15	780.16	779.47	777.21	750.89	770.52	749.10	781.24	782.54	774.07	762.24	779.36	776.13	756.07	779.53	756.66	777.19	745.21	774.29

Ash Pond Facility (Facility ID #02325)	Well Number	M-3	M-4R	MW-39A	MW-39B	MW-48A	MW-48B	MW-57	MW-59	MW-216R	MW-217	MW-220RR	SG-1	SG-2	SG-3	SG-4
	<b>Top of Casing Elevation (feet amsl)</b>	788.23	806.10	809.62	809.50	828.86	828.84	786.29	815.48	814.21	791.55	792.90	792.06	795.25	808.60	805.36
	<b>Screen Length (ft)</b>															
	<b>Total Depth (ft from top of casing)</b>	16.90	25.55	34.80	76.07	51.88	75.80	14.40	38.50	37.85	37.37	18.96	--	--	--	--
	<b>Top of Well Screen Elevation (ft)</b>	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--
	<b>Measurement Date</b>															
	October 2, 2012	780.13	786.76	781.49	781.34	782.03	781.93	780.58	779.88	781.91	780.95	780.55	789.14	793.85	dry	dry
	April 15, 2013	785.16	788.39	783.97	784.00	783.77	783.78	784.69	783.66	784.09	784.75	785.02	789.5 <sup>(1)</sup>	NM	dry	dry
	October 8, 2013	781.22	786.67	NM	NM	783.69	783.58	NM	NM	783.39	782.27	782.36	789.5 <sup>(1)</sup>	791.33	dry	dry
	October 15, 2013	NM	NM	782.94	782.81	NM	NM	782.47	783.49	NM	NM	NM	NM	NM	NM	NM
	April 14, 2014	786.04	788.96	783.57	783.68	783.56	783.57	785.51	783.41	783.73	785.25	785.87	788.90	dry	dry	dry
	October 1-3, 2014	781.16	787.55	783.42	783.32	784.05	783.94	782.32	783.55	783.79	782.63	783.03	NM	dry	dry	dry
	April 13-14, 2015	783.08	786.83	782.77	782.68	782.80	782.82	782.81	782.83	782.93	783.34	783.42	789.3	791.70	dry	dry
	October 6-7, 2015	780.66	786.12	782.97	782.81	783.10	783.01	781.82	783.25	783.18	781.95	782.26	788.48	791.58	dry	dry
	April 4-6, 2016	784.21	789.09	785.27	785.27	784.79	784.76	783.21	784.97	785.68	785.02	784.36	NM	793.40	dry	dry
	October 11-13, 2016	781.88	787.88	785.75	785.52	785.73	785.61	783.12	786.51	786.16	783.75	784.09	788.32	792.52	dry	dry
	April 10-13, 2017	782.94	787.95	785.44	785.20	785.82	785.69	782.77	786.09	785.95	784.29	784.09	788.31	793.85	dry	dry
	October 3-5, 2017	780.93	787.04	783.35	783.18	784.30	784.19	782.37	784.23	783.89	782.48	782.61	788.3	793.45	dry	dry
	April 23-25, 2018	782.89	790.43	782.86	782.87	783.14	783.09	783.04	783.02	783.23	783.26	783.45	788.38	>795.25	dry	dry
	October 23-25, 2018	782.95	788.47	787.12	786.88	787.12	786.99	783.48	787.73	787.49	784.90	784.52	787.76	793.25	dry	dry
	April 1-4, 2019	785.68	789.44	786.28	786.31	786.56	786.45	785.27	787.39	786.53	786.33	785.46	788.40	794.60	dry	dry
	October 7-9, 2019	785.33	790.65	787.10	787.02	786.68	786.65	785.29	786.68	787.07	786.01	785.42	748.48	795.20	dry	dry
	May 27-29, 2020	781.80	787.73	785.12	784.92	785.74	785.59	783.11	785.89	785.60	783.41	783.89	748.48	>795.25	dry	dry
	<b>Bottom of Well Elevation (ft)</b>	771.33	780.55	774.82	733.43	776.98	753.04	771.89	776.98	776.36	754.18	773.94	--	--	--	--

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network  
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25223067.00**

	Well Number	MW-301	MW-302	MW-303	MW-304	MW-305	M-4R	MW-33AR	MW-34A	MW-84A	MW-306	MW-307	MW-308	MW-309	MW-310	MW-311	MW-312	MW-313	MW-314	MW-315	
	<b>Top of Casing Elevation (feet amsl)</b>	806.89	813.00	815.72	805.42	806.32	806.10	808.29	805.95	814.28	807.63	806.89	806.9	813.27	813.62	809.74	826.786	820.30	821.57	819.78	
	<b>Screen Length (ft)</b>	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	
	<b>Total Depth (ft from top of casing)</b>	29.40	33.6	35.80	25.7	25.6	39.58	31.08	35.43	40.21	27	26.5	28	37.67	38.41	36.19	52.5				
	<b>Top of Well Screen Elevation (ft)</b>	787.49	789.40	785.72	789.72	790.72	776.52	787.21	780.52	784.07	790.63	790.39	788.90	785.60	785.21	783.55	784.29				
	<b>Measurement Date</b>																				
CCR Rule Wells	December 21-22, 2015	785.56	784.78	784.11	786.13	788.96	787.58	783.77	783.50	785.31	NI	NI	NI	NI	NI	NI	NI	NI	NI	NI	
	April 4-5, 2016	786.78	785.81	785.48	788.08	789.61	789.09	785.29	785.63	786.37	--	--	--	--	--	--	NI	NI	NI	NI	
	July 7-8, 2016	786.31	786.28	784.60	787.36	789.26	787.43	785.19	785.05	785.89	--	--	--	--	--	--	NI	NI	NI	NI	
	July 28, 2016	NM	NM	784.35	NM	NM	NM	NM	784.86	785.61	--	--	--	--	--	--	NI	NI	NI	NI	
	October 11-13, 2016	787.64	787.76	786.18	788.18	789.78	787.88	787.36	786.45	787.22	--	--	--	--	--	--	NI	NI	NI	NI	
	December 29, 2016	787.37	787.05	NM	NM	NM	NM	785.66	785.72	786.63	--	--	--	--	--	--	NI	NI	NI	NI	
	January 25-26, 2017	787.27	786.89	785.28	789.34	789.36	789.64	785.88	785.98	786.70	785.50	785.36	785.73	--	--	--	NI	NI	NI	NI	
	April 10 & 11, 2017	787.89	787.55	786.00	788.22	789.57	787.95	786.39	786.30	787.16	786.22	785.64	786.51	--	--	--	NI	NI	NI	NI	
	June 6, 2017	788.25	788.37	786.49	788.58	789.79	787.83	787.27	786.66	787.63	786.85	786.07	786.46	--	--	--	NI	NI	NI	NI	
	August 7-9, 2017	787.34	787.55	785.42	789.52	789.30	788.54	786.11	785.81	786.68	785.69	785.19	785.37	--	--	--	NI	NI	NI	NI	
	October 23-24, 2017	785.89	785.94	783.92	788.97	788.14	788.00	784.13	784.50	785.32	783.97	784.79	784.17	--	--	--	NI	NI	NI	NI	
	February 21, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.19	783.05	783.02	NI	NI	NI	NI
	March 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.10	783.10	783.00	NI	NI	NI	NI
	April 23-25, 2018	785.29	784.37	783.27	789.69	787.67	790.43	783.09	781.77	785.88	783.24	783.65	782.65	783.07	782.97	781.83	NI	NI	NI	NI	
	May 24, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.79	785.09	NM	NM	785.45	785.97	786.11	NI	NI	NI	NI
	June 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.03	786.64	786.47	NI	NI	NI	NI
	July 23, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.27	786.35	786.55	NI	NI	NI	NI
	August 7, 2018	787.06	NM	785.20	788.25	788.56	787.63	NM	NM	786.55	NM	NM	NM	NM	NM	NM	NI	NI	NI	NI	
	August 22, 2018	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.54	785.40	785.46	NI	NI	NI	NI
	September 21, 2018	NM	788.37	786.50	NM	NM	NM	787.90	787.01	NM	NM	NM	NM	NM	787.08	787.24	787.66	NI	NI	NI	NI
	October 22-24, 2018	788.98	789.16	787.51	789.05	790.04	788.47	788.77	787.88	788.32	787.66	786.57	787.81	787.99	788.18	788.64	NI	NI	NI	NI	
	April 1-4, 2019	787.04	787.56	786.52	789.72	790.07	789.44	786.63	786.82	787.35	786.72	786.71	787.53	786.30	786.38	786.38	NI	NI	NI	NI	
	June 12, 2019	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	787.25	NM	NI	NI	NI	NI	
	June 19, 2019	NM	NM	786.81	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI	NI	
	October 7-9, 2019	788.47	788.31	787.02	790.41	790.36	790.65	NM	NM	NM	787.47	786.99	787.18	787.26	787.94	787.64	NI	NI	NI	NI	
	December 13, 2019	--	--	--	--	--	--	--	--	--	787.03	785.68	786.43	--	--	--	NI	NI	NI	NI	
	December 23, 2019	--	--	--	--	--	--	--	--	--	--	--	--	--	775.22	--	NI	NI	NI	NI	
	January 17, 2020	--	--	785.58	--	--	--	--	--	--	--	--	--	--	--	--	NI	NI	NI	NI	
	February 3, 2020	787.24	NM	NM	NM	NM	NM	NM	NM	786.50	785.77	785.57	786.48	NM	NM	NM	NI	NI	NI	NI	
	May 27-29, 2020	787.77	787.29	785.56	789.30	787.78	787.73	786.01	785.98	787.02	785.77	785.35	786.28	785.98	785.81	785.85	NI	NI	NI	NI	
	June 30, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	786.18	NM	NI	NI	NI	NI	
	August 6, 2020	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	785.93	NM	NI	NI	NI	NI	
	October 7-8, 2020	786.53	786.74	785.16	788.52	787.96	787.74	785.91	785.70	786.10	785.39	784.71	785.68	785.47	785.56	785.83	NI	NI	NI	NI	
	December 11, 2020	NM	NM	NM	NM	788.19	NM	NM	NM	NM	NM	NM	NM	NM	785.26	785.26	NI	NI	NI	NI	
	February 25, 2021	NM	NM	784.27	NM	788.36	NM	NM	784.75	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI	NI	
	April 12, 2021	786.50	785.77	784.07	787.99	788.11	786.34	784.27	784.77	785.84	784.32	784.21	785.55	784.29	784.24	784.15	NI	NI	NI	NI	
	June 11, 2021	NM	NM	NM	NM	NM	NM	784.19	784.66	NM	NM	NM	NM	784.20	784.05	NM	NI	NI	NI	NI	
	July 20, 2021	NM	NM	783.64	NM	788.39	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI	NI	
	October 11-12, 14, 2021	785.28	785.09	783.09	787.78	787.75	786.33	783.73	784.42	784.96	782.93	782.44	783.76	783.65	783.48	783.48	NI	NI	NI	NI	
	December 21, 2021	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	782.93	NM	NI	NI	NI	NI	
February 24, 2022	NM	NM	782.34	NM	786.49	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI	NI		
April 11-13, 2022	785.44	784.42	783.40	788.20	787.87	788.26	783.27	784.30	785.02	783.11	783.32	784.19	783.14	783.19	783.04	NI	NI	NI	NI		
July 27, 2022	NM	NM	783.07	NM	787.03	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NI	NI	NI	NI		
October 25-27, 2022	784.91	784.62	778.94	781.79	784.97	783.85	781.94	783.61	784.57	778.32	777.89	784.16	781.50	780.96	781.23	NI	NI	NI	NI		
November 30, 2022	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	781.62	781.14	781.15	NI	NI	NI		
December 2, 2022	785.12	784.48	NM	783.97	NM	NM	781.91	783.71	784.76	778.52	779.54	NM	NM	NM	NM	NI	NI	NI	NI		
January 12-13, 2023	785.20	784.55	NM	NM	NM	NM	782.75	784.10	784.88	NM	NM	NM	782.57	782.45	782.32	NI	NI	NI	NI		
January 20, 2023	NM	NM	NM	788.08	NM	NM	NM	NM	NM	782.15	782.11	784.98	NM	NM	NM	NM	NM	NM	NM		
January 24, 2023	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	NM	783.36	783.63	783.77		
February 20-23, 2023	785.56	784.98	NM	NM	NM	NM	NM	NM	NM	783.04	782.91	785.32	783.31	783.34	783.40	NM	783.59	783.82	783.96		
	<b>Bottom of Well Elevation (ft)</b>	777.49	779.40	775.72	779.72	780.72	766.52	777.21	770.52	774.07	780.63	780.39	778.90	775.60	775.21	773.55	774.29	820.30	821.57	819.78	

**Table 3. Groundwater Elevation - State Monitoring Program and CCR Well Network  
Columbia Dry Ash and Ash Pond Disposal Facilities / SCS Engineers Project #25223067.00**

Notes:  
NM = not measured

Created by:	<u>MDB</u>	Date:	<u>5/6/2013</u>
Last revision by:	<u>NLB</u>	Date:	<u>4/25/2023</u>
Checked by:	<u>RM</u>	Date:	<u>5/1/2023</u>

- (1) The elevation for SG-1 is read off of the staff gauge (rather than measured from the top of the gauge).
- (2) SG-2 could not be located during the April 2013 event.
- (3) SG-3 could not be located during the October 2013 event. SG-1 could not be safely accessed during the October 2013 event.
- (4) LH-2 measurements are given as leachate depth, measured by a transducer.
- (5) LH-2 and LH-3 measurements were collected by WPL staff on October 9, 2017.
- (6) The depth to water at MW-84A was not measured prior to purging for sampling during the October 3-5 sampling event. The level was allowed to return to static and was measured on 10/10/2017.
- (7) BC = Brian Clepper; NS= Nate Sievers - Columbia Site employees.
- (8) MW-303 was extended in 2022 due to regrading. Prior to October 2022, the TOC elevation was 811.52'. For events in October 2022 and later, the TOC elevation is 815.72'.

I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Tables\[Table 3 - GW Elevations.xls]levels

**Table 4. Analytical Results - Lysimeters and Leachate Pond  
Columbia Dry Ash Disposal Facility  
SCS Engineers Project #25223067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LS-1	2015-Apr	DRY	--	--	--
	2015-Oct	BROKEN	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	--	6,530	12.3	789
	2017-Apr	--	6,510	20.7 J	814
	2017-Oct	--	6,200	14.2 J	764
	2018-Apr	--	5,920	16.0 J	856
	2018-Oct	DRY	--	--	--
	2019-Apr	--	5,640	22.0 J	911
	2019-Oct	--	6,180	19.2 J	861
	2020-May	--	6,180	25.4 J	1,040
	2020-Oct	--	5,640	27.2 J	950
	2021-Apr	--	6,010	21.1 J	976
	2021-Oct	--	6,230	14.3 J	987
	2022-Apr	--	6,140	13.3 J	1,040
2022-Oct	--	6,000	16.7 J	898	
LS-3R	2015-Apr	--	6,480	20.6 B	807
	2015-Oct	DRY	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	DRY	--	--	--
	2017-Apr	DRY	--	--	--
	2017-Oct	DRY	--	--	--
	2018-Apr	DRY	--	--	--
	2018-Oct	--	6,180	26.2 J	841
	2019-Apr	DRY	--	--	--
	2019-Oct	DRY	--	--	--
	2020-May	DRY	--	--	--
	2020-Oct	DRY	--	--	--
	2021-Apr	DRY	--	--	--
	2021-Oct	DRY	--	--	--
	2022-Apr	DRY	--	--	--
2022-Oct	DRY	--	--	--	

**Table 4. Analytical Results - Lysimeters and Leachate Pond  
Columbia Dry Ash Disposal Facility  
SCS Engineers Project #25223067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LP-1	2015-Apr	--	4,060	27.8	734
	2015-Oct	--	4,300	37.1	820
	2016-Apr	--	1,830	26.8	416
	2016-Oct	--	4,610	71.5	835
	2017-Apr	--	2,690	66.3	587
	2017-Oct	--	4,970	91.7	739
	2018-Apr	--	2,060	63.2	634
	2018-Oct	--	2,630	151	907
	2019-Apr	--	570	35.1	249
	2019-Oct	--	1,270	63.9	602
	2020-May	--	2,460	179	952
	2020-Oct	--	2,710	243	1,160
	2021-Apr	--	3,340	319	1,180
	2021-Oct	--	3,440	299	1,470
	2022-Apr	--	1,030	89.2	506
2022-Oct	--	2,040	175	752	

Abbreviations:

µg/L = micrograms per liter  
mg/L = milligrams per liter

-- = not analyzed

Notes:

B = Analyte was detected in the associated method blank.


J = Estimated concentration at or above the Limit of Detection (LOD) and below the Limit of Quantitation (LOQ).

Created by:           MDB            
Last revision by:           NLB            
Checked by:           RM          

Date:           12/1/2014            
Date:           5/1/2023            
Date:           5/1/2023

## Figures

- 1 Site Location Map
- 2 Site Plan and Monitoring Well Locations
- 3 Water Table Map – October 2022




POYNETTE QUADRANGLE  
 WISCONSIN-COLUMBIA CO.  
 7.5 MINUTE SERIES (TOPOGRAPHIC)  
 2018  
 SCALE: 1" = 2,000'



CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954		SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER PARDEEVILLE, WI		ENGINEER	SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830		FIGURE 1
	PROJECT NO.	25220067.00		DRAWN BY:	BSS		SITE LOCATION MAP		
	DRAWN:	12/02/2019		CHECKED BY:	MDB				
REVISED:	01/10/2020	APPROVED BY:	TK 04/10/2020						


I:\25220067.00\Drawings\ASD Mod 1-3 LF\Site Location Map.dwg, 4/12/2020 7:05:09 PM





- LEGEND
- (solid line) — EXISTING MAJOR CONTOUR (10' INTERVAL)
  - (dashed line) — EXISTING MINOR CONTOUR (2' CONTOUR)
  - x - x - EXISTING FENCELINE
  - ||||| EXISTING TRACKS
  - ==== EXISTING PAVED ROAD
  - EXISTING UNPAVED ROAD
  - . . - . . EDGE OF WATER
  - DRY ASH DISPOSAL FACILITY LIMITS
  - — — — — LIMITS OF WASTE
  - · — · — · LINER PHASE/MODULE LIMITS
  - ⊕ WATER SUPPLY WELL
  - ⊕ STAFF GAUGE
  - ⊕ WATER TABLE WELL
  - ⊕ PIEZOMETER
  - ⊗ SURFACE WATER SAMPLE LOCATION
  - ⊠ LYSIMETER
  - ⊕ ABANDONED WATER TABLE WELL
  - ⊕ ABANDONED PIEZOMETER
  - ⚡ LEACHATE HEADWELL
  - CCR UNIT
  - ⊕ CCR MONITORING WELL
  - ⊕ CCR BACKGROUND MONITORING WELL


- NOTES:
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, MAY 2019, SEPTEMBER 2020, AUGUST 2021, AND NOVEMBER 2021.
  2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016, AND BY SCS ENGINEERS IN FEBRUARY 2018.
  3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
  4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
  5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
  6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
  7. MONITORING WELLS MW-93A, MW-93B, AND MW-312 WERE INSTALLED BY CASCADE ENVIRONMENTAL ON MARCH 23-28, 2022.
  8. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.



PROJECT NO. 25222067.00	DRAWN BY: KP	<b>SCS ENGINEERS</b> 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULES 1-3 DRY ASH DISPOSAL FACILITY PARDEVILLE, WI	FIGURE 2
DRAWN: 12/02/2019	CHECKED BY: NDK/RM				
REVISED: 01/16/2023	APPROVED BY: TK 1/16/2023				

I:\25222067.00\Drawings\Modules 1-3\Site Plan and Monitoring Well Locations.dwg, 1/16/2023 11:52:11 AM






- LEGEND
- EXISTING MAJOR CONTOUR (10' INTERVAL)
  - EXISTING MINOR CONTOUR (2' CONTOUR)
  - x - x - EXISTING FENCELINE
  - ||||| EXISTING TRACKS
  - ==== EXISTING PAVED ROAD
  - EXISTING UNPAVED ROAD
  - · - · - · EDGE OF WATER
  - · · · · · · · · · DRY ASH DISPOSAL FACILITY LIMITS
  - — — — — LIMITS OF WASTE
  - · · · · · · · · · LINER PHASE/MODULE LIMITS
  - ⊕ WATER SUPPLY WELL
  - ⊙ STAFF GAUGE
  - ⊕ WATER TABLE WELL
  - ⊕⊕ PIEZOMETER
  - ⊗ SURFACE WATER SAMPLE LOCATION
  - ⊠ LYSIMETER
  - ⊕ ABANDONED WATER TABLE WELL
  - ⊕⊕ ABANDONED PIEZOMETER
  - ↖ LEACHATE HEADWELL
  - CCR UNIT
  - ⊕ CCR MONITORING WELL
  - ⊕ CCR BACKGROUND MONITORING WELL
  - 787.62 WATER TABLE ELEVATION
  - [788.87] POTENTIOMETRIC SURFACE ELEVATION (NOT CONTOURED)
  - (795.20) SURFACE WATER ELEVATION (NOT CONTOURED)
  - WATER TABLE CONTOUR
  - ➔ APPROXIMATE GROUNDWATER FLOW DIRECTION

- NOTES:
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEY BY SCS ENGINEERS IN MAY 2016, JUNE 2016, OCTOBER 2016, NOVEMBER 2016, APRIL 2017, NOVEMBER 2017, JULY 2018, AUGUST 2018, FEBRUARY 2019, AND MAY 2019.
  2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
  3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
  4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
  5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
  6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
  7. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON APRIL 12-14, 2021.
  8. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.
  9. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON OCTOBER 25-27, 2022.
  10. MONITORING WELLS MW-93A, MW-93B, AND MW-312 INSTALLED BY CASCADE ENVIRONMENTAL ON MARCH 25-28, 2022.
  11. DEWATERING WELLS (NOT SHOWN) AROUND THE SECONDARY POND WERE PUMPING AND DISCHARGING TO THE PRIMARY POND DURING THE OCTOBER 2022 SAMPLING EVENT.


PROJECT NO. 25222067.00	DRAWN BY: KP	ENGINEER <b>SCS ENGINEERS</b> 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULES 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	FIGURE 3
DRAWN: 12/15/2022	CHECKED BY: MDB				
REVISED: 12/30/2022	APPROVED BY: TK 1/16/2023				

I:\25222067.00\Drawings\Modules 1-3\Water Table Map-October 2022.dwg, 1/16/2023 12:43:58 PM



Appendix A  
Trend Plots for CCR Wells

# Boron




Time Series Analysis Run 5/9/2023 11:42 AM View: COL Primary Pond  
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

# Time Series

Constituent: Boron (ug/L) Analysis Run 5/9/2023 11:45 AM View: COL Primary Pond  
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			954	217.5 (D)		
12/22/2015	26.5	80			11.9	
4/5/2016	25.2	78.8	813	220	14	
7/7/2016		134	794	216		
7/8/2016	23.6				14.7	
10/13/2016	30.6	132	827	212	11.1	
12/29/2016	32.8	106	812	224	14.7	
1/25/2017	32.6	149	763	214	16.1	
4/11/2017	28.8	322	760	214	12.9	
6/6/2017	21.3	671	692	201	14.8	
8/7/2017			697	205		
8/8/2017	30.6	833			22.9	
10/23/2017	34.3					
10/24/2017		691	678	208	13.8	
4/24/2018		1950	601	209		
4/25/2018	24.3				25	
8/8/2018	22.8				12.8	
9/21/2018		203	683	241		
10/22/2018		296	682	233		
10/24/2018	27.8				10.1 (J)	
4/2/2019	26.9	254	568	204		
4/3/2019					13.6	
10/8/2019			548	207		
10/9/2019	35.9	246			12	
2/3/2020	27.9				15.7	
5/28/2020			566	210		
5/29/2020	21.3	611			10	
10/8/2020	28.8	648	569	213	9.7 (J)	
4/13/2021		521	473	203		
4/14/2021	22.2				14.3	16.1
10/12/2021			564	212		
10/14/2021	31.4	495			11.1	12.4
4/12/2022		389	558	237		
4/13/2022	28.7				10.5	
10/27/2022	37.5	374	586	264	12.2	

# Chloride



Time Series Analysis Run 5/9/2023 11:42 AM View: COL Primary Pond  
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020


# Time Series

Constituent: Chloride (mg/L) Analysis Run 5/9/2023 11:45 AM View: COL Primary Pond  
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			10.6	4.85 (D)		
12/22/2015	3.7 (J)	4.2			4.9	
4/5/2016	4	4.1	12.5	5.1	4.7	
7/7/2016		3.1 (J)	12.5	5.6		
7/8/2016	3.5 (J)				5.1	
10/13/2016	2.2	1.1 (J)	52.5	6.8	4.3	
12/29/2016	2 (J)	1.2 (J)	39.6	7.1	4.7	
1/25/2017	1.5 (J)	1.6 (J)	41.4	7.2	4.6	
4/11/2017	2	1.6 (J)	47.1	6.2	4.9	
6/6/2017	3.5	3.5	68.1	7.8	5.5	
8/7/2017			105	7.4		
8/8/2017	5.5	4.5			5.5	
10/23/2017	4					
10/24/2017		6.9	119	7.6	5.1	
4/24/2018		15	188	8.2		
4/25/2018	2.3				4.8	
8/8/2018	5.2				4.9	
9/21/2018		1.7 (J)	32.6	17.1		
10/22/2018		1.8 (J)	14.4	19.9		
10/24/2018	3.2				4.2	
4/2/2019	0.79 (J)	1.5 (J)	229	18.7		
4/3/2019					3.6	
10/8/2019			153	57.9		
10/9/2019	1.7 (J)	1.1 (J)			3.9	
2/3/2020	1.3 (J)				3.7	
5/28/2020			15.9	3.9		
5/29/2020	2 (J)	1.2 (J)			3.7	
10/8/2020	3.4	1.1 (J)	27.3	2.1	4.3	
4/13/2021		1.4 (J)	26.9	2.3		
4/14/2021	1.5 (J)				4.4	1.5 (J)
10/12/2021			22.6	1.9 (J)		
10/14/2021	2.7	1.3 (J)			3.5	1.2 (J)
4/12/2022		0.79 (J)	59	2.2		
4/13/2022	1.9 (J)				5.2	
10/27/2022	2.3	2.1	40.5	2.2	3.4	



### Sulfate




Time Series Analysis Run 5/9/2023 11:42 AM View: COL Primary Pond  
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

# Time Series

Constituent: Sulfate (mg/L) Analysis Run 5/9/2023 11:46 AM View: COL Primary Pond  
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			96.2	70.6 (D)		
12/22/2015	9.3	37.4			4.9	
4/5/2016	15.3	55.6	91.5	71.6	4.3	
7/7/2016		35.4	99.2	63.4		
7/8/2016	15				3.7 (J)	
10/13/2016	13.9	64.7	124	54.8	2.6 (J)	
12/29/2016	12.3 (J)	56.4	132	63.9	2.7 (J)	
1/25/2017	6.5	61.6	133	71.2	3	
4/11/2017	10.3	81.3	139	87.6	2.8 (J)	
6/6/2017	17.1	84.6	151	106	2.7 (J)	
8/7/2017			164	105		
8/8/2017	31.6	79			2 (J)	
10/23/2017	27.5					
10/24/2017		78.4	175	98	2.2 (J)	
4/24/2018		109	163	144		
4/25/2018	8.6				2.8 (J)	
8/8/2018	21.6				1.9 (J)	
9/21/2018		30	124	141		
10/22/2018		26.9	112	123		
10/24/2018	19.2				1.6 (J)	
4/2/2019	4.4	25.2	201	70.4		
4/3/2019					1.4 (J)	
10/8/2019			182	39.8		
10/9/2019	8.4	16.7			1.3 (J)	
2/3/2020	7.2				<2.2 (U)	
5/28/2020			104	44.4		
5/29/2020	11.5	34.6			1.5 (J)	
10/8/2020	25.1	36.5	97.4	58.7	1.3 (J)	
4/13/2021		36.9	94.3	59.3		
4/14/2021	8.5				1.4 (J)	4.4
10/12/2021			96.4	56.1		
10/14/2021	17.4	37.8			1.3 (J)	3.1
4/12/2022		22.1	155	146		
4/13/2022	12.7				1.4 (J)	
10/27/2022	11.6	30.3	153	169	1.1 (J)	



Appendix B  
Feasibility Study Water Quality Information

1370



FEASIBILITY STUDY  
PROPOSED FLY ASH AND/OR SCRUBBER SLUDGE  
DISPOSAL FACILITY-COLUMBIA SITE  
WISCONSIN POWER AND LIGHT COMPANY  
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

*Jan 78*

C 7134

conceivable that groundwater flow in the area north of Murray Road may be altered such that contaminants derived from the present ash settling basin might be diverted southerly towards the homes along Murray Road. These questions would have to be addressed in greater detail, consistent with the goals of Wisconsin Power and Light Company.

#### WATER QUALITY

During the first two weeks of December, 1977, 64 water samples were obtained from surface waters and groundwater monitoring wells at the Columbia Energy Center. The purpose of the sampling was to assess background water quality in the vicinity of the proposed disposal site. The sampling stations included 59 monitoring wells, the cooling lake, ash settling pond, the drainage ditch carrying the ash pond discharge waters and the agricultural drainage ditch along the southern boundary of the site. Due to the large number of sampling stations, the analyses were limited to pH, specific conductance, iron, calcium, magnesium, sulfate and chloride. The analytical data is contained in Appendix F and is discussed below.

#### pH

Most groundwaters found in the United States have pH values ranging from around 6.0 to 8.5. The pH of a water represents the result of a number of interrelated chemical equilibria. This equilibria can be altered shortly after sampling by gains or losses of carbon dioxide, the oxidation of ferrous iron and numerous other chemical reactions. Thus, pH measurements must be taken shortly after obtaining the sample. For this study, the pH of samples was determined immediately upon return to the laboratory.

Within the proposed site boundaries at the Columbia Energy Center, pH values ranged between 6.3 and 8.1 and averaged 7.5. Typically, the lower pH values were observed in the lowland areas and wetlands, probably as a result of acidic organic soils. The pH of water in the ash disposal settling pond and the cooling lake was 11.4 and 8.3, respectively.

#### SPECIFIC CONDUCTANCE

Specific conductance, or conductivity, is the ability of a substance to conduct an electric current. The conductance determination is correlative with the dissolved-solids concentration. Conductivity, however, is temperature dependent and thus requires the reference of specific conductance measurements to a standard temperature. The values discussed here are referred to 25°C.

The specific conductance of groundwater in the study area ranged from 220 umhos/cm to a maximum of 2600 umhos/cm. The highest conductivity readings were observed in monitoring wells located along the coal storage area and the drainage ditch carrying the ash pond discharge where values up to 2600 umhos/cm were measured. The conductivity of the ash pond effluent was 1380 umhos/cm. This data appears to confirm earlier speculation of infiltration of effluent from the ash pond discharge channel and from the coal storage area into the groundwater. Conductance within the proposed site boundaries averaged approximately 465 umhos/cm.

Conductivity in the ash disposal settling pond was measured at 1510 umhos/cm. Shallow monitoring wells M-6 and 39A, located adjacent to the pond also exhibited elevated values of 1160 umhos/cm and 1800 umhos/cm, respectively.


High conductivities were also observed along U. S. Highway 51 at monitoring wells 51A and 51B. The chloride data, discussed below, indicates infiltration of road salt has probably occurred at this location.

Specific conductance measurements obtained in the vicinity of the proposed disposal site are shown on Drawing C 7134-15.

### IRON

The element iron is an abundant element found in most rocks and soil. It generally occurs as sulfides and oxides in igneous and metamorphic rocks and as iron oxide and hydroxide cementing materials in coarse-grained sedimentary rocks.

Ferrous iron is unstable in the presence of oxygen where it is bound to hydroxide anions as  $2\text{Fe}(\text{OH})_3$ .



If subjected to a strong reducing environment, such as a marsh, the reaction is reversed and iron goes back into solution. The amount which dissolves is related to a number of variables including the velocity with which water moves through this environment.

The U. S. Public Health Service recommends an iron concentration of less than 0.3 mg/l in water used for drinking and culinary purposes. Laundry and porcelain tend to be stained when concentrations reach 0.5 to 1.0 mg/l. At this level it can also be tasted.



The presence of iron under the proposed disposal area in the majority of cases was below the detection limit of 0.1 mg/l. In monitoring wells 5 and 18, located in or near the central marsh area, iron increased to 10 mg/l and 5.7 mg/l, respectively. In the southern marsh, monitoring wells exhibited concentrations between 0.5 mg/l and 6.1 mg/l. Although the iron concentration in the cooling lake was below the detection limit, down-gradient wells 44 and 30A located on the cooling lake dike yielded values of 11 mg/l and 26 mg/l iron respectively. Boring logs indicated trace amounts of organic material at the base of the dike which is probably the reason for the high concentrations observed. At the same location, iron in well 30B installed to a depth of 100 feet below the surface was below 0.1 mg/l. Thus, the occurrence of high iron concentrations in this area appears restricted to groundwater in the upper portion of the aquifer where organic material is present and conditions are favorable for the dissolution of iron.

The ash pond discharge in the drainage ditch paralleling the west site boundary showed an iron concentration of 3.7 mg/l. Shallow monitoring wells 33A and 34A adjacent to the ditch indicated less than 0.1 mg/l iron.

North of Murray Road the iron concentration in monitoring wells in the marsh and uplands were typically less than 0.1 mg/l. Although the ash basin had less than 0.1 mg/l iron, several wells along cross-section F-F' showed anomalously high values (#M6-2.3 mg/l; #47-16 mg/l; #51B-21 mg/l).

#### CALCIUM

Calcium, because of its relative abundance and mobility, is the principle cation in most natural fresh water. Calcium is a constituent of many rock types but is found in greatest quantities in waters leaching deposits of limestone and dolomite. In sandstone and other detrital rock, calcium carbonate is a common cement between grains.

Monitoring wells located within the site boundaries exhibited calcium concentrations between 30 mg/l and 66 mg/l and averaged about 42 mg/l. Similar to iron, the concentrations of calcium in monitoring wells along cross-section F-F' were anomalously high, up to 150 mg/l calcium. Water table wells along the drainage ditch carrying the ash pond discharge averaged 83 mg/l while the ash pond effluent contained 28 mg/l. Generally the amount of calcium in groundwater decreased with depth. Nested monitoring wells typically showed somewhat lower concentrations of calcium in the deeper wells.

#### MAGNESIUM

As a relatively abundant element on the earth's crust, the principle sources of magnesium in natural waters are considered to be ferromagnesian minerals in igneous rocks and magnesium carbonate in carbonate rocks (limestone and dolomite). Waters in which magnesium is the predominant cation are somewhat unusual. Like calcium, magnesium imparts the property of hardness to water and is, therefore, of concern to industrial users.

Generally, concentrations of magnesium were 1/3 to 1/2 of the calcium levels. Magnesium concentrations within the site boundaries ranged between 10 mg/l and 36 mg/l and averaged 27 mg/l. Similar to calcium and iron, higher magnesium values were observed, in general, north of Murray Road and especially in monitoring wells along cross-section F-F'.

SULFATE

Sulphur is widely distributed in reduced form in both igneous and sedimentary rocks as metallic sulfides and when present in sufficient concentrations, constitutes ore of economic importance. During weathering processes with aerated water, the sulfides are oxidized to sulfate ions and are dissolved into water. Pyrite ( $\text{FeS}_2$ ) crystals often occur in sedimentary rocks and are particularly associated with biogenic deposits such as coal which were deposited under strongly reducing conditions.

The concentrations of sulfate in groundwater in the vicinity of the proposed disposal site ranged from less than 1 mg./l to 1,200 mg./l of sulfate. (Refer to Drawing C 7134-15.) Typically, within the site boundaries concentrations averaged approximately 12 mg./l. Near the coal storage area, however, significant increases were observed. Observation wells 26A, 26B, and 42 exhibited concentrations between 900 and 1100 mg./l. The depth of sulfate enrichment in groundwater, near the coal pile, appears to extend to considerable depths, indicated by relatively high sulfate concentrations in Well 26B sealed 100 feet below ground surface. The oxidation of pyrite minerals in the coal leaching into the groundwater is probably the major source of the high concentrations observed.

Sulfate concentrations in the ash disposal settling pond were 520 mg./l. In the ditch carrying the ash pond discharge, the effluent is treated with sulfuric acid which results in precipitation of barium sulfate and aluminum hydroxide (personal communication, Merlin Horn, 1978). Consequently, the sulfate concentration of the effluent waters is lowered considerably to 13 mg./l. Well 33A, however, located near the point of effluent discharge, exhibited 1200 mg./l sulfates.

CHLORIDE

Chloride is generally present in much lower concentrations in rocks than many of the other major constituents of natural water. Important sources, however, are associated with sedimentary rocks, particularly the evaporites. The chemical behavior of chloride in natural water is relatively inert compared to the other major ions. There are few oxidation-reduction reactions and no significant chemical complexing reactions which chloride enters into. In addition, chloride ions are not significantly adsorbed on mineral surfaces. For these reasons, chloride is commonly used as a tracer in groundwater.

Chloride concentrations in groundwater in the vicinity of the Columbia Energy Center typically range between 0.5 mg./l and 30 mg./l. The highest concentrations in monitoring wells tended to be located adjacent to U. S. Highway 51 where the use of road salt has resulted in the percolation of chloride into the groundwater. Monitoring Wells 51A and 51B located in a low area north of Murray Road along U. S. Highway 51, yielded chloride concentrations in excess of 200 mg./l. Two other wells, 52A and 19, also located along U. S. Highway 51, yielded values of 30 mg./l and 42.5 mg./l chloride, respectively.

Within the proposed site boundaries, the chloride concentration averaged 7.1 mg./l. Excluding the few wells adjacent to U. S. Highway 51 exhibiting elevated concentrations, no other significant trends in the occurrence of chloride were observed.

SUMMARY

In summary, the groundwater in the vicinity of the proposed disposal site exhibited a somewhat alkaline pH. In lowland areas, the pH was typically below 7.0, probably a result of the presence of acidic organic soils.

Specific conductance within the proposed site averaged 465 umhos/cm. Conductivities up to 2600 umhos/cm were observed, however, in the vicinity of the coal storage area, the present ash disposal pond and ash pond effluent channel where infiltration of water from these sources is occurring into the groundwater system.

The groundwater typically exhibited relatively low iron concentrations although, locally, concentrations in excess of drinking water standards were observed in about 20% of the wells. The occurrence of the higher iron concentrations appears to be related to the presence of organic soils.

Groundwater at the proposed site also tended to exhibit high calculated hardness (216 mg./l) based on average observed values for calcium (42 mg./l) and magnesium (27 mg./l). Dissolution of limestone and dolomite rocks in the glacial drift are the probable sources of these elements in the groundwater.

Enrichment of sulfate in groundwater has occurred as a result of leaching of pyrite ( $\text{FeS}_2$ ) minerals from the coal storage area where concentrations up to 1200 mg./l were observed. The depth of this enrichment appears to extend beyond the maximum depth into the aquifer investigated. Sulfate concentrations decreased rapidly away from the coal storage area to an average of 12 mg./l within the proposed site boundaries. Other local sources of sulfate in groundwater appear to be related to the present ash settling pond.

The concentration of chloride within the proposed site averaged 7.1 mg./l. Higher levels were generally observed in wells adjacent to U. S. Highway 51 where the infiltration of road salt has locally raised chloride concentrations.

The above interpretations are based on one round of water quality sampling only and should be considered as preliminary in nature. High sulfate and chloride concentrations observed at greater depths may be a temporary condition resulting from contamination of spoil backfill materials with coal dust or salt, respectively, during installation of the monitoring well. Future sampling of these monitoring wells will help to distinguish short term contamination from actual conditions existing in the aquifer.

APPENDIX F  
WATER QUALITY DATA

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
1A	7.6	550	17.	6.5	52	37	<0.1
1B	8.05	460	16.	10.5	39	31	<0.1
2	7.8	527	14.	2.5	45	32	<0.1
3A	7.5	548	13.	2.5	58	36	<0.1
3B	8.1	506	14.	7.0	50	34	<0.1
4	7.8	580	10.	4.0	59	34	<0.1
5	6.3	560	210.	12.5	13	29	10
16	7.6	408	12.	1.5	42	28	<0.1
17	6.45	350	30.	16.5	16	13	0.6
18	6.45	380	4.	4.5	33	22	5.7
19	7.9	570	10.	42.5	44	24	<0.1
20	8.0	340	10.	5.0	36	24	<0.1
21	6.9	220	20.	4.5	23	10	0.1
24A	7.45	775	18.	6.0	76	52	0.1
24B	7.85	440	15.	6.0	43	31	0.1
25	8.1	300	10.	2.5	29	20	<0.1
26A	7.2	2100	900	17.0	140	48	1.5
26B	7.5	2600	1100	16.5	43	7.0	0.2
27	7.15	400	6.	8.0	23	18	<0.1
28A	7.75	500	3.	0.5	48	31	<0.1
28B	7.6	480	4.	3.5	39	28	<0.1
29A	7.8	330	16.	1.5	33	21	0.5
30A	6.75	920	64.	11.0	38	30	26
30B	7.6	770	210	21.0	37	19	<0.1
33A	8.2	2500	1200	24.0	83	50	<0.1
33B	7.9	390	22.	6.5	31	27	0.2
34A	7.7	680	140.	10.0	58	45	0.1
34B	7.7	1700	660	15.0	48	22	<0.1
35	6.8	740	<1.0	4.0	66	33	2.9
36	6.8	740	<1.0	3.5	53	35	6.1
37A	7.7	460	9.	4.0	48	31	0.8
37B	7.5	630	73.	7.5	71	35	<0.1
39A	7.5	1800	350	22.0	180	100	0.1
39B	7.9	330	560	20.5	31	22	0.1
40A	8.0	630	140	8.5	43	29	<0.1
40B	8.1	330	17.	3.0	31	22	<0.1
41	6.8	590	16.	11.0	58	27	9.3



WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
42	7.4	2400	900	17.5	50	12	0.5
44	6.9	490	<1.	16.5	39	23	11
45	7.6	390	14.	3.0	40	25	<0.1
46A	7.3	1100	21.	15.5	140	82	<0.1
46B	7.8	470	25.	17.5	40	26	<0.1
47	6.6	1200	3.	8.0	140	40	16
48A	7.3	620	15.	8.0	62	37	<0.1
48B	7.1	520	22.	20.0	43	29	0.2
49	7.15	730	6.	3.5	75	41	<0.1
50A	7.6	520	28.	15.5	51	34	<0.1
50B	7.5	410	21.	18.0	31	21	<0.1
51A	6.1	1850	8.	205.	65	40	<0.1
51B	7.2	1250	23.	275.	57	36	21
52A	7.7	450	16.	30.5	36	17	<0.1
52B	7.4	430	40.	17.5	32	20	<0.1
53	7.75	450	27.	10.5	39	28	<0.1
54A	7.8	350	12.	4.0	34	21	0.1
54B	7.55	390	15.	5.5	40	24	0.1
55B	7.9	340	23.	17.5	32	22	0.1
56	7.8	450	22.	9.5	43	28	0.1
57	7.85	380	17.	7.0	38	24	0.1
M-6	7.0	1160	5.	7.0	150	91	2.3
Cooling Lake	8.3	370	31.	18.0	34	21	<0.1
Ash Pond Effluent	7.45	1380	13.	4.0	28	1.2	3.7
Ash Pond Drainage	11.4	1510	520.	23.5	29	0.2	<0.1
Ditch (A) Drainage	7.8	500	21.	7.0	43	29	<0.1
Ditch (B)	9.05	1780	750	14.0	42	5.4	<0.1

DEC 19 1979

APPENDICES TO

SUPPLEMENTARY FEASIBILITY STUDY REPORT  
AND PRELIMINARY ENGINEERING CONCEPTS  
COLUMBIA SITE  
WISCONSIN POWER AND LIGHT COMPANY  
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

D. N. R. APPROVED  
DATE 9/3/80  
Nile Ostenso, Hydro



APPENDIX I

WATER QUALITY DATA - DECEMBER 1978



WATER QUALITY DATA


12/78

C 7134

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
1A	7.3	530	30	3.1	54	35	<0.1	-
1B	7.0	470	67	6.1	49	30	<0.1	-
2	7.25	458	91	<.5	48	24	<0.1	-
3A	7.0	560	36	<.5	61	31	<0.1	-
3B	7.15	530	52	35.7	37	33	<0.1	-
4	7.2	750	69	5.8	49	30	<0.1	-
5	6.35	1,650	670	14.1	14	13	1.7	-
16	6.9	390	69	1.0	49	23	<0.1	-
17	5.55	295	57	16.3	14	8.6	0.2	-
18	5.9	430	10	4.2	47	21	1.1	-
19	7.4	765	75	4.2	51	28	<0.1	-
20	7.4	380	26	1.6	39	26	<0.1	-
21	5.7	250	54	10.4	15	8.3	0.2	-
24A	7.2	730	36	1.6	65	42	<0.1	-
24B	7.2	470	10	7.3	42	28	<0.1	-
25	7.0	335	29	7.8	39	21	0.2	-
26A	7.4	2,250	650	12.6	32	8.6	<0.1	-
26B	6.8	2,530	840	20.8	49	18	<0.1	-
27	6.9	410	24	4.2	40	24	0.4	-
28A	7.2	500	61	0.5	45	28	<0.1	-
28B	7.0	465	6	2.1	39	26	0.1	-
29A	7.1	410	24	3.6	31	22	0.1	-
30A	5.8	1,140	15	<0.5	97	56	38	-
30B	6.65	835	160	14.6	37	20	<0.1	-
33A	7.8	1,970	830	16.7	21	8.9	<0.1	-
33B	7.5	380	31	7.3	24	27	<0.1	-
34A	7.25	560	46	4.2	53	33	<0.1	-
34B	8.5	1,575	730	21.9	28	29	0.1	-
35	6.7	545	61	3.6	60	26	1.0	-
36	6.4	515	5.0	2.6	43	24	4.8	-
37A	7.05	438	30	3.7	50	28	<0.1	-
37B	6.7	325	18	7.3	1.0	0.5	<0.1	-
39A	6.35	1,260	33	13.6	70	7.6	0.1	-
39B	6.7	385	25	4.2	30	21	<0.1	<.05
40A	7.35	483	40	<0.5	48	24	<0.1	-
40B	7.25	343	4	4.2	21	14	<0.1	-
41	6.1	640	54	19.8	43	32	<0.1	-

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
42 <i>near old</i>	7.15	2,050	910	15.6	23	7.5	0.1	-
44 <i>near old</i>	6.15	710	6	0.5	56	27	3.5	-
45 <i>near old</i>	7.2	420	32	1.0	44	26	<0.1	-
46A <i>near old</i>	7.0	560	93	<0.5	130	75	<0.1	<0.05
46B <i>near old</i>	6.5	1,290	170	20.8	46	30	<0.1	<0.05
47 <i>near old</i>	7.3	958	120	<0.5	110	48	<0.1	-
48A <i>near old</i>	6.15	640	59	<0.5	42	51	<0.1	<0.05
48B <i>near old</i>	6.8	450	23	5.2	40	27	<0.1	<0.05
49 <i>near old</i>	7.0	880	26	2.1	93	58	0.1	-
50A <i>near old</i>	7.4	660	25	17.7	60	36	<0.1	-
50B <i>near old</i>	7.1	405	16	17.7	38	23	<0.1	-
51A <i>near old</i>	7.0	1,170	57	135	66	31	<0.1	-
51B <i>near old</i>	7.3	1,410	22	330	46	39	<0.1	-
52A <i>near old</i>	7.0	370	110	18.5	35	10	<0.1	-
52B <i>near old</i>	7.0	595	43	52.5			0.1	-
53	Frozen							
54A <i>near old</i>	7.5	345	10	1.0	36	22	<0.1	<0.05
54B	Frozen							
55B <i>near old</i>	7.3	505	26	15.6	52	29	<0.1	<0.05
56	Frozen							
57	Frozen							
M-6								
58 <i>near old</i>	6.55	1,265	140*	<0.5	110	65	0.1	-
59 <i>near old</i>	6.8	925	40	<0.5	86	60	<0.1	-
60 <i>near old</i>	7.2	1,510	54	4.7	130	85	<0.1	-
61A <i>near old</i>	6.85	590	39	30.2	58	31	<0.1	-
61B <i>near old</i>	7.2	505	6	13.5	48	29	<0.1	-
62 <i>Insect Hygiene</i>	6.7	1,517	72	178	120	53	<0.1	-
64 <i>near old</i>	6.9	670	100	26.8	63	36	0.8	-
65 <i>near old</i>	7.2	830	57	17.8	78	50	<0.1	-
66 <i>near old</i>	6.5	680	55	40	66	24	3.6	-

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
67	7.0	560	100	1.0	57	32	1.0	-
68A	7.6	440	32	2.1	40	27	<0.1	-
68B	7.2	400	36	1.0	42	25	<0.1	-
70A	7.5	440	20	<0.5	27	37	<0.1	-
70B	7.3	520	25	5.2	51	34	<0.1	-
72AZ	6.45	860	11	<0.5	100	41	1.8	-
72B	8.4	230	45	<0.5	17	19	<0.1	-
M-4	7.6	864	180	26.1	20	11	<0.1	0.39
MM-4			2	2.6	14	21	0.9	-
Cooling Lake at 1	7.7	355	36	13.6	31	21.2	<0.1	-
Ash Pond at 2	11.4	3,210	1,100	22.9	34	<0.1	<0.1	-
Ash Pond at 3	8.7	725	34	21.9	48	16	<0.1	-
Ash Pond Effluent at 4	6.7	3,090	1,400	25.0	39	0.4	<0.1	-
Drainage Ditch at 5	7.2	730	74	33.9	56	38	<0.1	-
Drainage Ditch at 6	7.35	2,750	640	18.8	34	7.5	<0.1	-
Drainage Ditch at 7	8.05	1,780	740	27.1	31	0.2	<0.1	-




# Appendix C


## Long-Term Concentration Trend Plots



**Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-33A and MW-33AR - Boron ( $\mu\text{g/l as B}$ )**




Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW34A - Boron ( $\mu\text{g/l}$  as B)




I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Graphs\[Bo\_COL Dry.xlsx]MW-34A

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-302 and MW-85 - Boron ( $\mu\text{g/l}$  as B)




I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Graphs\[Bo\_COL Dry.xlsx]MW-85

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-33 and MW-33AR - Chloride (mg/l as Cl)




I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Graphs\[Cl\_COL Dry.xlsx]MW-33AR

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW34A - Chloride (mg/l as Cl)




I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Graphs\[Cl\_COL Dry.xlsx]MW-34A

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-33 and MW-33AR - Sulfate (mg/l as SO<sub>4</sub>)



I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Graphs\[SO4\_COL Dry.xlsx]MW-33AR CCR


Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-34A - Sulfate (mg/l as SO4)



I:\25223067.00\Deliverables\COL MOD 1 - 3 ASD October 2022\Graphs\[SO4\_COL Dry.xlsx]MW-34A CCR



Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-85 and MW-302 - Sulfate (mg/l as SO4)



Appendix D  
Historical Groundwater Flow Maps






**LEGEND**

- ..... PROPOSED PROJECT AREA
- 720.29 OBSERVATION WELL LOCATION, NUMBER, AND WATER TABLE ELEVATION
- BORING LOCATION AND NUMBER
- WETLANDS
- TOPOGRAPHIC CONTOURS (CONTOUR INTERVAL: 20FT.)
- PRIVATE RESIDENCES (ASSUMED LOCATIONS OF PRIVATE WATER SUPPLY WELLS)
- COMMERCIAL BUILDINGS (ASSUMED LOCATIONS OF POSSIBLE PUBLIC WATER SUPPLY WELLS)
- SURFACE WATERS (STREAMS OR DRAINAGE DITCHES; ARROWS INDICATE DIRECTION OF FLOW)
- OTHER BUILDINGS (GARAGES, BARN, ETC.)
- HIGH CAPACITY WELLS
- 790- WATER TABLE CONTOURS (CONTOUR INTERVAL: 1 FT.)
- ➔ DIRECTION OF GROUNDWATER FLOW


NO.	BY	DATE	REVISION	APPD.
<b>WATER TABLE CONTOUR MAP 2/4/81</b>				
<b>PLAN OF OPERATION - ASH DISPOSAL FACILITY</b>				
<b>COLUMBIA SITE</b>				
<b>WISCONSIN POWER &amp; LIGHT COMPANY</b>				
PART OF SECTIONS 27 & 34, T12N, R9E				
<b>TOWN OF PACIFIC COLUMBIA CO. WISCONSIN</b>				
<b>WARZYN</b>		DRAWN TDH	SCALE 1"=300'	SHEET 39 OF 39
		CHECKED RJK	DATE 2/10/81	DRAWING NO.
		APPROVED		C7134-94
ENGINEERING INC.		REFERENCE		PRINTED 8/3/88





- LEGEND**
- PROPERTY LINE
  - EXISTING RAILROAD TRACKS
  - EXISTING GROUND CONTOUR
  - CONTOUR DEPRESSION
  - EXISTING PAVED ROAD
  - EXISTING UNPAVED ROAD
  - EXISTING FENCE
  - EXISTING BUILDING
  - EXISTING SPOT ELEVATION
  - TREES AND/OR BRUSH
  - WETLAND AREA
  - EDGE OF WATER
  - HC 1 WATER SUPPLY WELL
  - MW61A WATER TABLE WELL
  - MW61B PIEZOMETER
  - ABANDONED WATER TABLE WELL
  - ABANDONED PIEZOMETER
  - SG1 STAFF GAUGE
  - ▲ LLS-1 LYSMETER
  - DESIGN MANAGEMENT ZONE
  - PROPERTY LINE
  - O.S. OPEN STORAGE
  - O.H. OVERHEAD STRUCTURE
  - E.P.S. ELECTRICAL POWER STATION
  - T TANK
  - W WALL
  - (785.31) WATER TABLE ELEVATION (FT.-MSL)  
(N.M. = NOT MEASURED)
  - 786 GROUNDWATER CONTOUR LINE  
(FT. INTERVAL - FT. M.S.L.)  
(DASHED WHERE INFERRED)
  - GROUNDWATER FLOW DIRECTION

- NOTES**
1. BASE MAP IS PROVIDED BY WISCONSIN POWER & LIGHT CO. AND IS BASED ON PHOTOS TAKEN ON APRIL 6, 1995 BY AERO-METRIC ENGINEERING, SHEBOYGAN, WI.
  2. HORIZONTAL DATUM IS BASED ON THE WISCONSIN STATE PLANE COORDINATE SYSTEM, SOUTH ZONE - DATUM NAD 83(01).
  3. VERTICAL DATUM IS REFERENCED TO U.S.G.S. MEAN SEA LEVEL (MSL). TOPOGRAPHIC CONTOUR INTERVAL IS TWO FEET.
  4. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER & LIGHT CO. IN DECEMBER 1994 & NOVEMBER 1996.
  5. THE LOCATION OF THE DESIGN MANAGEMENT ZONE DEMARCATION LINE IS APPROXIMATE.
  6. WATER ELEVATION USED TO PREPARE THIS MAP WERE MEASURED ON OCTOBER 24, 2002.
  7. THE WATER LEVEL AT MW 33A AND MW 33B COULD NOT BE MEASURED DURING OCTOBER 2002 DUE TO AN OBSTRUCTION IN THE WELL CASING.



3.			
2.			
1.			
NO. BY DATE	REVISION		APP'D.
PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY			
SHEET TITLE: WATER TABLE MAP (OCTOBER 2002)			
DRAWN BY: defoe	SCALE: 1"=200'	PROJ. NO. 3024.28	
CHECKED BY: JMR		FILE NO. WATERTBL.PLT	
APPROVED BY: JCD	DATE PRINTED:		FIGURE 3
DATE: JANUARY 2003			

PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY  
 SHEET: WATER TABLE MAP (OCTOBER 2002)  
 DRAWN BY: defoe  
 CHECKED BY: JMR  
 APPROVED BY: JCD  
 DATE: JANUARY 2003  
 SCALE: 1"=200'  
 PROJ. NO. 3024.28  
 FILE NO. WATERTBL.PLT  
 FIGURE 3



## E2 April 2023 Detection Monitoring Alternative Source Demonstration

# Alternative Source Demonstration April 2023 Detection Monitoring

Dry Ash Disposal Facility, Modules 1-3  
Columbia Energy Center  
Pardeeville, Wisconsin

Prepared for:



**SCS ENGINEERS**

25223067.00 | November 21, 2023

2830 Dairy Drive  
Madison, WI 53718-6751  
608-224-2830

## Table of Contents

Section	Page
<b>PE Certification</b> .....	<b>iii</b>
<b>1.0 Introduction</b> .....	<b>1</b>
1.1 §257.94(e)(2) Alternative Source Demonstration Requirements .....	1
1.2 Site Information and Map .....	1
1.3 Statistically Significant Increases Identified .....	2
1.4 Overview of Alternative Source Demonstration.....	2
<b>2.0 Background</b> .....	<b>3</b>
2.1 Regional Geology and Hydrogeology .....	3
2.1.1 Regional Information .....	3
2.1.2 Site Information .....	3
2.2 CCR Rule Monitoring System .....	4
2.3 Other Monitoring Wells.....	4
<b>3.0 Methodology and Analysis Review</b> .....	<b>4</b>
3.1 Sampling and Field Analysis .....	4
3.2 Laboratory Analysis Review .....	5
3.3 Statistical Evaluation Review.....	5
3.4 Summary of Methodology and Analysis Review Findings .....	5
<b>4.0 Alternative Sources</b> .....	<b>5</b>
4.1 Potential Causes of SSI.....	5
4.1.1 Natural Variation .....	5
4.1.2 Man-Made Alternative Sources .....	6
4.2 Lines of Evidence .....	6
4.2.1 Pre-Landfill Water Quality .....	6
4.2.2 Long-Term Concentration Trends .....	7
4.2.3 Groundwater Flow Direction Changes.....	7
4.2.4 Chloride and Boron Concentrations .....	8
<b>5.0 Alternative Source Demonstration Conclusions</b> .....	<b>8</b>
<b>6.0 Site Groundwater Monitoring Recommendations</b> .....	<b>9</b>
<b>7.0 References</b> .....	<b>10</b>

### Tables

Table 1.	Groundwater Analytical Results Summary – April 2023 Event
Table 2.	Historical Analytical Results for Parameters with SSIs
Table 3.	Groundwater Elevation – State Monitoring Program and CCR Well Network
Table 4.	Analytical Results – Lysimeters and Leachate Pond



## Figures



- Figure 1. Site Location Map
- Figure 2. Site Plan and Monitoring Well Locations
- Figure 3. Water Table Map – April 2023

## Appendices

- Appendix A Trend Plots for CCR Wells
- Appendix B Feasibility Study Water Quality Information
- Appendix C Long-Term Concentration Trend Plots
- Appendix D Historical Groundwater Flow Maps

I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\231121\_COL\_1-3 LF\_Apr 2023 ASD\_Final.docx

# PE CERTIFICATION

 <p>11/20/2023</p>	<p>I, Sherren Clark, hereby certify that the information in this alternative source demonstration is accurate and meets the requirements of 40 CFR 257.94(e)(2). This certification is based on my review of the groundwater data and related site information available for the Columbia Energy Center Dry Ash Disposal Facility. I am a duly licensed Professional Engineer under the laws of the State of Wisconsin.</p>
	
	<p>11/20/2023</p>
	<p>(signature) (date)</p>
	<p>Sherren Clark, PE (printed or typed name)</p>
<p>License number E-29863</p>	
<p>My license renewal date is July 31, 2024.</p>	
<p>Pages or sheets covered by this seal: Alternative Source Demonstration, April 2023 Detection Monitoring, Dry Ash Disposal Facility, Modules 1-3, Columbia Energy Center, Pardeeville, Wisconsin</p>	

[This page left blank intentionally]

## 1.0 INTRODUCTION

This Alternative Source Demonstration (ASD) was prepared to support compliance with the groundwater monitoring requirements of the “Coal Combustion Residuals (CCR) Final Rule” published by the U.S. Environmental Protection Agency (U.S. EPA) in the *Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule*, dated April 17, 2015 (U.S. EPA, 2015), and subsequent amendments. Specifically, this report was prepared to fulfill the requirements of 40 CFR 257.94(e)(2). The applicable sections of the Rule are provided below in *italics*.

### 1.1 §257.94(E)(2) ALTERNATIVE SOURCE DEMONSTRATION REQUIREMENTS

*The owner and operator may demonstrate that a source other than the CCR Unit caused the statistically significant increase over background levels for a constituent or that the statistically significant increase resulted from error in sampling, analysis, statistical evaluation, or natural variation in groundwater quality. The owner or operator must complete the written demonstration within 90 days of detecting a statistically significant increase over background levels.*

An ASD is completed when there are exceedances of one or more benchmarks established within the groundwater monitoring program to determine if any other sources are likely causes of the identified exceedance(s) of established benchmark(s) at the site. This ASD was performed in response to results indicating a statistically significant increase (SSI) over background levels during detection monitoring under the CCR Rule.

This ASD report evaluates the SSIs observed in the statistical evaluation of the October 2022 detection monitoring event at the Columbia Energy Center (COL) Dry Ash Disposal Facility (ADF), Modules 1-3 CCR Unit. The first ASD was prepared for this facility evaluating the SSIs observed in the statistical evaluation of the October 2017 detection monitoring event (SCS Engineers [SCS], 2018). The October 2017 ASD and subsequent semiannual updates have provided several lines of evidence demonstrating that SSIs reported for boron, chloride, field pH, and sulfate concentrations in the downgradient monitoring wells were likely due to man-made sources other than the CCR Units and/or naturally occurring constituents in the alluvial aquifer.

As discussed in more detail in **Section 4.2** of this ASD, the findings for the April 2023 monitoring event were consistent with those for the previous events.

### 1.2 SITE INFORMATION AND MAP

The COL site is located at W8375 Murray Road, Pardeeville, Columbia County, Wisconsin (**Figure 1**). The COL site is an active coal-burning generating station, which has been burning coal and disposing of CCR on site since the mid-1970s. The layout of the site is shown on **Figure 2**. The COL property includes two areas of CCR storage and disposal. These are the ADF and the Ash Ponds Facility. This ASD will evaluate the conditions at the site for Modules 1-3 of the ADF only. The ADF is operated under the Wisconsin Department of Natural Resources (WDNR) License No. 3025.

The groundwater monitoring system monitors the following CCR Unit:

- COL Dry ADF – Modules 1-3 (existing CCR Landfill)

Modules 1-3 were originally described as separate existing CCR landfills, although they are contiguous and are managed as a single landfill by the facility and by the WDNR. Wisconsin Power and Light Company (WPL) subsequently clarified that Modules 1-3 are one existing CCR landfill under the federal CCR Rule, and this report reflects WPL's clarification.

A map showing the CCR Unit and all background (or upgradient) and downgradient monitoring wells with identification numbers for the CCR groundwater monitoring program and the state monitoring program is provided as **Figure 2**. Separate monitoring systems have been established for the other CCR Units at COL, which include Modules 4-6 of the COL ADF, Modules 10-11 of the COL ADF, the primary ash pond, and the secondary ash pond.

### 1.3 STATISTICALLY SIGNIFICANT INCREASES IDENTIFIED

SSIs were identified by comparing the monitoring results to Upper Prediction Limits (UPLs) established in accordance with 40 CFR 257.93(f)(3) and the statistical method previously selected for the CCR Unit. The UPLs are based on an interwell approach using two background monitoring wells: MW-84A and MW-301. The interwell UPLs were calculated based on a 1-of-2 resampling approach. The UPLs and results for the April 2023 monitoring event are summarized in **Table 1**.

The April 2023 SSIs include the following parameters and wells:

- Boron: MW-33AR, MW-34A, MW-302
- Chloride: MW-33AR
- Sulfate: MW-33AR, MW-34A, MW-302

Concentration trends for the parameters with SSIs are shown in **Appendix A**.

### 1.4 OVERVIEW OF ALTERNATIVE SOURCE DEMONSTRATION

This ASD report includes:

- Background information (**Section 2.0**).
- Evaluation of potential that SSIs are due to methodology or analysis (**Section 3.0**).
- Evaluation of potential that SSIs are due to natural sources or man-made sources other than the CCR Units (**Section 4.0**).
- ASD conclusions (**Section 5.0**).
- Monitoring recommendations (**Section 6.0**).

The CCR Rule constituent results from background and compliance sampling for parameters with SSIs are provided in **Table 2**. The laboratory reports for the April 2023 detection monitoring event will be included in the 2023 Annual Groundwater Monitoring and Corrective Action Report to be completed in January 2024. Complete laboratory reports for the background monitoring events and the previous detection monitoring events were included in previous annual groundwater monitoring and corrective action reports.



## 2.0 BACKGROUND

To provide context for the ASD evaluation, the following background information is provided in this section of the report, prior to the ASD evaluation sections:

- Geologic and hydrogeologic setting
- CCR Rule monitoring system
- Other monitoring wells

A more detailed discussion of the background information for the site is provided in the ASD for the October 2017 event (SCS, 2018).

## 2.1 REGIONAL GEOLOGY AND HYDROGEOLOGY

### 2.1.1 Regional Information

For the purposes of groundwater monitoring, the surficial sand and gravel aquifer is considered the uppermost aquifer, as defined under 40 CFR 257.53. Immediately underlying the surficial sand and gravel aquifer is the Cambrian-Ordovician sandstone aquifer.

Additional details on the regional geology and hydrogeology were provided in the October 2017 ASD (SCS, 2018).

### 2.1.2 Site Information

Soils at the site are primarily sand to a depth of approximately 50 to 100 feet, and overlie sandstone bedrock. Soils encountered during the site feasibility study for the COL ADF were described as generally sandy with interbedded silty clay lenses up to 20 feet thick (Warzyn Engineering, Inc. [Warzyn], 1978). During drilling of CCR wells MW-301 and MW-302, the unconsolidated materials were identified as consisting primarily of silty sand and sand. Boring logs for previously installed monitoring wells MW-33AR, MW-34A, MW-84A, and MW-1AR (abandoned) show silty sand and sand as the primary unconsolidated materials at these locations. All CCR monitoring wells are screened within the unconsolidated sand unit.

Shallow groundwater at the site generally flows to the north and west across the existing landfill Modules 1-3 area, then generally flows west toward the Wisconsin River. The groundwater flow map for April 2023 is shown on **Figure 3**. Historically, localized groundwater mounding was associated with the ash ponds; however, flow in the ash pond area changed in 2022 and 2023 as the ponds were closed and CCR was removed. In 2022, dewatering wells located around the Secondary Pond lowered the water table near the Secondary Ash Pond and discharged groundwater to the Primary Ash Pond. Beginning in spring 2023, dewatering activities switched to the Primary Ash Pond area, and groundwater pumped from dewatering wells around the Primary Ash Pond was discharged to the large cooling pond south of the generating station. The April 2023 groundwater flow map shows temporary inward gradients in the vicinity of the Primary Ash Pond due to dewatering activities. These temporary changes may have had some impact on flow directions in the MOD 1-3 area, but the general flow directions to the north and/or west did not change. The groundwater elevation data for the CCR monitoring wells and state monitoring program wells are provided in **Table 3**.

## 2.2 CCR RULE MONITORING SYSTEM

The groundwater monitoring system established in accordance with the CCR Rule consists of two upgradient (background) monitoring wells and three downgradient monitoring wells (**Table 1** and **Figure 2**). The background wells include MW-301 and MW-84A. The downgradient wells include MW-302, MW-33AR, and MW-34A. MW-1AR was added to the monitoring program in 2021 as a supplemental well because monitoring data have indicated that the groundwater flow direction in this part of the site is sometimes to the northeast. MW-1AR was abandoned in 2022 because it was within the footprint of the Modules 10-11 expansion area. The monitoring network certification was updated with the abandonment of MW-1AR in October 2022. Flow direction in this area of the site will continue to be monitored by additional wells in the State monitoring program, including water level-only monitoring wells MW-312 and MW-93A, and CCR rule monitoring wells for Modules 10-11, including MW-313, MW-314, and MW-315. The CCR Rule wells are installed within the sand and gravel aquifer. Well depths range from approximately 29 to 51 feet, measured from the top of the well casing.

## 2.3 OTHER MONITORING WELLS

Additional groundwater monitoring wells currently exist at COL as part of the monitoring systems developed for the state monitoring program and for the other CCR Units.

Monitoring wells for the state monitoring program are installed in the unconsolidated sand and gravel unit, which is the uppermost aquifer as defined under 40 CFR 257.53. This shallow monitoring system includes water table wells and mid-depth piezometers. Well depths range from approximately 14 to 76 feet, measured from the top of the well casing.

## 3.0 METHODOLOGY AND ANALYSIS REVIEW

To evaluate the potential that an SSI is due to a source other than the regulated CCR Unit, SCS used a two-step evaluation process. First, the sample collection, field and laboratory analysis, and statistical evaluation were reviewed to identify any potential error or analysis that led to exceedance of the benchmark. Second, potential alternative sources, including natural variation and man-made sources other than the CCR Unit, were evaluated. This section of the report provides the findings of the methodology and analysis review. **Section 4.0** of the report addresses the potential alternative sources.

## 3.1 SAMPLING AND FIELD ANALYSIS

Field notes and sampling results were reviewed to determine if any sampling error may have caused or contributed to the observed SSIs. Potential field sampling errors or issues could include mislabeling of samples, improper sample handling, missed holding times, cross-contamination during sampling, or other field error. Field blank sample results were also reviewed for any indication of potential contamination from sampling equipment or containers.

SCS did not identify any sampling errors for field data that may have caused or contributed to observed SSIs.

The April 2023 monitoring event was completed in accordance with the Sampling and Analysis Plan for the monitoring system.

## 3.2 LABORATORY ANALYSIS REVIEW

The laboratory reports for the April 2023 detection monitoring event were reviewed to determine if any laboratory analysis error or issue may have caused or contributed to an observed SSI for boron, chloride, or sulfate. The laboratory report review included reviewing the laboratory quality control flags and narrative, verifying that correct methods were used and desired detection limits were achieved, and checking the field and laboratory blank sample results.

Based on the review of the laboratory reports, SCS did not identify any laboratory analysis issues that could have caused or contributed to the observed SSIs for boron, chloride, and sulfate.

Time series plots of the SSI constituent analytical data were also reviewed for any anomalous results that might indicate a possible sampling or laboratory error (e.g., dilution error or incorrect sample labeling). The time series plots are provided in **Appendix A**. The concentrations observed are similar to historical concentrations for sulfate, boron, and chloride.

## 3.3 STATISTICAL EVALUATION REVIEW

The review of the statistical results and methods included a quality control check of the following:

- Input analytical data vs. laboratory analytical reports
- Statistical method and process for each SSI

Based on the review of the statistical evaluation, SCS did not identify any errors or issues in the statistical evaluation that caused or contributed to the determination of interwell SSIs for the April 2023 detection monitoring event.

## 3.4 SUMMARY OF METHODOLOGY AND ANALYSIS REVIEW FINDINGS

In summary, there were no changes to the SSI determinations for the April 2023 monitoring event based on the methodology and analysis review. No other errors or issues causing or contributing to the reported SSIs were identified.

## 4.0 ALTERNATIVE SOURCES

This section of the report discusses the potential alternative sources for the boron, chloride, and sulfate SSIs at the downgradient monitoring wells; identifies the most likely alternative source(s); and presents the lines of evidence indicating that an alternative source is the most likely cause of the observed SSIs.

### 4.1 POTENTIAL CAUSES OF SSI

#### 4.1.1 Natural Variation

The statistical analysis was completed using an interwell approach, comparing the April 2023 detection monitoring results to the UPLs calculated based on the sampling of the background wells (MW-84A and MW-301). If concentrations of a constituent that is naturally present in the aquifer vary spatially, then the potential exists that the downgradient concentrations may be higher than upgradient concentrations due to natural variation. Previous monitoring results for boron, chloride, and sulfate at COL Modules 1-3 landfill are shown in **Table 2**.

Although natural variation is present in the shallow aquifer, it does not appear likely that natural variation is the primary source causing the boron, chloride, and sulfate SSIs.

#### **4.1.2 Man-Made Alternative Sources**

Man-made alternative sources that could potentially contribute to the boron, chloride, and sulfate SSIs could include the closed ash pond landfill, the active and inactive ash ponds, the former ash pond effluent ditch, the coal storage area, road salt use, railroad operations, or other plant operations.

Based on the groundwater flow directions and on previous investigations at the site, the former ash pond effluent ditch, a non CCR alternative source, appears to be the most likely cause of the boron and/or sulfate SSIs for wells MW-33AR, MW-34A, and MW-302. The ash pond effluent ditch may also have contributed to the chloride SSI at MW-33AR.

### **4.2 LINES OF EVIDENCE**

The lines of evidence indicating that the SSIs for boron, chloride, and sulfate in compliance wells MW-33AR, MW-34A, and MW-302, relative to the background wells, are due to an alternative source include:

1. Elevated levels of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located before the landfill was constructed.
2. Monitoring performed under the state program documents that the concentrations of boron, chloride, and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation.
3. Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing west and/or north.
4. The variations in chloride results for well MW-33AR since detection monitoring was initiated have not correlated with boron concentrations, as would be expected for a CCR leachate source; therefore, an alternative source is more likely.

#### **4.2.1 Pre-Landfill Water Quality**

Elevated levels of boron, chloride, and sulfate were present in the area west of the landfill, where the three compliance wells are located, before the landfill was constructed. Groundwater monitoring performed in 1977 and 1978 as part of the Feasibility Study for the landfill permitting showed that wells located along the west side of the future landfill footprint, where the current compliance wells are located, had elevated results for sulfate, chloride, and specific conductance. The 1978 Feasibility Study (Warzyn, 1978) for the Dry ADF discusses the influence of the ash pond effluent ditch on groundwater west of the proposed site. The former ash pond effluent ditch carried effluent from the ash ponds located north of the plant, and flowed south between the west side of the current landfill and the substation. Groundwater monitoring in December 1977 indicated that sulfate was present at 1,200 milligrams per liter (mg/L) in MW-33A, which was located near the point where the ash pond effluent discharged from a culvert into the effluent ditch. The sulfate concentration at this well decreased to 830 mg/L in the December 1978 sampling (Warzyn, 1979). Current concentrations of sulfate in this area, while above background, are much lower. The April

2023 sulfate result for MW-33AR (installed to replace MW-33A) was 104 mg/L, for MW-34A was 48.4 mg/L, and for MW-302 was 36.6 mg/L (**Table 1**).

Selected text and tables from the 1978 Feasibility Study and the 1979 Supplementary Feasibility Study Report are included in **Appendix B**.

#### 4.2.2 Long-Term Concentration Trends

Monitoring performed under the state program documents that the concentrations of boron and sulfate were elevated before CCR disposal in the landfill began, and have decreased since the landfill has been in operation. Routine groundwater monitoring for the COL ADF began after the Plan of Operation was approved and prior to initial CCR disposal. The earliest data available from the WDNR Groundwater Environmental Monitoring System (GEMS) database is from September 1984. Initial placement of CCR in test plots in Module 1 of the ADF was approved in October 1984, and CCR disposal began sometime after that. Therefore, the initial groundwater monitoring results in the GEMS database represent pre-disposal conditions for the landfill.

The earliest historic monitoring data show that before CCR disposal in the landfill began, concentrations of boron and sulfate were significantly higher than current concentrations in the area west of the landfill where the compliance wells are located. Graphs of historical concentrations are provided in **Appendix C**. Results for compliance well MW-33AR are plotted with results from well MW-33A. MW-33AR was a replacement well for MW-33A at a slightly different location and depth. The well screen was installed approximately 10 feet higher in MW-33AR than in MW-33A, intersecting the water table, which may explain the increase in concentration that occurred with the well replacement. Results for compliance well MW-302 are plotted with results from monitoring well MW-85, which was located near the current MW-302 location (see **Figure 2**) and was monitored from September 1984 through September 1995.

The recent boron concentrations are consistent with generally decreasing or stable historical concentrations at MW-33AR and MW-34A (**Appendix A** and **Appendix C**). Recent boron concentrations at MW-302 have been variable, but remain well below the concentrations observed in samples from MW-85 prior to CCR disposal in the landfill.

#### 4.2.3 Groundwater Flow Direction Changes

Groundwater flow directions have changed through time due to changes in water management at the plant, so that groundwater impacted by the effluent ditch formerly flowed to the east, under the landfill, and is now flowing north and/or west. The 1978 Feasibility Study report states that the southern 2/3 of the proposed fill area (including the area of the active CCR landfill phases) exhibits a southeast and southerly groundwater flow direction, toward an agricultural drainage ditch southeast and south of the landfill area. The 1981 Plan of Operation indicates that flow in the landfill area is to the east-southeast. A water table map prepared by RMT, based on October 2002 water level measurements, shows flow under the landfill generally to the east and northeast from a groundwater high near the effluent ditch and Wisconsin Pollutant Discharge Elimination System (WPDES) pond between the landfill and the substation. The 1981 and 2002 water table maps are provided in **Appendix D**.

Under current conditions, groundwater flow below the active landfill area is generally to the north and northwest. The flow changes with time reflect the termination of discharge to the ash pond effluent ditch in the mid-2000s. When discharge via this ditch was active, the ditch was a source of recharge to the groundwater and created a high groundwater area with flow moving away from the



ditch to the east. After discharge to the ditch was terminated, water levels in this area decreased significantly and the groundwater flow direction changed.

With the changes in groundwater flow, historically impacted groundwater moved in alternating directions. While the effluent ditch was active, impacted groundwater likely moved eastward past the current compliance wells, as indicated by the long-term concentration data. Although the compliance wells on the west side of Modules 1-3 are downgradient from the landfill under current flow conditions, the observed groundwater impacts may be residual from the past when the wells were downgradient from the effluent ditch.

#### 4.2.4 Chloride and Boron Concentrations

The variations in chloride results for well MW-33AR since detection monitoring was initiated have not correlated with boron concentrations, as would be expected for a CCR leachate source; therefore, an alternative source is more likely. The chloride results for well MW-33AR increased beginning in 2016, peaked in April 2018 and April 2019, decreased significantly in May 2020, and have remained relatively low since then. The 2022 and April 2023 concentrations exceeded the interwell UPL but were significantly lower than the values observed in 2019 (**Table 2** and **Appendix A**). Current chloride concentrations at MW-33AR are similar to those reported for samples from MW-33A prior to CCR disposal in the landfill (**Appendix B**).

Over the time period since 2016, when chloride concentrations at MW-33AR were highly variable, boron concentrations at MW-33AR have been generally following a long, steady decreasing trend. The lack of correlation with boron indicates the source of the increase and subsequent decrease in chloride is not likely the CCR landfill.

Sampling of the landfill leachate pond and lysimeters LS-1 and LS-3R, located on the western and southern edges of Modules 1-3, indicates that boron and chloride concentrations are generally both higher than background (**Table 4**); therefore, a leachate source would tend to influence concentrations of both parameters. Furthermore, the peak chloride concentrations in the groundwater samples from MW-33AR in 2018 and 2019 exceeded the chloride concentrations measured in the leachate at that time, indicating the leachate was not the source of chloride at this location (**Table 2**, **Table 4**, and **Appendix A**). Recent samples from the leachate pond have shown increased concentrations of chloride, but this increase does not correlate with results at MW-33AR, which have decreased, or with chloride results from the lysimeters, which remain low. Based on the comparison of groundwater and leachate chloride results, an alternative man-made source, such as road salt, is a more likely source of chloride than the CCR Unit.

## 5.0 ALTERNATIVE SOURCE DEMONSTRATION CONCLUSIONS

The lines of evidence discussed above regarding the SSIs reported for boron, chloride, and sulfate concentrations in downgradient monitoring wells MW-33AR, MW-34A, and/or MW-302 demonstrate that the SSIs are likely primarily due to sources other than the CCR Unit. Boron and sulfate concentrations were elevated prior to disposal of CCR in the landfill and are associated with historical discharges from the ash ponds via the effluent ditch located west of the landfill. Pre-landfill chloride concentrations at MW-33A were also similar to current concentrations at MW-33AR and historic impacts may have contributed to the SSI for chloride. However, based on more recent higher concentrations of chloride, elevated chloride concentrations detected at well MW-33AR appear more likely to be related to an alternative non-CCR source, such as salt.

## **6.0 SITE GROUNDWATER MONITORING RECOMMENDATIONS**

In accordance with section 257.94(e)(2) of the CCR Rule, the COL Modules 1-3 CCR Units may continue with detection monitoring based on this ASD. The ASD report will be included in the 2023 Annual Report due January 31, 2024.

## 7.0 REFERENCES

SCS Engineers, 2018, Alternative Source Demonstration, October 2017 Detection Monitoring, Columbia Energy Center Dry Ash Disposal Facility, April 2018.

U.S. EPA, 2015, Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities; Final Rule, April 2015.

Warzyn Engineering, Inc., 1978, Feasibility Study, Proposed Fly Ash and/or Scrubber Sludge Disposal Facility – Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

Warzyn Engineering, Inc., 1979, and Preliminary Engineering Concepts, Columbia Site, Wisconsin Power and Light Company, Town of Pacific, Columbia County, WI, January 1978.

## Tables

- 1 Groundwater Analytical Results Summary – April 2023 Event
- 2 Historical Analytical Results for Parameters with SSIs
- 3 Groundwater Elevation – State Monitoring Program and CCR Well Network
- 4 Analytical Results – Lysimeters and Leachate Pond

**Table 1. Groundwater Analytical Results Summary -  
Columbia Landfill MOD 1-3 / SCS Engineers Project #25223067.00**

Parameter Name	UPL Method	UPL	Background Wells		Compliance Wells		
			MW-84A	MW-301	MW-33AR	MW-34A	MW-302
			4/27/2023	4/27/2023	4/24/2023	4/26/2023	4/27/2023
<b>Appendix III</b>							
Boron, ug/L	P	35.6	10.3	20.1	532	220	541
Calcium, ug/L	NP	129,000	68600	120000	55300	49600	66500
Chloride, mg/L	P	6.2	3.0	1.5 J	19.0	2.0	1.3 J
Fluoride, mg/L	DQ	DQ	<0.095	<0.095	<0.095	<0.095	<0.095
Field pH, Std. Units	P	7.78	7.01	6.65	7.61	7.53	7.36
Sulfate, mg/L	P	30.3	1.3 J	12.3	104	48.4	36.6
Total Dissolved Solids, mg/L	NP	514	326	526	394	302	352

4.4 Blue shaded cell indicates the compliance well result exceeds the UPL (background) and the Limit of Quantitation (LOQ).

**Abbreviations:**

UPL = Upper Prediction Limit  
 DQ = Double Qualification  
 SSI = Statistically Significant Increase  
 -- = Not Measured  
 µg/L = micrograms per liter

NP = Nonparametric UPL with 1-of-2 retesting  
 P = Parametric UPL with 1-of-2 retesting  
 LOQ = Limit of Quantitation  
 LOD = Limit of Detection  
 mg/L = milligrams per liter

J = Estimated concentration at or above the LOD and below the LOQ.  
 M0 = Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits

**Notes:**

1. An individual result above the UPL does not constitute an SSI above background. See the accompanying report text for identification of statistically significant results.
2. Interwell UPLs calculated based on results from background wells MW-84A and MW-301. Interwell UPLs based on 1-of-2 retesting approach. UPLs updated in January 2020 based on background well results through October 2019.
3. Interwell UPLs calculated based on results from background wells MW-84 and MW-301.

Created by:	<u>NDK</u>	Date:	<u>5/17/2022</u>
Last revision by:	<u>NLB</u>	Date:	<u>9/20/2023</u>
Checked by:	<u>RM</u>	Date:	<u>10/3/2023</u>
Scientist/Proj Mgr QA/QC:	<u>TK</u>	Date:	<u>11/11/2023</u>



**Table 2. Historical Analytical Results for Parameters with SSIs  
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Background	MW-301	12/22/2015	26.5	3.70 J	9.30
		4/5/2016	25.2	4.00	15.3
		7/8/2016	23.6	3.50 J	15.0
		10/13/2016	30.6	2.20	13.9
		12/29/2016	32.8	2.00 J	12.3 J
		1/25/2017	32.6	1.50 J	6.50
		4/11/2017	28.8	2.00	10.3
		6/6/2017	21.3	3.50	17.1
		8/8/2017	30.6	5.50	31.6
		10/23/2017	34.3	4.00	27.5
		4/25/2018	24.3	2.30	8.60
		8/8/2018	22.8	--	--
		10/22/2018	27.8	3.20	19.2
		4/3/2019	26.9	2.90 J, B	5.30 J
		10/9/2019	35.9	1.70	8.40
		5/29/2020	21.3	2.00 J	11.5 J
		10/8/2020	28.8	3.40	25.1
		4/13/2021	22.2	1.50 J	8.5
		10/14/2021	31.4	2.70	17.4
		4/13/2022	28.7	1.90 J	12.7
	10/27/2022	37.5	2.3	11.6	
	4/27/2023	20.1	1.5 J	12.3	
	MW-84A	12/22/2015	11.9	4.90	4.90
		4/5/2016	14.0	4.70	4.30
		7/8/2016	14.7	5.10	3.70 J
		7/28/2016	--	--	--
		10/13/2016	11.1	4.30	2.60 J
		12/29/2016	14.7	4.70	2.70 J
		1/25/2017	16.1	4.60	3.00
		4/11/2017	12.9	4.90	2.80 J
		6/6/2017	14.8	5.50	2.70 J
		8/8/2017	22.9	5.50	2.00 J
		10/24/2017	13.8	5.10	2.20 J
		4/25/2018	25.0	4.80	2.80 J
8/8/2018		12.8	--	--	
10/22/2018		10.1 J	4.20	1.60 J	
4/3/2019	13.6	3.60 B	1.40 J		
10/9/2019	12.0	3.90	1.30 J		
5/29/2020	10.0	3.70	1.50 J		
10/8/2020	9.7 J	4.30	1.30 J		
4/13/2021	14.3	4.40	1.40 J		
10/14/2021	11.1	3.50	17.4		
4/13/2022	10.5	5.20	1.40 J, M0		
10/27/2022	12.2	3.4	1.1 J		
4/27/2023	10.3	3.0	1.3 J		

**Table 2. Historical Analytical Results for Parameters with SSIs  
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-302	12/22/2015	80.0	4.20	37.4
		4/5/2016	78.8	4.10	55.6
		7/7/2016	134	3.10 J	35.4
		10/13/2016	132	1.10 J	64.7
		12/29/2016	106	1.20 J	56.4
		1/25/2017	149	1.60 J	61.6
		4/11/2017	322	1.60 J	81.3
		6/6/2017	671	3.50	84.6
		8/8/2017	833	4.50	79.0
		10/24/2017	691	6.90	78.4
		4/24/2018	1,950	15.0	109
		9/21/2018	203	1.70 J	30.0
		10/22/2018	296	1.80 J	26.9
		4/2/2019	254	1.50 J	25.2
		10/9/2019	246	1.10 J	16.7
		5/29/2020	611	1.20 J	34.6
		10/8/2020	648	1.10 J	36.5
		4/13/2021	521	1.40 J	36.9
		10/14/2021	495	1.30 J	37.8
		4/12/2022	389	0.79 J	22.1 M0
	10/27/2022	374	2.1	30.3	
	4/27/2023	541	1.3 J	36.6	
	MW-33AR	12/21/2015	954	10.6	96.2
		4/5/2016	813	12.5	91.5
		7/7/2016	794	12.5	99.2
		10/13/2016	827	52.5	124
		12/29/2016	812	39.6	132
		1/25/2017	763	41.4	133
		4/11/2017	760	47.1	139
		6/6/2017	692	68.1	151
		8/7/2017	697	105	164
		10/24/2017	678	119	175
		4/24/2018	601	188	163
		9/21/2018	683	32.6	124
10/22/2018		682	14.4	112	
4/2/2019		568	229	201	
10/8/2019	548	153	182		
5/28/2020	566	15.9	104		
10/8/2020	569	27.3	97.4		
4/13/2021	473	26.9	94.3		
6/11/2021	--	--	--		
10/12/2021	564	22.6	96.4		
4/12/2022	558	59.0	155		
10/27/2022	586	40.5	153		
4/27/2023	532	19.0	104		

**Table 2. Historical Analytical Results for Parameters with SSIs  
Columbia Dry ADF, Modules 1-3**

Well Group	Well	Collection Date	Boron (µg/L)	Chloride (mg/L)	Sulfate (mg/L)
Compliance	MW-34A	12/21/2015	230	4.90	69.9
		4/5/2016	220	5.10	71.6
		7/7/2016	216	5.60	63.4
		7/28/2016	--	--	--
		10/13/2016	212	6.80	54.8
		12/29/2016	224	7.10	63.9
		1/25/2017	214	7.20	71.2
		4/11/2017	214	6.20	87.6
		6/6/2017	201	7.80	106
		8/7/2017	205	7.40	105
		10/24/2017	208	7.60	98.0
		4/24/2018	209	8.20	144
		9/21/2018	241	17.1	141
		10/22/2018	233	19.9	123
		4/4/2019	204	18.7	70.4
		10/8/2019	207	57.9	39.8
		5/28/2020	210	3.90	44.4
		10/8/2020	213	2.10	58.7
		4/13/2021	203	2.30	59.3
		6/11/2022	--	--	--
		10/12/2021	212	1.90 J, M0	56.1
		4/12/2022	237	2.20	146
	10/27/2022	264	2.20	169	
4/28/2023	220	2.0	48.4		
	MW-1AR <sup>(2)</sup>	4/14/2021	16.1	1.50 J	4.40 M0
		10/14/2021	12.4	1.20 J	3.10

Abbreviations:

µg/L = micrograms per liter or parts per billion (ppb)

mg/L = milligrams per liter or parts per million (ppm)

J = Estimated value below the laboratory's limit of quantitation

B = Analyte was detected in the associated Method Blank.

M0 = matrix spike recovery and/or matrix spike duplicate recovery outside of laboratory control limits.

Notes:

(1) Analytical laboratory reports provided in the Annual Groundwater Monitoring and Corrective Action Reports.

(2) MW-1AR was added to the sampling network in 2021 to provide additional evaluation of site conditions in the CCR unit. MW-1AR was abandoned in March of 2022.

Created by:	<u>NDK</u>	Date:	<u>3/19/2020</u>
Last revision by:	<u>NLB</u>	Date:	<u>9/20/2023</u>
Checked by:	<u>RM</u>	Date:	<u>10/3/2023</u>
PM/Scientist Check:	<u>TK</u>	Date:	<u>11/11/2023</u>







**Table 4. Analytical Results - Lysimeters and Leachate Pond  
Columbia Dry Ash Disposal Facility  
SCS Engineers Project #25223067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LS-1	2015-Apr	DRY	--	--	--
	2015-Oct	BROKEN	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	--	6,530	12.3	789
	2017-Apr	--	6,510	20.7 J	814
	2017-Oct	--	6,200	14.2 J	764
	2018-Apr	--	5,920	16.0 J	856
	2018-Oct	DRY	--	--	--
	2019-Apr	--	5,640	22.0 J	911
	2019-Oct	--	6,180	19.2 J	861
	2020-May	--	6,180	25.4 J	1,040
	2020-Oct	--	5,640	27.2 J	950
	2021-Apr	--	6,010	21.1 J	976
	2021-Oct	--	6,230	14.3 J	987
	2022-Apr	--	6,140	13.3 J	1,040
	2022-Oct	--	6,000	16.7 J	898
2023-Apr	--	6,200	27.1 J	969	
LS-3R	2015-Apr	--	6,480	20.6 B	807
	2015-Oct	DRY	--	--	--
	2016-Apr	DRY	--	--	--
	2016-Oct	DRY	--	--	--
	2017-Apr	DRY	--	--	--
	2017-Oct	DRY	--	--	--
	2018-Apr	DRY	--	--	--
	2018-Oct	--	6,180	26.2 J	841
	2019-Apr	DRY	--	--	--
	2019-Oct	DRY	--	--	--
	2020-May	DRY	--	--	--
	2020-Oct	DRY	--	--	--
	2021-Apr	DRY	--	--	--
	2021-Oct	DRY	--	--	--
	2022-Apr	DRY	--	--	--
	2022-Oct	DRY	--	--	--
2023-Apr	DRY	--	--	--	

**Table 4. Analytical Results - Lysimeters and Leachate Pond  
Columbia Dry Ash Disposal Facility  
SCS Engineers Project #25223067.00**

Monitoring Point	Monitoring Period	Monitoring Point Dry/ Broken	Boron, Total (µg/L)	Chloride, Total (mg/L)	Sulfate, Total (mg/L)
LP-1	2015-Apr	--	4,060	27.8	734
	2015-Oct	--	4,300	37.1	820
	2016-Apr	--	1,830	26.8	416
	2016-Oct	--	4,610	71.5	835
	2017-Apr	--	2,690	66.3	587
	2017-Oct	--	4,970	91.7	739
	2018-Apr	--	2,060	63.2	634
	2018-Oct	--	2,630	151	907
	2019-Apr	--	570	35.1	249
	2019-Oct	--	1,270	63.9	602
	2020-May	--	2,460	179	952
	2020-Oct	--	2,710	243	1,160
	2021-Apr	--	3,340	319	1,180
	2021-Oct	--	3,440	299	1,470
	2022-Apr	--	1,030	89.2	506
2022-Oct	--	2,040	175	752	
2023-Apr	--	2,110	404	856	

Abbreviations:

µg/L = micrograms per liter  
mg/L = milligrams per liter

-- = not analyzed

Notes:

B = Analyte was detected in the associated method blank.


J = Estimated concentration at or above the Limit of Detection (LOD) and below the Limit of Quantitation (LOQ).

Created by:           MDB            
Last revision by:           NLB            
Checked by:           RM          

Date:   12/1/2014    
Date:   10/3/2023    
Date:   10/3/2023

## Figures

- 1 Site Location Map
- 2 Site Plan and Monitoring Well Locations
- 3 Water Table Map – April 2023




POYNETTE QUADRANGLE  
 WISCONSIN-COLUMBIA CO.  
 7.5 MINUTE SERIES (TOPOGRAPHIC)  
 2018  
 SCALE: 1" = 2,000'



CLIENT	ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954		SITE	ALLIANT ENERGY COLUMBIA ENERGY CENTER PARDEEVILLE, WI		ENGINEER	SITE LOCATION MAP	
	PROJECT NO.	25223067.00		DRAWN BY:	BSS		SCS ENGINEERS 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	FIGURE
DRAWN:	12/02/2019	CHECKED BY:	TK	APPROVED BY:	TK 11/11/2023			
REVISED:	05/01/2023							

I:\25223067.00\Drawings\Site Location Map.dwg, 10/12/2023 9:55:52 AM





LEGEND


	EXISTING MAJOR CONTOUR (10' INTERVAL)
	EXISTING MINOR CONTOUR (2' CONTOUR)
	EXISTING FENCELINE
	EXISTING TRACKS
	EXISTING PAVED ROAD
	EXISTING UNPAVED ROAD
	EDGE OF WATER
	DRY ASH DISPOSAL FACILITY LIMITS
	LIMITS OF WASTE
	LINER PHASE/MODULE LIMITS
	WATER SUPPLY WELL
	STAFF GAUGE
	WATER TABLE WELL
	PIEZOMETER
	SURFACE WATER SAMPLE LOCATION
	LYSIMETER
	ABANDONED WATER TABLE WELL
	ABANDONED PIEZOMETER
	LEACHATE HEADWELL
	CCR UNIT
	CCR MONITORING WELL
	CCR BACKGROUND MONITORING WELL

- NOTES:
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEYS BY SCS ENGINEERS IN MAY 2019, DECEMBER 2020, NOVEMBER 2021, AND DECEMBER 2021, AND BY DRONE SURVEY BY AMES IN NOVEMBER 2022.
  2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016, AND BY SCS ENGINEERS IN FEBRUARY 2018.
  3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
  4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
  5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
  6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
  7. MONITORING WELLS MW-93A, MW-93B, AND MW-312 WERE INSTALLED BY CASCADE ENVIRONMENTAL ON MARCH 23-28, 2022.
  8. MONITORING WELLS MW-313, MW-314, AND MW-315 WERE INSTALLED BY HORIZON CONSTRUCTION & EXPLORATION ON DECEMBER 12 AND 19, 2022.
  9. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.

PROJECT NO. 25223067.00	DRAWN BY: KP	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULES 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	FIGURE 2
DRAWN: 12/02/2019	CHECKED BY: TK				
REVISED: 10/12/2023	APPROVED BY: TK 11/11/2023				

I:\25223067.00\Drawings\Modules 1-3\Site Plan and Monitoring Well Locations.dwg, 10/12/2023 11:22:45 AM






- LEGEND**
- EXISTING MAJOR CONTOUR (10' INTERVAL)
  - EXISTING MINOR CONTOUR (2' CONTOUR)
  - x - x - EXISTING FENCELINE
  - ||||| EXISTING TRACKS
  - ==== EXISTING PAVED ROAD
  - EXISTING UNPAVED ROAD
  - - - - - EDGE OF WATER
  - · · · · DRY ASH DISPOSAL FACILITY LIMITS
  - — — — — LIMITS OF WASTE
  - · - · - · - LINER PHASE/MODULE LIMITS
  - ▲ WATER SUPPLY WELL
  - Ⓢ STAFF GAUGE
  - ⊕ WATER TABLE WELL
  - ⊗ PIEZOMETER
  - ⊗ SURFACE WATER SAMPLE LOCATION
  - ⊗ LYSIMETER
  - ⊕ ABANDONED WATER TABLE WELL
  - ⊗ ABANDONED PIEZOMETER
  - ↖ LEACHATE HEADWELL
  - APPROXIMATE LOCATION OF DEWATERING WELLS
  - CCR UNIT
  - ⊕ CCR MONITORING WELL
  - ⊕ CCR BACKGROUND MONITORING WELL
  - 787.62 WATER TABLE ELEVATION
  - [788.87] POTENTIOMETRIC SURFACE ELEVATION (NOT CONTOURED)
  - (795.20) SURFACE WATER ELEVATION (NOT CONTOURED)
  - WATER TABLE CONTOUR
  - APPROXIMATE GROUNDWATER FLOW DIRECTION

- NOTES:**
1. BASE MAP CREATED FROM AERIAL SURVEY BY KBM, FLOWN DECEMBER 1, 2014, AND GROUND SURVEYS BY SCS ENGINEERS IN MAY 2019, DECEMBER 2020, NOVEMBER 2021, AND DECEMBER 2021, AND BY DRONE SURVEY BY AMES IN NOVEMBER 2022.
  2. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER AND LIGHT, INC. IN DECEMBER 1994, NOVEMBER 1996, APRIL 2003, AND JANUARY 2016 AND BY SCS ENGINEERS IN FEBRUARY 2018.
  3. SUPPLY WELL LOCATIONS ARE APPROXIMATE AND ASSUMED BASED ON JANUARY 2013 DRAWINGS BY TRC.
  4. MONITORING WELLS MW-301 THROUGH MW-305 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 11-13, 2015.
  5. MONITORING WELLS MW-306 THROUGH MW-308 INSTALLED BY BADGER STATE DRILLING ON NOVEMBER 14-15, 2016.
  6. MONITORING WELLS MW-309 THROUGH MW-311 INSTALLED BY BADGER STATE DRILLING ON FEBRUARY 13-14, 2018.
  7. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON APRIL 12-14, 2021.
  8. BACKGROUND MONITORING WELLS FOR THE MODULE 1-3 DRY ASH FACILITY ARE: MW-301 AND MW-84A.
  9. MONITORING WELLS MW-93A, MW-93B, AND MW-312 INSTALLED BY CASCADE ENVIRONMENTAL ON MARCH 25-28, 2022.
  8. MONITORING WELLS MW-313, MW-314, AND MW-315 WERE INSTALLED BY HORIZON CONSTRUCTION & EXPLORATION ON DECEMBER 12 AND 19, 2022.
  9. GROUNDWATER AND SURFACE WATER ELEVATIONS WERE MEASURED ON APRIL 24-27, 2023.
  10. DEWATERING WELLS WERE ACTIVE AROUND THE PRIMARY POND DURING THE APRIL 2023 SAMPLING EVENT.


PROJECT NO. 25223067.00	DRAWN BY: KP	 2830 DAIRY DRIVE MADISON, WI 53718-6751 PHONE: (608) 224-2830	CLIENT ALLIANT ENERGY COLUMBIA ENERGY CENTER W8375 MURRAY ROAD PARDEEVILLE, WI 53954	SITE ALLIANT ENERGY COLUMBIA ENERGY CENTER MODULES 1-3 DRY ASH DISPOSAL FACILITY PARDEEVILLE, WI	WATER TABLE MAP APRIL 2023	FIGURE 3
DRAWN: 10/12/2023	CHECKED BY: TK					
REVISED: 11/10/2023	APPROVED BY: TK 11/11/2023					

I:\25223067.00\Drawings\Modules 1-3\Water Table Map-April 2023.dwg, 11/10/2023 3:27:53 PM



Appendix A  
Trend Plots for CCR Wells

# Boron




Time Series Analysis Run 10/4/2023 2:00 PM View: COL Secondary Pond  
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

# Time Series

Constituent: Boron (ug/L) Analysis Run 10/4/2023 2:01 PM View: COL Secondary Pond  
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			954	217.5 (D)		
12/22/2015	26.5	80			11.9	
4/5/2016	25.2	78.8	813	220	14	
7/7/2016		134	794	216		
7/8/2016	23.6				14.7	
10/13/2016	30.6	132	827	212	11.1	
12/29/2016	32.8	106	812	224	14.7	
1/25/2017	32.6	149	763	214	16.1	
4/11/2017	28.8	322	760	214	12.9	
6/6/2017	21.3	671	692	201	14.8	
8/7/2017			697	205		
8/8/2017	30.6	833			22.9	
10/23/2017	34.3					
10/24/2017		691	678	208	13.8	
4/24/2018		1950	601	209		
4/25/2018	24.3				25	
8/8/2018	22.8				12.8	
9/21/2018		203	683	241		
10/22/2018		296	682	233		
10/24/2018	27.8				10.1 (J)	
4/2/2019	26.9	254	568	204		
4/3/2019					13.6	
10/8/2019			548	207		
10/9/2019	35.9	246			12	
2/3/2020	27.9				15.7	
5/28/2020			566	210		
5/29/2020	21.3	611			10	
10/8/2020	28.8	648	569	213	9.7 (J)	
4/13/2021		521	473	203		
4/14/2021	22.2				14.3	16.1
10/12/2021			564	212		
10/14/2021	31.4	495			11.1	12.4
4/12/2022		389	558	237		
4/13/2022	28.7				10.5	
10/27/2022	37.5	374	586	264	12.2	
4/26/2023				220		
4/27/2023	20.1	541	532		10.3	

# Chloride



Time Series Analysis Run 10/4/2023 2:00 PM View: COL Secondary Pond  
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020




# Time Series

Constituent: Chloride (mg/L) Analysis Run 10/4/2023 2:01 PM View: COL Secondary Pond  
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			10.6	4.85 (D)		
12/22/2015	3.7 (J)	4.2			4.9	
4/5/2016	4	4.1	12.5	5.1	4.7	
7/7/2016		3.1 (J)	12.5	5.6		
7/8/2016	3.5 (J)				5.1	
10/13/2016	2.2	1.1 (J)	52.5	6.8	4.3	
12/29/2016	2 (J)	1.2 (J)	39.6	7.1	4.7	
1/25/2017	1.5 (J)	1.6 (J)	41.4	7.2	4.6	
4/11/2017	2	1.6 (J)	47.1	6.2	4.9	
6/6/2017	3.5	3.5	68.1	7.8	5.5	
8/7/2017			105	7.4		
8/8/2017	5.5	4.5			5.5	
10/23/2017	4					
10/24/2017		6.9	119	7.6	5.1	
4/24/2018		15	188	8.2		
4/25/2018	2.3				4.8	
8/8/2018	5.2				4.9	
9/21/2018		1.7 (J)	32.6	17.1		
10/22/2018		1.8 (J)	14.4	19.9		
10/24/2018	3.2				4.2	
4/2/2019	0.79 (J)	1.5 (J)	229	18.7		
4/3/2019					3.6	
10/8/2019			153	57.9		
10/9/2019	1.7 (J)	1.1 (J)			3.9	
2/3/2020	1.3 (J)				3.7	
5/28/2020			15.9	3.9		
5/29/2020	2 (J)	1.2 (J)			3.7	
10/8/2020	3.4	1.1 (J)	27.3	2.1	4.3	
4/13/2021		1.4 (J)	26.9	2.3		
4/14/2021	1.5 (J)				4.4	1.5 (J)
10/12/2021			22.6	1.9 (J)		
10/14/2021	2.7	1.3 (J)			3.5	1.2 (J)
4/12/2022		0.79 (J)	59	2.2		
4/13/2022	1.9 (J)				5.2	
10/27/2022	2.3	2.1	40.5	2.2	3.4	
4/26/2023				2		
4/27/2023	1.5 (J)	1.3 (J)	19		3	

### Sulfate




Time Series Analysis Run 10/4/2023 2:00 PM View: COL Secondary Pond  
Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

# Time Series

Constituent: Sulfate (mg/L) Analysis Run 10/4/2023 2:01 PM View: COL Secondary Pond  
 Columbia Energy Center Client: SCS Engineers Data: December - Chem- export-Dec2020

	MW-301 (bg)	MW-302	MW-33AR	MW-34A	MW-84A (bg)	MW-1AR
12/21/2015			96.2	70.6 (D)		
12/22/2015	9.3	37.4			4.9	
4/5/2016	15.3	55.6	91.5	71.6	4.3	
7/7/2016		35.4	99.2	63.4		
7/8/2016	15				3.7 (J)	
10/13/2016	13.9	64.7	124	54.8	2.6 (J)	
12/29/2016	12.3 (J)	56.4	132	63.9	2.7 (J)	
1/25/2017	6.5	61.6	133	71.2	3	
4/11/2017	10.3	81.3	139	87.6	2.8 (J)	
6/6/2017	17.1	84.6	151	106	2.7 (J)	
8/7/2017			164	105		
8/8/2017	31.6	79			2 (J)	
10/23/2017	27.5					
10/24/2017		78.4	175	98	2.2 (J)	
4/24/2018		109	163	144		
4/25/2018	8.6				2.8 (J)	
8/8/2018	21.6				1.9 (J)	
9/21/2018		30	124	141		
10/22/2018		26.9	112	123		
10/24/2018	19.2				1.6 (J)	
4/2/2019	4.4	25.2	201	70.4		
4/3/2019					1.4 (J)	
10/8/2019			182	39.8		
10/9/2019	8.4	16.7			1.3 (J)	
2/3/2020	7.2				<2.2 (U)	
5/28/2020			104	44.4		
5/29/2020	11.5	34.6			1.5 (J)	
10/8/2020	25.1	36.5	97.4	58.7	1.3 (J)	
4/13/2021		36.9	94.3	59.3		
4/14/2021	8.5				1.4 (J)	4.4
10/12/2021			96.4	56.1		
10/14/2021	17.4	37.8			1.3 (J)	3.1
4/12/2022		22.1	155	146		
4/13/2022	12.7				1.4 (J)	
10/27/2022	11.6	30.3	153	169	1.1 (J)	
4/26/2023				48.4		
4/27/2023	12.3	36.6	104		1.3 (J)	



Appendix B  
Feasibility Study Water Quality Information

1370



FEASIBILITY STUDY  
PROPOSED FLY ASH AND/OR SCRUBBER SLUDGE  
DISPOSAL FACILITY-COLUMBIA SITE  
WISCONSIN POWER AND LIGHT COMPANY  
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

*Jan 78*

C 7134



conceivable that groundwater flow in the area north of Murray Road may be altered such that contaminants derived from the present ash settling basin might be diverted southerly towards the homes along Murray Road. These questions would have to be addressed in greater detail, consistent with the goals of Wisconsin Power and Light Company.

#### WATER QUALITY

During the first two weeks of December, 1977, 64 water samples were obtained from surface waters and groundwater monitoring wells at the Columbia Energy Center. The purpose of the sampling was to assess background water quality in the vicinity of the proposed disposal site. The sampling stations included 59 monitoring wells, the cooling lake, ash settling pond, the drainage ditch carrying the ash pond discharge waters and the agricultural drainage ditch along the southern boundary of the site. Due to the large number of sampling stations, the analyses were limited to pH, specific conductance, iron, calcium, magnesium, sulfate and chloride. The analytical data is contained in Appendix F and is discussed below.

#### pH

Most groundwaters found in the United States have pH values ranging from around 6.0 to 8.5. The pH of a water represents the result of a number of interrelated chemical equilibria. This equilibria can be altered shortly after sampling by gains or losses of carbon dioxide, the oxidation of ferrous iron and numerous other chemical reactions. Thus, pH measurements must be taken shortly after obtaining the sample. For this study, the pH of samples was determined immediately upon return to the laboratory.

Within the proposed site boundaries at the Columbia Energy Center, pH values ranged between 6.3 and 8.1 and averaged 7.5. Typically, the lower pH values were observed in the lowland areas and wetlands, probably as a result of acidic organic soils. The pH of water in the ash disposal settling pond and the cooling lake was 11.4 and 8.3, respectively.

#### SPECIFIC CONDUCTANCE

Specific conductance, or conductivity, is the ability of a substance to conduct an electric current. The conductance determination is correlative with the dissolved-solids concentration. Conductivity, however, is temperature dependent and thus requires the reference of specific conductance measurements to a standard temperature. The values discussed here are referred to 25°C.

The specific conductance of groundwater in the study area ranged from 220 umhos/cm to a maximum of 2600 umhos/cm. The highest conductivity readings were observed in monitoring wells located along the coal storage area and the drainage ditch carrying the ash pond discharge where values up to 2600 umhos/cm were measured. The conductivity of the ash pond effluent was 1380 umhos/cm. This data appears to confirm earlier speculation of infiltration of effluent from the ash pond discharge channel and from the coal storage area into the groundwater. Conductance within the proposed site boundaries averaged approximately 465 umhos/cm.

Conductivity in the ash disposal settling pond was measured at 1510 umhos/cm. Shallow monitoring wells M-6 and 39A, located adjacent to the pond also exhibited elevated values of 1160 umhos/cm and 1800 umhos/cm, respectively.


High conductivities were also observed along U. S. Highway 51 at monitoring wells 51A and 51B. The chloride data, discussed below, indicates infiltration of road salt has probably occurred at this location.

Specific conductance measurements obtained in the vicinity of the proposed disposal site are shown on Drawing C 7134-15.

### IRON

The element iron is an abundant element found in most rocks and soil. It generally occurs as sulfides and oxides in igneous and metamorphic rocks and as iron oxide and hydroxide cementing materials in coarse-grained sedimentary rocks.

Ferrous iron is unstable in the presence of oxygen where it is bound to hydroxide anions as  $2\text{Fe}(\text{OH})_3$ .



If subjected to a strong reducing environment, such as a marsh, the reaction is reversed and iron goes back into solution. The amount which dissolves is related to a number of variables including the velocity with which water moves through this environment.

The U. S. Public Health Service recommends an iron concentration of less than 0.3 mg/l in water used for drinking and culinary purposes. Laundry and porcelain tend to be stained when concentrations reach 0.5 to 1.0 mg/l. At this level it can also be tasted.

The presence of iron under the proposed disposal area in the majority of cases was below the detection limit of 0.1 mg/l. In monitoring wells 5 and 18, located in or near the central marsh area, iron increased to 10 mg/l and 5.7 mg/l, respectively. In the southern marsh, monitoring wells exhibited concentrations between 0.5 mg/l and 6.1 mg/l. Although the iron concentration in the cooling lake was below the detection limit, down-gradient wells 44 and 30A located on the cooling lake dike yielded values of 11 mg/l and 26 mg/l iron respectively. Boring logs indicated trace amounts of organic material at the base of the dike which is probably the reason for the high concentrations observed. At the same location, iron in well 30B installed to a depth of 100 feet below the surface was below 0.1 mg/l. Thus, the occurrence of high iron concentrations in this area appears restricted to groundwater in the upper portion of the aquifer where organic material is present and conditions are favorable for the dissolution of iron.

The ash pond discharge in the drainage ditch paralleling the west site boundary showed an iron concentration of 3.7 mg/l. Shallow monitoring wells 33A and 34A adjacent to the ditch indicated less than 0.1 mg/l iron.

North of Murray Road the iron concentration in monitoring wells in the marsh and uplands were typically less than 0.1 mg/l. Although the ash basin had less than 0.1 mg/l iron, several wells along cross-section F-F' showed anomalously high values (#M6-2.3 mg/l; #47-16 mg/l; #51B-21 mg/l).

#### CALCIUM

Calcium, because of its relative abundance and mobility, is the principle cation in most natural fresh water. Calcium is a constituent of many rock types but is found in greatest quantities in waters leaching deposits of limestone and dolomite. In sandstone and other detrital rock, calcium carbonate is a common cement between grains.

Monitoring wells located within the site boundaries exhibited calcium concentrations between 30 mg/l and 66 mg/l and averaged about 42 mg/l. Similar to iron, the concentrations of calcium in monitoring wells along cross-section F-F' were anomalously high, up to 150 mg/l calcium. Water table wells along the drainage ditch carrying the ash pond discharge averaged 83 mg/l while the ash pond effluent contained 28 mg/l. Generally the amount of calcium in groundwater decreased with depth. Nested monitoring wells typically showed somewhat lower concentrations of calcium in the deeper wells.

#### MAGNESIUM

As a relatively abundant element on the earth's crust, the principle sources of magnesium in natural waters are considered to be ferromagnesian minerals in igneous rocks and magnesium carbonate in carbonate rocks (limestone and dolomite). Waters in which magnesium is the predominant cation are somewhat unusual. Like calcium, magnesium imparts the property of hardness to water and is, therefore, of concern to industrial users.

Generally, concentrations of magnesium were 1/3 to 1/2 of the calcium levels. Magnesium concentrations within the site boundaries ranged between 10 mg/l and 36 mg/l and averaged 27 mg/l. Similar to calcium and iron, higher magnesium values were observed, in general, north of Murray Road and especially in monitoring wells along cross-section F-F'.



SULFATE

Sulphur is widely distributed in reduced form in both igneous and sedimentary rocks as metallic sulfides and when present in sufficient concentrations, constitutes ore of economic importance. During weathering processes with aerated water, the sulfides are oxidized to sulfate ions and are dissolved into water. Pyrite ( $\text{FeS}_2$ ) crystals often occur in sedimentary rocks and are particularly associated with biogenic deposits such as coal which were deposited under strongly reducing conditions.

The concentrations of sulfate in groundwater in the vicinity of the proposed disposal site ranged from less than 1 mg./l to 1,200 mg./l of sulfate. (Refer to Drawing C 7134-15.) Typically, within the site boundaries concentrations averaged approximately 12 mg./l. Near the coal storage area, however, significant increases were observed. Observation wells 26A, 26B, and 42 exhibited concentrations between 900 and 1100 mg./l. The depth of sulfate enrichment in groundwater, near the coal pile, appears to extend to considerable depths, indicated by relatively high sulfate concentrations in Well 26B sealed 100 feet below ground surface. The oxidation of pyrite minerals in the coal leaching into the groundwater is probably the major source of the high concentrations observed.

Sulfate concentrations in the ash disposal settling pond were 520 mg./l. In the ditch carrying the ash pond discharge, the effluent is treated with sulfuric acid which results in precipitation of barium sulfate and aluminum hydroxide (personal communication, Merlin Horn, 1978). Consequently, the sulfate concentration of the effluent waters is lowered considerably to 13 mg./l. Well 33A, however, located near the point of effluent discharge, exhibited 1200 mg./l sulfates.

CHLORIDE

Chloride is generally present in much lower concentrations in rocks than many of the other major constituents of natural water. Important sources, however, are associated with sedimentary rocks, particularly the evaporites. The chemical behavior of chloride in natural water is relatively inert compared to the other major ions. There are few oxidation-reduction reactions and no significant chemical complexing reactions which chloride enters into. In addition, chloride ions are not significantly adsorbed on mineral surfaces. For these reasons, chloride is commonly used as a tracer in groundwater.

Chloride concentrations in groundwater in the vicinity of the Columbia Energy Center typically range between 0.5 mg./l and 30 mg./l. The highest concentrations in monitoring wells tended to be located adjacent to U. S. Highway 51 where the use of road salt has resulted in the percolation of chloride into the groundwater. Monitoring Wells 51A and 51B located in a low area north of Murray Road along U. S. Highway 51, yielded chloride concentrations in excess of 200 mg./l. Two other wells, 52A and 19, also located along U. S. Highway 51, yielded values of 30 mg./l and 42.5 mg./l chloride, respectively.

Within the proposed site boundaries, the chloride concentration averaged 7.1 mg./l. Excluding the few wells adjacent to U. S. Highway 51 exhibiting elevated concentrations, no other significant trends in the occurrence of chloride were observed.

SUMMARY

In summary, the groundwater in the vicinity of the proposed disposal site exhibited a somewhat alkaline pH. In lowland areas, the pH was typically below 7.0, probably a result of the presence of acidic organic soils.

Specific conductance within the proposed site averaged 465 umhos/cm. Conductivities up to 2600 umhos/cm were observed, however, in the vicinity of the coal storage area, the present ash disposal pond and ash pond effluent channel where infiltration of water from these sources is occurring into the groundwater system.

The groundwater typically exhibited relatively low iron concentrations although, locally, concentrations in excess of drinking water standards were observed in about 20% of the wells. The occurrence of the higher iron concentrations appears to be related to the presence of organic soils.

Groundwater at the proposed site also tended to exhibit high calculated hardness (216 mg./l) based on average observed values for calcium (42 mg./l) and magnesium (27 mg./l). Dissolution of limestone and dolomite rocks in the glacial drift are the probable sources of these elements in the groundwater.

Enrichment of sulfate in groundwater has occurred as a result of leaching of pyrite ( $\text{FeS}_2$ ) minerals from the coal storage area where concentrations up to 1200 mg./l were observed. The depth of this enrichment appears to extend beyond the maximum depth into the aquifer investigated. Sulfate concentrations decreased rapidly away from the coal storage area to an average of 12 mg./l within the proposed site boundaries. Other local sources of sulfate in groundwater appear to be related to the present ash settling pond.

The concentration of chloride within the proposed site averaged 7.1 mg./l. Higher levels were generally observed in wells adjacent to U. S. Highway 51 where the infiltration of road salt has locally raised chloride concentrations.

The above interpretations are based on one round of water quality sampling only and should be considered as preliminary in nature. High sulfate and chloride concentrations observed at greater depths may be a temporary condition resulting from contamination of spoil backfill materials with coal dust or salt, respectively, during installation of the monitoring well. Future sampling of these monitoring wells will help to distinguish short term contamination from actual conditions existing in the aquifer.

APPENDIX F  
WATER QUALITY DATA

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
1A	7.6	550	17.	6.5	52	37	<0.1
1B	8.05	460	16.	10.5	39	31	<0.1
2	7.8	527	14.	2.5	45	32	<0.1
3A	7.5	548	13.	2.5	58	36	<0.1
3B	8.1	506	14.	7.0	50	34	<0.1
4	7.8	580	10.	4.0	59	34	<0.1
5	6.3	560	210.	12.5	13	29	10
16	7.6	408	12.	1.5	42	28	<0.1
17	6.45	350	30.	16.5	16	13	0.6
18	6.45	380	4.	4.5	33	22	5.7
19	7.9	570	10.	42.5	44	24	<0.1
20	8.0	340	10.	5.0	36	24	<0.1
21	6.9	220	20.	4.5	23	10	0.1
24A	7.45	775	18.	6.0	76	52	0.1
24B	7.85	440	15.	6.0	43	31	0.1
25	8.1	300	10.	2.5	29	20	<0.1
26A	7.2	2100	900	17.0	140	48	1.5
26B	7.5	2600	1100	16.5	43	7.0	0.2
27	7.15	400	6.	8.0	23	18	<0.1
28A	7.75	500	3.	0.5	48	31	<0.1
28B	7.6	480	4.	3.5	39	28	<0.1
29A	7.8	330	16.	1.5	33	21	0.5
30A	6.75	920	64.	11.0	38	30	26
30B	7.6	770	210	21.0	37	19	<0.1
33A	8.2	2500	1200	24.0	83	50	<0.1
33B	7.9	390	22.	6.5	31	27	0.2
34A	7.7	680	140.	10.0	58	45	0.1
34B	7.7	1700	660	15.0	48	22	<0.1
35	6.8	740	<1.0	4.0	66	33	2.9
36	6.8	740	<1.0	3.5	53	35	6.1
37A	7.7	460	9.	4.0	48	31	0.8
37B	7.5	630	73.	7.5	71	35	<0.1
39A	7.5	1800	350	22.0	180	100	0.1
39B	7.9	330	560	20.5	31	22	0.1
40A	8.0	630	140	8.5	43	29	<0.1
40B	8.1	330	17.	3.0	31	22	<0.1
41	6.8	590	16.	11.0	58	27	9.3



WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)
42	7.4	2400	900	17.5	50	12	0.5
44	6.9	490	<1.	16.5	39	23	11
45	7.6	390	14.	3.0	40	25	<0.1
46A	7.3	1100	21.	15.5	140	82	<0.1
46B	7.8	470	25.	17.5	40	26	<0.1
47	6.6	1200	3.	8.0	140	40	16
48A	7.3	620	15.	8.0	62	37	<0.1
48B	7.1	520	22.	20.0	43	29	0.2
49	7.15	730	6.	3.5	75	41	<0.1
50A	7.6	520	28.	15.5	51	34	<0.1
50B	7.5	410	21.	18.0	31	21	<0.1
51A	6.1	1850	8.	205.	65	40	<0.1
51B	7.2	1250	23.	275.	57	36	21
52A	7.7	450	16.	30.5	36	17	<0.1
52B	7.4	430	40.	17.5	32	20	<0.1
53	7.75	450	27.	10.5	39	28	<0.1
54A	7.8	350	12.	4.0	34	21	0.1
54B	7.55	390	15.	5.5	40	24	0.1
55B	7.9	340	23.	17.5	32	22	0.1
56	7.8	450	22.	9.5	43	28	0.1
57	7.85	380	17.	7.0	38	24	0.1
M-6	7.0	1160	5.	7.0	150	91	2.3
Cooling Lake	8.3	370	31.	18.0	34	21	<0.1
Ash Pond Effluent	7.45	1380	13.	4.0	28	1.2	3.7
Ash Pond Drainage	11.4	1510	520.	23.5	29	0.2	<0.1
Ditch (A) Drainage	7.8	500	21.	7.0	43	29	<0.1
Ditch (B)	9.05	1780	750	14.0	42	5.4	<0.1

DEC 19 1979

APPENDICES TO

SUPPLEMENTARY FEASIBILITY STUDY REPORT  
AND PRELIMINARY ENGINEERING CONCEPTS  
COLUMBIA SITE  
WISCONSIN POWER AND LIGHT COMPANY  
TOWN OF PACIFIC, COLUMBIA COUNTY, WISCONSIN

D. N. R. APPROVED  
DATE 9/3/80  
Nile Ostenso, Hydro



APPENDIX I

WATER QUALITY DATA - DECEMBER 1978



WATER QUALITY DATA

12/78


C 7134

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
1A	7.3	530	30	3.1	54	35	<0.1	-
1B	7.0	470	67	6.1	49	30	<0.1	-
2	7.25	458	91	<.5	48	24	<0.1	-
3A	7.0	560	36	<.5	61	31	<0.1	-
3B	7.15	530	52	35.7	37	33	<0.1	-
4	7.2	750	69	5.8	49	30	<0.1	-
5	6.35	1,650	670	14.1	14	13	1.7	-
16	6.9	390	69	1.0	49	23	<0.1	-
17	5.55	295	57	16.3	14	8.6	0.2	-
18	5.9	430	10	4.2	47	21	1.1	-
19	7.4	765	75	4.2	51	28	<0.1	-
20	7.4	380	26	1.6	39	26	<0.1	-
21	5.7	250	54	10.4	15	8.3	0.2	-
24A	7.2	730	36	1.6	65	42	<0.1	-
24B	7.2	470	10	7.3	42	28	<0.1	-
25	7.0	335	29	7.8	39	21	0.2	-
26A	7.4	2,250	650	12.6	32	8.6	<0.1	-
26B	6.8	2,530	840	20.8	49	18	<0.1	-
27	6.9	410	24	4.2	40	24	0.4	-
28A	7.2	500	61	0.5	45	28	<0.1	-
28B	7.0	465	6	2.1	39	26	0.1	-
29A	7.1	410	24	3.6	31	22	0.1	-
30A	5.8	1,140	15	<0.5	97	56	38	-
30B	6.65	835	160	14.6	37	20	<0.1	-
33A	7.8	1,970	830	16.7	21	8.9	<0.1	-
33B	7.5	380	31	7.3	24	27	<0.1	-
34A	7.25	560	46	4.2	53	33	<0.1	-
34B	8.5	1,575	730	21.9	28	29	0.1	-
35	6.7	545	61	3.6	60	26	1.0	-
36	6.4	515	5.0	2.6	43	24	4.8	-
37A	7.05	438	30	3.7	50	28	<0.1	-
37B	6.7	325	18	7.3	1.0	0.5	<0.1	-
39A	6.35	1,260	33	13.6	70	7.6	0.1	-
39B	6.7	385	25	4.2	30	21	<0.1	<.05
40A	7.35	483	40	<0.5	48	24	<0.1	-
40B	7.25	343	4	4.2	21	14	<0.1	-
41	6.1	640	54	19.8	43	32	<0.1	-

WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
42 <i>near old</i>	7.15	2,050	910	15.6	23	7.5	0.1	-
44 <i>near old</i>	6.15	710	6	0.5	56	27	3.5	-
45 <i>near old</i>	7.2	420	32	1.0	44	26	<0.1	-
46A <i>near old</i>	7.0	560	93	<0.5	130	75	<0.1	<0.05
46B <i>near old</i>	6.5	1,290	170	20.8	46	30	<0.1	<0.05
47 <i>near old</i>	7.3	958	120	<0.5	110	48	<0.1	-
48A <i>near old</i>	6.15	640	59	<0.5	42	51	<0.1	<0.05
48B <i>near old</i>	6.8	450	23	5.2	40	27	<0.1	<0.05
49 <i>near old</i>	7.0	880	26	2.1	93	58	0.1	-
50A <i>near old</i>	7.4	660	25	17.7	60	36	<0.1	-
50B <i>near old</i>	7.1	405	16	17.7	38	23	<0.1	-
51A <i>near old</i>	7.0	1,170	57	135	66	31	<0.1	-
51B <i>near old</i>	7.3	1,410	22	330	46	39	<0.1	-
52A <i>near old</i>	7.0	370	110	18.5	35	10	<0.1	-
52B <i>near old</i>	7.0	595	43	52.5			0.1	-
53	Frozen							
54A <i>near old</i>	7.5	345	10	1.0	36	22	<0.1	<0.05
54B	Frozen							
55B <i>near old</i>	7.3	505	26	15.6	52	29	<0.1	<0.05
56	Frozen							
57	Frozen							
M-6								
58 <i>near old</i>	6.55	1,265	140*	<0.5	110	65	0.1	-
59 <i>near old</i>	6.8	925	40	<0.5	86	60	<0.1	-
60 <i>near old</i>	7.2	1,510	54	4.7	130	85	<0.1	-
61A <i>near old</i>	6.85	590	39	30.2	58	31	<0.1	-
61B <i>near old</i>	7.2	505	6	13.5	48	29	<0.1	-
62 <i>Insect Hygiene</i>	6.7	1,517	72	178	120	53	<0.1	-
64 <i>near old</i>	6.9	670	100	26.8	63	36	0.8	-
65 <i>near old</i>	7.2	830	57	17.8	78	50	<0.1	-
66 <i>near old</i>	6.5	680	55	40	66	24	3.6	-




WELL NO.	pH	SPECIFIC CONDUCTANCE (umhos/cm @ 25°C)	SULFATE (mg/l)	CHLORIDE (mg/l)	CALCIUM (mg/l)	MAGNESIUM (mg/l)	IRON (mg/l)	BORON (mg/l)
67	7.0	560	100	1.0	57	32	1.0	-
68A	7.6	440	32	2.1	40	27	<0.1	-
68B	7.2	400	36	1.0	42	25	<0.1	-
70A	7.5	440	20	<0.5	27	37	<0.1	-
70B	7.3	520	25	5.2	51	34	<0.1	-
72AZ	6.45	860	11	<0.5	100	41	1.8	-
72B	8.4	230	45	<0.5	17	19	<0.1	-
M-4	7.6	864	180	26.1	20	11	<0.1	0.39
MM-4			2	2.6	14	21	0.9	-
Cooling Lake at 1	7.7	355	36	13.6	31	21.2	<0.1	-
Ash Pond at 2	11.4	3,210	1,100	22.9	34	<0.1	<0.1	-
Ash Pond at 3	8.7	725	34	21.9	48	16	<0.1	-
Ash Pond Effluent at 4	6.7	3,090	1,400	25.0	39	0.4	<0.1	-
Drainage Ditch at 5	7.2	730	74	33.9	56	38	<0.1	-
Drainage Ditch at 6	7.35	2,750	640	18.8	34	7.5	<0.1	-
Drainage Ditch at 7	8.05	1,780	740	27.1	31	0.2	<0.1	-




Appendix C  
Long-Term Concentration Trend Plots

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-33A and MW-33AR - Boron ( $\mu\text{g/l as B}$ )




Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW34A - Boron ( $\mu\text{g/l as B}$ )



I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\Graphs\[Bo\_COL Dry.xlsx]MW-34A


Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-302 and MW-85 - Boron ( $\mu\text{g/l}$  as B)



I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\Graphs\[Bo\_COL Dry.xlsx]MW-85\_MW-302




Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-33 and MW-33AR - Chloride (mg/l as Cl)




I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\Graphs\[Cl\_COL Dry.xlsx]MW-33AR

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW34A - Chloride (mg/l as Cl)




I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\Graphs\[Cl\_COL Dry.xlsx]MW-34A

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-33 and MW-33AR - Sulfate (mg/l as SO<sub>4</sub>)




I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\Graphs\[SO<sub>4</sub>\_COL Dry.xlsx]MW-33AR CCR

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-34A - Sulfate (mg/l as SO4)



I:\25223067.00\Deliverables\COL 1-3 ASD - April 2023\Graphs\[SO4\_COL Dry.xlsx]MW-34A CCR

Wisconsin Power & Light Company  
Columbia Dry Ash Disposal Facility  
MW-85 and MW-302 - Sulfate (mg/l as SO<sub>4</sub>)





Appendix D  
Historical Groundwater Flow Maps






**LEGEND**

- ..... PROPOSED PROJECT AREA
- ⊕ 720.29 OBSERVATION WELL LOCATION, NUMBER, AND WATER TABLE ELEVATION
- ⊕ BORING LOCATION AND NUMBER
- WETLANDS
- TOPOGRAPHIC CONTOURS (CONTOUR INTERVAL: 20FT.)
- PRIVATE RESIDENCES (ASSUMED LOCATIONS OF PRIVATE WATER SUPPLY WELLS)
- ▣ COMMERCIAL BUILDINGS (ASSUMED LOCATIONS OF POSSIBLE PUBLIC WATER SUPPLY WELLS)
- SURFACE WATERS (STREAMS OR DRAINAGE DITCHES); ARROWS INDICATE DIRECTION OF FLOW
- OTHER BUILDINGS (GARAGES, BARN, ETC.)
- ⊕ HIGH CAPACITY WELLS
- 790- WATER TABLE CONTOURS (CONTOUR INTERVAL: 1 FT.)
- ➔ DIRECTION OF GROUNDWATER FLOW


NO.	BY	DATE	REVISION	APPD.
<b>WATER TABLE CONTOUR MAP 2/4/81</b>				
<b>PLAN OF OPERATION - ASH DISPOSAL FACILITY</b>				
<b>COLUMBIA SITE</b>				
<b>WISCONSIN POWER &amp; LIGHT COMPANY</b>				
PART OF SECTIONS 27 & 34, T12N, R9E				
<b>TOWN OF PACIFIC COLUMBIA CO. WISCONSIN</b>				
<b>WARZYN</b>		DRAWN TDH	SCALE 1"=300'	SHEET 39 OF 39
		CHECKED RJK	DATE 2/10/81	DRAWING NO.
		APPROVED		C7134-94
ENGINEERING INC.		REFERENCE		PRINTED 8/3/88





- LEGEND**
- PROPERTY LINE
  - EXISTING RAILROAD TRACKS
  - EXISTING GROUND CONTOUR
  - CONTOUR DEPRESSION
  - EXISTING PAVED ROAD
  - EXISTING UNPAVED ROAD
  - EXISTING FENCE
  - EXISTING BUILDING
  - EXISTING SPOT ELEVATION
  - TREES AND/OR BRUSH
  - WETLAND AREA
  - EDGE OF WATER
  - HC 1 WATER SUPPLY WELL
  - MW61A WATER TABLE WELL
  - MW61B PIEZOMETER
  - ABANDONED WATER TABLE WELL
  - ABANDONED PIEZOMETER
  - SG1 STAFF GAUGE
  - ALS-1 LYSMETER
  - DESIGN MANAGEMENT ZONE
  - PROPERTY LINE
  - O.S. OPEN STORAGE
  - O.H. OVERHEAD STRUCTURE
  - E.P.S. ELECTRICAL POWER STATION
  - T TANK
  - W WALL
  - (785.31) WATER TABLE ELEVATION (FT.-MSL)  
(N.M. = NOT MEASURED)
  - 786 GROUNDWATER CONTOUR LINE  
(FT. INTERVAL - FT. M.S.L.)  
(DASHED WHERE INFERRED)
  - GROUNDWATER FLOW DIRECTION

- NOTES**
1. BASE MAP IS PROVIDED BY WISCONSIN POWER & LIGHT CO. AND IS BASED ON PHOTOS TAKEN ON APRIL 6, 1995 BY AERO-METRIC ENGINEERING, SHEBOYGAN, WI.
  2. HORIZONTAL DATUM IS BASED ON THE WISCONSIN STATE PLANE COORDINATE SYSTEM, SOUTH ZONE - DATUM NAD 83/01.
  3. VERTICAL DATUM IS REFERENCED TO U.S.G.S. MEAN SEA LEVEL (MSL). TOPOGRAPHIC CONTOUR INTERVAL IS TWO FEET.
  4. MONITORING WELL LOCATIONS AND ELEVATIONS SURVEYED BY WISCONSIN POWER & LIGHT CO. IN DECEMBER 1994 & NOVEMBER 1996.
  5. THE LOCATION OF THE DESIGN MANAGEMENT ZONE DEMARCATION LINE IS APPROXIMATE.
  6. WATER ELEVATION USED TO PREPARE THIS MAP WERE MEASURED ON OCTOBER 24, 2002.
  7. THE WATER LEVEL AT MW 33A AND MW 33B COULD NOT BE MEASURED DURING OCTOBER 2002 DUE TO AN OBSTRUCTION IN THE WELL CASING.



3.			
2.			
1.			
NO. BY DATE	REVISION		APP'D.
PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY			
SHEET TITLE: WATER TABLE MAP (OCTOBER 2002)			
DRAWN BY: defoe	SCALE: 1"=200'	PROJ. NO. 3024.28	
CHECKED BY: JMR		FILE NO. WATERTBL.PLT	
APPROVED BY: JCD	DATE PRINTED:		FIGURE 3
DATE: JANUARY 2003			

PROJECT: ALLIANT ENERGY - WP&L COLUMBIA ASH PONDS & DRY ASH DISPOSAL FACILITY  
 SHEET: WATER TABLE MAP (OCTOBER 2002)  
 DRAWN BY: defoe  
 CHECKED BY: JMR  
 APPROVED BY: JCD  
 DATE: JANUARY 2003  
 SCALE: 1"=200'  
 PROJ. NO. 3024.28  
 FILE NO. WATERTBL.PLT  
 FIGURE 3