

Annual CCR Landfill Inspection

Edgewater I-43 Ash Disposal Facility

Prepared for:

Wisconsin Power and Light Company
Edgewater Generating Station
3739 Lakeshore Drive
Sheboygan, Wisconsin 53081

SCS ENGINEERS

25225069.00 | December 9, 2025

2830 Dairy Drive
Madison, WI 53718-6751
608-224-2830



Table of Contents

Section	Page
PE Certification	iii
1.0 Introduction	1
1.1 Purpose.....	1
1.2 Background.....	1
2.0 Summary of Results and Recommendations	2
3.0 Annual Inspection	3
3.1 Operating Record Review.....	3
3.2 Visual Inspection.....	3
4.0 Inspection Results	4
4.1 Changes in Geometry.....	4
4.2 CCR Volumes.....	4
4.3 Appearance of Structural Weakness.....	5
4.3.1 Signs of Surface Movement or Instability.....	5
4.3.2 Inappropriate Vegetation Growth.....	6
4.3.3 Animal Burrows.....	6
4.3.4 Erosion Damage.....	6
4.3.5 Unusual Surface Damage Caused by Vehicle Traffic.....	7
4.4 Disruptive Conditions.....	7
4.4.1 Existing Disruptive Conditions.....	7
4.4.1.1 Current Inspection.....	7
4.4.1.2 Previous Inspection.....	7
4.4.2 Potentially Disruptive Conditions.....	7
4.4.2.1 Current Inspection.....	7
4.4.2.2 Previous Inspections.....	7
4.5 Other Changes Since Previous Annual Inspection.....	7
5.0 Future Inspections	7
5.1 Existing CCR Landfill.....	7
5.2 New CCR Landfills and Lateral Expansions.....	8

I:\25225069.00\Deliverables\2025 Federal CCR Inspection\251209_I43_Annual CCR Landfill Inspection_v1.0.docx

[This page left blank intentionally]

PE CERTIFICATION

	<p>I, Phillip E. Gearing, hereby certify that this Annual CCR Landfill Inspection Report meets the requirements of 40 CFR 257.84(b)(2), was prepared by me or under my direct supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Wisconsin.</p>	
		<p>12/9/2025</p>
	<p>(signature)</p>	<p>(date)</p>
	<p>Phillip E. Gearing</p>	
	<p>(printed or typed name)</p>	
	<p>License number <u>E-45115</u></p>	
	<p>My license renewal date is July 31, 2026.</p>	
	<p>Pages or sheets covered by this seal:</p>	
	<p>All – Annual CCR Landfill Inspection – Edgewater I43 Ash Disposal Facility</p>	

[This page left blank intentionally]

1.0 INTRODUCTION

1.1 PURPOSE

SCS Engineers (SCS) completed an annual inspection of the Wisconsin Power and Light Company (WPL) Edgewater I-43 Ash Disposal Facility (I-43) in Sheboygan, Wisconsin. The annual inspection was completed on July 25, 2025, in accordance with the U.S. Environmental Protection Agency (U.S. EPA) Coal Combustion Residuals (CCR) rule, 40 CFR 257 Subpart D, in particular 257.84(b)(1). According to 40 CFR 257.84(b)(1), an annual inspection by a qualified professional engineer is required for all existing and new CCR landfills and any lateral expansion of a CCR landfill. The purpose of the annual inspection is to ensure that the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering standards. The inspection must, at a minimum, include:

- A review of available information regarding the status and condition of the CCR unit, including, but not limited to, files available in the operating record (e.g., the results of inspections by a qualified person and results of previous annual inspections); and
- A visual inspection of the CCR unit to identify signs of distress or malfunction of the CCR unit.

This report has been prepared in accordance with 40 CFR 257.84(b)(2) to document the annual inspection.

1.2 BACKGROUND

The I-43 facility includes a closed CCR landfill, which consists of Phase 1 and Phase 2, and an active CCR landfill, which currently consists of an existing CCR unit in Phase 3 and Phase 4. The two landfills are located on the same property but are not contiguous. Phase 1 and Phase 2, which comprise an inactive CCR landfill that closed prior to October 15, 2015, are not the subject of this report. The inspection requirements in 40 CFR 257.84(b)(1) apply to the existing (active) CCR unit.

The active CCR landfill at I-43, includes the following modules:

- Phase 3, Module 1
- Phase 3, Module 2
- Phase 4, Module 1

The modules are managed as a single landfill by the facility and by the Wisconsin Department of Natural Resources (DNR). WPL previously clarified that Phase 3, Module 1; Phase 3, Module 2; and Phase 4, Module 1 are one existing CCR landfill under the federal CCR Rule, and this report reflects WPL's clarification.

The modules are used to describe the location of items observed during the inspection. At the time of the inspection, the active CCR landfill modules were in various stages of development and use as described in the table below.

Unit	CCR Rule Status	Basis for Status
Existing Active Landfill (Includes Phase 3, Module 1; Phase 3, Module 2; Phase 4, Module 1)	Existing CCR Landfill. Currently accepting CCR.	Filling is occurring in Phase 3, Module 2 and overlay from Phase 3, Module 2 is currently occurring on Phase 3, Module 1. Final or interim waste grades have been reached in some areas, and final or intermediate cover is present on portions of the CCR unit. Final closure per 257.102 will not be completed until final grades are reached throughout the CCR unit.
Contact Water Swale Module	Future New CCR Landfill module pending approval and acceptance of CCR.	Construction activities had commenced at time of inspection. Construction finished in November 2025 and awaiting DNR approval.

2.0 SUMMARY OF RESULTS AND RECOMMENDATIONS

SCS identified no deficiencies or releases during the annual inspection of the CCR unit at I-43. Deficiencies and releases must be remedied by the owner or operator as soon as feasible and the remedy documented.

SCS identified conditions during the annual inspection that are not considered deficiencies but have the potential to become a deficiency if left unaddressed. Each condition and the recommendations provided by SCS to address them are summarized in the table below. Based on correspondence with WPL in follow-up to the visual inspection, the recommended maintenance was performed and will continue to be performed during routine landfill maintenance.

These conditions, recommendations, and maintenance performed are described in further detail in **Section 4.0**.

Condition	CCR Unit / Location	Recommendation(s)	Report Section
Vegetation growth	<ul style="list-style-type: none"> Separation berm between Phase 3, Module 2 Phase 3, Module 2 drainage layer material (Southwest corner) and near leachate vault Contact water swale <p>Note: Contact Water Swale construction was started during the inspection. It was understood that vegetation material would be removed from the contact swale area during construction activities.</p>	<p>Remove vegetation, especially woody and deep-rooted vegetation, before it becomes established. [COMPLETED, REMAINING VEGETATION SPRAYED]</p> <p>Monitor during 7-day inspections.</p> <p>Continue to inspect and remove vegetation growth in drainage layer material and other areas during general maintenance.</p>	4.3.2

Condition	CCR Unit / Location	Recommendation(s)	Report Section
Minor erosion and bare soil observed	North Boundary – Phase 3, Module 2 and Phase 3, Module 1 areas	Place topsoil, seed, and install erosion mat. [COMPLETED] Monitor during 7-day inspections. Continue to observe and maintain as necessary.	4.3.4
Exposed exterior toe drain geotextile	Southeast corner of Phase 4, Module 1	Add additional geotextile fabric, place rooting zone material / topsoil to match existing grades, place seed and erosion mat. [COMPLETED] Monitor during 7-day inspections. Continue to observe and maintain as necessary.	4.3.4

3.0 ANNUAL INSPECTION

Mr. Phillip Gearing of SCS completed an annual inspection of the active CCR landfill at I-43 on July 25, 2025. Mr. Gearing is a licensed professional engineer in Wisconsin and holds a Bachelor of Science degree in Geological Engineering. He has over 19 years of experience in the design, construction, and operation of solid waste disposal facilities. The scope of the annual inspection is described in **Sections 3.1 and 3.2**. The results of the annual inspection are discussed in **Section 4.0**.

3.1 OPERATING RECORD REVIEW

SCS reviewed the available information in the operating record for I-43. Information reviewed by SCS included operating record materials provided by WPL and the information posted on Alliant Energy's CCR Rule Compliance Data and Information website for the I-43 facility.

3.2 VISUAL INSPECTION

SCS completed a visual inspection of the I-43 landfill to identify signs of distress or malfunction of the CCR unit.

The visual inspection included observations of the following:

- CCR placement areas include active filling areas, intermediate cover areas, final cover areas, and exterior non-CCR berms or slopes.
- Leachate collection and removal system components including visible leachate drainage layer materials.

- Leachate and contact water run-off management features including swales, the storage basin, and the storage basin pumping system.
- Non-contact storm water run-on and run-off control features, including swales located adjacent to active fill areas but outside the landfill limits and the on-site storm water management basin.

4.0 INSPECTION RESULTS

The results of the annual inspection, along with a description of any deficiencies or releases identified during the visual inspection, are summarized in the following sections.

4.1 CHANGES IN GEOMETRY

No apparent changes in geometry were noted that would indicate distress or malfunction of the CCR unit since the previous annual inspection at the I-43 facility completed under 40 CFR 257.84(b)(1). All changes in geometry observed during the annual inspection were the result of planned CCR filling.

At the time of the visual inspection, CCR placement was ongoing in Phase 3, Module 2 and overlay from Phase 3, Module 2 is currently occurring on Phase 3, Module 1. Final or interim waste grades have been reached in some areas through the unit. Final cover or intermediate cover exists in areas where final waste grades have been reached, and intermediate cover exists in remaining interim grade areas that are awaiting future CCR placement.

4.2 CCR VOLUMES

The approximate volume of CCR contained in the CCR unit at the time of the inspection is summarized below. A description of how the estimate was developed and the sources used are also summarized below.

Unit	Estimated Volume of CCR in Place	Basis for Estimate and Source
Existing Active Landfill (Includes Phase 3, Module 1; Phase 3, Module 2; Phase 4, Module 1)	511,800 cubic yards	<p>Estimated volume is:</p> <ul style="list-style-type: none"> Based on a July 31, 2025, existing conditions survey compared to approved base grades in Phase 3, Module 1 and documented drainage layer grades in Phase 3, Module 2. Excludes final cover or intermediate cover material installed at time of survey. Includes minor slope overfill within active area outside of final cover or intermediate cover. Note: Slope overfill areas are temporary and based on interim CCR grades. Areas of overfill will be rectified during connection/overlay with the constructed contact water swale module. The July 31, 2025, CCR volume is approximated to be similar to the CCR volume in place during the July 25, 2025, inspection.

4.3 APPEARANCE OF STRUCTURAL WEAKNESS

The inspection included a review of the appearance of actual or potential structural weakness of the CCR unit. The visual inspection included a review of CCR fill areas including the top slopes, internal side slopes, external side slopes, and internal ramps/haul roads for the presence of the following conditions:

- Signs of surface movement or instability:
 - Sloughing, slumping, or sliding
 - Surface cracking
 - Slopes greater than three horizontal to one vertical (3H:1V)
 - Toe of slope bench movement
 - Evidence of inadequate compaction of exposed CCR
- Inappropriate vegetation growth
- Animal burrows
- Erosion damage
- Unusual surface damage caused by vehicle traffic

4.3.1 Signs of Surface Movement or Instability

No signs of surface movement or instability were noted during the inspection of the landfill.

4.3.2 Inappropriate Vegetation Growth

No inappropriate vegetation growth impacting the CCR unit was noted during the inspection, except as observed below:

- Vegetation growth was observed in the separation of berm drainage layer material between Phase 3, Module 2; the drainage layer material in the Phase 3, Module 2 southwest corner; and in the contact water swale.

SCS recommends the removal of vegetation, especially woody and deep-rooted vegetation before it becomes established, and these areas be monitored during the 7-day inspections. Vegetation growth in the drainage layer and other areas should continue to be inspected and removed during general maintenance.

- Dense vegetation growth in the exterior drainage swales and around features (toe drains, cleanouts, discharge structures, etc.) makes access for inspection more difficult. Regular vegetation maintenance is likely to aid in the identification of issues before they become significant. Additional vegetation maintenance could be beneficial for future weekly and annual inspections. This condition is not considered an operating deficiency, but SCS recommends woody vegetation and dense vegetation be spot removed, using hand trimmers around structures and performing additional mowing in swale areas of dense growth. These areas should be monitored during the 7-day inspections.

Vegetation growth was discussed with plant staff. The recommended vegetation maintenance has been performed based on observations during ongoing construction activities in follow-up to the visual inspection.

4.3.3 Animal Burrows

No animal burrows were noted during the inspection of the CCR unit.

4.3.4 Erosion Damage

The following erosion damage or the potential for erosion damage was noted during the inspection:

- Minor erosion and bare soil areas were observed along the north boundary of Phase 3, Module 2 and Phase 3, Module 1 areas. Placement of topsoil, seed, and erosion mat is recommended in the area. It is recommended that areas be monitored during 7-day inspections and maintained, as necessary.
- Intermittent areas of bare soil and thin vegetation were observed in Phase 3, Module 1 cover and the intermediate cover in Phase 3, Module 2. These areas appear to result from mowing scuffing or limited vegetation growth. While no erosion was observed, placement of additional topsoil, seed, and erosion mat is recommended to prevent potential future erosion. Areas should be monitored during 7-day inspections and maintained, as necessary.

Erosion and potential erosion areas were discussed with plant staff. The recommended maintenance has been performed based on observations during ongoing construction activities in follow-up to the visual inspection.

4.3.5 Unusual Surface Damage Caused by Vehicle Traffic

No unusual surface damage caused by vehicle traffic was noted during the inspection of the CCR unit.

4.4 DISRUPTIVE CONDITIONS

4.4.1 Existing Disruptive Conditions

4.4.1.1 Current Inspection

No existing conditions that were disrupting the operation and safety of the CCR unit were noted during the annual inspection.

4.4.1.2 Previous Inspection

No existing conditions that disrupted the operation and safety of the CCR unit were noted during the previous inspection.

4.4.2 Potentially Disruptive Conditions

4.4.2.1 Current Inspection

Exposed exterior toe drain geotextile was observed on the slope of the southeast corner of Phase 4, Module 1. Additional exposure could impact the operation of the toe drain system. It was recommended that additional geotextile fabric, rooting zone material, topsoil, seed and erosion mat were placed over the area.

The observation was discussed with plant staff. The recommended maintenance has been performed based on observations during ongoing construction activities in follow-up to the visual inspection. The area should be monitored during 7-day inspections and maintained, as necessary.

4.4.2.2 Previous Inspections

No potentially disruptive conditions to operation and safety of the CCR unit were noted during the previous annual inspection.

4.5 OTHER CHANGES SINCE PREVIOUS ANNUAL INSPECTION

No changes to site conditions that appear to have the potential to affect the stability or operation of the facility were noted during the inspection.

5.0 FUTURE INSPECTIONS

5.1 EXISTING CCR LANDFILL

As stated in 40 CFR 257.84(b)(4), the owner or operator of the CCR unit must conduct the inspection required by paragraphs (b)(1) and (2) of this section on an annual basis. The date of completing the inspection report is the basis for establishing the deadline to complete the next subsequent inspection. Any required inspection may be conducted prior to the required deadline, provided the

owner or operator places the completed inspection report into the facility's operating record within a reasonable amount of time. In all cases, the deadline for completing subsequent inspection reports is based on the date of completing the previous inspection report. The owner or operator has completed an inspection when the inspection report has been placed in the facility's operating record.

The next annual inspection of the existing landfill unit must be completed within 1 year of the placement of this inspection report in the operating record for the facility.

5.2 NEW CCR LANDFILLS AND LATERAL EXPANSIONS

For any newly constructed CCR modules (e.g., future Phases or Modules), the initial annual inspection must be completed within 14 months of the first receipt of CCR in the module, in accordance with 40 CFR 257.84(b)(3)(ii). Construction and placement activities should be documented, and preventive measures for drainage, erosion, and vegetation should be implemented before the initial inspection.